



COLORADO

Department of Transportation

2022 Cost Data

(January to December)

Compiled By:

Cost Estimating Services Unit of the
Construction Engineering Services Branch

March 7, 2022

2022 Cost Data: Construction

Table of Contents

Number
of Pages

List of 2023 Bid Projects.....	7
Bridge Cost per Square Feet.....	1
Item Unit Costs by Projects.....	665

Colorado Cost Data

Foreword

The Colorado Department of Transportation's Cost Estimating Services Unit of the Construction Engineering Services Branch publishes the Cost Data Book annually. A joint effort has been made between the Department's sections and the Cost Estimating Services Unit to gather and record cost data for this publication.

The following data includes weighted average prices for items on highway construction projects that were bid during the 2023 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.

Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome.

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 1

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220106	BRANNAN SAND AND GRAVEL, LLC NHPP2873-189	US 287 (FEDERAL BLVD) - COLFAX	1	U	4	\$4,704,411.40	106.92
20220106	STURGEON ELECTRIC COMPANY, INC ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	00	M	1	\$8,447,636.00	163.49
20220106	ROADSAFE TRAFFIC SYSTEMS, INC MTCE R500-218		5	U	2	\$1,168,613.00	87.75
20220106	Straight Stripe Painting, Inc. MTCE R500-219		5	R	3	\$2,256,065.00	102.19
20220113	INTERMOUNTAIN SLURRY SEAL, INC. STR0505-050		2	P	3	\$2,019,305.00	91.60
20220113	AMES CONSTRUCTION, INC. NHPP0702-383	I-70 EB AUX FRISCO TO SILVERTH	3	M	5	\$26,917,300.00	119.30
20220113	TRICON 2, LLC NH0504-910	US50B L-24-B MIN REP AT MP 406	2	P	8	\$1,697,000.00	80.81
20220113	ROADSAFE TRAFFIC SYSTEMS, INC MTCER400-391	VARIOUS HIGHWAY SEGMENTS ACROS	4	R	4	\$1,564,170.00	101.46
20220203	Myers & Sons Construction, LLC STA0252-459		1	R	3	\$6,297,433.64	131.20
20220203	A and S CONSTRUCTION CO. NHPP1601-083		5	R	2	\$21,890,679.16	120.85
20220203	CC ENTRPRS TRAFFIC CONTROL SPECIALISTS MTCER300-262		3	M	3	\$1,742,097.00	82.96
20220217	MCATEE CONSTRUCTION CO. C0762-055		4	R	4	\$13,997,628.23	109.36
20220217	MCATEE CONSTRUCTION CO. STR0141-031		3	M	3	\$5,420,000.00	92.36
20220217	OLDCASTLE SW GROUP, INC. STR133A-051		3	R	3	\$1,540,725.10	123.76
20220224	OLDCASTLE SW GROUP, INC. NHPP0063-063		3	U	2	\$9,208,179.50	125.31
20220303	A and S CONSTRUCTION CO. STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 IN	2	R	3	\$4,623,000.00	102.73
20220310	BRANNAN SAND AND GRAVEL, LLC NHPP0703-472		1	U	4	\$8,027,827.75	101.50

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 2

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220310	FLATIRON CONSTRUCTORS, INC. C0761-239 NHPP 0761-238	I-76 DAHLIA TO YORK	1 1	R R	8	\$25,426,004.45	87.29
20220311	RLW/SEMA, A Joint Venture NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5 &	4	R	1	\$6,514,608.17	111.89
20220314	IHC Scott, Inc. CR100-362		1	U	1	\$4,644,427.21	100.00
20220315	KIEWIT INFRASTRUCTURE CO. ER007A-035		4	M	1	\$5,520,588.70	107.47
20220317	KSK, LLC STR R500-171	Various locations on SH 141 an	5	R	3	\$1,400,000.00	86.60
20220317	OLDCASTLE SW GROUP, INC. STR160A-034	US160A LA VETA PASS EAST SURFA	2	M	2	\$8,614,391.16	99.02
20220317	Myers & Sons Construction, LLC BRC040-057		2	U	4	\$4,120,979.48	124.88
20220317	OLDCASTLE SW GROUP, INC. STR092A-031		3	R	1	\$7,346,956.34	97.35
20220317	KRAEMER NORTH AMERICA, LLC M R100-351	FY22 R1 SIGN STRUCTURE REPLACE	1	U	2	\$1,217,455.60	101.45
20220324	MORTON ELECTRIC, INC. MP0503-098		2	U	2	\$646,748.00	77.92
20220331	CASTLE ROCK CONST. CO. OF COLO, LLC NHM765-007		2	U	3	\$13,605,608.18	102.30
20220331	ABCO CONTRACTING, INC. C0703-499	EJMT GROUT BED REPAIR AND PANE	1	M	2	\$1,341,361.00	148.29
20220407	MARTIN MARIETTA MATERIALS NH0504-911		2	P	2	\$17,781,881.53	107.77
20220414	KSK, LLC CC030-081	ADA RAMP AND CURBS - FT. LUPTO	4	U	3	\$2,035,000.00	82.70
20220418	KIEWIT INFRASTRUCTURE CO. NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	3	M	1	\$21,966,094.79	100.00
20220421	CASTLE ROCK CONST. CO. OF COLO, LLC STM1151-038	SH115 MP 27 TO MP 38	2	R	5	\$39,607,433.98	120.02
20220505	RALPH L. WADSWORTH CONSTRUCTION CO., LLC MTCE2873-204	MTCE FY22 SH287 CONC PANEL REP	4	U	2	\$693,896.87	98.15

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 3

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220505	AMERICAN CIVIL CONSTRUCTORS, LLC dba A 2670703-479	I-70 BRIDGE OVER HARLAN	1	R	6	\$17,879,000.00	107.64
20220506	LAWRENCE CONSTRUCTION CO. ER0702-420	PR I-70 GWC MATERIAL FLOWS 202	3	M	2	\$3,888,046.00	121.16
20220512	INTERFACE COMMUNICATIONS COMPANY CM760-047	COLFAX AND QUAIL	1	U	5	\$706,289.00	130.08
20220512	IHC Scott, Inc. STA0712-019	SH 71: Frieght Improvements	4	P	1	\$11,946,689.77	111.68
20220512	ZAK DIRT, INC. NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOSI	2	M	3	\$7,334,391.55	112.84
20220512	COULSON EXCAVATING COMPANY STA001A-005	SH1 WELLINGTON SOUTH RESURFACI	4	P	2	\$5,897,002.35	80.69
20220526	A and S CONSTRUCTION CO. NHFP 3851-018	US 385 NORTH OF CHEYENNE WELLS	4	P	2	\$13,523,000.00	109.88
20220526	CC ENTRPRS TRAFFIC CONTROL SPECIALISTS FSA0702-409	I-70 VAIL WILDLIFE FENCE PHASE	3	M	1	\$3,032,752.00	98.81
20220526	AMERICAN WEST CONSTRUCTION, LLC C0852-120	Rehabilitation of Culvert by s	1	R	1	\$749,206.00	68.11
20220526	STRUCTURES, INC. STAR100-358	3 STRUCTURES IN REGION 1 METRO	1	U	3	\$1,580,730.00	66.09
20220602	MOUNTAIN CONSTRUCTORS, INC. FSA3921-019	SH 392 AND WCR 55 ISLANDS	4	P	3	\$174,037.00	105.44
20220602	MORTON ELECTRIC, INC. ITS 0741-024	VMS SIGN INSTALLATIONS AND VSL	1	M	2	\$2,152,940.00	142.77
20220609	AB Underground FSA052A-046	SH52 WCR 37 INTERSECTION IMPRO	4	R	5	\$3,098,847.35	84.58
20220609	BRANNAN SAND AND GRAVEL, LLC NHPP072A-047	SH-72 RESURFACING: I-70 TO IND	1	R	1	\$8,097,793.64	112.67
20220609	ROADSAFE TRAFFIC SYSTEMS, INC MPR200-278	R2 - VARIOUS LOCATIONS	2	R	3	\$2,824,931.56	95.98
20220609	ROADSAFE TRAFFIC SYSTEMS, INC MPR200-279	FY 23 STENCIL MARKING PROJECT	2	R	3	\$448,255.86	93.48
20220616	RALPH L. WADSWORTH CONSTRUCTION CO., LLC MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2B	4	R	2	\$2,499,779.84	131.35

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 4

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220623	THE TRUESDELL CORPORATION NHPP0252-448	I-25 TREX NARROWS BRIDGE PREVE	1	U	4	\$2,827,827.00	94.26
20220630	ROADSAFE TRAFFIC SYSTEMS, INC MTCE R100-380	REGION 1 FY 23/24 PAVEMENT MAR	1	U	1	\$11,849,087.88	98.74
20220707	A-1 CHIPSEAL COMPANY MTCE 072A-045	SH 72B MP 37.00 TO MP 45.3 NEA	4	M	1	\$1,096,643.80	95.41
20220707	AMERICAN STRIPING COMPANY LLC MTCE0702-426	I70 FROM MP 155 TO 180 AND MP	3	M	4	\$693,730.00	91.82
20220707	KOLBE STRIPING INC. MTCE0702-423	REGION 3 ROUNDABOUT STRIPING A	3	M	3	\$324,225.00	89.44
20220707	KOLBE STRIPING INC. MTCE0702-414	I-70 MM 75-116, OTHER REGION 3	3	M	3	\$1,518,388.73	97.40
20220708	KIEWIT INFRASTRUCTURE CO. FBR0702-423	VAIL PASS AUX BE F-12-AT PHASE	3	M	1	\$47,957,757.02	100.00
	NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	3	M			
20220804	MOUNTAIN CONSTRUCTORS, INC. FSA052A-057	SH52 BOX CULVERT EXTENSION (MP	4	R	3	\$704,678.03	108.34
20220804	TLM CONSTRUCTORS, INC. STR0711-022	SH 71 OVER THE ARKANSAS	2	P	3	\$572,763.00	115.71
20220818	OLDCASTLE SW GROUP, INC. NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	3	R	2	\$16,532,414.25	107.63
20220825	ZAK DIRT, INC. FBR0761-236	I-76 OVER CLR CRK SCOUR MIT	1	R	3	\$1,677,136.45	83.86
20220825	STURGEON ELECTRIC COMPANY, INC CI211-099	SH 121 NORTH SGA SIGNALS	1	U	2	\$3,855,000.00	80.00
20220825	AMERICAN STRIPING COMPANY LLC MTCE0400-396	REGION 4	4	R	3	\$1,225,327.30	87.91
20220829	WILLIAMS CONSTRUCTION CONTRACTORS ER0502-092	US 50 MP 204 EB MONARCH TRUCK	5	M	3	\$1,024,007.51	87.33
20220831	LAWRENCE CONSTRUCTION CO. BR0343-046	US 34 TIMBER BRIDGE REPL. PKG.	4	P	1	\$4,432,957.09	103.02
	FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL.	4	P			
20220901	STRUCTURES, INC. NHPPR100-266	R1 ESSENTIAL REPAIRS	1	U	3	\$3,070,798.76	133.51
20220901	CRUZ CONSTRUCTION, INC. PAN0761-245	ALONG I-76 & RAMPS MILEPOST 95	4	P	2	\$348,232.00	110.33

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 5

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220901	STRUCTURES, INC. STAR100-374	5 STRUCTURES IN REGION 1	1	U	1	\$2,745,838.90	130.43
20220914	RALPH L. WADSWORTH CONSTRUCTION CO., LLC ER0253-297	WCR 34 BRIDGE OVER I-25 (MM 245	4	R	4	\$224,907.20	54.37
20220915	VILLALOBOS CONCRETE INC. SHE2873-193	US 287 & CO 52 INTERSECTION IM	4	R	6	\$5,138,361.59	86.17
20220915	LAWRENCE CONSTRUCTION CO. 2670703-497	I-70_GENESEE WILDLIFE XING	1	M	7	\$9,900,432.72	99.00
20220915	AMERICAN CIVIL CONSTRUCTORS, LLC dba A 2670403-065	US40_FLOYD HILL ROUNDABOUTS	1	M	3	\$9,157,473.00	109.66
20220929	KSK, LLC NHFP0701-231	I-70 SALT WASH BRIDGES SCOUR	3	R	2	\$3,300,000.00	77.89
20221006	ABCO CONTRACTING, INC. MTCE0253-281	MTCE FY23 I-25 CONC PANEL REPL	4	R	4	\$1,351,993.00	107.06
20221013	Kilgore Companies, LLC dba Elam NHFP0821-114	Construc SH 82 ASPEN/INDEPENDENCE PASS	3	M	3	\$1,165,615.42	85.25
20221013	WORK ZONE TRAFFIC CONTROL, LLC C0831-126	SH83 EL PASO COUNTY TO BAYOU G	1	R	2	\$512,963.00	102.17
20221027	SIMON CONTRACTORS STA3852-015	US 385 HOLYOKE NORTH	4	P	1	\$16,494,822.00	103.14
20221027	MARTIN MARIETTA MATERIALS STA207A-004	Resurfacing SH207A MANZANOLA (2	P	3	\$6,049,464.37	100.82
20221027	ZAK DIRT, INC. TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	4	U	8	\$13,166,577.55	101.32
20221027	ABCO CONTRACTING, INC. NHFP0705-088	I-70 AGATE STRUCTURE REHAB	4	P	4	\$5,098,771.00	105.76
20221027	Geovert, LLC C5502-111	US 550 MP 81 AND 89 RED MOUNTA	5	M	2	\$744,942.00	132.84
20221027	TRICON 2, LLC C170A-002	CRITICAL CULVERT CONST. PKG D	4	U	4	\$679,000.00	88.68
20221027	OLDCASTLE SW GROUP, INC. NHFP0701-253	I-70 EAST OF DEBEQUE	3	R	2	\$5,028,719.80	86.05
20221027	ARROW ELECTRIC SERVICE, INC. FSAM240-200	SH21B CO SPRINGS SIGNAL REPLAC	2	P	4	\$2,720,098.85	100.74

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 6

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20221101	LAWRENCE CONSTRUCTION CO. NHPP0343-048	US 34 (MP 169.3-171.4)	4	P	4	\$2,191,362.00	70.77
20221103	AMES CONSTRUCTION, INC. STU0252-457	I-25:ALAMEDA RIVER PH 2.0	1	U	3	\$22,317,300.00	90.58
20221103	TEZAK HEAVY EQUIPMENT CO., INC. SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF F	2	M	3	\$2,097,272.44	110.38
20221110	ASPHALT SPECIALTIES CO., INC. NHPP0853-126	US85C: PLATTEVILLE NORTH MP (2	4	P	5	\$5,111,254.25	74.46
20221110	OLDCASTLE SW GROUP, INC. STR064A-010	SH 64 AND SH 13 AT MEEKER	3	M	2	\$6,203,531.45	90.31
20221117	Kilgore Companies, LLC dba Elam C5502-097	Construc US550 MP 117.28-126.06	3	R	3	\$18,991,815.84	99.30
20221117	ARROW ELECTRIC SERVICE, INC. STRC090-011	US 50B AND SH71/CR18 INTERSECT	2	R	2	\$2,854,417.85	124.11
20221117	WORK ZONE TRAFFIC CONTROL, LLC MPR200-280	PUEBLO AREA	2	R	2	\$894,364.00	99.37
20221201	AMERICAN CIVIL CONSTRUCTORS, LLC dba A BR2854-148 STAM420-001 STM0091-046	INTERSECTION OF US 285 & SH 9 US 285 AT HWY 9C IMPROVEMENTS ADA RAMP IMPROVEMENTS - FAIRPL	2 2 2	R R M	4	\$24,091,000.00	133.10
20221201	STRUCTURES, INC. STR109A-019	M-22-AY BRIDGE REHAB ON SH109	2	R	2	\$5,635,899.39	98.88
20221201	Kilgore Companies, LLC dba Elam STR318A-001	Construc SH 318 MP 0 - 12.5 MOFFAT COUN	3	R	2	\$6,686,562.84	98.21
20221201	BRANNAN SAND AND GRAVEL, LLC NHPP0021-041	SH2 RESURFACING MLK TO 52ND	1	U	4	\$3,269,122.13	86.60
20221201	A and S CONSTRUCTION CO. STR114A-015	SH114 SILLSVILLE SOUTH TO MP30	3	M	2	\$14,324,912.69	86.49
20221201	A and S CONSTRUCTION CO. STA0711-021	SH71: REGION LINE NORTH	4	P	3	\$14,314,966.60	85.12
20221201	Myers & Sons Construction, LLC NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLAC	3	M	2	\$7,080,420.17	66.99
20221201	OLDCASTLE SW GROUP, INC. STR0641-107	SH 13 MM 104-128.1 IN MOFFAT C	3	R	3	\$3,297,815.15	91.83
20221201	SEMA CONSTRUCTION, INC. IM025A-050	I25-MP103.9 - INTERSECTION DRE	2		3	\$10,512,989.35	126.66

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 7

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20221201	Lobato Construction, LLC 2670703-487	I-70 BRIDGES OVER WARD ROAD- B	1	U	5	\$16,387,878.20	101.16
20221208	BRANNAN SAND AND GRAVEL, LLC NHFP083A-046	SH83 RESURFACING STROH RD TO H	1	R	2	\$3,893,820.48	97.35
20221215	OLDCASTLE SW GROUP, INC. NHFP0063-048	US6 / 20 ROAD INTERSECTION IMP	3	R	4	\$3,776,448.13	86.54
20221215	OLDCASTLE SW GROUP, INC. NHFP0931-033	SH93:US6 TO 58TH RESURFACING	1	R	4	\$5,039,495.35	75.72
20221215	GENEVA ROCK PRODUCTS, INC. NHM175-029	CANON CITY, CO	2	U	2	\$2,012,665.10	105.93
20221215	MOUNTAIN CONSTRUCTORS, INC. FSA0853-122	WCR14.5 AND US-85, FORT LUPTON	4	R	3	\$289,870.00	82.11
20221222	TRICON 2, LLC STA385A-016	SH 385 MP 97.76	2	P	4	\$3,775,000.00	126.41
20221222	Siete, Inc. BR012A-048	CO 12 STRUCTURE P-17-F AT MP 4	2	M	2	\$4,696,233.75	111.82
20221222	IHC Scott, Inc. NHFP0502-090	SH 50 MP 134.6-136 GUNNISON CO	3	R	5	\$7,499,484.80	96.53
20221222	MARTIN MARIETTA MATERIALS STA0361-129	US 36: HYGIENE RD AND NELSON R	4	U	5	\$3,618,938.30	78.23
20221222	Kilgore Companies, LLC dba Elam STR0092-024	Construc SH 9 North of Silverthorne	3	M	2	\$6,632,329.84	96.72
20221222	A and S CONSTRUCTION CO. STR096A-050	SH 96 MP 168.99 TO 193.77	2	P	3	\$12,723,069.27	123.52
					=====	=====	=====
TOTALS					337	\$773,250,391.75	102.53

Colorado Department of Transportation
2022 Cost Data
BRIDGE COST PER SQUARE FOOT
(01/01/22 THROUGH 12/31/22)

19:22 Tuesday, March 7, 2023 1

DATE LET	PROJECT NUMBER/ PROJECT LOCATION	TERR/ BRIDGE ID	LENGTH	WIDTH	TOTAL SQUARE FT	TOTAL COST	COST PER SQUARE FOOT
BRIDGE REPAIR							
220317	STR R500-171 Various locations on SH 141 an	R K-02-C L-02-B K-01-A	117.4200 103.4200 243.6500	24.0000 28.0000 24.0000	2818.1 2895.8 5847.6	\$133,594 \$109,396 \$202,464	\$47.41 \$37.78 \$34.62
220914	ER0253-297 WCR 34 BRIDGE OVER I-25 (MM 245	R 0300	223.0000	30.0000	6690.0	\$46,840	\$7.00
221201	STA0711-021 SH71: REGION LINE NORTH	P 0300	70.0000	32.0000	2240.0	\$100,994	\$45.09
			WEIGHTED AVERAGE COST: NEW STRUCTURES		20491.4	\$593,288	\$28.95
BRIDGE WIDENING							
221103	STU0252-457 I-25:ALAMEDA RIVER PH 2.0	U 0300	189.0000	142.0000	26838.0	\$9,710,150	\$361.81
			WEIGHTED AVERAGE COST: NEW STRUCTURES		26838.0	\$9,710,150	\$361.81
CONCRETE SLAB AND GIRDER							
220421	STM1151-038 SH115 MP 27 TO MP 38	R J-17-A	94.0000	30.0000	2820.0	\$2,445,085	\$867.05
			WEIGHTED AVERAGE COST: NEW STRUCTURES		2820.0	\$2,445,085	\$867.05
MAJOR STRUCTURE CBC OR PIPES							
221027	STA207A-004 Resurfacing SH207A MANZANOLA (P L-21-BK	21.7000	60.0000	1302.0	\$558,912	\$429.27
221222	STA385A-016 SH 385 MP 97.76	P 0300	26.5000	92.6700	2455.8	\$892,100	\$363.27
			WEIGHTED AVERAGE COST: NEW STRUCTURES		3757.8	\$1,451,012	\$386.14
MISCELLANEOUS							
220708	FBR0702-423 VAIL PASS AUX BE F-12-AT PHASE	M 0300	600.0000	52.0000	31200.0	\$8,819,532	\$282.68
			WEIGHTED AVERAGE COST: NEW STRUCTURES		31200.0	\$8,819,532	\$282.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 1

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00000		Clear and Grub		LUMP SUM	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	160000.00	249794.77	251778.00
NHPP1601-083			02/03/22	1.00	15000.00	100098.69	80000.00
STA0252-459			02/03/22	1.00	119152.17	47566.67	8700.00
STR0141-031			02/17/22	1.00	25000.00	25300.00	12900.00
NHPP0063-063			02/24/22	1.00	20000.00	4875.00	5000.00
CR100-362			03/14/22	1.00	84573.11	84573.11	84573.11
BRC040-057			03/17/22	1.00	12500.00	33000.00	22000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	20000.00	2704.50	1709.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	57028.16	86341.06	58332.51
NH0504-911			04/07/22	1.00	10000.00	12150.00	19300.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	108053.02	108053.02	108053.02
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	243401.38	182927.55
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	80000.05	61000.32	21423.73
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	25000.00	156101.33	193304.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	10000.00	31500.00	24000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	30000.00	13500.00	13500.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	2000.00	6484.00	9000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	40000.00	38718.17	11350.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	45005.90	88328.88	64762.03
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	92027.89	92027.89	92027.89
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	20000.00	66654.52	100000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	40000.00	22500.00	20000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	5000.00	39566.62	8699.87
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	5061.04	9470.36	9470.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	20000.00	66170.75	30000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	80000.00	86034.54	21041.78
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	5000.00	75609.63	13000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	70000.00	52375.00	54750.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	34215.00	65098.85	38776.66
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	10000.00	22445.00	2500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00000 Clear and Grub LUMP SUM =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	30000.00	25937.50	18750.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	20000.00	76861.02	85000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	78839.30	63000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	30000.00	48280.87	22842.62
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	10000.00	16915.00	24000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	30000.00	11904.00	25000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	50000.00	114606.07	90980.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	1500.00	19933.50	2500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	18091.00	71300.00	100000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	25000.00	108333.33	50000.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	75000.00	123505.86	18000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	30000.00	21064.33	12300.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	50000.00	121763.90	195182.41
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	21389.18	18870.91
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	100000.00	72500.00	50000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				16.00	38099.44	63738.47	54642.70
WEIGHTED AVERAGE FOR THE YEAR				42.00	42163.24	72287.55	54126.38
===== 201-00001 Clear and Grub Acre =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	33058.05	20000.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1.00	8000.00	33058.05	20000.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	23.00	900.00	6303.25	6303.25
WEIGHTED AVERAGE FOR THE SECOND QUARTER				23.00	900.00	6303.25	6303.25
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	0.20	25000.00	55926.71	13260.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.40	50000.00	184500.00	18000.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	2000.00	20097.54	27292.62
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.60	16875.00	65676.80	23215.39
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	5500.00	7634.83	4928.41

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 3

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00001 Clear and Grub Acre =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA385A-016		SH 385 MP 97.76	12/22/22	3.50	7500.00	14875.00	5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.50	6060.00	9662.08	4948.46
	WEIGHTED AVERAGE FOR THE YEAR			38.10	3450.13	14076.83	6928.48
===== 201-00005 Rem of Debris LUMP SUM =====							
NH0504-911			04/07/22	1.00	5000.00	55050.00	10100.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	29776.13	6200.61
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	7500.00	36997.24	8150.31
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	10000.00	9131.28	10000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	5000.00	22240.58	12000.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	3000.00	4866.67	5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	6000.00	11784.69	9000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	6600.00	22166.32	8660.12
===== 202-00000 Rem Str and Obstructions LUMP SUM =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2000.00	16896.96	25000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	20000.00	14456.79	10000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	15000.00	21132.50	10000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	12333.33	18541.75	15000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	8000.00	5000.00	5000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	41135.14	34086.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	41500.00	32101.35	19543.10
	WEIGHTED AVERAGE FOR THE YEAR			5.00	24000.00	22157.65	16817.24
===== 202-00001 Rem Structure Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	75000.00	2690.74	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 4

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00001 Rem Structure Each =====							
C0761-239							
NHM765-007			03/31/22	3.00	900.00	2505.03	238.74
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	19425.00	2592.42	804.06
===== 202-00002 Rem of Structure (Spec) Each =====							
NHM765-007			03/31/22	5.00	500.00	2452.92	100.06
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	500.00	2452.92	100.06
	WEIGHTED AVERAGE FOR THE YEAR			5.00	500.00	2452.92	100.06
===== 202-00003 Rem of Structure (Spec) LUMP SUM =====							
ER0502-092			08/29/22	1.00	25000.00	11526.66	14329.99
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	25000.00	11526.66	14329.99
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	11526.66	14329.99
===== 202-00009 Tree Trimming LUMP SUM =====							
NHM765-007			03/31/22	1.00	7200.00	11419.13	3735.30
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	7200.00	11419.13	3735.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 5

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00009 Tree Trimming LUMP SUM =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1.00	10000.00	25470.10	10000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	25470.10	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	8600.00	20200.99	6867.65
===== 202-00010 Rem Tree Each =====							
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	6.00	500.00	1147.66	1200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	500.00	1147.66	1200.00
NH0504-911			04/07/22	1.00	500.00	2300.00	2600.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	40.00	551.05	551.05	551.05
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	258.00	340.00	286.19	250.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	14.00	400.00	962.96	2197.51
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	10.00	700.00	1250.00	750.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	5.00	1200.00	1354.34	576.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			328.00	392.87	372.58	397.22
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	16.00	562.07	562.07	562.07
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	10.00	500.00	831.89	1350.00
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	11.00	600.00	1350.00	1200.00
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	48.00	1000.00	532.66	200.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	13.00	1000.00	921.39	1000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			98.00	832.58	714.81	594.83
C5502-111	US 550 MP 81 AND 89 RED MOUNT		10/27/22	2.00	300.00	1375.00	2000.00
C170A-002	CRITICAL CULVERT CONST. PKG D		10/27/22	25.00	400.00	1193.75	375.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	109.00	1000.00	753.65	635.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
===== 202-00010	Rem Tree			Each	=====		
C5502-097	US550 MP 117.28-126.06	11/17/22		3.00	1000.00	1380.06	1780.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		10.00	500.00	1929.14	5180.66
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		23.00	350.00	716.67	350.00
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22		20.00	500.00	1304.01	2000.00
STA385A-016	SH 385 MP 97.76	12/22/22		15.00	500.00	1362.50	500.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			207.00	739.86	992.70	943.41
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			639.00	573.72	582.18	612.00
=====							
===== 202-00015	Rem Headwall			Each	=====		
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		1.00	1500.00	2916.21	4981.95
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	2916.21	4981.95
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22		1.00	3559.01	3559.01	3559.01
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		3.00	2300.00	3520.78	3415.68
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22		3.00	1680.00	1666.67	1500.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	2214.14	2854.83	2615.15
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT	08/25/22		1.00	1500.00	2386.67	970.00
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22		2.00	2200.00	4469.58	1583.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	1966.67	4053.00	1378.67
C5502-097	US550 MP 117.28-126.06	11/17/22		5.00	3000.00	1553.46	130.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		3.00	1736.00	1667.26	1684.92
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22		1.00	1500.00	3083.85	2250.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	2412.00	1794.98	883.86
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			20.00	2230.35	2663.04	1768.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 7

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00019 Rem Inlet Each =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	9.00	1230.00	1757.29	1300.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	3.00	1200.00	1581.95	1800.00
C0761-239							
NHM765-007			03/31/22	19.00	1000.00	1416.63	1073.33
WEIGHTED AVERAGE FOR THE FIRST QUARTER				31.00	1086.13	1569.78	1209.46
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	1.00	1559.71	1559.71	1559.71
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	2.00	1200.00	1581.12	2424.46
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	7.00	1500.00	1808.85	1408.54
WEIGHTED AVERAGE FOR THE SECOND QUARTER				10.00	1445.97	1761.18	1626.84
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	1.00	1650.55	1650.55	1650.55
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	14.00	1500.00	417.35	360.00
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	2.00	1500.00	2289.75	1926.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				17.00	1508.86	995.44	620.15
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	2.00	1400.00	1933.99	700.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	7.00	2000.00	2900.59	1200.00
C5502-097	US550 MP 117.28-126.06		11/17/22	1.00	1500.00	1809.13	502.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	2.00	1500.00	1626.89	1684.93
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	1.00	1776.00	1816.61	1430.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	1.00	2000.00	2700.00	1100.00
STA0361-129	US 36: HYGIENE RD AND NELSON		12/22/22	1.00	1400.00	3898.13	1925.64
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				15.00	1765.07	2409.38	1208.50
WEIGHTED AVERAGE FOR THE YEAR				73.00	1373.37	1704.34	1129.20
===== 202-00021 Rem Manhole Each =====							
NHM765-007			03/31/22	3.00	2000.00	2186.51	3299.39
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	2000.00	2186.51	3299.39

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 8

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00021 Rem Manhole Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	3588.97	3588.97	3588.97
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	18.00	1400.00	461.49	400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			25.00	2012.91	970.61	1292.91
===== 202-00023 Rem Emb Prot Ty 3 Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	2566.24	2600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	3500.00	3291.88	5866.67
	WEIGHTED AVERAGE FOR THE YEAR			29.00	2062.85	1576.83	1929.71
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	1000.00	1328.45	850.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	1000.00	1328.45	850.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1000.00	1076.03	1082.07
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	1000.00	1076.03	1082.07
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	4.00	800.00	1438.33	1000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	800.00	1438.33	1000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	1200.00	1139.45	880.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1200.00	1139.45	880.00
	WEIGHTED AVERAGE FOR THE YEAR			22.00	981.82	1204.91	996.04

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 9

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00024 Rem Emb Prot Ty 5 Each =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	2.00	500.00	1264.00	1050.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	500.00	1264.00	1050.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	500.00	1264.00	1050.00
===== 202-00025 Rem Ditch Lining Lin Foot =====							
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	1,450.00	12.00	26.38	15.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,450.00	12.00	26.38	15.00
C5502-097	US550 MP 117.28-126.06		11/17/22	165.00	20.00	18.18	8.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			165.00	20.00	18.18	8.00
	WEIGHTED AVERAGE FOR THE YEAR			1,615.00	12.82	25.94	14.28
===== 202-00026 Rem S and D Pave Sq Yard =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1,252.00	25.00	20.38	27.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,252.00	25.00	20.38	27.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	852.00	22.00	20.68	34.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			852.00	22.00	20.68	34.75
FSA052A-057 NHPP0063-054	SH52 BOX CULVERT EXTENSION (M		08/04/22	4.00	50.00	281.00	66.30
	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	8.00	50.00	228.16	400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	50.00	250.81	288.77

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00026 Rem S and D Pave Sq Yard =====							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	5.00	60.00	1742.00	2500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,290.00	25.00	20.08	28.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,050.00	23.90	18.36	17.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	206.00	40.00	37.33	40.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,551.00	25.83	22.48	27.98
WEIGHTED AVERAGE FOR THE YEAR				4,667.00	24.97	21.70	29.30
===== 202-00027 Rem Riprap Sq Yard =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	209.00	40.00	32.70	15.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				209.00	40.00	32.70	15.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	33.00	42.15	42.15	42.15
WEIGHTED AVERAGE FOR THE SECOND QUARTER				33.00	42.15	42.15	42.15
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	180.00	43.19	43.19	43.19
2670403-065		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231		US40_FLOYD HILL ROUNDABOUTS	09/15/22	9.00	40.00	117.10	100.00
		I-70 SALT WASH BRIDGES SCOUR	09/29/22	218.00	50.00	29.15	19.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				407.00	46.77	36.77	31.49
STAM420-001 BR2854-148		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	110.00	20.00	51.87	14.81
STM0091-046		INTERSECTION OF US 285 & SH 9					
IM025A-050		ADA RAMP IMPROVEMENTS - FAIRP					
		I25-MP103.9 - INTERSECTION DR	12/01/22	141.00	40.00	37.33	22.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				251.00	31.24	44.74	18.85
WEIGHTED AVERAGE FOR THE YEAR				900.00	40.69	36.85	24.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 11

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00030 Rem Water Service Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	2000.00	4193.39	4000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	2000.00	4193.39	4000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2000.00	4193.39	4000.00
===== 202-00031 Rem of Fire Hydrant Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		4.00	1800.00	347.12	300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	1800.00	347.12	300.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1800.00	347.12	300.00
===== 202-00032 Rem Valve Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		26.00	300.00	282.76	300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			26.00	300.00	282.76	300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	1923.59	800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1000.00	1923.59	800.00
	WEIGHTED AVERAGE FOR THE YEAR			28.00	350.00	452.50	335.71
===== 202-00033 Rem Pipe Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	9.00	1200.00	1627.80	1211.52
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	1200.00	1627.80	1211.52
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	4000.00	2676.61	1430.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	4000.00	2676.61	1430.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	1900.00	1890.00	1266.14

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 12

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00035 Rem Pipe Lin Foot =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	559.00	35.00	83.73	85.00
NHPP1601-083			02/03/22	109.00	75.00	429.49	300.00
NHPP0063-063			02/24/22	617.00	35.00	30.40	26.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	782.00	29.00	41.09	28.00
C0761-239							
NHM765-007			03/31/22	276.00	30.00	54.47	49.62
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,343.00	34.27	58.89	56.27
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	296.00	38.30	38.30	38.30
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	231.00	30.00	56.88	96.59
STA0712-019	SH 71: Frieight Improvements		05/12/22	337.00	35.00	42.81	42.81
WEIGHTED AVERAGE FOR THE SECOND QUARTER				864.00	34.79	51.81	55.64
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	493.00	50.86	50.86	50.86
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	33.00	75.00	118.22	28.32
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	15,727.00	30.00	25.75	28.00
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	96.00	59.49	28.97	28.97
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
2670403-065	US40 FLOYD HILL ROUNDABOUTS		09/15/22	112.00	55.00	41.23	30.00
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	289.00	30.00	45.38	41.73
WEIGHTED AVERAGE FOR THE THIRD QUARTER				16,750.00	31.04	27.54	28.93
C170A-002	CRITICAL CULVERT CONST. PKG D		10/27/22	83.00	75.00	205.38	112.50
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	320.00	30.00	44.87	28.00
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	42.00	65.00	52.00	52.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	293.00	60.00	137.69	63.00
C5502-097	US550 MP 117.28-126.06		11/17/22	3,329.00	40.00	16.47	11.50
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	867.00	30.00	49.07	75.00
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	361.00	40.00	49.00	32.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	83.00	40.00	77.18	65.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C		12/22/22	40.00	60.00	84.22	53.49

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 13

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00035							
		Rem Pipe		Lin Foot			
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	135.00	50.00	55.86	45.31
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	95.00	10.00	80.40	100.00
STA385A-016		SH 385 MP 97.76	12/22/22	160.00	20.00	100.00	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,808.00	38.97	42.98	33.24
		WEIGHTED AVERAGE FOR THE YEAR		25,765.00	33.25	38.20	33.28
===== 202-00036							
		Rem of Pipe (Spec)		Lin Foot			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	168.00	524.82	524.82	524.82
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		168.00	524.82	524.82	524.82
===== 202-00037							
		Rem of End Section		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5.00	430.00	709.42	800.00
NHPP1601-083			02/03/22	8.00	500.00	1175.29	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	500.00	424.36	600.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	476.67	760.17	560.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	698.96	698.96	698.96
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19.00	515.00	474.77	330.87
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	360.00	883.33	650.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	532.03	506.66	415.29
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	912.77	912.77	912.77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	202-00037	Rem of End Section		Each	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3.00	600.00	78.25	68.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4.00	800.00	471.63	240.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	700.00	815.92	481.00
				<hr/>			
WEIGHTED AVERAGE FOR THE THIRD QUARTER				11.00	767.12	509.73	398.48
<hr/>							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	600.00	684.83	300.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	19.00	500.00	550.00	550.00
C5502-097		US550 MP 117.28-126.06	11/17/22	10.00	700.00	643.36	125.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	443.10	682.63	842.47
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	800.00	583.73	440.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	350.00	1366.67	300.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	600.00	1019.90	2100.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	600.00	1431.85	551.26
				<hr/>			
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				47.00	583.46	761.96	520.89
				<hr/>			
WEIGHTED AVERAGE FOR THE YEAR				98.00	574.61	663.08	486.89
<hr/>							
=====	202-00040	Rem Elec Conduit		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	202.00	10.00	51.56	58.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	100.00	16.00	52.11	12.00
C0761-239							
				<hr/>			
WEIGHTED AVERAGE FOR THE FIRST QUARTER				302.00	11.99	51.80	42.77
<hr/>							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	335.00	15.00	7.82	9.16
				<hr/>			
WEIGHTED AVERAGE FOR THE SECOND QUARTER				335.00	15.00	7.82	9.16
<hr/>							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	483.00	39.00	12.76	12.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,878.00	25.00	8.70	11.73
BR2854-148		INTERSECTION OF US 285 & SH 9					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 15

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00040		Rem Elec Conduit		Lin Foot	=====		
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,361.00	27.86	10.08	11.79
	WEIGHTED AVERAGE FOR THE YEAR			2,998.00	24.83	14.75	14.61
===== 202-00055		Rem of FO Cable		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT 01/13/22		4,775.00	5.00	2.88	3.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,775.00	5.00	2.88	3.00
2670703-479		I-70 BRIDGE OVER HARLAN 05/05/22		335.00	3.00	1.17	1.31
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			335.00	3.00	1.17	1.31
2670703-497		I-70_GENESEE WILDLIFE XING 09/15/22		3,452.00	4.40	3.32	2.95
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,452.00	4.40	3.32	2.95
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		1,771.00	8.00	2.54	1.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		451.00	11.30	5.01	3.57
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD- 12/01/22		2,600.00	3.50	2.84	2.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,822.00	5.88	2.83	2.28
	WEIGHTED AVERAGE FOR THE YEAR			13,384.00	5.11	2.95	2.69
===== 202-00070		Rem Barricade		Each	=====		
MPR200-280		PUEBLO AREA 11/17/22		1.00	750.00	700.00	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	750.00	700.00	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	750.00	700.00	1200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00080 Rem Guard Post Each =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	4.00	200.00	581.19	280.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	200.00	581.19	280.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	200.00	581.19	280.00
===== 202-00090 Rem Delineator Each =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	15.00	15.00	24.73	10.00
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	189.00	2.00	12.08	10.00
NHPP1601-083			02/03/22	256.00	8.00	23.18	10.00
STR0141-031			02/17/22	253.00	10.00	9.67	9.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	350.00	10.00	9.31	10.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	34.00	10.00	16.50	20.00
C0761-239							
NHPP0703-472			03/10/22	375.00	8.00	13.70	14.00
STR092A-031			03/17/22	938.00	6.00	9.00	9.00
NHM765-007			03/31/22	22.00	9.00	33.29	29.64
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,432.00	7.34	12.83	10.44
NH0504-911			04/07/22	698.00	8.00	7.00	6.00
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	34.00	10.00	60.00	25.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	273.00	5.00	7.99	19.67
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	208.00	9.00	12.30	10.50
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	10.00	10.00	27.33	12.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	384.00	9.00	10.88	12.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	23.00	12.00	18.13	18.13
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,630.00	7.97	10.12	10.88
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	80.00	10.70	10.70	10.70
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	48.00	10.50	95.00	85.00
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	2.00	30.00	26.95	15.85
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	23.00	20.00	12.09	13.00
2670703-497	I-70 GENESEE WILDLIFE XING		09/15/22	14.00	20.00	48.44	4.54
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	50.00	10.00	23.63	20.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			217.00	12.26	35.14	29.17

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00090		Rem Delineator		Each =====			
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	30.00	44.73	16.20
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	78.00	12.00	10.00	10.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	240.00	8.00	5.33	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	415.00	10.00	9.77	6.30
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	7.00	12.00	37.31	17.92
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	298.00	12.00	12.97	13.25
C5502-097		US550 MP 117.28-126.06	11/17/22	350.00	15.00	8.24	5.40
MPR200-280		PUEBLO AREA	11/17/22	20.00	28.00	13.50	25.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	12.00	42.75	10.50
STA0711-021		SH71: REGION LINE NORTH	12/01/22	364.00	8.60	5.58	6.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4,914.00	10.00	13.25	20.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	20.00	41.13	55.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	8.00	34.00	28.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	15.00	9.00	11.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	177.00	9.25	19.50	14.99
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	26.00	15.00	23.55	5.25
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	3.00	75.00	110.13	27.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	91.00	10.00	25.90	20.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	16.00	20.00	30.99	14.24
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	232.00	12.00	22.01	37.34
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	21.00	10.00	25.07	40.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	15.00	25.53	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	566.00	8.10	19.67	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,022.00	10.31	14.38	16.19
		WEIGHTED AVERAGE FOR THE YEAR		12,301.00	9.45	13.95	14.62
===== 202-00150		Rem Wall		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	500.00	3661.66	3411.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	500.00	3661.66	3411.36
		WEIGHTED AVERAGE FOR THE YEAR		6.00	500.00	3661.66	3411.36
===== 202-00155		Rem Wall		Lin Foot =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	222.00	80.00	53.71	79.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	350.00	58.00	58.50	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00155	Rem Wall		Lin Foot	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	180.00	270.00	193.98	104.27
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	31.00	50.00	186.67	180.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	48.00	95.00	135.33	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		831.00	111.64	109.01	66.71
		WEIGHTED AVERAGE FOR THE YEAR		831.00	111.64	109.01	66.71
=====	202-00160	Rem Wall		Sq Foot	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	226.00	45.00	31.16	21.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		226.00	45.00	31.16	21.00
		WEIGHTED AVERAGE FOR THE YEAR		226.00	45.00	31.16	21.00
=====	202-00170	Grinding And Texturing Conc Pvmt		Sq Yard	=====	=====	=====
C0762-055			02/17/22	133,975.00	4.50	4.68	4.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		133,975.00	4.50	4.68	4.25
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	101,079.00	5.50	5.60	4.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101,079.00	5.50	5.60	4.80
		WEIGHTED AVERAGE FOR THE YEAR		235,054.00	4.93	4.93	4.49
=====	202-00172	Diamond Grinding Concrete Pavement		Sq Yard	=====	=====	=====
STA0252-459			02/03/22	60,000.00	5.50	7.95	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60,000.00	5.50	7.95	5.00
		WEIGHTED AVERAGE FOR THE YEAR		60,000.00	5.50	7.95	5.00
=====	202-00190	Rem of Conc Median Cover Matl		Sq Yard	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	64.00	20.00	81.33	92.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 19

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00190							
		Rem of Conc Median Cover Matl		Sq Yard			
NHPP0063-063			02/24/22	1,756.00	10.00	7.68	9.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	15.00	16.64	14.00
C0761-239							
NHM765-007			03/31/22	3,438.00	10.00	9.85	2.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,458.00	10.30	11.51	6.19
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	561.00	35.00	21.61	13.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		561.00	35.00	21.61	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	484.00	20.00	16.58	14.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,164.00	9.00	20.62	18.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,648.00	12.23	20.12	16.83
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	158.00	35.00	22.53	10.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	28.00	65.00	54.49	44.97
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	488.00	15.00	24.69	20.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		674.00	21.77	24.36	19.06
		WEIGHTED AVERAGE FOR THE YEAR		8,341.00	13.27	15.96	9.79
===== 202-00195							
		Rem of Median Cover		Sq Yard			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	32.00	14.00	52.20	44.92
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32.00	14.00	52.20	44.92
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	36.00	18.00	21.69	21.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	18.00	21.69	21.69
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	444.00	44.00	40.00	42.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		444.00	44.00	40.00	42.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00195 Rem of Median Cover Sq Yard =====							
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	22.00	40.00	45.80	50.10
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			22.00	40.00	45.80	50.10
	WEIGHTED AVERAGE FOR THE YEAR			534.00	40.28	41.06	41.14
===== 202-00200 Rem Sidewalk Sq Yard =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	904.00	36.00	47.08	44.92
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	707.00	50.00	24.13	16.00
NHPP0063-063			02/24/22	238.00	30.00	16.73	25.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	131.00	30.00	16.23	11.00
C0761-239							
CR100-362			03/14/22	3,974.00	79.84	79.84	79.84
STR092A-031			03/17/22	607.00	30.00	15.00	15.00
NHM765-007			03/31/22	295.00	20.00	49.99	4.83
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,856.00	61.31	46.05	56.47
NH0504-911			04/07/22	694.00	31.00	29.95	19.90
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,371.00	30.00	24.18	19.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	408.00	26.00	24.11	11.50
CM760-047		COLFAX AND QUAIL	05/12/22	52.00	35.50	40.60	40.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,480.00	30.00	43.37	43.37
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4,005.00	29.84	28.36	27.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,165.00	15.00	17.83	16.50
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	625.00	50.00	39.00	38.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	267.00	40.00	23.39	23.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,057.00	28.88	24.98	23.88
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	122.00	30.00	43.12	43.35

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00200							
		Rem Sidewalk		Sq Yard			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	150.60	30.00	61.13	39.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	539.00	26.80	20.44	12.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	440.00	60.00	60.00	60.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,097.00	50.00	24.17	13.00
C5502-097		US550 MP 117.28-126.06	11/17/22	53.00	100.00	30.27	15.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	621.00	33.00	33.24	48.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	218.00	60.00	18.62	20.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	378.00	25.00	22.67	12.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	150.10	50.00	28.74	5.63
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	266.00	32.00	38.49	44.97
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	341.00	25.00	23.86	20.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5,375.70	42.18	26.99	24.40
WEIGHTED AVERAGE FOR THE YEAR				18,293.70	45.15	32.79	37.07
===== 202-00201							
		Rem Curb		Lin Foot			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	93.00	10.00	17.60	14.97
C0762-055			02/17/22	4,648.00	5.00	3.61	0.26
NHPP0063-063			02/24/22	18,887.00	6.00	7.33	6.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	271.00	11.00	9.30	6.50
C0761-239							
BRC040-057			03/17/22	120.00	15.00	36.00	23.00
NHM765-007			03/31/22	199.00	12.00	15.04	7.02
WEIGHTED AVERAGE FOR THE FIRST QUARTER				24,218.00	5.97	6.62	5.03
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	59.00	22.00	16.49	13.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	86.00	25.00	14.04	14.16
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	299.00	10.00	14.46	14.46
WEIGHTED AVERAGE FOR THE SECOND QUARTER				444.00	14.50	14.60	14.21
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1,783.00	12.63	10.50	5.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,060.00	7.00	7.51	8.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				5,843.00	8.72	8.05	7.08

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 22

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00201 Rem Curb Lin Foot =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	59.00	9.74	112.44	79.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	530.00	25.90	7.90	7.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	27.00	24.49	24.98
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			595.00	24.31	16.49	14.97
	WEIGHTED AVERAGE FOR THE YEAR			31,100.00	6.96	7.46	5.74
===== 202-00202 Rem Gutter Lin Foot =====							
NHPP0063-063			02/24/22	36.00	25.00	30.18	54.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	119.00	16.00	11.02	7.00
C0761-239							
NHM765-007			03/31/22	129.00	15.00	17.52	7.02
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			284.00	16.69	13.78	12.97
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	20.00	14.46	14.46
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			55.00	20.00	14.46	14.46
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	312.00	16.00	8.62	7.25
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			312.00	16.00	8.62	7.25
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	158.00	20.00	17.00	8.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			158.00	20.00	17.00	8.50
	WEIGHTED AVERAGE FOR THE YEAR			809.00	17.29	13.13	9.99
===== 202-00203 Rem Curb and Gutter Lin Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	257.00	14.00	23.47	14.97

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 23

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00203							
		Rem Curb and Gutter		Lin Foot			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,040.00	15.00	8.61	7.00
NHPP0063-063			02/24/22	15,008.00	6.00	8.33	8.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	13.00	9.37	7.00
C0761-239							
CR100-362			03/14/22	4,715.00	29.64	29.64	29.64
BRC040-057			03/17/22	120.00	15.00	35.00	34.00
STR092A-031			03/17/22	845.00	12.00	15.00	15.00
NHM765-007			03/31/22	17,689.00	8.00	5.68	1.25
WEIGHTED AVERAGE FOR THE FIRST QUARTER				41,874.00	10.39	8.32	7.77
NH0504-911			04/07/22	2,720.00	10.00	12.50	11.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,307.00	20.00	17.38	15.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,583.00	14.00	10.09	15.25
CM760-047		COLFAX AND QUAIL	05/12/22	103.00	18.00	17.40	19.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,415.00	20.00	14.46	14.46
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8,128.00	15.46	13.18	13.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4,015.00	18.00	7.57	8.75
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1,440.00	25.00	18.00	18.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,741.00	15.00	10.78	11.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				9,196.00	17.88	10.63	11.11
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	532.00	20.00	15.13	12.40
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	422.00	15.00	30.40	15.60
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,013.00	18.00	11.82	14.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	760.00	40.00	34.00	34.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,140.00	13.00	10.61	6.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,182.00	20.00	17.63	6.50
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	194.00	25.00	25.60	24.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,118.00	15.00	23.00	28.98
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	785.00	21.50	11.86	14.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	902.00	20.00	11.33	3.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	123.80	30.00	12.02	2.61
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	563.00	28.00	24.49	24.98

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 24

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00203	Rem Curb and Gutter		Lin Foot	=====	=====	=====
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	72.00	20.00	25.69	31.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,096.00	15.00	11.93	10.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9,902.80	19.99	15.54	14.84
	WEIGHTED AVERAGE FOR THE YEAR			69,100.80	13.36	10.63	9.92
=====	202-00204	Rem C, G and Sidewalk		Lin Foot	=====	=====	=====
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	155.00	35.00	37.66	19.71
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			155.00	35.00	37.66	19.71
	WEIGHTED AVERAGE FOR THE YEAR			155.00	35.00	37.66	19.71
=====	202-00206	Rem Conc Curb Ramp		Sq Yard	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1,489.00	36.00	48.01	44.92
NHM765-007			03/31/22	321.00	20.00	29.53	9.14
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,810.00	33.16	45.44	38.57
NH0504-911			04/07/22	306.00	42.00	35.00	30.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,582.00	32.00	23.86	18.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	31.00	40.00	64.54	102.51
CM760-047		COLFAX AND QUAIL	05/12/22	24.00	35.00	44.40	43.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,943.00	33.15	25.81	20.34
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	534.00	50.00	41.00	42.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			534.00	50.00	41.00	42.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	31.00	60.00	47.43	43.30
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	374.00	25.00	42.69	36.75

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00206							
		Rem Conc Curb Ramp		Sq Yard			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	88.00	50.00	35.09	30.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	751.00	45.00	34.00	34.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	603.00	32.26	44.35	46.74
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	156.70	65.00	28.81	5.99
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,003.70	39.45	40.04	36.12
		WEIGHTED AVERAGE FOR THE YEAR		7,290.70	36.12	36.30	30.79
===== 202-00207							
		Rem of Brick Pavers		Sq Yard			
CM760-047		COLFAX AND QUAIL	05/12/22	2.00	29.00	88.00	63.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	29.00	88.00	63.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	29.00	88.00	63.00
===== 202-00210							
		Rem Conc Pavement		Sq Yard			
STA0252-459			02/03/22	1,606.00	26.00	139.33	146.00
NHPP0063-063			02/24/22	237.00	40.00	18.35	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	38,581.00	21.00	9.37	7.00
C0761-239							
CR100-362			03/14/22	20.00	95.34	95.34	95.34
STR092A-031			03/17/22	46.00	40.00	25.00	25.00
NHM765-007			03/31/22	722.00	20.00	12.44	5.21
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		41,212.00	21.34	11.39	12.55
NH0504-911			04/07/22	1,139.00	16.00	29.95	9.90
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	49.00	50.00	34.80	18.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,015.00	16.00	18.42	15.00
CM760-047		COLFAX AND QUAIL	05/12/22	87.00	45.00	51.90	53.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	136.00	30.00	21.69	21.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,426.00	17.12	20.04	14.73
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	175.00	25.00	30.79	19.25

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 26

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00210 Rem Conc Pavement Sq Yard =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	298.00	60.00	48.00	46.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,693.00	40.00	27.10	19.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4,166.00	40.80	27.70	20.94
===== 202-00212 Rem Conc Pavement (Spec) Sq Yard =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	36.00	20.00	300.75	75.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,519.00	35.00	27.74	20.00
C5502-097		US550 MP 117.28-126.06	11/17/22	163.00	50.00	43.77	39.30
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	70.00	21.00	158.23	338.81
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,839.00	20.00	18.75	25.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	216.00	25.00	30.67	22.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	73.00	120.00	100.76	88.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				6,916.00	29.56	27.15	26.80
WEIGHTED AVERAGE FOR THE YEAR				57,720.00	23.34	14.57	15.07
===== 202-00215 Rem Conc Pvmt (Planing) Sq Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	86.00	50.00	577.61	221.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				86.00	50.00	577.61	221.00
WEIGHTED AVERAGE FOR THE YEAR				86.00	50.00	577.61	221.00
===== 202-00217 Rem Conc Pvmt (Planing) (Spec) Sq Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,000.00	22.00	61.42	65.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,000.00	22.00	61.42	65.00
WEIGHTED AVERAGE FOR THE YEAR				1,000.00	22.00	61.42	65.00
===== 202-00217 Rem Conc Pvmt (Planing) (Spec) Sq Yard =====							
BRC040-057			03/17/22	2,329.00	25.00	49.00	18.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,329.00	25.00	49.00	18.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 27

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00217 Rem Conc Pvmt (Planing) (Spec) Sq Yard =====							
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2,827.00	45.00	49.25	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,827.00	45.00	49.25	25.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,417.00	50.00	69.49	76.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4,480.00	45.00	29.35	4.70
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,897.00	47.16	53.59	35.55
		WEIGHTED AVERAGE FOR THE YEAR		13,053.00	42.74	51.47	30.13
===== 202-00220 Rem Asphalt Mat Sq Yard =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	33.00	12.00	92.63	200.37
STR0505-050			01/13/22	16.00	100.00	275.00	250.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	7,067.00	10.00	7.13	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,256.00	20.00	34.57	38.00
NHPP1601-083			02/03/22	5,163.00	10.00	10.27	11.00
STA0252-459			02/03/22	10.00	6.71	92.52	82.50
STR0141-031			02/17/22	400.00	8.00	19.83	19.00
NHPP0063-063			02/24/22	13,248.00	6.00	7.68	8.50
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	69,358.00	11.00	5.68	4.50
C0761-239							
NHPP0703-472			03/10/22	100.00	7.00	77.76	145.00
CR100-362			03/14/22	50.00	85.71	85.71	85.71
ER007A-035			03/15/22	1,216.00	11.95	12.78	12.78
STR092A-031			03/17/22	13,999.00	10.00	8.00	8.00
NHM765-007			03/31/22	32,352.00	12.00	13.61	6.03
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		145,268.00	10.76	7.49	6.63
NH0504-911			04/07/22	250.00	3.00	49.10	48.20
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,145.00	32.00	23.57	13.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,759.00	4.56	4.56	4.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	78,045.00	7.00	4.78	3.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,029.00	8.00	10.97	6.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00220							
		Rem Asphalt Mat		Sq Yard			
STA0712-019		SH 71: Frieght Improvements	05/12/22	12,775.00	8.00	14.07	14.07
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,088.00	8.00	39.33	28.00
CM760-047		COLFAX AND QUAIL	05/12/22	128.00	28.50	42.60	48.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	119.00	13.00	27.67	25.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,526.00	10.00	239.80	239.80
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14,511.00	9.00	7.79	4.90
WEIGHTED AVERAGE FOR THE SECOND QUARTER				118,375.00	7.63	6.93	8.65
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10,997.00	9.60	9.60	9.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	80.00	50.00	70.04	25.74
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	21,375.00	6.00	12.79	9.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	452.00	50.00	48.50	37.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,650.00	9.28	27.35	27.35
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	10,696.00	10.00	14.31	9.50
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	4,395.00	12.00	11.08	9.22
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2,160.00	20.00	14.63	4.85
WEIGHTED AVERAGE FOR THE THIRD QUARTER				51,805.00	9.24	13.20	9.93
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2,765.00	35.00	15.30	9.90
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	299.00	20.00	32.06	20.25
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	164.00	70.00	62.97	6.88
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,703.00	8.25	9.04	3.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	19,013.00	8.00	4.50	4.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	492.00	26.00	31.20	50.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	18,773.00	10.00	10.96	10.50
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	644.00	11.00	38.78	17.33
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,318.00	30.00	10.53	9.75
C5502-097		US550 MP 117.28-126.06	11/17/22	20,464.00	10.00	14.19	19.30
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6,283.00	6.00	13.10	19.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	29,832.00	3.00	5.97	2.12
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12,084.00	10.00	16.25	22.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,944.00	10.00	10.04	9.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	9,192.00	8.00	10.00	7.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	427.50	75.00	45.80	55.67
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,405.00	9.00	15.40	7.90
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	418.00	50.00	42.04	23.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00220							
		Rem Asphalt Mat		Sq Yard			
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,089.00	10.00	12.98	14.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3,916.00	10.00	8.86	22.16
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	6,909.00	6.00	9.07	1.95
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4,352.00	21.00	12.00	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	11,268.00	5.00	10.81	6.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		165,754.50	8.92	10.63	10.42
		WEIGHTED AVERAGE FOR THE YEAR		481,202.50	9.19	8.66	8.84
===== 202-00222							
		Removal of Detour Pavement		Sq Yard			
NH0504-911			04/07/22	1,440.00	5.21	7.45	8.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,440.00	5.21	7.45	8.90
STU0252-457							
		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,470.00	20.00	15.33	27.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,470.00	20.00	15.33	27.00
		WEIGHTED AVERAGE FOR THE YEAR		2,910.00	12.68	12.22	18.04
===== 202-00226							
		Rem of Asph Mat (Special)		Sq Yard			
NHM765-007			03/31/22	15,032.00	20.00	9.98	8.73
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15,032.00	20.00	9.98	8.73
STA001A-005							
		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	5.00	50.00	502.00	230.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	50.00	502.00	230.00
		WEIGHTED AVERAGE FOR THE YEAR		15,037.00	20.01	10.57	9.04
===== 202-00240							
		Rem Asphalt Mat (Planing)		Sq Yard			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	79,039.00	2.60	4.84	3.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240		Rem Asphalt Mat (Planing)		Sq Yard			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	89,107.00	3.00	3.91	2.50
NHPP1601-083			02/03/22	1,795.00	5.00	17.29	12.00
C0762-055			02/17/22	126,303.00	2.00	1.93	1.50
STR0141-031			02/17/22	33,569.00	5.00	4.27	3.30
NHPP0063-063			02/24/22	122,804.00	2.50	3.85	2.45
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	9,160.00	4.57	5.85	7.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	14,018.00	7.50	4.79	3.50
C0761-239							
NHPP0703-472			03/10/22	324,332.00	2.40	2.36	2.25
ER007A-035			03/15/22	257,206.00	1.76	2.02	2.02
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	411,619.00	2.00	2.83	2.66
STR R500-171		Various locations on SH 141 a	03/17/22	1,734.00	14.00	12.33	9.00
STR092A-031			03/17/22	25,696.00	4.00	3.25	3.25
NHM765-007			03/31/22	190.00	10.00	34.71	23.53
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,496,572.00	2.37	2.99	2.45
NH0504-911			04/07/22	627,069.00	3.00	2.51	1.76
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8,654.00	7.00	4.51	4.08
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6,204.00	3.00	5.48	4.10
STA0712-019		SH 71: Frieght Improvements	05/12/22	45,074.00	3.50	3.05	3.05
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	24,391.00	6.50	2.48	3.25
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,616.00	2.00	7.33	5.00
CM760-047		COLFAX AND QUAIL	05/12/22	282.00	6.50	23.80	16.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	201,873.00	3.50	2.13	3.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	164,244.00	6.00	3.81	3.81
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	5,594.00	7.50	3.47	2.40
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,085,001.00	3.70	2.68	2.43
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4,769.00	2.71	2.71	2.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	297.00	25.00	27.28	17.85
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	472.00	3.00	27.67	24.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,530.00	8.00	6.40	7.25
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	10,540.00	4.81	6.53	6.53
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	807.00	25.00	12.36	19.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	18,517.00	3.60	4.36	2.55
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	12,160.00	6.50	4.08	3.80
WEIGHTED AVERAGE FOR THE THIRD QUARTER				53,092.00	5.32	4.74	4.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240		Rem Asphalt Mat (Planing)		Sq Yard	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	12,571.00	8.08	5.80	4.80
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	38,057.00	6.00	4.20	3.60
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	166,058.00	2.80	1.78	1.78
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	850.00	4.00	10.00	5.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,777.00	10.00	5.05	7.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	4,090.00	3.00	7.03	6.09
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5,357.00	4.00	14.00	8.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	42,890.00	3.20	3.36	2.05
C5502-097		US550 MP 117.28-126.06	11/17/22	103,148.00	3.00	2.51	2.15
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	8.00	25.00	272.50	295.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10,007.00	3.00	4.60	1.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2,319.00	4.60	6.95	7.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	8,939.00	5.00	11.50	9.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9,524.00	2.50	4.50	6.20
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,492.00	3.00	6.03	3.60
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,689.00	8.00	13.05	17.10
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	6,966.00	8.00	8.36	6.71
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	87,921.90	4.00	3.77	2.65
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	136,176.00	2.00	2.94	1.97
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,141.00	10.00	6.82	5.60
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	133,972.00	3.50	3.59	2.67
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	22,531.00	4.00	3.14	5.59
STR0092-024		SH 9 North of Silverthorne	12/22/22	29,688.00	5.00	5.88	7.45
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	113,135.00	3.00	3.25	2.76
STA385A-016		SH 385 MP 97.76	12/22/22	922.00	10.00	20.06	10.24
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	5,612.00	7.40	8.00	7.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				951,840.90	3.42	3.41	2.75
WEIGHTED AVERAGE FOR THE YEAR				3,586,505.90	3.09	3.12	2.57
===== 202-00246		Rem Asphalt Mat (Planing)(Special)		Sq Yard	=====		
NHPP1601-083			02/03/22	5.00	25.00	2713.40	2100.00
C0762-055			02/17/22	1,880.00	20.00	11.09	9.50
BRC040-057			03/17/22	1,189.00	12.00	19.50	9.00
STR R500-171		Various locations on SH 141 a	03/17/22	955.00	46.00	26.51	10.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,029.00	23.81	18.43	12.07
NH0504-911			04/07/22	4,113.00	15.00	6.45	7.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00246							
STM1151-038	Rem Asphalt Mat (Planing) (Special)	SH115 MP 27 TO MP 38	04/21/22	Sq Yard 314.00	32.00	30.22	33.38
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,427.00	16.21	10.26	9.71
STA0711-021	SH71: REGION LINE NORTH		12/01/22	386.00	14.00	60.17	40.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3		12/01/22	539.00	35.00	43.00	22.00
STR109A-019	M-22-AY BRIDGE REHAB ON SH109		12/01/22	4,693.00	30.00	35.53	36.06
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5,618.00	29.38	29.96	30.97
WEIGHTED AVERAGE FOR THE YEAR				14,074.00	23.64	21.25	19.97
===== 202-00250							
Rem Pavement Marking				Sq Foot			
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	20,000.00	0.60	1.51	0.74
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	2,200.00	5.00	3.81	3.33
MTCER400-391	VARIOUS HIGHWAY SEGMENTS ACRO		01/13/22	481,308.00	0.60	0.55	0.30
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	106,264.00	1.50	0.87	0.75
STA0252-459			02/03/22	15,000.00	4.00	1.53	1.25
C0762-055			02/17/22	59,529.00	1.50	1.46	1.25
STR0141-031			02/17/22	82,991.00	1.50	0.44	0.37
STR133A-051			02/17/22	98,627.00	1.00	0.74	0.90
NHPP0063-063			02/24/22	10,182.00	1.50	6.68	7.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	300.00	3.00	6.03	6.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	30,000.00	1.00	1.50	1.50
C0761-239							
NHPP0703-472			03/10/22	60,000.00	0.60	0.74	0.55
CR100-362			03/14/22	1,000.00	5.35	5.35	5.35
ER007A-035			03/15/22	2,000.00	2.30	2.45	2.45
STR R500-171	Various locations on SH 141 a		03/17/22	1,800.00	4.35	4.42	5.00
STR092A-031			03/17/22	74,326.00	1.00	0.85	0.85
NHM765-007			03/31/22	46,550.00	2.00	1.12	0.74
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,092,077.00	1.02	0.82	0.67
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	1,710.00	6.00	3.10	2.75
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	11,334.00	2.14	2.14	2.14
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	1,000.00	0.70	2.66	2.60
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	80,000.00	0.75	0.41	0.01
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	104,292.00	1.00	1.23	1.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00250	Rem Pavement Marking		Sq Foot	=====	=====	=====
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	25.00	5.00	46.33	10.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	43,530.00	1.00	0.65	0.65
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	5,111,908.00	0.36	0.36	0.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,353,799.00	0.39	0.41	0.38
MT CER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	1,093,411.00	0.35	0.59	0.43
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	11,300.00	4.00	4.17	3.75
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,000.00	2.14	2.14	2.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	510.00	6.50	6.86	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16,527.00	4.00	1.34	1.07
MT CER400-396		REGION 4	08/25/22	810,078.00	0.49	0.33	0.35
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7,074.00	3.00	4.00	3.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,500.00	2.75	3.09	3.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	22,488.00	2.75	1.77	1.70
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	10,000.00	3.50	2.13	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,976,888.00	0.52	0.57	0.46
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	92,800.00	1.00	0.68	0.60
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	38,775.00	1.00	0.83	1.20
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	5,460.00	3.00	3.02	4.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8,390.00	2.50	3.10	1.40
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	143.00	8.00	17.36	19.44
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10,214.00	1.00	3.50	1.25
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	5,199.00	2.20	2.48	1.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	15,000.00	0.60	2.28	2.20
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	5,000.00	0.43	3.80	2.39
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	71,148.00	1.00	0.50	0.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	24,049.00	1.25	1.11	0.65
C5502-097		US550 MP 117.28-126.06	11/17/22	44,490.00	2.50	1.73	1.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	23,132.00	1.00	2.40	3.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	63,822.00	0.85	0.75	0.80
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	185,596.00	2.00	0.60	0.70
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,500.00	2.80	1.70	1.10
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	31,263.00	1.00	2.50	2.25
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,557.00	2.00	4.27	1.30
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	71,887.00	1.00	0.63	0.60
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8,000.00	1.50	2.19	2.46

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00250							
		Rem Pavement Marking		Sq Foot			
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	178,423.00	1.00	0.60	0.52
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	30,000.00	1.25	0.88	1.06
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10,612.00	2.00	2.20	1.65
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	750.00	7.50	6.36	5.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	52,738.00	1.00	0.87	0.77
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	512.00	10.00	7.04	7.05
STR0092-024		SH 9 North of Silverthorne	12/22/22	153,956.00	1.00	0.55	0.50
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	22,999.00	1.30	1.37	0.62
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	700.00	3.00	12.62	12.00
STA385A-016		SH 385 MP 97.76	12/22/22	4,900.00	3.00	2.32	5.56
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,167,015.00	1.28	1.00	0.85
		WEIGHTED AVERAGE FOR THE YEAR		9,589,779.00	0.60	0.66	0.49
===== 202-00251							
		Rem Pvmt Marking (Asph Grooving)		Sq Foot			
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	1,146,863.00	0.50	0.44	0.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,146,863.00	0.50	0.44	0.37
STR090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	7,307.00	1.00	3.63	3.25
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	32.00	5.00	49.33	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,339.00	1.02	1.32	1.20
		WEIGHTED AVERAGE FOR THE YEAR		1,154,202.00	0.50	0.50	0.42
===== 202-00254							
		Rem of Pvmt Mkg (12 In)		Sq Foot			
STA0252-459			02/03/22	5,000.00	1.36	1.57	1.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,000.00	1.36	1.57	1.25
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5,000.00	1.30	1.76	2.81
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,000.00	1.30	1.76	2.81
		WEIGHTED AVERAGE FOR THE YEAR		10,000.00	1.33	1.64	2.03

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 35

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00300 Rem Bldg(s) LUMP SUM =====							
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	3000.00	24601.68	6500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	24601.68	6500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	24601.68	6500.00
===== 202-00400 Rem Bridge Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	50000.00	33552.98	18750.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	120000.00	126884.70	100000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	96666.67	95774.13	72916.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	114978.97	73870.94
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	100000.00	272648.49	185000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	100000.00	200980.52	129435.47
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	59697.04	55737.00	55737.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	59697.04	55737.00	55737.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	400000.00	344739.58	355000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	55000.00	307107.94	73875.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	230000.00	177916.56	294000.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	100000.00	150000.00	100000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	25000.00	90000.00	25000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	173333.33	210182.72	220267.91
	WEIGHTED AVERAGE FOR THE YEAR			14.00	122077.94	159253.99	145780.49

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 36

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00420 Rem Ped Rail Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	629.00	10.00	22.65	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			629.00	10.00	22.65	20.00
	WEIGHTED AVERAGE FOR THE YEAR			629.00	10.00	22.65	20.00
===== 202-00425 Rem Bridge Railing Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,751.00	29.00	27.17	16.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	29.00	40.00	147.12	125.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,780.00	29.18	30.27	17.78
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	617.00	24.98	41.80	46.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	920.00	24.00	27.07	27.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	18.00	250.00	23.60	25.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	150.00	24.00	22.10
STA0711-021		SH71: REGION LINE NORTH	12/01/22	248.00	36.00	33.50	30.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	147.00	25.00	125.00	130.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	30.00	136.74	110.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,376.00	30.78	63.46	51.79
	WEIGHTED AVERAGE FOR THE YEAR			4,156.00	30.09	44.92	37.22
===== 202-00450 Rem Port Present Str (1) Sq Yard =====							
BRC040-057			03/17/22	356.00	170.00	253.75	270.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			356.00	170.00	253.75	270.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	141.00	140.00	267.50	155.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			141.00	140.00	267.50	155.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	13.00	200.00	447.50	595.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13.00	200.00	286.25	174.39
	WEIGHTED AVERAGE FOR THE YEAR			510.00	162.47	268.15	213.91

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 37

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00453 Rem Port Present Str (2) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	354.00	350.00	624.52	582.00
C0762-055			02/17/22	56.00	400.00	616.30	630.00
BRC040-057			03/17/22	179.00	400.00	462.25	565.00
STR R500-171		Various locations on SH 141 a	03/17/22	76.00	380.00	436.21	463.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				665.00	371.10	569.73	567.87
NH0504-911			04/07/22	351.00	337.00	438.00	476.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	48.00	746.00	411.41	275.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				399.00	386.20	431.23	451.82
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	800.00	1088.32	505.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3.00	800.00	1088.32	505.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	439.00	375.00	274.22	231.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	43.00	330.00	508.33	550.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	216.00	600.00	445.00	550.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,916.00	325.00	325.06	328.11
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,614.00	356.20	338.23	327.09
WEIGHTED AVERAGE FOR THE YEAR				3,681.00	362.51	407.41	380.18
===== 202-00458 Rem Port Pres Str (Hydrodem) (Fast-Track) Sq Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,417.00	150.00	187.82	192.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				3,417.00	150.00	187.82	192.00
WEIGHTED AVERAGE FOR THE YEAR				3,417.00	150.00	187.82	192.00
===== 202-00460 Rem Port Present Str (3) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	71.00	700.00	1444.84	1820.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 38

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00460							
		Rem Port Present Str (3)		Sq Yard			
BRC040-057			03/17/22	10.00	900.00	1161.75	1000.00
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	685.00	1440.67	1775.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		101.00	716.83	1419.40	1729.90
NH0504-911			04/07/22	40.00	645.00	1740.00	2380.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	16.00	900.00	1155.57	800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		56.00	717.86	1447.78	1928.57
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	1800.00	2035.12	565.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	1800.00	2035.12	565.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	101.00	1100.00	440.07	385.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	12.00	800.00	1221.67	1200.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	12.00	1800.00	990.00	1160.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	238.00	500.00	554.05	330.10
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		363.00	719.83	671.90	459.88
		WEIGHTED AVERAGE FOR THE YEAR		523.00	725.24	894.22	777.40
===== 202-00495							
		Rem Port Present Str		LUMP SUM			
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1.00	3000.00	4801.89	3337.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	4801.89	3337.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	18377.13	18377.13	18377.13
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	10000.00	20871.21	3827.20
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	1.00	5000.00	4700.64	4700.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	11125.71	17138.28	8968.32

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00495 Rem Port Present Str LUMP SUM =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	13788.68	9000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	50000.00	53090.71	21610.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	75000.00	33439.70	15305.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	31062.86	21481.09	10142.00
===== 202-00500 Rem Port Present Str Each =====							
BRC040-057			03/17/22	34.00	400.00	333.50	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34.00	400.00	333.50	200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	5000.00	9833.33	10000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	5000.00	9833.33	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	655.56	734.90	744.44
===== 202-00502 Rem Port Present Str Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	1000.00	3722.92	2762.00
NHPP1601-083			02/03/22	8.00	5000.00	3255.09	1600.00
STR R500-171		Various locations on SH 141 a	03/17/22	12.00	1070.00	2635.94	1580.00
NHM765-007			03/31/22	1.00	3000.00	5188.32	11483.22
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	2583.64	3019.25	2091.15
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	4.00	8000.00	18660.94	3600.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	3000.00	2707.66	3100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	5857.14	14310.05	3385.71
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	5000.00	5145.00	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	202-00502	Rem Port Present Str		Cubic Yard	=====		
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	2000.00	5805.00	4310.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		17.00	2176.47	5766.18	4497.65
		WEIGHTED AVERAGE FOR THE YEAR		46.00	2931.30	5965.74	3177.50
=====							
=====	202-00503	Rem Port Present Str		Sq Yard	=====		
STA0252-459			02/03/22	42.00	320.00	874.67	387.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	55.00	800.00	365.99	230.00
C0761-239							
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	65.00	2000.00	4490.00	3280.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		162.00	1157.04	1228.37	1494.47
=====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	295.00	300.00	59.85	55.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	21.00	400.00	2875.00	3000.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	35.00	270.00	267.67	300.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11.00	150.00	923.33	520.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	584.00	1100.00	1096.74	868.47
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		946.00	793.23	677.69	637.03
		WEIGHTED AVERAGE FOR THE YEAR		1,108.00	846.43	808.54	762.40
=====							
=====	202-00504	Rem Exp Device		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	256.00	200.00	293.40	230.00
NHPP1601-083			02/03/22	68.00	500.00	518.14	400.00
C0762-055			02/17/22	100.00	250.00	372.90	475.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		424.00	259.91	327.74	315.05
=====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	154.00	170.00	197.26	125.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		154.00	170.00	197.26	125.00
=====							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	400.00	359.30	275.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		40.00	400.00	359.30	275.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00504 Rem Exp Device Lin Foot =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	203.00	315.00	133.52	124.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	552.00	250.00	99.00	88.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	60.00	225.00	439.58	654.15
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	252.00	220.00	55.67	60.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,067.00	253.88	118.12	122.51
WEIGHTED AVERAGE FOR THE YEAR				1,685.00	251.20	196.17	170.56
===== 202-00505 Rem Port of Present Structure Sq Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,413.00	95.00	85.54	57.00
BRC040-057			03/17/22	21.00	122.00	399.00	175.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,434.00	95.23	87.71	58.02
NH0504-911			04/07/22	205.00	122.00	398.75	297.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	410.00	180.00	123.87	75.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				615.00	160.67	169.68	149.17
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	255.00	185.00	124.07	97.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	60.00	150.00	240.33	260.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	169.00	180.00	206.67	220.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				484.00	178.92	162.67	161.47
WEIGHTED AVERAGE FOR THE YEAR				3,533.00	118.09	108.06	88.37
===== 202-00520 Rem of Exp Joint Matl Lin Foot =====							
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	330.00	58.67	67.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				80.00	330.00	58.67	67.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 42

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00520 Rem of Exp Joint Matl Lin Foot =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	350.00	738.00	800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		50.00	350.00	738.00	800.00
		WEIGHTED AVERAGE FOR THE YEAR		130.00	337.69	258.47	348.92
===== 202-00700 Rem Light Standard Each =====							
NHM765-007			03/31/22	27.00	500.00	1065.10	957.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	500.00	1065.10	957.60
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	800.00	2425.52	1840.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	800.00	2425.52	1840.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	250.00	438.75	450.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	2100.02	2100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	764.00	1512.50	1525.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	750.00	968.40	1466.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	1100.00	866.67	1300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		16.00	645.50	708.81	1100.90
		WEIGHTED AVERAGE FOR THE YEAR		47.00	575.06	994.71	1081.48
===== 202-00705 Rem Light Standard Foundation Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	13.00	900.00	2218.91	2900.00
NHPP0063-063			02/24/22	59.00	960.00	677.00	710.00
NHM765-007			03/31/22	27.00	250.00	1553.28	1396.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		99.00	758.48	1325.49	1184.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 43

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00705 Rem Light Standard Foundation Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	13.00	750.00	521.21	614.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			13.00	750.00	521.21	614.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	1000.00	4480.89	3800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	1000.00	4480.89	3800.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	350.00	698.56	700.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	850.00	1588.06	2541.23
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	1137.50	1466.67	1100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			14.00	717.86	1015.64	1360.31
	WEIGHTED AVERAGE FOR THE YEAR			130.00	760.69	1209.29	1229.11
===== 202-00710 Rem Power Pole Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4000.00	1660.58	1787.31
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	1660.58	1787.31
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	1660.58	1787.31
===== 202-00715 Rem CCTV Pole Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	750.00	3210.11	3783.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	750.00	3210.11	3783.49
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	550.00	736.15	770.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	550.00	736.15	770.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	616.67	1410.87	1774.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00720 Rem CCTV Camera Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	106.00	450.00	965.00	965.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		106.00	450.00	965.00	965.00
===== 202-00750 Rem Luminaire Each =====							
NHM765-007			03/31/22	54.00	200.00	221.90	199.50
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		54.00	200.00	221.90	199.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	7.00	100.00	421.39	365.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		7.00	100.00	421.39	365.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	500.00	276.22	276.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	130.00	258.74	390.96
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	400.00	156.84	150.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		7.00	260.00	225.41	305.69
	WEIGHTED AVERAGE FOR THE YEAR			68.00	195.88	236.02	227.47
===== 202-00800 Rem Overpass Mtd Sign Brkt Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	5000.00	105.45	120.44
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		11.00	5000.00	105.45	120.44
	WEIGHTED AVERAGE FOR THE YEAR			11.00	5000.00	105.45	120.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 45

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00805 Rem Overhead Sign Str Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	7000.00	17326.05	7500.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4.00	15000.00	16048.50	14347.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	12333.33	16900.20	12064.67
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	5000.00	5769.53	5978.96
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	5000.00	5769.53	5978.96
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	8000.00	9139.54	7680.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	8000.00	9139.54	7680.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	10000.00	12309.45	9970.59
===== 202-00810 Rem Ground Sign Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	300.00	1285.00	1285.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	100.00	171.58	210.84
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	74.00	150.00	132.93	110.00
MTCER300-262			02/03/22	483.00	125.00	206.67	120.00
C0762-055			02/17/22	104.00	150.00	124.13	155.00
STR0141-031			02/17/22	7.00	185.00	191.67	180.00
NHPP0063-063			02/24/22	27.00	120.00	165.00	172.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	132.00	100.00	75.33	80.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	32.00	120.00	167.25	100.00
C0761-239							
NHPP0703-472			03/10/22	14.00	120.00	187.06	150.00
ER007A-035			03/15/22	133.00	173.40	185.50	185.50
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	3.00	2000.00	3046.50	2088.00
NHM765-007			03/31/22	47.00	95.00	125.54	114.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,080.00	136.16	170.27	138.55
NH0504-911			04/07/22	14.00	75.00	134.75	119.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00810		Rem Ground Sign		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	158.00	105.00	80.91	75.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	18.00	105.00	122.98	134.84
STA0712-019		SH 71: Frieight Improvements	05/12/22	10.00	120.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	90.00	398.33	195.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	21.00	120.00	162.50	150.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	100.00	198.33	200.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	96.00	120.00	151.05	151.05
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	20.00	125.00	108.40	20.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	128.00	200.00	346.53	381.06
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		467.00	135.03	143.25	182.53
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	163.71	163.71	163.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	350.00	312.85	93.60
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	31.00	110.00	173.68	225.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	200.00	210.00	220.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	15.00	200.00	220.25	170.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	17.00	100.00	160.29	160.50
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		94.00	150.79	183.95	193.03
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	174.00	120.00	150.00	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	20.00	90.00	138.59	145.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	17.00	165.00	165.00	165.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	19.00	150.00	174.62	175.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	7.00	200.00	164.60	170.00
C5502-097		US550 MP 117.28-126.06	11/17/22	38.00	200.00	152.44	151.00
MPR200-280		PUEBLO AREA	11/17/22	311.00	97.00	90.00	120.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	9.00	180.00	156.50	175.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	54.00	115.00	181.05	113.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	140.00	156.67	150.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	15.00	150.00	618.94	850.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	100.00	93.33	110.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	16.00	150.00	200.60	254.21
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	37.00	150.00	88.34	103.68
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	21.00	170.00	220.84	165.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	70.00	200.00	186.07	230.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	14.00	180.00	215.43	234.74
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	350.00	189.00	178.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 47

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00810							
		Rem Ground Sign		Each			
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	300.00	147.09	103.46
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50.00	121.50	91.00
STA385A-016		SH 385 MP 97.76	12/22/22	3.00	100.00	162.42	166.67
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	156.00	140.00	228.33	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,018.00	131.34	170.44	156.34
		WEIGHTED AVERAGE FOR THE YEAR		2,659.00	134.63	165.91	155.02
===== 202-00815							
		Rem of Sign (Special)		Each			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	14.00	500.00	955.50	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	500.00	955.50	400.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1309.68	1309.68	1309.68
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	300.00	290.14	289.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	300.00	290.14	289.00
		WEIGHTED AVERAGE FOR THE YEAR		19.00	500.51	769.40	424.51
===== 202-00821							
		Rem Sign Panel		Each			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	10.00	80.00	71.27	37.21
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	70.00	605.44	707.00
MTCER300-262			02/03/22	3,039.00	30.00	131.67	80.00
C0762-055			02/17/22	10.00	125.00	144.78	80.00
NHPP0063-063			02/24/22	44.00	40.00	55.40	58.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	80.00	1313.54	600.00
C0761-239							
NHPP0703-472			03/10/22	2.00	60.00	110.90	110.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	32.00	1000.00	951.00	1114.00
NHM765-007			03/31/22	38.00	45.00	107.38	114.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,182.00	40.65	140.68	91.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 48

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00821 Rem Sign Panel Each =====							
NH0504-911			04/07/22	2.00	75.00	159.75	119.50
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	12.00	60.00	71.94	70.70
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	116.00	80.00	110.50	160.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	24.00	80.00	151.05	151.05
WEIGHTED AVERAGE FOR THE SECOND QUARTER				154.00	78.38	105.66	151.12
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	100.00	230.00	110.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	700.00	179.38	140.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	9.00	100.00	57.58	31.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				12.00	200.00	74.93	55.75
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	143.00	105.00	85.00	125.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	120.00	70.37	87.00
MPR200-280		PUEBLO AREA	11/17/22	138.00	87.00	80.00	100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	120.00	120.00	100.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	82.00	100.00	153.75	250.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	200.00	607.06	57.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	90.00	88.33	110.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	12.00	80.00	48.48	64.96
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	160.00	147.82	100.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	50.00	154.23	205.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				400.00	96.83	100.66	139.45
WEIGHTED AVERAGE FOR THE YEAR				3,748.00	48.70	136.12	99.07
===== 202-00823 Rem Dynamic Message Sign Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	125.00	1000.00	1285.00	1285.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				125.00	1000.00	1285.00	1285.00
WEIGHTED AVERAGE FOR THE YEAR				125.00	1000.00	1285.00	1285.00
===== 202-00825 Rem Flashing Beacon Each =====							
NHM765-007			03/31/22	3.00	500.00	1553.28	1396.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	500.00	1553.28	1396.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 49

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00825 Rem Flashing Beacon Each =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	2000.00	1729.18	630.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	500.00	645.22	568.17
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	1000.00	862.01	588.78
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	450.00	1681.10	1869.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-146		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	450.00	1681.10	1869.39
		WEIGHTED AVERAGE FOR THE YEAR		11.00	763.64	1133.80	1041.91
===== 202-00827 Rem of Pull Box Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	500.00	392.49	415.00
NHPP0063-063			02/24/22	49.00	650.00	728.50	765.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	465.00	332.72	100.00
C0761-239							
CR100-362			03/14/22	25.00	428.00	428.00	428.00
MP0503-098			03/24/22	2.00	320.00	340.00	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		83.00	562.11	593.27	623.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	26.00	600.00	495.49	620.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	24.00	500.00	569.36	569.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	552.00	512.87	595.69
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	1309.68	1309.68	1309.68

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	202-00827	Rem of Pull Box		Each	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	500.00	525.00	525.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	610.00	386.86	586.44
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	300.00	156.19	150.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5.00	250.00	138.96	129.91
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	550.00	386.54	445.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			30.00	492.67	400.12	488.63
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			170.00	577.66	530.32	618.39
=====							
=====	202-00828	Rem Traf Sig Equipment		LUMP SUM	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	40000.00	17766.45	20772.54
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5000.00	9895.00	6450.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	20000.00	28767.76	28767.76
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	21666.67	15403.45	18663.43
=====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	25000.00	44907.77	50000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	100000.00	62375.00	59750.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	10000.00	12010.47	8500.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	45000.00	28662.83	39416.67
=====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	22000.00	28375.00	19200.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	25000.00	1298.41	1260.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	70000.00	26517.75	26500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	9200.00	23877.16	36163.65
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	18000.00	9808.84	7150.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	28840.00	14703.67	18054.73
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			11.00	31290.91	17992.32	24046.72

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00831 Rem Traf Sig Head Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	325.00	57.02	55.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	150.00	186.94	174.88
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13.00	271.15	70.01	91.89
	WEIGHTED AVERAGE FOR THE YEAR			13.00	271.15	70.01	91.89
===== 202-00848 Rem Traf Sig Control+Cab Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	2000.00	726.16	682.13
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	2000.00	726.16	682.13
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2000.00	726.16	682.13
===== 202-00855 Rem Traf Sig Control Cab Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	2500.00	3850.00	3850.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	2500.00	3850.00	3850.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2500.00	3850.00	3850.00
===== 202-00858 Rem Pedestal Pole Each =====							
CR100-362			03/14/22	13.00	936.25	936.25	936.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13.00	936.25	936.25	936.25
	WEIGHTED AVERAGE FOR THE YEAR			13.00	936.25	936.25	936.25
===== 202-00860 Rem Ped Push Button Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	120.00	85.80	79.89
CR100-362			03/14/22	83.00	363.80	363.80	363.80
NHM765-007			03/31/22	8.00	150.00	177.52	159.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			99.00	326.82	267.64	324.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 52

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00860 Rem Ped Push Button Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	12.00	150.00	425.49	410.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	46.00	90.00	41.95	41.95
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		58.00	102.41	210.33	118.10
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	400.00	38.49	31.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	400.00	32.75	27.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		29.00	400.00	35.47	28.69
		WEIGHTED AVERAGE FOR THE YEAR		186.00	268.25	160.43	213.94
===== 202-00887 Rem Radar Detect Sys Each =====							
MP0503-098			03/24/22	42.00	500.00	280.00	440.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42.00	500.00	280.00	440.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	1000.00	366.18	350.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1000.00	366.18	350.00
		WEIGHTED AVERAGE FOR THE YEAR		44.00	522.73	289.17	435.91
===== 202-00888 Rem Video Detect Sys Each =====							
MP0503-098			03/24/22	75.00	600.00	295.00	440.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		75.00	600.00	295.00	440.00
		WEIGHTED AVERAGE FOR THE YEAR		75.00	600.00	295.00	440.00
===== 202-00889 Rem of Detect Warning Each =====							
STR0505-050			01/13/22	1.00	500.00	1833.33	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	1833.33	2000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 53

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00889 Rem of Detect Warning Each =====							
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	2.00	200.00	375.00	420.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	200.00	375.00	420.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	300.00	1000.00	946.67
===== 202-00895 Rem of Impact Attenuator Each =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	2.00	1500.00	2057.89	1600.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	4.00	1800.00	1880.66	1800.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	1700.00	1922.86	1733.33
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1700.00	1922.86	1733.33
===== 202-00900 Rem Conc Footing Each =====							
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	2.00	1500.00	4584.39	10949.94
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1500.00	4584.39	10949.94
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1500.00	4584.39	10949.94
===== 202-01000 Rem Fence Lin Foot =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	1,420.00	3.00	3.63	1.88
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	28,572.00	5.00	1.70	1.40
STA0252-459			02/03/22	57,215.00	1.24	0.73	0.50
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	1,886.00	1.50	5.78	6.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			89,093.00	2.48	1.46	0.93
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	257.00	16.00	8.79	8.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01000							
		Rem Fence		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	767.00	3.00	6.73	7.50
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	7,741.00	10.00	6.00	6.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8,765.00	9.56	6.51	6.19
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	10.00	9.37	9.10
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	131.00	6.00	16.81	11.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	356.00	3.75	8.04	8.04
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	18,410.00	3.70	1.08	0.70
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	185.00	2.50	11.24	7.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				19,202.00	3.74	1.24	1.02
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,535.00	4.00	9.60	8.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	195.00	2.00	7.00	2.99
C5502-097		US550 MP 117.28-126.06	11/17/22	6,535.00	6.00	2.28	2.55
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,213.00	4.50	4.10	3.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	252.00	3.00	6.80	6.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	46.00	2.00	14.50	6.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	506.00	3.00	4.45	7.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,174.00	2.00	5.05	3.90
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,384.00	10.00	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	2.00	5.35	4.39
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				14,340.00	5.07	4.35	4.01
WEIGHTED AVERAGE FOR THE YEAR				131,400.00	3.42	1.80	1.63
===== 202-01020							
		Rem Noise Barrier Fence		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,310.00	50.00	22.61	4.40
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,310.00	50.00	22.61	4.40
WEIGHTED AVERAGE FOR THE YEAR				1,310.00	50.00	22.61	4.40
===== 202-01030							
		Rem of Road Closure Gate		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2034.79	1800.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	2000.00	2034.79	1800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 55

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01030 Rem of Road Closure Gate Each =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	3000.00	3250.00	3250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	1700.00	3100.00	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	2566.67	3160.00	3166.67
	WEIGHTED AVERAGE FOR THE YEAR			5.00	2340.00	2409.86	2620.00
===== 202-01035 Rem of Gate Each =====							
STA0252-459			02/03/22	12.00	160.00	232.29	225.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	160.00	232.29	225.00
C5502-097		US550 MP 117.28-126.06	11/17/22	17.00	300.00	286.04	227.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			17.00	300.00	286.04	227.00
	WEIGHTED AVERAGE FOR THE YEAR			29.00	242.07	263.80	226.17
===== 202-01130 Rem Gdrail Ty 3 Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,145.00	5.00	8.20	8.94
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,766.00	5.00	4.92	4.00
NHPP1601-083			02/03/22	7,117.50	5.00	4.51	5.00
STA0252-459			02/03/22	720.00	5.00	5.96	5.75
C0762-055			02/17/22	957.00	6.00	5.98	7.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	3,279.00	8.00	7.08	6.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16,888.00	6.00	4.07	4.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	15,626.00	5.00	5.79	5.58
STR092A-031			03/17/22	2,656.00	6.00	8.00	8.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			52,154.50	5.58	4.80	5.13
NH0504-911			04/07/22	6,550.00	11.51	6.10	6.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01130	Rem Gdrail Ty 3		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	13,203.00	5.00	5.60	5.60
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,049.00	6.00	5.17	5.10
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	590.00	5.00	11.00	12.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	768.00	6.00	14.42	14.42
WEIGHTED AVERAGE FOR THE SECOND QUARTER				22,160.00	7.01	5.79	6.23
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	401.00	15.43	15.43	15.43
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	387.50	15.00	7.55	8.22
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,248.00	5.72	5.72	5.72
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	150.00	8.00	13.00	5.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1,136.00	8.00	9.17	9.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	3,965.00	6.00	10.45	10.17
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	445.00	20.00	10.77	11.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				7,732.50	8.03	10.15	9.40
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10,793.00	7.00	5.43	7.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	665.00	6.50	7.75	8.25
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	250.00	7.50	13.04	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	526.00	10.00	7.49	6.50
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,342.00	6.00	6.75	9.26
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,475.00	8.00	4.95	5.10
C5502-097		US550 MP 117.28-126.06	11/17/22	5,008.00	8.00	5.30	4.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	395.00	10.00	8.13	8.25
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,202.00	4.20	5.99	7.19
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	150.00	7.00	8.08	5.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,108.00	12.00	14.25	15.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,123.00	3.80	5.62	5.20
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	11,961.00	7.00	8.75	2.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	254.00	4.00	8.33	7.50
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	400.00	8.00	20.39	13.15
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,248.00	6.00	4.29	3.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	878.00	10.00	9.48	7.21
STR0092-024		SH 9 North of Silverthorne	12/22/22	6,605.00	7.00	9.15	4.30
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	590.00	15.00	5.39	5.66
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	429.00	5.00	11.30	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,025.00	6.00	6.75	5.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 57

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01130	STR096A-050	Rem Gdrail Ty 3 SH 96 MP 168.99 TO 193.77	12/22/22	Lin Foot 1,143.50	6.60	6.33	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		51,570.50	7.04	7.13	5.57
		WEIGHTED AVERAGE FOR THE YEAR		133,617.50	6.52	6.07	5.72
===== 202-01140		Rem Gdrail Ty 4		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,559.00	25.00	26.10	42.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,559.00	25.00	26.10	42.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	520.00	60.00	37.60	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		520.00	60.00	37.60	20.00
		WEIGHTED AVERAGE FOR THE YEAR		2,079.00	33.75	27.25	36.50
===== 202-01170		Rem Gdrail Ty 7		Lin Foot			
NHPP 0761-238 C0761-239 NHPP0703-472 M R100-351		I-76 DAHLIA TO YORK	03/10/22	6,766.00	18.00	19.65	13.00
			03/10/22	584.00	26.00	58.85	55.00
		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	361.00	100.00	145.50	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,711.00	22.44	22.84	20.02
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,312.00	25.00	18.51	18.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,312.00	25.00	18.51	18.75
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,478.00	17.04	17.04	17.04
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,478.00	17.04	17.04	17.04

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 58

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01170 Rem Gdrail Ty 7 Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	82.00	30.00	52.19	58.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	252.00	22.00	30.00	15.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	463.00	30.00	154.00	108.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			797.00	27.47	66.10	57.37
	WEIGHTED AVERAGE FOR THE YEAR			11,298.00	22.39	24.40	23.31
===== 202-01175 Rem of Guardrail (Spec) Lin Foot =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	108.00	100.00	32.04	35.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			108.00	100.00	32.04	35.00
STR096A-050 SH 96 MP 168.99 TO 193.77 12/22/22							
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			84.00	100.00	82.00	75.00
	WEIGHTED AVERAGE FOR THE YEAR			192.00	100.00	53.90	52.50
===== 202-01200 Rem High-Tension Cable Barrier Lin Foot =====							
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	200.00	20.00	13.70	15.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			200.00	20.00	13.70	15.00
	WEIGHTED AVERAGE FOR THE YEAR			200.00	20.00	13.70	15.00
===== 202-01300 Rem End Anchorage Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	600.00	389.24	373.33
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	350.00	193.20	235.00
NHPP1601-083			02/03/22	30.00	200.00	483.93	400.00
STA0252-459			02/03/22	2.00	400.00	417.08	418.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	340.00	291.98	300.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01300	Rem End Anchorage		Each =====			
C0761-239						
STR160A-034	US160A LA VETA PASS EAST SURF	03/17/22	26.00	300.00	270.44	240.87
STR092A-031		03/17/22	16.00	350.00	550.00	550.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		98.00	303.67	340.04	355.26
NH0504-911		04/07/22	42.00	324.90	324.50	324.00
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	50.00	350.00	373.98	278.00
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	3.00	350.00	285.53	301.93
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	350.00	642.50	700.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	350.00	650.30	650.30
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	375.00	221.68	206.36
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		114.00	340.97	373.88	355.48
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	588.53	588.53	588.53
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092	US 50 MP 204 EB MONARCH TRUCK	08/29/22	4.00	600.00	647.90	920.38
PAN0761-245	ALONG I-76 & RAMPS MILEPOST 9	09/01/22	24.00	340.00	450.00	475.00
2670403-065	US40 FLOYD HILL ROUNDABOUTS	09/15/22	8.00	400.00	403.74	380.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.00	700.00	346.51	505.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		43.00	426.18	458.97	509.47
NHPP0701-253	I-70 EAST OF DEBEQUE	10/27/22	22.00	300.00	504.00	265.00
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22	8.00	360.00	693.33	850.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	350.00	338.42	300.00
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	4.00	350.00	628.23	354.69
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	12.00	700.00	1352.50	1375.00
C5502-097	US550 MP 117.28-126.06	11/17/22	26.00	500.00	529.42	492.00
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	870.00	780.00	810.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	14.00	400.00	305.02	366.36
BR2854-148	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12.00	550.00	607.50	600.00
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	43.00	600.00	385.00	400.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	350.00	320.00	260.00
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	2.00	900.00	12959.76	7819.52
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	500.00	638.14	700.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01300 Rem End Anchorage Each =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	16.00	450.00	316.94	425.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	39.00	500.00	702.53	533.72
STR0092-024		SH 9 North of Silverthorne	12/22/22	38.00	1000.00	367.50	275.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	700.00	407.13	430.44
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	400.00	502.67	600.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	16.00	370.00	470.33	600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		275.00	564.62	582.71	522.10
		WEIGHTED AVERAGE FOR THE YEAR		530.00	457.03	485.12	457.32
===== 202-04000 Plug Structure Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	2368.16	3923.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	2368.16	3923.57
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	3362.92	7961.79
===== 202-04001 Plug Culvert Each =====							
NHPP1601-083			02/03/22	2.00	4000.00	8548.07	4000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	3820.00	3250.63	2500.00
C0761-239							
NHM765-007			03/31/22	1.00	3000.00	18142.27	3100.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	3705.00	7641.61	3400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4000.00	2351.29	3923.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	4000.00	2351.29	3923.57
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	2500.00	2021.24	1200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2500.00	2021.24	1200.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	4000.00	4042.16	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 61

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04001	Plug Culvert			Each =====			
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22		1.00	3000.00	3312.80	2300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	3750.00	3961.12	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	3632.00	4740.12	2432.36
===== 202-04002	Clean Culvert			Each =====			
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		44.00	2000.00	3003.89	2800.00
NHPP1601-083		02/03/22		19.00	4000.00	3760.92	3600.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22		18.00	500.00	2352.63	1600.00
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22		5.00	1700.00	2199.47	2000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			86.00	2110.47	2894.29	2679.07
NH0504-911		04/07/22		3.00	2000.00	2015.00	1530.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22		11.00	2428.24	2428.24	2428.24
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		62.00	1000.00	2673.08	2749.91
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22		4.00	2000.00	1992.72	2429.43
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22		6.00	1900.00	4733.33	7700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			86.00	1326.87	2711.33	2996.66
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22		25.00	3759.87	3759.87	3759.87
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M	08/04/22		1.00	3000.00	5424.46	3213.60
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22		1.00	2000.00	4811.22	3025.00
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT	08/25/22		1.00	3000.00	9500.00	4500.00
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22		5.00	3500.00	2875.00	4000.00
NHPPR100-266	R1 ESSENTIAL REPAIRS	09/01/22		8.00	1500.00	2469.93	3159.80
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			41.00	3207.24	3528.67	3658.87
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22		2.00	1200.00	3843.33	1830.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		10.00	2500.00	2327.01	2500.00
STA3852-015	US 385 HOLYOKE NORTH	10/27/22		30.00	2200.00	1550.00	1550.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04002 Clean Culvert Each =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	2000.00	2026.70	780.11
C5502-097		US550 MP 117.28-126.06	11/17/22	129.00	2500.00	2007.60	2210.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5400.00	3363.00	3000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1883.00	2661.19	2215.98
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	10.00	1600.00	3165.09	1530.18
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	5.00	4000.00	3172.14	300.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	3000.00	2802.96	2600.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	5000.00	3805.13	2560.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.00	3000.00	3486.28	7012.77
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	3000.00	3123.32	1506.59
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		210.00	2493.88	2415.67	2114.77
		WEIGHTED AVERAGE FOR THE YEAR		423.00	2247.81	2654.41	2548.21
===== 202-04003 Clean Culvert (Spec) Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	38212.89	39140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	38212.89	39140.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	38212.89	39140.00
===== 202-04005 Clean Valve Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	38.00	240.00	293.24	92.18
CR100-362			03/14/22	5.00	555.82	555.82	555.82
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		43.00	276.72	301.60	146.09
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	7.00	360.00	546.54	127.42
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	300.00	89.00	89.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		62.00	306.77	287.11	93.34
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	500.00	615.91	125.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04005 Clean Valve Box Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	13.00	300.00	396.28	244.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	7.00	150.00	400.90	440.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	32.00	400.00	357.32	282.36
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	150.00	381.60	81.19
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	300.00	359.10	355.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			66.00	341.67	389.79	269.43
	WEIGHTED AVERAGE FOR THE YEAR			171.00	312.68	341.99	174.57
===== 202-04007 Plug Culvert Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	43.00	200.00	432.44	375.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			43.00	200.00	432.44	375.00
	WEIGHTED AVERAGE FOR THE YEAR			43.00	200.00	623.01	587.26
===== 202-04008 Clean Culvert Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,200.00	70.00	59.85	28.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,200.00	70.00	59.85	28.00
	WEIGHTED AVERAGE FOR THE YEAR			1,200.00	70.00	59.85	28.00
===== 202-04010 Clean Inlet Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	98.00	500.00	708.13	202.79
C0762-055			02/17/22	4.00	1100.00	1174.42	350.00
NHPP0703-472			03/10/22	29.00	600.00	1286.53	300.00
BRC040-057			03/17/22	26.00	500.00	1048.75	75.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			157.00	533.76	883.26	203.33
NH0504-911			04/07/22	38.00	730.00	4087.00	8024.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	1500.00	866.25	906.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	900.00	687.62	285.84
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	54.00	2000.00	195.80	195.80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04010 Clean Inlet Each =====							
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	31.00	300.00	610.50	1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			139.00	1181.58	1358.31	2561.31

C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7.00	1000.00	2375.00	4000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	1000.00	2375.00	4000.00

STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	44.00	850.00	1315.00	3540.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	37.00	1000.00	1335.06	650.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	1076.30	1713.05	550.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	16.00	300.00	1173.33	520.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	80.00	150.00	221.61	164.22
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	43.00	850.00	1111.84	282.36
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	25.00	860.00	1528.00	356.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	12.00	1000.00	1517.03	1530.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	16.00	780.00	301.00	300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			278.00	644.29	1021.76	892.87
	WEIGHTED AVERAGE FOR THE YEAR			581.00	747.25	1048.23	1143.14
===== 202-04050 Clean Exp Joint Lin Foot =====							
BRC040-057			03/17/22	927.00	10.00	13.75	7.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			927.00	10.00	13.75	7.00

NH0504-911			04/07/22	140.00	16.00	89.75	59.50
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1,504.00	10.00	16.50	15.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,644.00	10.51	19.76	18.79

NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	293.00	20.00	28.21	15.77
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			293.00	20.00	28.21	15.77
	WEIGHTED AVERAGE FOR THE YEAR			2,864.00	11.32	18.65	14.66

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-05008 Sawing Concrete (8 In) Lin Foot =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	144.00	20.00	7.81	4.10
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		144.00	20.00	7.81	4.10
		WEIGHTED AVERAGE FOR THE YEAR		144.00	20.00	7.81	4.10
===== 202-05026 Sawing Asphalt Mat (6 In) Lin Foot =====							
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG 08/31/22 US 6/US 34 TIMBER BRIDGE REPL		6,170.00	4.85	10.21	10.21
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		6,170.00	4.85	10.21	10.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA 10/27/22		1,506.00	3.00	7.08	6.30
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1,506.00	3.00	7.08	6.30
		WEIGHTED AVERAGE FOR THE YEAR		7,676.00	4.49	8.66	9.44
===== 202-05030 Sawing Asphalt Mat (10 In) Lin Foot =====							
STR160A-034		US160A LA VETA PASS EAST SURF 03/17/22		2,000.00	6.00	2.33	1.66
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2,000.00	6.00	2.33	1.66
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL 05/26/22		13,000.00	3.00	3.25	3.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		13,000.00	3.00	3.25	3.00
2670703-487 BR012A-048		I-70 BRIDGES OVER WARD ROAD- 12/01/22 CO 12 STRUCTURE P-17-F AT MP 12/22/22		1,471.00 56.00	10.00 5.00	4.87 36.57	5.10 63.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1,527.00	9.82	5.34	7.22
		WEIGHTED AVERAGE FOR THE YEAR		16,527.00	3.99	3.57	3.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-05100 Sandblasting Reinf Steel Sq Yard =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	32.00	50.00	83.60	88.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		32.00	50.00	83.60	88.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	50.00	83.60	88.00
===== 202-05300 Rem and Disposal of Paint LUMP SUM =====							
NH0504-911			04/07/22	1.00	45000.00	78000.00	150000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	45000.00	78000.00	150000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	51950.00	117375.00
===== 203-00000 Uncl Excav Cubic Yard =====							
STA0252-459			02/03/22	40.00	48.00	110.40	54.50
ER007A-035			03/15/22	49.00	268.35	149.75	149.75
STR092A-031			03/17/22	8,288.00	40.00	19.00	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,377.00	41.37	21.05	19.93
NH0504-911			04/07/22	111.00	20.00	65.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		111.00	20.00	65.00	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	303.00	30.00	140.67	65.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		303.00	30.00	140.67	65.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	110.00	80.00	211.25	150.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	153.00	40.00	82.33	55.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	9,181.00	40.00	57.50	65.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00000							
		Uncl Excav		Cubic Yard			
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	96.00	50.00	241.70	130.00
STA385A-016		SH 385 MP 97.76	12/22/22	296.00	10.00	64.75	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				9,836.00	39.64	64.29	65.98
WEIGHTED AVERAGE FOR THE YEAR				18,627.00	40.15	54.52	45.46
===== 203-00010							
		Uncl Excav (CIP)		Cubic Yard			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5,029.00	50.00	15.14	25.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	27,784.00	22.00	27.60	14.50
NHPP0063-063			02/24/22	1,748.00	25.00	41.10	59.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	33,816.00	30.00	23.33	18.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				68,377.00	28.09	24.05	18.14
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	45,687.00	20.99	20.99	20.99
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6,341.00	25.00	30.66	18.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	41,564.00	40.00	17.07	17.07
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	100.00	20.00	61.50	38.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	28,977.00	32.00	32.17	32.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	94.00	60.00	70.67	28.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14,437.00	20.00	26.67	18.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				137,200.00	29.18	26.63	21.88
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	146,165.00	25.41	25.41	25.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	215.00	65.00	85.80	44.26
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	13,183.00	35.00	47.44	56.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	8,152.00	25.00	73.68	60.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	22,221.00	35.00	27.77	11.96
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	11,144.00	38.00	31.47	20.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2,850.00	40.00	70.83	51.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				203,930.00	27.99	32.06	27.40
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	860.00	80.00	60.47	55.40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00010		Uncl Excav (CIP)		Cubic Yard	=====	=====	=====
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	297.00	40.00	88.22	90.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	16,696.00	28.00	53.26	29.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,332.00	30.00	29.70	24.40
C5502-097		US550 MP 117.28-126.06	11/17/22	32,317.00	30.00	23.07	22.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,371.00	62.00	37.95	29.90
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,007.00	20.00	27.94	23.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	19,049.00	30.00	33.33	25.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,994.00	50.00	47.14	34.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	58,514.00	25.00	20.57	15.53
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	725.00	35.00	51.45	47.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	7,097.00	50.00	35.95	40.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,537.00	20.00	45.50	25.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		147,796.00	29.35	27.50	22.45
		WEIGHTED AVERAGE FOR THE YEAR		557,303.00	28.66	27.58	23.59
===== 203-00040		Uncl Excav (Spec)		Cubic Yard	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	26,721.00	4.93	4.93	4.93
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26,721.00	4.93	4.93	4.93
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	800.00	46.38	46.38	46.38
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		800.00	46.38	46.38	46.38
		WEIGHTED AVERAGE FOR THE YEAR		27,521.00	6.13	6.13	6.13
===== 203-00041		Uncl Excav (Spec)		Ton	=====	=====	=====
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	15,086.00	35.00	45.50	41.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15,086.00	35.00	45.50	41.00
		WEIGHTED AVERAGE FOR THE YEAR		15,086.00	35.00	45.50	41.00
===== 203-00050		Unsuitable Material		Cubic Yard	=====	=====	=====
STA0252-459			02/03/22	10.00	32.00	255.03	145.75

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00050	Unsuitable Material		Cubic Yard	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	725.00	100.00	47.96	22.00
C0761-239							
CR100-362			03/14/22	250.00	265.31	265.31	265.31
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	323.00	40.00	46.63	49.25
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,308.00	116.26	56.83	76.18
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	75.00	61.36	42.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	200.00	75.00	50.63	22.55
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,000.00	20.00	37.61	37.61
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,500.00	30.00	17.50	16.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,000.00	35.00	40.82	10.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,800.00	31.77	32.67	20.07
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	300.00	35.16	25.36	25.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
WEIGHTED AVERAGE FOR THE THIRD QUARTER				300.00	35.16	25.36	25.36
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	200.00	100.00	78.46	63.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	148.00	48.00	65.36	90.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,046.00	70.00	76.00	38.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	50.00	20.00	95.36	134.09
C5502-097		US550 MP 117.28-126.06	11/17/22	150.00	80.00	167.47	86.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	220.00	21.00	34.55	35.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,020.00	13.04	45.16	36.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	247.00	40.00	58.11	51.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	30.00	62.12	66.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	260.00	50.00	190.75	96.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	100.00	50.00	83.33	65.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	10.00	150.00	176.31	180.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	150.00	68.21	76.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	250.00	40.00	73.95	61.61
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	40.00	106.00	100.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				8,401.00	58.16	75.92	48.60
WEIGHTED AVERAGE FOR THE YEAR				14,809.00	54.27	61.58	41.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 70

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00060 Emb Matl (CIP) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	6,726.00	35.00	35.34	25.00
NHPP1601-083			02/03/22	48,171.00	18.00	27.82	26.00
STA0252-459			02/03/22	160.00	51.00	105.42	45.25
STR0141-031			02/17/22	770.00	80.00	57.67	61.00
NHM765-007			03/31/22	1,880.00	22.00	42.84	48.78
WEIGHTED AVERAGE FOR THE FIRST QUARTER				57,707.00	21.03	31.58	27.15
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	137,735.00	16.00	23.36	21.34
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25,833.00	25.00	17.46	7.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				163,568.00	17.42	22.95	19.08
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	680.00	75.00	45.64	26.93
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4,305.00	75.10	78.16	78.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4,985.00	75.08	67.71	71.17
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	312.00	75.00	94.69	43.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	39,052.00	25.00	21.20	12.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	56,428.00	28.00	34.00	34.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,500.00	28.00	76.06	55.18
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	880.00	16.00	87.50	85.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	23,899.00	10.00	29.56	27.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	900.00	50.00	71.33	44.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	100.00	2981.15	2562.30
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4,942.00	70.00	45.09	48.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	11,281.00	30.00	45.64	35.00
STA385A-016		SH 385 MP 97.76	12/22/22	4,896.00	30.00	64.00	50.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	506.00	40.00	133.67	66.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				144,598.00	26.08	32.12	30.79
WEIGHTED AVERAGE FOR THE YEAR				370,858.00	22.13	28.22	26.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 71

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00062 Emb Matl (CIP) (Spec) Cubic Yard =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	24,521.00	24.00	24.37	19.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24,521.00	24.00	24.37	19.75
	WEIGHTED AVERAGE FOR THE YEAR			24,521.00	24.00	24.37	19.75
===== 203-00065 Emb Matl (CIP) (R20) Cubic Yard =====							
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	2,992.00	150.00	37.78	32.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,992.00	150.00	37.78	32.00
	WEIGHTED AVERAGE FOR THE YEAR			2,992.00	150.00	37.78	32.00
===== 203-00066 Emb Matl (CIP) (R40) Cubic Yard =====							
STA0712-019	SH 71: Frieght Improvements		05/12/22	20,092.00	30.00	37.42	37.42
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	78.00	20.00	74.60	62.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	528.00	50.00	43.00	60.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS		06/02/22	52.00	60.00	115.00	90.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			20,750.00	30.55	38.53	38.22
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	162.00	80.00	112.33	104.56
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	6,245.00	40.00	34.93	21.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6,407.00	41.01	35.92	23.11
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	8,771.00	25.00	36.69	29.00
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	13,410.00	44.00	50.00	50.00
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	1,286.00	45.00	39.58	28.20
STA0711-021	SH71: REGION LINE NORTH		12/01/22	185.00	25.00	85.47	50.00
STA0361-129	US 36: HYGIENE RD AND NELSON		12/22/22	715.00	60.00	65.45	49.82
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24,367.00	37.54	40.16	41.29
	WEIGHTED AVERAGE FOR THE YEAR			51,524.00	35.15	38.89	37.79

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00100 Muck Excav Cubic Yard =====							
NHPP1601-083			02/03/22	500.00	36.00	55.03	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			500.00	36.00	55.03	40.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	100.00	186.88	190.64
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			20.00	100.00	186.88	190.64
	WEIGHTED AVERAGE FOR THE YEAR			520.00	38.46	62.49	45.79
===== 203-00400 Rock Excav Cubic Yard =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	855.00	180.00	195.92	125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	275.00	269.01	232.03
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	40.00	50.00	459.57	852.71
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	659.00	200.00	169.15	78.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,574.00	186.28	192.34	125.18
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	4,801.00	80.00	88.02	88.55
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,801.00	80.00	88.02	88.55
	WEIGHTED AVERAGE FOR THE YEAR			6,375.00	106.24	113.77	97.59
===== 203-00440 Rock Excav (Spec) Cubic Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7,197.00	25.52	25.52	25.52
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,197.00	25.52	25.52	25.52
	WEIGHTED AVERAGE FOR THE YEAR			7,197.00	25.52	25.52	25.52
===== 203-00450 Rem Rock Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19.00	105.00	840.46	77.74
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			19.00	105.00	840.46	77.74
	WEIGHTED AVERAGE FOR THE YEAR			19.00	105.00	840.46	77.74

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00710 Clay Plating (CIP) Cubic Yard =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	50.00	463.85	463.85	463.85
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	463.85	463.85	463.85
	WEIGHTED AVERAGE FOR THE YEAR			50.00	463.85	463.85	463.85
===== 203-00850 Polystyrene Fill (CIP) Cubic Yard =====							
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	8.59	300.00	1864.02	1300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.59	300.00	1864.02	1300.00
	WEIGHTED AVERAGE FOR THE YEAR			8.59	300.00	1864.02	1300.00
===== 203-01100 Proof Rolling Hour =====							
NHPP0702-383 NHPP 0761-238 C0761-239 ER007A-035 NHM765-007		I-70 EB AUX FRISCO TO SILVERT I-76 DAHLIA TO YORK	01/13/22 03/10/22	40.00 750.00	125.00 140.00	204.23 119.41	245.00 110.00
			03/15/22	25.00	234.05	242.73	242.73
			03/31/22	40.00	100.00	144.54	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			855.00	140.18	123.04	119.73
STM1151-038 2670703-479 NHC540-017 FSA052A-046		SH115 MP 27 TO MP 38 I-70 BRIDGE OVER HARLAN R2 CHAINUP STA @ KENOSHA/HOOS SH52 WCR 37 INTERSECTION IMPR	04/21/22 05/05/22 05/12/22 06/09/22	80.00 40.00 40.00 40.00	155.00 170.00 130.00 150.00	147.33 157.95 133.33 159.40	110.00 209.04 100.00 125.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			200.00	152.00	150.75	130.81
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	120.00	143.12	250.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			20.00	120.00	143.12	250.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	100.00	241.39	269.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	203-01100	Proof Rolling		Hour	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	250.00	146.68	99.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	100.00	213.00	125.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		70.00	121.43	216.93	224.14
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		1,145.00	140.74	129.76	130.32
=====							
=====	203-01140	Rolling		Hour	=====		
NHPP1601-083			02/03/22	20.00	150.00	276.06	110.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	150.00	276.06	110.00
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		20.00	150.00	276.06	110.00
=====							
=====	203-01500	Blading		Hour	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	140.00	150.00	221.00	255.00
NHPP1601-083			02/03/22	20.00	160.00	283.02	130.00
STA0252-459			02/03/22	15.00	150.00	278.48	290.00
STR0141-031			02/17/22	40.00	200.00	145.00	175.00
NHPP0063-063			02/24/22	20.00	140.00	155.00	160.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	150.00	175.25	130.00
C0761-239							
ER007A-035			03/15/22	10.00	170.83	182.79	182.79
STR092A-031			03/17/22	40.00	160.00	125.00	125.00
NHM765-007			03/31/22	30.00	150.00	188.00	110.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		345.00	157.56	202.24	193.85
=====							
NH0504-911			04/07/22	150.00	175.00	162.65	155.30
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	277.93	277.93	277.93
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	150.00	202.59	140.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	155.00	207.39	233.16
STA0712-019		SH 71: Frieght Improvements	05/12/22	40.00	150.00	164.01	164.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	150.00	160.00	160.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	175.00	397.40	132.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	20.00	150.00	140.00	120.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	40.00	190.00	172.00	135.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		536.00	168.57	190.68	158.54

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 75

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01500	Blading			Hour =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	55.00	283.34	283.34	283.34
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	159.00	188.33	115.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	140.00	192.26	125.00
CI211-099		SH 121 NORTH SGA SIGNALS	08/25/22	16.00	200.00	300.00	400.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	72.00	205.16	226.10	226.10
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	120.00	266.09	232.27
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	300.00	186.59	168.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	40.00	300.00	179.32	161.29
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	150.00	183.94	125.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	180.00	124.16	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				423.00	207.39	194.12	172.59
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10.00	150.00	139.00	126.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	100.00	150.00	149.57	183.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	240.00	150.00	187.24	130.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	50.00	150.00	155.00	155.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	55.00	150.00	190.59	170.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	200.00	263.73	275.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	80.00	150.00	188.27	284.81
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	180.00	142.50	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	150.00	201.36	248.80
C5502-097		US550 MP 117.28-126.06	11/17/22	60.00	180.00	261.10	280.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	150.00	198.72	300.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	150.00	162.67	130.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	80.00	180.00	127.50	130.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	40.00	300.00	202.92	180.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	150.00	192.50	100.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	145.00	178.33	210.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	170.00	143.00	160.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	160.00	311.68	200.35
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	150.00	198.52	179.40
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	180.00	209.80	244.54
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	140.00	201.41	190.00
STA385A-016		SH 385 MP 97.76	12/22/22	50.00	150.00	244.50	150.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,299.00	166.69	199.26	198.36
WEIGHTED AVERAGE FOR THE YEAR				2,603.00	172.48	197.46	185.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 203-01510	Backhoe			Hour	=====		
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	80.00	150.00	178.68	230.00
NHPP1601-083			02/03/22	20.00	200.00	327.13	200.00
NHPP0063-063			02/24/22	20.00	200.00	155.00	160.00
CR100-362			03/14/22	50.00	138.33	138.33	138.33
STR092A-031			03/17/22	30.00	150.00	113.00	113.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				200.00	157.08	180.47	179.53
<hr/>							
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	20.00	274.20	274.20	274.20
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	80.00	140.00	180.76	130.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	40.00	180.00	60.00	60.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				140.00	170.60	174.32	130.60
<hr/>							
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	20.00	188.55	188.55	188.55
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	20.00	200.00	159.49	103.47
2670703-497	I-70 GENESEE WILDLIFE XING		09/15/22	60.00	150.00	169.95	144.52
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	40.00	180.00	61.40	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				140.00	171.22	154.54	109.37
<hr/>							
C5502-097	US550 MP 117.28-126.06		11/17/22	60.00	200.00	154.64	165.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3		12/01/22	40.00	200.00	132.50	140.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	20.00	200.00	207.48	150.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU		12/01/22	40.00	200.00	123.25	125.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				160.00	200.00	156.92	146.88
WEIGHTED AVERAGE FOR THE YEAR				640.00	173.86	166.63	145.32
<hr/>							
===== 203-01549	Pump			Hour	=====		
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	100.00	107.27	107.27	107.27
WEIGHTED AVERAGE FOR THE SECOND QUARTER				100.00	107.27	107.27	107.27

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01549 Pump Hour =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	182.99	182.99	182.99
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			100.00	182.99	182.99	182.99
	WEIGHTED AVERAGE FOR THE YEAR			200.00	145.13	145.13	145.13
===== 203-01550 Dozing Hour =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	150.00	214.07	260.00
STR0141-031			02/17/22	40.00	185.00	137.00	131.00
NHPP0063-063			02/24/22	20.00	160.00	180.00	180.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	160.00	180.89	135.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			170.00	161.18	190.85	198.18
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	45.00	263.97	263.97	263.97
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	170.00	211.12	248.64
STA0712-019		SH 71: Frieight Improvements	05/12/22	20.00	175.00	184.11	184.11
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	175.00	156.67	150.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	200.00	30.00	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			155.00	206.64	178.40	169.25
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	165.00	90.26	90.26	90.26
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	150.00	211.11	130.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	130.00	306.07	198.20
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	80.00	180.00	186.87	124.12
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	200.00	107.99	20.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			395.00	135.68	173.51	102.80
C5502-097		US550 MP 117.28-126.06	11/17/22	60.00	200.00	197.51	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 78

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01550 Dozing Hour =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	175.00	181.10	321.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	40.00	325.00	212.12	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	180.00	156.67	180.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	200.00	187.61	160.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	170.00	235.13	256.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	200.00	238.11	272.65
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	140.00	196.34	190.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				320.00	197.50	196.60	217.18
WEIGHTED AVERAGE FOR THE YEAR				1,040.00	169.44	186.73	165.47
===== 203-01565 Hydraulic Excavator Hour =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	400.00	349.32	349.32	349.32
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	60.00	240.00	229.50	229.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				460.00	335.06	321.67	333.63
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	400.00	359.21	359.21	359.21
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
WEIGHTED AVERAGE FOR THE THIRD QUARTER				400.00	359.21	359.21	359.21
WEIGHTED AVERAGE FOR THE YEAR				860.00	346.29	337.99	345.53
===== 203-01582 Truck (Dump) Hour =====							
NHPP1601-083			02/03/22	10.00	150.00	404.51	110.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20.00	120.00	103.75	90.00
STR092A-031			03/17/22	20.00	160.00	141.00	141.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				50.00	142.00	171.35	114.40
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	154.08	154.08	154.08
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	100.00	90.00	90.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				75.00	125.24	119.90	119.90

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 79

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01582 Truck (Dump) Hour =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	35.00	180.02	180.02	180.02
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	200.00	128.62	130.87
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	110.00	85.40	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				95.00	154.74	119.14	102.30
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	137.00	114.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	10.00	160.00	112.50	100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	132.00	180.00	90.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	150.00	141.25	160.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				90.00	147.11	145.72	127.56
WEIGHTED AVERAGE FOR THE YEAR				310.00	143.33	138.13	115.84
===== 203-01590 Front End Loader (Rubber) Hour =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	30.00	150.00	133.27	130.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				30.00	150.00	133.27	130.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	75.00	179.12	179.12	179.12
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	80.00	145.00	168.58	140.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				155.00	161.51	170.25	158.93
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	200.00	69.08	69.08	69.08
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	150.00	67.77	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				240.00	82.57	68.70	60.90
C5502-097		US550 MP 117.28-126.06	11/17/22	96.00	200.00	226.67	255.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				96.00	200.00	226.67	255.00
WEIGHTED AVERAGE FOR THE YEAR				521.00	131.57	156.56	129.81

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01594 Combination Loader Hour =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	150.00	184.02	157.00
NHPP1601-083			02/03/22	20.00	150.00	287.13	120.00
C0762-055			02/17/22	10.00	160.00	112.07	90.00
NHPP0063-063			02/24/22	20.00	140.00	145.00	140.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	150.00	132.71	100.00
C0761-239							
ER007A-035			03/15/22	10.00	145.08	155.24	155.24
STR R500-171		Various locations on SH 141 a	03/17/22	15.00	200.00	132.56	10.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				185.00	153.25	165.33	126.28
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	130.00	138.33	115.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	200.00	30.00	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	20.00	150.00	210.51	210.51
WEIGHTED AVERAGE FOR THE SECOND QUARTER				90.00	165.56	119.07	98.45
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	150.00	125.85	125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	200.00	123.63	115.90
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	80.00	120.00	184.99	141.71
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	130.00	157.88	110.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				220.00	141.82	165.03	128.89
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	24.00	140.00	171.88	112.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	50.00	160.00	155.00	155.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	200.00	235.25	174.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	140.50	121.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	130.00	178.27	308.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	20.00	100.00	188.60	150.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	157.00	370.00	90.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	130.00	143.67	150.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	150.00	127.18	119.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	140.00	183.72	205.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	50.00	150.00	139.50	160.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				544.00	162.50	195.12	177.73
WEIGHTED AVERAGE FOR THE YEAR				1,039.00	156.74	177.79	152.34

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01597	Potholing			Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	250.00	665.00	665.00
MTCE R500-218			01/06/22	8.00	300.00	250.00	50.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	120.00	260.00	316.48	215.09
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	350.00	387.65	395.00
NHPP1601-083			02/03/22	10.00	350.00	620.37	350.00
STA0252-459			02/03/22	600.00	250.00	311.67	380.00
STR0141-031			02/17/22	20.00	400.00	359.78	289.34
NHPP0063-063			02/24/22	100.00	250.00	282.50	215.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20.00	200.00	296.63	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	750.00	280.00	252.17	185.00
C0761-239							
NHPP0703-472			03/10/22	30.00	280.00	322.73	250.00
CR100-362			03/14/22	200.00	278.92	278.92	278.92
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	330.00	336.23	350.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	400.00	417.00	439.00
STR092A-031			03/17/22	50.00	350.00	500.00	500.00
NHM765-007			03/31/22	120.00	220.00	412.24	456.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,188.00	273.90	284.79	292.48
NH0504-911			04/07/22	200.00	250.00	353.50	307.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	40.00	250.00	261.13	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	616.94	616.94	616.94
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	275.00	353.93	370.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	260.00	282.03	322.98
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	80.00	275.00	425.00	350.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	100.00	100.00	297.19	297.19
CM760-047		COLFAX AND QUAIL	05/12/22	100.00	235.00	348.20	276.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	350.00	425.00	425.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	120.00	220.00	187.50	275.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	150.00	350.00	207.67	207.67
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	40.00	300.00	270.20	250.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	80.00	350.00	283.50	202.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,310.00	293.58	321.47	314.90
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	636.41	636.41	636.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	500.00	498.69	267.80
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	300.00	296.67	190.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01597 Potholing Hour =====							
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	250.00	476.60	390.00	
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22	200.00	250.00	335.00	380.00	
ER0502-092	US 50 MP 204 EB MONARCH TRUCK	08/29/22	8.00	400.00	356.79	270.38	
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22	30.00	268.72	309.60	309.60	
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
2670403-065	US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	260.00	363.69	314.00	
2670703-497	I-70 GENESEE WILDLIFE XING	09/15/22	60.00	270.00	399.20	439.58	
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	40.00	200.00	337.14	220.00	
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	16.00	400.00	316.10	200.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER			818.00	304.28	406.07	395.96	
C0831-126	SH83 EL PASO COUNTY TO BAYOU	10/13/22	50.00	275.00	325.00	300.00	
NHPP0701-253	I-70 EAST OF DEBEQUE	10/27/22	20.00	400.00	386.00	500.00	
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA	10/27/22	209.00	175.00	325.00	225.00	
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	50.00	350.00	400.00	400.00	
NHPP0343-048	US 34 (MP 169.3-171.4)	11/01/22	33.00	270.00	328.19	450.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	400.00	405.82	430.00	
SHE0242-087	US 24 SAFETY IMPRVMTS, E OF	11/03/22	40.00	275.00	279.87	214.62	
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	10.00	500.00	425.00	400.00	
C5502-097	US550 MP 117.28-126.06	11/17/22	100.00	400.00	426.67	450.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	40.00	439.00	302.50	255.00	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	92.00	250.00	375.66	401.96	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22	25.00	400.00	365.00	330.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	400.00	364.66	400.00	
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	80.00	400.00	470.00	340.00	
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	400.00	425.00	450.00	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	35.00	300.00	357.82	282.36	
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22	10.00	50.00	320.00	200.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	20.00	270.00	362.65	287.30	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	30.00	400.00	516.15	265.00	
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	5.00	400.00	299.03	255.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	150.00	350.00	292.47	358.50	
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	350.00	377.87	524.28	
STA385A-016	SH 385 MP 97.76	12/22/22	20.00	200.00	304.38	187.50	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,679.00	340.80	368.24	367.15	
WEIGHTED AVERAGE FOR THE YEAR			5,995.00	301.08	324.65	332.41	
===== 203-01598 Potholing (Spec) Each =====							
STA0252-459		02/03/22	16.00	2000.00	493.33	380.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	2000.00	493.33	380.00	
WEIGHTED AVERAGE FOR THE YEAR			16.00	2000.00	493.33	380.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 83

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01620 Sweeping Hour =====							
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	10.00	145.00	176.33	150.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	50.00	50.00	100.00	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		60.00	65.83	112.72	66.67
		WEIGHTED AVERAGE FOR THE YEAR		60.00	65.83	112.72	66.67
===== 203-01622 Sweeping (With Pickup Broom) Hour =====							
MTCE R500-218			01/06/22	150.00	200.00	155.00	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		150.00	200.00	155.00	75.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	200.00	155.00	75.00
===== 203-02300 Rock Scaler Hour =====							
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	250.00	450.00	400.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	60.00	100.00	453.74	161.23
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		80.00	137.50	453.06	220.92
		WEIGHTED AVERAGE FOR THE YEAR		80.00	137.50	453.06	220.92
===== 203-02330 Laborer Hour =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	60.00	70.81	90.53
NHPP1601-083			02/03/22	40.00	60.00	153.72	88.00
NHPP0063-063			02/24/22	50.00	60.00	49.50	49.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	30.00	50.00	60.48	90.00
CR100-362			03/14/22	250.00	52.88	52.88	52.88
ER007A-035			03/15/22	10.00	58.43	62.52	62.52
STR R500-171		Various locations on SH 141 a	03/17/22	30.00	83.00	47.62	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		430.00	56.73	66.41	57.97
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	40.00	49.11	49.11	49.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 84

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-02330 Laborer Hour =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,120.00	50.00	50.00	50.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	50.00	70.00	50.00	50.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,210.00	50.80	49.98	49.97
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	40.00	49.56	49.56	49.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	20.00	60.00	56.42	45.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	40.00	60.00	57.99	50.21
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	80.00	52.00	67.11	58.67
WEIGHTED AVERAGE FOR THE THIRD QUARTER				180.00	54.12	63.99	53.25
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	55.00	46.15	46.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	70.00	117.50	160.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	63.00	46.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	60.00	60.00	59.18	61.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	60.00	50.75	55.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	80.00	80.00	53.00	60.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				220.00	67.73	60.21	66.36
WEIGHTED AVERAGE FOR THE YEAR				2,040.00	54.17	56.48	53.71
===== 206-00000 Str Excav Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	170.00	25.00	45.95	28.75
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,868.00	33.52	44.91	24.00
NHPP1601-083			02/03/22	158.00	50.00	566.80	140.00
STA0252-459			02/03/22	300.00	54.00	141.69	242.75
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3,576.00	22.00	23.12	27.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	132.00	83.51	92.07	92.07
STR R500-171		Various locations on SH 141 a	03/17/22	13.00	380.00	361.65	88.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6,217.00	29.85	36.28	40.94
NH0504-911			04/07/22	642.00	27.98	44.75	49.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00000							
		Str Excav		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	9,503.00	35.19	35.19	35.19
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	878.00	25.00	26.64	26.01
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	19.00	80.00	131.70	153.40
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	19,899.00	28.00	29.63	20.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				30,941.00	30.15	30.10	25.53
=====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4,392.00	56.44	56.44	56.44
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	124.00	90.00	69.74	65.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	216.00	35.00	55.95	80.75
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1,014.00	75.00	45.72	27.17
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	103.00	35.00	125.93	198.78
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	370.00	80.00	71.12	51.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2,145.00	31.00	40.08	21.57
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	507.00	25.00	34.92	23.50
WEIGHTED AVERAGE FOR THE THIRD QUARTER				8,871.00	51.29	45.57	44.92
=====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	129.00	100.00	133.88	62.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,176.00	27.00	26.75	13.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	40.00	863.28	440.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,000.00	60.00	41.40	49.50
C5502-097		US550 MP 117.28-126.06	11/17/22	434.00	70.00	64.70	83.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,095.00	28.00	51.20	16.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	14,099.00	40.00	30.32	26.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,883.00	20.00	36.67	35.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	108.00	50.00	83.80	34.97
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	286.00	50.00	66.12	28.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,164.00	35.00	32.60	50.00
STA385A-016		SH 385 MP 97.76	12/22/22	710.00	35.00	62.50	35.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				31,086.00	39.53	34.43	29.76
WEIGHTED AVERAGE FOR THE YEAR				77,115.00	36.34	33.87	30.70
=====							
===== 206-00010							
		Str Excav (Spec)		Cubic Yard	=====		
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	559.00	300.00	240.50	231.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				559.00	300.00	240.50	231.00
WEIGHTED AVERAGE FOR THE YEAR				559.00	300.00	240.50	231.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 86

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00050 Str Bkfl (Spec) Cubic Yard =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,708.00	100.00	83.38	46.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,708.00	100.00	83.38	46.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	736.00	72.37	72.37	72.37
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		736.00	72.37	72.37	72.37
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	5,850.00	40.00	48.63	16.36
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,850.00	40.00	48.63	16.36
		WEIGHTED AVERAGE FOR THE YEAR		8,294.00	55.23	59.50	27.43
===== 206-00060 Str Bkfl (Spec) (Flow-Fill) Cubic Yard =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	160.00	180.00	238.16	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	180.00	238.16	150.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	288.00	135.00	442.11	584.16
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		288.00	135.00	442.11	584.16
		WEIGHTED AVERAGE FOR THE YEAR		448.00	151.07	334.77	429.10
===== 206-00065 Str Bkfl (Flow-Fill) Cubic Yard =====							
NHPP1601-083			02/03/22	4.00	250.00	3072.78	2400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 87

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00065 Str Bkfl (Flow-Fill) Cubic Yard =====							
BRC040-057			03/17/22	20.00	230.00	677.00	710.00
STR R500-171		Various locations on SH 141 a	03/17/22	12.00	390.00	1003.57	455.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				36.00	285.56	926.38	812.78
NH0504-911			04/07/22	138.00	142.00	298.25	196.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	133.00	395.56	395.56	395.56
WEIGHTED AVERAGE FOR THE SECOND QUARTER				271.00	266.44	329.89	294.19
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	463.44	463.44	463.44
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	137.00	350.00	265.40	281.19
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	178.00	250.00	241.18	214.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				365.00	316.77	254.96	273.39
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	240.00	642.19	169.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	27.00	260.00	316.61	270.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	280.00	823.33	800.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	45.00	260.00	693.33	680.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				87.00	261.15	569.27	537.18
WEIGHTED AVERAGE FOR THE YEAR				759.00	290.95	344.34	336.64
===== 206-00066 Str Bkfl (FF Ash) Cubic Yard =====							
STA0252-459			02/03/22	155.00	257.50	327.05	244.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				155.00	257.50	327.05	244.50
WEIGHTED AVERAGE FOR THE YEAR				155.00	257.50	327.05	244.50
===== 206-00100 Str Bkfl (CL 1) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	365.00	63.00	92.57	71.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00100	Str Bkfl (CL 1)		Cubic Yard	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,678.00	44.00	54.17	43.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	868.00	47.25	48.19	48.19
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,911.00	47.35	58.19	48.06
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20,246.00	74.92	74.92	74.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,242.00	60.00	66.18	66.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	22,183.00	35.00	42.40	36.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43,671.00	54.22	47.45	54.91
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,337.00	78.52	78.52	78.52
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	106.00	100.00	92.12	76.18
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	208.00	40.00	137.33	195.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	363.00	50.00	99.83	75.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	171.00	75.00	121.86	144.58
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,311.00	139.56	109.77	109.77
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	140.00	80.00	80.17	70.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1,283.00	65.00	58.86	53.28
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	265.00	50.00	63.09	70.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9,184.00	82.73	74.25	82.80
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	124.00	85.00	147.25	75.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,397.00	41.00	118.23	145.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	31.00	90.00	235.58	58.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4,078.00	65.00	65.08	42.00
C5502-097		US550 MP 117.28-126.06	11/17/22	259.00	85.00	96.59	98.80
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,200.00	33.00	48.88	49.51
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	12,811.00	80.00	38.37	48.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,234.00	40.00	77.00	60.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	38.00	65.00	155.52	248.91
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	68.20	90.00	139.09	67.96
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	719.00	70.00	89.54	112.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 89

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00100	Str Bkfl (CL 1)		Cubic Yard	=====		
STA385A-016		SH 385 MP 97.76	12/22/22	485.00	50.00	117.50	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		23,444.20	68.02	56.25	56.93
		WEIGHTED AVERAGE FOR THE YEAR		79,210.20	61.36	52.94	58.46
=====	206-00200	Str Bkfl (CL 2)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	145.00	40.00	80.18	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	906.00	31.50	52.97	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	172.00	40.00	31.93	43.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2,374.00	33.29	31.10	31.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,597.00	33.43	47.75	30.64
NH0504-911			04/07/22	174.00	174.00	85.90	51.80
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	689.00	67.14	67.14	67.14
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	235.00	28.00	30.94	19.86
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,117.00	35.00	26.30	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,215.00	55.17	32.39	34.63
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	879.00	46.73	46.73	46.73
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	82.00	37.69	28.56	28.56
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	172.00	35.00	125.67	110.01
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	169.00	41.00	48.02	7.15
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,302.00	43.87	62.06	48.81
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	117.00	50.00	50.37	35.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,665.00	25.00	30.92	51.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	109.00	47.00	58.33	64.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00200							
		Str Bkfl (CL 2)		Cubic Yard			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	113.00	50.00	28.44	22.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	330.00	30.00	41.67	20.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	89.00	60.00	193.76	325.00
STA385A-016		SH 385 MP 97.76	12/22/22	165.00	20.00	80.00	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,588.00	29.67	39.94	52.48
WEIGHTED AVERAGE FOR THE YEAR				9,702.00	38.79	41.97	40.28
===== 206-00360							
		Mechanical Reinforcement of Soil		Cubic Yard			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	365.00	125.00	30.64	34.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,641.00	22.00	24.45	20.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,006.00	40.74	25.20	22.55
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11,728.00	2.11	2.11	2.11
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,050.00	20.00	27.85	24.99
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17,527.00	18.00	14.51	7.25
WEIGHTED AVERAGE FOR THE SECOND QUARTER				30,305.00	11.92	13.90	5.88
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,972.00	0.94	0.94	0.94
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1,283.00	21.00	29.18	48.93
WEIGHTED AVERAGE FOR THE THIRD QUARTER				5,255.00	5.84	20.52	12.66
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,400.00	35.00	35.61	32.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4,370.00	21.00	41.66	30.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9,449.00	10.20	21.75	8.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,420.00	16.00	18.33	20.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	719.00	30.00	42.69	27.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				19,358.00	18.15	29.20	18.85
WEIGHTED AVERAGE FOR THE YEAR				56,924.00	14.49	20.51	11.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 91

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00510 Filter Matl (CL A) Cubic Yard =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	140.00	314.00	845.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	140.00	314.00	845.64
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	70.00	100.00	117.42	118.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	100.00	117.42	118.00
C5502-097		US550 MP 117.28-126.06	11/17/22	74.00	200.00	115.70	156.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	106.00	100.00	146.67	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		180.00	141.11	133.93	146.58
		WEIGHTED AVERAGE FOR THE YEAR		254.00	129.76	131.28	149.71
===== 206-00520 Filter Matl (CL B) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	24.00	45.00	211.06	145.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	45.00	211.06	145.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	45.00	211.06	145.00
===== 206-00530 Filter Matl (CL C) Cubic Yard =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	117.00	125.00	104.90	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		117.00	125.00	104.90	75.00
		WEIGHTED AVERAGE FOR THE YEAR		117.00	125.00	104.90	75.00
===== 206-01001 Bed Course Matl (Spec) Cubic Yard =====							
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	110.00	263.83	256.88
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	110.00	263.83	256.88
		WEIGHTED AVERAGE FOR THE YEAR		5.00	110.00	263.83	256.88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01600 Temp Excav Support LUMP SUM =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	15000.00	22500.00	10000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	15000.00	22500.00	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	22500.00	10000.00
===== 206-01750 Shoring LUMP SUM =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	30000.00	335000.00	55000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	30000.00	335000.00	55000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	30000.00	59686.72	41060.16
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	30000.00	36638.41	52415.22
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	30000.00	48162.56	46737.69
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	85000.00	176537.50	150000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	40000.00	83486.11	30944.44
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	62500.00	130011.81	90472.22
	WEIGHTED AVERAGE FOR THE YEAR			5.00	43000.00	137298.22	65883.96
===== 206-01781 Shoring (A 1) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	142131.28	126000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	44000.00	38880.85	6000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	34500.00	78592.55	66000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	828.18	828.18	828.18

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01781		Shoring (A 1)		LUMP SUM	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	75000.00	50053.34	37400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	51296.27	58691.78
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	55276.06	46572.71	32306.65
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	64075.85	64075.85	64075.85
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	30000.00	88189.92	21319.76
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	62000.00	126917.17	76802.90
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	37637.64	21200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	45268.96	99410.85	45849.63
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	76775.00	95000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	146018.72	95000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	353800.00	74025.00	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	76151.42	57500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	121700.00	86455.66	65625.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	69438.77	79345.35	51909.11
===== 206-01782		Shoring (A 2)		LUMP SUM	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	138233.63	99600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	40000.00	38630.85	5000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	32500.00	76939.62	52300.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	8868.16	8868.16	8868.16
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	35000.00	47134.78	35750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	82518.71	95798.27
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	44622.72	61637.86	46805.48

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 94

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01782 Shoring (A 2) LUMP SUM =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	24000.00	90966.74	45344.24
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	40152.76	21200.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	24500.00	79674.74	33272.12
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	71139.63	90000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	181823.91	95000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	39000.00	57487.50	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	77527.52	61700.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	43000.00	86608.82	65425.00
WEIGHTED AVERAGE FOR THE YEAR				11.00	38169.83	77576.27	52114.61
===== 206-01783 Shoring (A 3) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	58350.22	23000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	16000.00	38269.41	5000.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	20500.00	45992.80	14000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	8868.16	8868.16	8868.16
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	90225.65	83766.73
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.00	14434.08	78603.15	46317.45
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	126000.00	99625.99	97397.01
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	30992.25	23000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	75500.00	84374.04	60198.51

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 95

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01783 Shoring (A 3) LUMP SUM =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	37826.55	8000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	20000.00	82159.08	69000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	19500.00	55762.50	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	75151.42	57500.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	28125.00	57394.84	37375.00
WEIGHTED AVERAGE FOR THE YEAR				10.00	33336.82	62354.93	39053.19
===== 206-01784 Shoring (A 4) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	76866.80	85000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	18000.00	37251.35	4000.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	21500.00	52488.07	44500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	97308.54	88688.37
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	20000.00	97308.54	88688.37
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	24000.00	50685.66	29147.66
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	36022.51	23000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	24500.00	47427.18	26073.83
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	63599.13	55000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	20000.00	92709.77	66000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	76109.77	57400.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				3.00	31000.00	72966.95	59466.67
WEIGHTED AVERAGE FOR THE YEAR				8.00	25625.00	65011.64	51029.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 96

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01785 Shoring (A 5) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	75266.80	85000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	18000.00	37343.35	4000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2.00	21500.00	51929.30	44500.00

2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	78924.19	85264.05
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1.00	65000.00	78924.19	85264.05

2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	142000.00	160488.20	121237.26
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		1.00	142000.00	160488.20	121237.26

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	31686.48	8000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	187192.03	105000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	118230.32	98100.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		3.00	43666.67	87888.72	70366.67
	WEIGHTED AVERAGE FOR THE YEAR			7.00	54428.57	87577.69	72371.62
===== 206-01786 Shoring (A 6) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	77066.80	85000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	42000.00	37382.97	4000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2.00	33500.00	52645.98	44500.00

2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	85503.47	86618.50
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1.00	65000.00	85503.47	86618.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 97

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01786 Shoring (A 6) LUMP SUM =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	96000.00	99755.37	99228.20
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	96000.00	99755.37	99228.20
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	31973.98	8000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	129759.69	125000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	116658.12	89600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	43666.67	76772.60	74200.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	51285.71	74382.57	71063.81
===== 206-01787 Shoring (A 7) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	58891.25	22000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	25000.00	58891.25	22000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	87353.19	80373.69
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	87353.19	80373.69
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	17069.53	32700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	17069.53	32700.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	18333.33	62127.43	45024.56
===== 206-01788 Shoring (A 8) LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	94561.48	88073.17
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	94561.48	88073.17
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	94561.48	88073.17

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01789 Shoring (A 9) LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	87599.07	97733.18
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	90000.00	87599.07	97733.18
		WEIGHTED AVERAGE FOR THE YEAR		1.00	90000.00	87599.07	97733.18
===== 206-01790 Shoring (A 10) LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	95730.30	94000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	90000.00	95730.30	94000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	90000.00	95730.30	94000.00
===== 206-01791 Shoring (A 11) LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	50000.00	138220.45	103000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	138220.45	103000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	138220.45	103000.00
===== 206-01803 Shoring (A 23) LUMP SUM =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	31720.06	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	31720.06	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	31720.06	33715.23	33715.23
===== 206-01804 Shoring (A 24) LUMP SUM =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	39247.42	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	39247.42	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	39247.42	33715.23	33715.23
===== 206-01805 Shoring (A 25) LUMP SUM =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	36947.87	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	36947.87	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	36947.87	33715.23	33715.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 99

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01806 Shoring (A 26) LUMP SUM =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	33633.23	33715.23	33715.23
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	33633.23	33715.23	33715.23
	WEIGHTED AVERAGE FOR THE YEAR			1.00	33633.23	33715.23	33715.23
===== 207-00205 Topsoil Cubic Yard =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	235.00	20.00	41.83	13.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			235.00	20.00	41.83	13.00
	WEIGHTED AVERAGE FOR THE YEAR			235.00	20.00	41.83	13.00
===== 207-00210 Stockpile Topsoil Cubic Yard =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	396.00	8.00	27.44	18.75
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			396.00	8.00	27.44	18.75
	WEIGHTED AVERAGE FOR THE YEAR			396.00	8.00	27.44	18.75
===== 207-00305 Wetland Topsoil Cubic Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	82.00	115.08	115.08	115.08
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			82.00	115.08	115.08	115.08
===== 207-00310 Stockpile Wetland Topsoil Cubic Yard =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	25.00	104.23	25.60
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	25.00	104.23	25.60
	WEIGHTED AVERAGE FOR THE YEAR			50.00	25.00	104.23	25.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 100

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00700		Topsoil (Onsite)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	544.00	10.00	16.76	15.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10,350.00	15.00	18.10	14.00
NHPP1601-083			02/03/22	12,298.00	6.00	8.49	9.00
C0762-055			02/17/22	2,581.00	10.00	17.55	1.25
STR0141-031			02/17/22	333.00	50.00	36.67	25.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4,073.00	15.00	15.53	11.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				30,179.00	11.20	15.59	10.61
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4,832.00	30.72	30.72	30.72
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	41,631.00	18.00	9.68	4.81
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,694.00	10.00	25.47	27.75
STA0712-019		SH 71: Frieight Improvements	05/12/22	7,704.00	12.00	5.08	5.08
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	10.00	12.00	54.35	35.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3,028.00	17.00	18.33	15.00
CM760-047		COLFAX AND QUAIL	05/12/22	7.00	25.00	110.20	95.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,460.00	12.00	5.13	4.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	200.00	130.00	120.00	120.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	60.00	25.00	31.67	45.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3,767.00	15.00	13.24	6.30
WEIGHTED AVERAGE FOR THE SECOND QUARTER				65,393.00	17.93	11.12	8.28
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,840.00	33.46	33.46	33.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	161.00	30.00	48.75	36.17
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	17.00	81.67	35.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	298.00	30.00	34.30	25.90
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4,316.00	29.47	29.56	29.56
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,500.00	25.00	31.09	20.77
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	587.00	15.00	53.55	95.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,673.00	26.00	24.88	40.12
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,203.00	20.00	21.08	32.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3,896.00	40.00	42.21	41.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				23,514.00	29.78	28.39	34.86
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	589.00	11.20	53.40	52.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 101

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00700 Topsoil (Onsite) Cubic Yard =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	60.00	170.25	72.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	396.00	40.00	29.31	18.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9,820.00	10.00	14.46	8.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	21,156.00	5.00	3.75	3.75
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,912.00	45.00	33.18	23.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	670.00	13.40	49.39	45.18
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	565.00	30.00	26.20	13.30
C5502-097		US550 MP 117.28-126.06	11/17/22	34,848.00	20.00	13.08	15.20
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	320.00	25.00	44.05	52.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,689.00	15.00	15.73	22.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	242.00	24.00	41.77	26.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,252.00	45.10	30.59	18.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	40.00	15.80	125.50	66.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,023.00	30.00	25.00	14.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,453.00	35.00	22.40	18.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	716.00	20.00	36.78	18.45
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	7,260.00	35.00	14.74	5.77
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	575.00	30.00	32.36	18.12
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	304.00	30.00	95.37	135.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,580.00	15.00	31.00	20.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				91,460.00	18.47	16.62	13.99
WEIGHTED AVERAGE FOR THE YEAR				210,546.00	18.52	15.56	14.06
===== 207-00702 Topsoil (Offsite) Cubic Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	118.00	50.00	53.69	55.00
C0761-239							
BRC040-057			03/17/22	80.00	50.00	262.75	140.00
NHM765-007			03/31/22	10.00	100.00	183.24	190.76
WEIGHTED AVERAGE FOR THE FIRST QUARTER				208.00	52.40	108.39	94.22
NH0504-911			04/07/22	1,500.00	82.00	56.05	47.10
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,500.00	82.00	56.05	47.10
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	210.00	40.00	213.73	170.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				210.00	40.00	213.73	170.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 102

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00702 Topsoil (Offsite) Cubic Yard =====							
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	150.00	76.10	113.32	134.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	20.00	76.10	155.16	197.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	355.00	120.00	86.40	45.10
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	444.00	140.00	103.67	90.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			969.00	121.46	102.64	87.37
	WEIGHTED AVERAGE FOR THE YEAR			2,887.00	90.06	92.00	73.05
===== 207-00703 Topsoil (Wetlnd) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	17.00	60.00	104.39	46.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.00	60.00	104.39	46.25
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	900.00	47.66	47.66	47.66
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	30.00	54.24	50.73
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,000.00	45.89	49.30	47.96
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	50.00	78.97	41.00
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	20.00	82.00	80.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			200.00	27.50	81.24	70.25
	WEIGHTED AVERAGE FOR THE YEAR			1,217.00	43.07	64.77	51.60
===== 207-00704 Sub Soil Prep Sq Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	12,100.00	2.00	1.69	1.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,320.00	5.00	3.43	2.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 103

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	207-00704	Sub Soil Prep		Sq Yard	=====	=====	=====
NHPP1601-083			02/03/22	57,112.00	0.50	1.66	2.00
C0762-055			02/17/22	14,520.00	2.00	2.03	2.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	25,091.00	2.00	1.37	2.50
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				110,143.00	1.26	1.61	2.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	249,787.00	0.50	0.50	0.52
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,872.00	2.50	4.01	3.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	46,222.00	2.00	0.37	0.37
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	15,004.00	2.50	1.92	0.75
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	14,762.00	2.00	1.50	2.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				329,647.00	0.89	0.62	0.61
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	968.00	2.50	8.24	6.85
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	300.00	2.00	25.50	7.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	25,894.00	2.41	2.90	2.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1,207.00	3.00	9.62	5.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	23,377.00	2.50	4.40	1.50
WEIGHTED AVERAGE FOR THE THIRD QUARTER				51,746.00	2.46	4.53	2.41
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2,372.00	3.00	5.97	1.88
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	58,919.00	2.00	0.91	0.30
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	190,406.00	0.60	1.05	1.05
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	17,476.00	2.00	2.92	2.30
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	4,017.00	3.00	6.71	3.62
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	3,388.00	3.80	2.52	1.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24,200.00	1.00	1.31	1.55
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,460.00	1.60	2.37	1.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10,572.00	5.00	1.84	3.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12,100.00	2.00	1.33	0.40
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	7,580.00	2.00	3.10	6.15
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4,187.00	5.00	3.15	3.25
STA385A-016		SH 385 MP 97.76	12/22/22	14,520.00	1.00	2.31	1.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				351,197.00	1.29	1.52	1.21
WEIGHTED AVERAGE FOR THE YEAR				842,733.00	1.20	1.22	1.16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00706 Seeding Media Cubic Yard =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,289.00	50.00	32.50	19.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,289.00	50.00	32.50	19.00
	WEIGHTED AVERAGE FOR THE YEAR			1,289.00	50.00	32.50	19.00
===== 208-00002 Erosion Log Type 1 (12 In) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10,960.00	6.25	6.37	10.50
NHPP1601-083			02/03/22	11,032.00	10.00	5.91	6.00
STR0141-031			02/17/22	500.00	8.00	10.47	10.41
NHPP0063-063			02/24/22	150.00	6.00	10.33	15.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	420.00	6.00	6.53	5.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,000.00	5.00	6.16	5.31
STR R500-171		Various locations on SH 141 a	03/17/22	100.00	6.00	13.79	30.00
STR092A-031			03/17/22	1,850.00	8.00	6.00	6.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			26,012.00	7.94	6.36	8.08
NH0504-911			04/07/22	300.00	5.00	4.08	2.90
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10,000.00	5.67	5.67	5.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	68,080.00	4.50	5.87	4.24
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	120.00	5.00	6.11	6.63
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,000.00	6.00	7.18	8.35
STA0712-019		SH 71: Frieght Improvements	05/12/22	4,300.00	5.00	4.88	4.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	300.00	5.00	5.30	5.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,580.00	5.00	7.57	7.70
C0852-120		Rehabilitation of Culvert by	05/26/22	850.00	10.00	4.00	4.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1,000.00	11.00	10.00	10.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1,400.00	7.00	13.00	12.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	200.00	5.00	7.90	7.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	5.00	31.11	31.11
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	9,660.00	8.00	5.25	5.15
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	125.00	10.00	9.66	9.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			99,015.00	5.16	5.87	4.80
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7,500.00	7.16	7.16	7.16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00002		Erosion Log Type 1 (12 In)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	600.00	7.00	6.94	6.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	4.84	56.17	15.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,150.00	4.00	6.27	4.75
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2,171.00	8.00	5.97	7.30
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	96.00	10.00	18.00	25.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	875.00	10.00	8.01	7.03
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	8,536.00	8.56	10.90	10.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	700.00	10.00	6.58	8.40
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	40.00	10.00	17.49	21.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,351.00	6.00	8.95	7.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	5,000.00	6.00	6.76	8.68
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20,395.00	6.00	6.29	4.86
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,561.00	6.00	10.24	15.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		52,005.00	6.73	6.82	7.21
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	300.00	8.00	11.00	12.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	100.00	7.00	18.13	31.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	250.00	6.00	12.69	13.75
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	40.00	15.00	27.50	15.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	900.00	6.50	7.75	7.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,136.00	5.00	5.80	6.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8,000.00	15.00	6.83	11.50
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	800.00	8.50	5.83	6.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	230.00	8.00	8.08	6.25
C5502-097		US550 MP 117.28-126.06	11/17/22	3,500.00	6.00	6.79	5.65
MPR200-280		PUEBLO AREA	11/17/22	1,000.00	5.00	5.13	8.25
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	750.00	8.00	7.30	8.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	16,622.00	5.00	5.70	6.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	350.00	6.00	6.48	8.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	800.00	10.00	7.85	10.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	400.00	5.00	6.96	5.20
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	150.00	12.00	12.75	13.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6,160.00	5.00	6.00	5.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	788.00	5.00	7.73	8.45
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	250.00	7.00	9.98	10.20
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2,365.00	5.00	6.17	5.73
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,270.00	7.00	7.29	7.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	5.00	5.40	4.70
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	500.00	10.00	6.75	8.14
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	25.00	6.13	5.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 106

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00002 Erosion Log Type 1 (12 In) Lin Foot =====							
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,480.00	8.50	5.87	5.65
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	120.00	7.90	9.53	12.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			55,261.00	7.11	6.27	7.26
	WEIGHTED AVERAGE FOR THE YEAR			232,293.00	6.29	6.22	6.30
===== 208-00004 Silt Berm Lin Foot =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	75.00	16.04	16.04
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,000.00	0.50	12.00	19.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,012.00	1.38	12.02	18.96
	WEIGHTED AVERAGE FOR THE YEAR			1,012.00	1.38	12.02	18.96
===== 208-00008 Erosion Log Type 2 (12 In) Lin Foot =====							
NH0504-911			04/07/22	300.00	5.57	6.65	5.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			300.00	5.57	6.65	5.80
SHE0242-087 US 24 SAFETY IMPRVMTS, E OF 11/03/22 3,115.00 8.00 8.95 9.85							
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,115.00	8.00	8.95	9.85
	WEIGHTED AVERAGE FOR THE YEAR			3,415.00	7.79	8.81	9.49
===== 208-00009 Erosion Log Type 2 (18 In) Lin Foot =====							
STA0252-459			02/03/22	900.00	10.00	12.67	11.30
NHM765-007			03/31/22	100.00	8.00	22.31	16.19
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,000.00	9.80	13.64	11.79
2670703-497 I-70_GENESEE WILDLIFE XING 09/15/22 50.00 7.00 14.70 22.76							
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	7.00	14.70	22.76

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 107

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00009 Erosion Log Type 2 (18 In) Lin Foot =====							
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	330.00	14.00	15.17	16.52
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			330.00	14.00	15.17	16.52
	WEIGHTED AVERAGE FOR THE YEAR			1,380.00	10.70	14.07	13.32
===== 208-00011 Erosion Bales (Weed Free) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	10.00	37.62	43.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20.00	10.00	37.62	43.75
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	48.00	40.00	41.88	34.64
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	40.00	65.57	75.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	50.00	54.25	20.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			78.00	41.28	48.32	43.11
	WEIGHTED AVERAGE FOR THE YEAR			98.00	34.90	43.86	43.24
===== 208-00012 Erosion Log Type 1 (9 In) Lin Foot =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	200.00	22.00	19.00	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			200.00	22.00	19.00	25.00
NH0504-911			04/07/22	300.00	13.00	6.90	10.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			300.00	13.00	6.90	10.80
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	5.80	56.17	15.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			30.00	5.80	56.17	15.00
	WEIGHTED AVERAGE FOR THE YEAR			530.00	15.99	15.41	16.40

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 108

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00013 Erosion Log Type 1 (20 In) Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	790.00	6.00	8.71	8.75
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,460.00	8.90	8.73	13.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,250.00	8.36	8.73	12.21
NH0504-911			04/07/22	300.00	8.00	9.00	8.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	23.61	23.61	23.61
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,000.00	10.00	11.00	12.00
C0852-120		Rehabilitation of Culvert by	05/26/22	300.00	10.00	7.00	7.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	8.00	33.70	33.70
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,800.00	10.31	11.36	12.35
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,000.00	12.11	12.11	12.11
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	16.00	14.42	13.72
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	60.00	10.00	11.51	11.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2,755.00	8.00	11.63	15.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3,915.00	9.28	11.81	14.17
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	60.00	12.00	14.67	8.10
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	400.00	8.00	9.35	6.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,180.00	12.00	9.52	9.37
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	400.00	6.00	11.53	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,000.00	7.00	11.25	10.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5,040.00	9.22	10.30	9.84
WEIGHTED AVERAGE FOR THE YEAR				15,005.00	9.13	9.88	11.94
===== 208-00016 Erosion Log Type 1 (Special) (12 In) Lin Foot =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	900.00	10.00	7.75	8.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				900.00	10.00	7.75	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 109

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00016 Erosion Log Type 1 (Special) (12 In) Lin Foot =====							
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	2,475.00	6.00	5.75	5.75
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,475.00	6.00	5.75	5.75
	WEIGHTED AVERAGE FOR THE YEAR			3,375.00	7.07	6.59	6.35
===== 208-00017 Erosion Log Type 2 BioD Netting (12 In) Lin Foot =====							
C0762-055			02/17/22	4,980.00	5.00	7.84	9.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,980.00	5.00	7.84	9.50
	WEIGHTED AVERAGE FOR THE YEAR			4,980.00	5.00	7.84	9.50
===== 208-00020 Silt Fence Lin Foot =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	200.00	4.00	3.79	2.50
NHPP1601-083			02/03/22	1,547.00	5.00	4.57	3.00
STA0252-459			02/03/22	5,000.00	1.69	3.24	1.30
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	16,270.00	2.25	2.04	1.25
C0761-239							
STR R500-171	Various locations on SH 141 a		03/17/22	100.00	3.00	3.58	5.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23,117.00	2.33	2.23	1.40
NH0504-911			04/07/22	4,600.00	5.00	1.50	1.50
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	1,455.00	2.50	1.65	1.60
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	1,580.00	4.00	6.05	3.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,635.00	4.32	2.51	1.86
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	200.00	2.00	14.25	5.75
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	500.00	2.00	2.48	3.50
ER0253-297	WCR 34 BRIDGE OVER I-25(MM 24		09/14/22	200.00	3.00	3.32	2.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 110

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00020	Silt Fence			Lin Foot	=====		
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22		1,600.00	2.10	3.08	1.32
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,500.00	2.14	3.56	2.17
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22		2,600.00	4.00	3.42	3.75
C170A-002	CRITICAL CULVERT CONST. PKG D	10/27/22		825.00	3.00	3.06	2.25
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		100.00	2.00	5.19	8.00
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22		1,750.00	2.25	2.21	1.62
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22		1,200.00	2.50	3.23	2.45
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		250.00	1.50	3.63	5.81
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		4,099.00	7.60	2.57	1.40
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		870.00	2.00	2.87	1.60
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22		1,490.00	3.00	3.66	5.31
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22		400.00	3.00	6.69	10.00
STA385A-016	SH 385 MP 97.76	12/22/22		500.00	5.00	4.25	6.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			14,084.00	4.36	2.66	2.52
	WEIGHTED AVERAGE FOR THE YEAR			47,336.00	3.25	2.46	1.99
===== 208-00021	Silt Fence (Reinf)			Lin Foot	=====		
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22		1,500.00	5.00	5.06	5.00
BRC040-057		03/17/22		706.00	10.00	4.76	3.54
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,206.00	6.60	4.94	4.53
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22		100.00	16.09	16.09	16.09
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		4,545.00	3.00	5.90	3.25
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22		100.00	3.00	4.97	5.58
C0852-120	Rehabilitation of Culvert by	05/26/22		300.00	10.00	4.00	4.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,045.00	3.68	5.90	3.60
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22		100.00	22.35	22.35	22.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 111

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00021	Silt Fence (Reinf)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	6.00	7.40	8.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	386.00	5.00	7.38	7.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		586.00	8.13	8.29	9.79
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	792.00	8.00	7.15	9.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	850.00	3.50	5.83	6.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA385A-016		SH 385 MP 97.76	12/22/22	1,500.00	7.00	7.75	6.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,142.00	6.31	7.07	6.87
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		10,979.00	5.25	6.14	5.05
=====	208-00023	Erosion Log (Type 3) (12 In)		Lin Foot	=====		
STA0252-459			02/03/22	200.00	7.13	5.84	5.08
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	7.13	5.84	5.08
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,668.00	6.70	6.89	6.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	755.00	5.50	8.88	8.75
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,423.00	6.50	7.23	6.47
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		4,623.00	6.52	7.19	6.41
=====	208-00024	Erosion Log (Type 3) (20 In)		Lin Foot	=====		
NHPP0703-472			03/10/22	100.00	7.00	19.21	40.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	7.00	19.21	40.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	400.00	8.40	19.01	33.36
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		400.00	8.40	19.01	33.36
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		500.00	8.12	19.03	34.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 112

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00026 Coir Roll Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	130.00	50.05	50.05	50.05
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		130.00	50.05	50.05	50.05
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	780.00	23.45	23.45	23.45
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		780.00	23.45	23.45	23.45
		WEIGHTED AVERAGE FOR THE YEAR		910.00	27.25	27.25	27.25
===== 208-00027 Silt Fence (Type 2) Lin Foot =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3,500.00	5.00	4.35	4.35
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,500.00	5.00	4.35	4.35
		WEIGHTED AVERAGE FOR THE YEAR		3,500.00	5.00	4.35	4.35
===== 208-00033 Sediment Trap Each =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	2500.00	3707.09	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	3707.09	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	3707.09	1200.00
===== 208-00035 Aggregate Bag Lin Foot =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	120.00	10.00	23.00	23.00
MTCE R500-218			01/06/22	100.00	10.00	11.88	7.75
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	484.00	9.00	11.01	7.67
STR0505-050			01/13/22	80.00	6.00	65.33	150.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	600.00	10.00	11.86	18.00
STA0252-459			02/03/22	200.00	10.00	7.20	6.65
C0762-055			02/17/22	600.00	7.00	7.48	8.75
STR0141-031			02/17/22	100.00	15.00	8.58	7.75

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	208-00035	Aggregate Bag		Lin Foot	=====	=====	=====
STR133A-051			02/17/22	250.00	10.00	13.80	13.00
NHPP0063-063			02/24/22	900.00	8.00	12.30	11.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	250.00	6.00	10.44	10.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	90.00	9.00	9.92	7.25
C0761-239							
NHPP0703-472			03/10/22	100.00	9.00	11.30	14.00
BRC040-057			03/17/22	176.00	12.00	11.61	9.45
STR R500-171		Various locations on SH 141 a	03/17/22	100.00	14.00	10.28	5.00
STR092A-031			03/17/22	100.00	10.00	8.75	8.75
NHM765-007			03/31/22	600.00	11.00	15.48	8.61
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,850.00	9.23	12.07	13.05
<hr/>							
NH0504-911			04/07/22	400.00	9.00	9.60	10.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,000.00	13.37	13.37	13.37
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	690.00	8.50	10.24	9.50
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	200.00	10.00	13.12	11.24
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	72.00	10.00	9.64	10.39
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	400.00	11.00	16.00	15.00
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	60.00	9.00	6.70	6.50
CM760-047		COLFAX AND QUAIL	05/12/22	72.00	15.50	27.70	20.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	300.00	10.00	16.75	18.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	25.00	20.00	17.20	13.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	15.00	12.00	12.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	22.00	17.00	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	15.00	13.00	12.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	440.00	10.00	29.67	29.67
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,500.00	6.00	7.38	7.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	150.00	12.00	27.17	6.50
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	50.00	25.00	20.00	20.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	35.00	15.00	17.06	23.12
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	290.00	20.00	19.53	7.60
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5,904.00	10.48	11.74	12.24
<hr/>							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	8.61	8.61	8.61
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	200.00	15.00	11.95	13.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	12.00	23.67	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,404.00	8.00	10.65	8.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	100.00	12.00	10.17	13.50
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	102.00	15.00	17.00	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00035 Aggregate Bag Lin Foot =====							
BR0343-046	US 34	TIMBER BRIDGE REPL. PKG	08/31/22	108.00	8.58	10.35	10.35
FBR0343-047	US 6/US 34	TIMBER BRIDGE REPL					
STAR100-374	5	STRUCTURES IN REGION 1	09/01/22	25.00	20.00	12.34	12.34
NHPPR100-266	R1	ESSENTIAL REPAIRS	09/01/22	500.00	12.00	12.59	14.46
PAN0761-245	ALONG I-76 &	RAMPS MILEPOST 9	09/01/22	100.00	20.00	23.50	13.00
ER0253-297	WCR 34	BRIDGE OVER I-25(MM 24	09/14/22	180.00	12.00	12.60	5.00
2670403-065	US40	FLOYD HILL ROUNDABOUTS	09/15/22	2,802.00	12.00	13.51	14.00
SHE2873-193	US 287 & CO 52	INTERSECTION I	09/15/22	700.00	8.00	14.46	7.49
NHPP0701-231	I-70	SALT WASH BRIDGES SCOUR	09/29/22	100.00	10.00	9.14	5.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6,521.00	10.86	13.31	11.61
MTCE0253-281	MTCE FY23 I-25	CONC PANEL REP	10/06/22	400.00	12.00	19.27	10.00
NHPP0821-114	SH 82	ASPEN/INDEPENDENCE PASS	10/13/22	150.00	15.00	20.00	27.00
C0831-126	SH83	EL PASO COUNTY TO BAYOU	10/13/22	100.00	15.00	12.50	15.00
NHPP0701-253	I-70	EAST OF DEBEQUE	10/27/22	50.00	12.00	23.80	35.00
FSAM240-200	SH21B	CO SPRINGS SIGNAL REPLA	10/27/22	60.00	12.00	18.15	11.60
C5502-111	US 550 MP 81	AND 89 RED MOUNT	10/27/22	40.00	16.00	35.00	30.00
TRG0253-264	I-25	AND SH 119 PARK-N-RIDE	10/27/22	48.00	10.00	11.87	15.00
STA3852-015	US 385	HOLYOKE NORTH	10/27/22	2,500.00	8.00	7.85	7.85
NHPP0343-048	US 34 (MP 169.3-171.4)		11/01/22	82.00	14.00	19.89	18.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	3,040.00	20.00	9.43	13.00
STR064A-010	SH 64	AND SH 13 AT MEEKER	11/10/22	250.00	40.00	10.85	9.00
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	200.00	10.00	9.80	8.30
C5502-097	US550 MP 117.28-126.06		11/17/22	1,100.00	10.00	11.86	13.00
STRC090-011	US 50B	AND SH71/CR18 INTERSEC	11/17/22	48.00	10.00	13.05	12.10
STAM420-001	US 285	AT HWY 9C IMPROVEMENTS	12/01/22	1,240.00	13.05	8.60	9.83
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71:	REGION LINE NORTH	12/01/22	300.00	9.00	9.79	11.00
STR114A-015	SH114	SILLSVILLE SOUTH TO MP3	12/01/22	150.00	15.00	12.50	15.00
2670703-487	I-70	BRIDGES OVER WARD ROAD-	12/01/22	240.00	8.70	11.76	7.80
NHPP0701-252	I-70	RIFLE TO SILT SLAB REPLA	12/01/22	150.00	15.00	13.27	8.54
IM025A-050	I25-MP103.9 -	INTERSECTION DR	12/01/22	119.00	9.00	11.00	8.00
STR318A-001	SH 318 MP 0 - 12.5	MOFFAT COU	12/01/22	150.00	20.00	25.50	20.00
STR109A-019	M-22-AY	BRIDGE REHAB ON SH109	12/01/22	1,184.00	10.00	10.06	11.11
NHPP0021-041	SH2	RESURFACING MLK TO 52ND	12/01/22	120.00	12.00	9.37	9.82
STR0641-107	SH 13	MM 104-128.1 IN MOFFAT	12/01/22	100.00	20.00	25.33	15.00
NHPP083A-046	SH83	RESURFACING STROH RD TO	12/08/22	500.00	11.50	9.92	8.84
NHPP0063-048	US6 / 20	ROAD INTERSECTION IM	12/15/22	100.00	20.00	12.73	23.00
NHM175-029	CANON CITY, CO		12/15/22	80.00	12.00	10.00	15.00
NHPP0931-033	SH93:US6 TO 58TH	RESURFACING	12/15/22	300.00	9.00	8.71	7.70
STR0092-024	SH 9	North of Silverthorne	12/22/22	100.00	30.00	18.10	13.20
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				12,901.00	13.62	11.12	11.55
=====							
WEIGHTED AVERAGE FOR THE YEAR				30,176.00	11.70	11.90	11.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 115

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00041 Rock Check Dam Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	39.00	900.00	1262.72	1000.00
BRC040-057			03/17/22	1.00	1000.00	2980.25	6714.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	902.50	1297.24	1142.85

NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5000.00	3574.15	6500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	5000.00	3574.15	6500.00

NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	8.00	1200.00	2337.19	3500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	750.00	1360.00	980.00
STA385A-016		SH 385 MP 97.76	12/22/22	4.00	500.00	1337.50	600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14.00	935.71	1808.76	2033.75
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1057.14	1451.29	1573.34
===== 208-00045 Conc Washout Str Each =====							
NHPP1601-083			02/03/22	3.00	1500.00	2720.56	1500.00
MP0503-098			03/24/22	1.00	1500.00	580.00	250.00
NHM765-007			03/31/22	2.00	5000.00	1794.15	1140.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	4000.00	3310.00	4000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	2857.14	2179.26	1575.71

MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	2000.00	4905.16	4210.31
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	3200.00	803.79	803.79
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	3000.00	766.67	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2850.00	1959.70	1479.47

BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	3424.00	2893.68	2893.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 116

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00045 Conc Washout Str Each =====							
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	3000.00	2249.00	2400.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10.00	3254.40	2463.89	2696.21
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	5000.00	4091.83	5500.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	2000.00	2364.84	2600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2000.00	3996.41	1900.00
MPR200-280		PUEBLO AREA	11/17/22	1.00	1850.00	1450.00	2500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	2909.00	2937.01	3898.02
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	2700.00	2070.00	860.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	2000.00	2637.88	2170.76
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				20.00	2474.75	2963.16	2664.44
WEIGHTED AVERAGE FOR THE YEAR				41.00	2766.80	2725.22	2377.69
===== 208-00046 Pre-fab Conc Washout Str (Type 1) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	1600.00	3491.14	3641.09
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	1.00	2000.00	2266.06	500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	1500.00	4670.52	6500.00
STA0252-459			02/03/22	6.00	2000.00	3698.00	2050.00
C0762-055			02/17/22	2.00	1500.00	2987.66	2500.00
NHPP0063-063			02/24/22	4.00	3000.00	1519.50	2300.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	3000.00	1055.10	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	3000.00	4493.82	1100.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2050.00	2452.09	2000.00
BRC040-057			03/17/22	4.00	1500.00	2476.43	498.72
STR R500-171		Various locations on SH 141 a	03/17/22	2.00	790.00	2114.08	2500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	10800.00	6566.00	10828.00
STR092A-031			03/17/22	1.00	3500.00	3000.00	3000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				34.00	2372.94	3473.13	2482.50
NH0504-911			04/07/22	8.00	5000.00	595.00	590.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	10903.84	10903.84	10903.84

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00046		Pre-fab Conc Washout Str (Type 1)		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	1370.00	3609.26	2500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1800.00	5943.34	2198.06
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	2100.00	4833.33	3500.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	1900.00	2338.60	1678.00
C0852-120		Rehabilitation of Culvert by	05/26/22	3.00	5000.00	960.00	960.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2.00	1500.00	2500.00	2500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	500.00	1289.50	550.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	2000.00	2871.75	2871.75
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	2500.00	5667.83	3185.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	10.00	600.00	882.50	1.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	2691.65	2492.30	1721.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	11174.01	11174.01	11174.01
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	2100.00	2516.67	2000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2500.00	5500.69	6250.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	1800.00	6500.00	10000.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	2500.00	1780.00	2000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	3000.00	1333.18	2349.55
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	1200.00	2948.11	3144.33
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	3000.00	6018.71	1200.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	2500.00	6357.03	5319.11
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	3000.00	4734.80	1500.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	2200.00	1531.47	2500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	3252.40	4179.42	4000.27
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	1.00	2500.00	2000.00	2500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2.00	3000.00	2365.00	3095.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	2000.00	1992.50	1450.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	2000.00	4000.00	6500.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	5000.00	2547.50	1000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	15.00	5000.00	1855.58	3400.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	2000.00	2200.00	2500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	4000.00	1584.05	541.00
STR090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	2500.00	1070.00	1390.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	3500.00	2750.00	3000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	3070.80	4982.04	2750.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	2373.00	5562.50	5800.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	2.00	3500.00	4830.71	2602.59
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	2000.00	6461.44	2522.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 118

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 208-00046		Pre-fab Conc Washout Str (Type 1)		Each =====			
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	3000.00	1713.37	1950.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	2000.00	2249.76	2560.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.00	2500.00	2680.19	4054.52
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	5000.00	3052.00	604.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	3000.00	3276.72	2500.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	1000.00	3812.50	1000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	2500.00	2283.33	2300.00
				<hr/>			
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		50.00	3427.75	2718.02	2745.02
				<hr/>			
		WEIGHTED AVERAGE FOR THE YEAR		145.00	2948.09	3058.81	2568.34
<hr/>							
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	100.00	20.00	24.76	37.00
NHPP0063-063			02/24/22	54.00	20.00	21.30	29.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	500.00	19.00	11.75	10.00
C0761-239							
BRC040-057			03/17/22	14.00	15.00	23.79	18.15
				<hr/>			
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		668.00	19.15	13.51	15.75
<hr/>							
NH0504-911			04/07/22	50.00	13.00	14.30	13.60
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	42.00	15.00	10.32	10.39
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	40.00	30.00	23.00	21.00
				<hr/>			
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		132.00	18.79	13.59	14.82
<hr/>							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	290.00	12.00	17.14	13.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	68.00	30.00	28.00	31.00
				<hr/>			
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		358.00	15.42	19.21	16.42
<hr/>							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	72.00	20.00	22.35	22.05
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	10.00	18.56	17.25
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	175.00	10.00	10.24	11.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	32.00	25.00	18.79	39.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 119

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot	=====		
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	117.00	20.00	15.70	16.16
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			556.00	14.26	14.25	16.93
	WEIGHTED AVERAGE FOR THE YEAR			1,714.00	16.76	14.23	16.20
===== 208-00052		Storm Drain Inlet Protection (Type II)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	20.00	75.57	107.00
STR092A-031			03/17/22	70.00	70.00	11.00	11.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	180.00	80.00	30.25	12.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			270.00	72.96	36.26	19.11
NH0504-911			04/07/22	100.00	18.00	25.70	26.40
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	40.00	60.00	82.50	76.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			140.00	30.00	41.93	40.57
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	49.00	15.00	57.26	43.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			49.00	15.00	57.26	43.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	162.00	50.00	63.52	73.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			162.00	50.00	60.72	71.39
	WEIGHTED AVERAGE FOR THE YEAR			621.00	52.71	52.07	46.89
===== 208-00053		Storm Drain Inlet Protect (Ty I) (84 In)		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	220.00	243.93	169.71
NHM765-007			03/31/22	12.00	120.00	240.37	173.64
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	134.29	241.01	173.08

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 120

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00053 Storm Drain Inlet Protect (Ty I) (84 In) Each =====							
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	250.00	295.00	295.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	33.00	190.00	485.45	485.45
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	193.43	474.57	474.57
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	20.00	275.65	323.94
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	7.00	150.00	283.06	140.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	205.00	286.58	197.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	141.67	283.03	166.77
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	38.00	180.00	194.30	176.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	175.00	203.33	210.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	250.00	240.17	237.34
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	9.00	200.00	205.05	225.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		57.00	184.91	197.94	191.01
		WEIGHTED AVERAGE FOR THE YEAR		115.00	177.96	241.42	273.23
===== 208-00054 Storm Drain Inlet Protection (Type II) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	98.00	280.00	215.24	214.13
NHPP0063-063			02/24/22	174.00	260.00	125.50	115.00
NHM765-007			03/31/22	22.00	200.00	321.15	283.21
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		294.00	262.18	185.16	160.63
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17.00	300.00	220.09	266.56
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	300.00	293.40	348.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	240.00	911.20	911.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	274.55	303.00	544.98

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 121

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00054 Storm Drain Inlet Protection (Type II) Each =====							
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	300.00	348.21	348.21
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	20.00	268.78	313.34
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	5.00	55.00	346.40	240.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				8.00	111.88	334.94	276.22
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	54.00	250.00	220.65	211.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	295.00	296.73	337.52
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	400.00	320.53	200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	300.00	233.33	200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	30.00	350.00	289.26	251.67
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	250.00	274.81	205.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				108.00	288.66	259.48	239.57
WEIGHTED AVERAGE FOR THE YEAR				443.00	266.84	219.39	210.59
===== 208-00055 Rigid Inlet Prot Device Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	150.00	905.00	905.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	400.00	453.09	450.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				11.00	172.73	800.71	863.64
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	500.00	526.54	313.05
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1.00	500.00	526.54	313.05
WEIGHTED AVERAGE FOR THE YEAR				12.00	200.00	736.20	817.75
===== 208-00056 Storm Drain Inlet Protection (Type III) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	300.00	510.00	510.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 122

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00056	Storm Drain Inlet Protection (Type III)			Each =====			
STA0252-459			02/03/22	100.00	260.00	166.20	130.00
NHPP0063-063			02/24/22	48.00	280.00	116.50	115.00
NHPP0703-472			03/10/22	30.00	350.00	209.79	250.00
BRC040-057			03/17/22	36.00	300.00	296.88	208.50
NHM765-007			03/31/22	10.00	300.00	344.67	326.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			234.00	285.21	206.30	179.01
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	30.00	320.00	159.78	177.71
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	1.00	400.00	230.50	213.00
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV		06/23/22	36.00	250.00	288.00	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			67.00	283.58	216.85	163.35
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	30.00	150.00	386.13	290.00
NHPPR100-266	R1 ESSENTIAL REPAIRS		09/01/22	6.00	20.00	284.81	244.44
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	6.00	350.00	325.97	145.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			42.00	160.00	355.85	262.78
NHPP0705-088	I-70 AGATE STRUCTURE REHAB		10/27/22	2.00	260.00	406.44	312.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	7.00	220.00	266.71	267.73
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	4.00	250.00	180.00	140.00
NHPP083A-046	SH83 RESURFACING STROH RD TO		12/08/22	3.00	500.00	210.95	149.89
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	285.00	261.94	219.24
	WEIGHTED AVERAGE FOR THE YEAR			359.00	270.25	223.99	187.68
===== 208-00057	Storm Drain Inlet Protect (Ty I) (144 In)			Each =====			
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	1.00	250.00	424.76	267.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	250.00	424.76	267.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	8.00	250.00	386.22	280.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 123

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00057 Storm Drain Inlet Protect (Ty I) (144 In) Each =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	225.00	276.67	280.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	3.00	220.00	282.89	324.77
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	240.42	366.86	291.19
	WEIGHTED AVERAGE FOR THE YEAR			13.00	241.15	373.18	289.33
===== 208-00058 Storm Drain Inlet Protect (Ty I) (204 In) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	301.00	395.25	387.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	275.00	310.00	280.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	300.00	299.64	337.27
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	294.25	360.86	347.82
	WEIGHTED AVERAGE FOR THE YEAR			4.00	294.25	360.86	347.82
===== 208-00070 Vehicle Tracking Pad Each =====							
NHPP1601-083			02/03/22	2.00	3500.00	11027.81	1200.00
STA0252-459			02/03/22	2.00	4000.00	2574.67	2345.00
NHM765-007			03/31/22	4.00	4300.00	6784.67	855.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	4025.00	6407.97	1313.75
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	4000.00	6784.48	3437.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	2945.00	3900.00	3700.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	3000.00	11439.50	11439.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	3347.50	5818.07	4569.17
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	3400.00	4766.67	4000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	2995.28	1981.32	1981.32
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	3500.00	5655.91	3217.72
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	5000.00	5307.83	4675.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 124

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00070 Vehicle Tracking Pad Each =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	5000.00	3346.23	2346.78
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	12.00	2300.00	1400.62	100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			27.00	3184.14	3142.76	1737.66
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	3500.00	4131.48	3250.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	3000.00	7318.27	3800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	4051.00	6454.32	3894.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	3544.90	4298.36	3860.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	3000.00	5078.67	6024.34
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3500.00	4183.23	3266.45
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	3000.00	2769.41	2050.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.00	4000.00	6526.71	10812.05
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21.00	3490.47	5556.29	4479.09
	WEIGHTED AVERAGE FOR THE YEAR			64.00	3410.18	4940.04	2984.84
===== 208-00071 Maint Aggregate (Veh Track Pad) Cubic Yard =====							
NHPP1601-083			02/03/22	31.00	135.00	182.77	30.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			31.00	135.00	182.77	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	60.00	110.00	66.67	90.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	110.00	66.67	90.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	30.00	94.00	95.65	49.22
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			30.00	94.00	95.65	49.22
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	14.00	100.00	248.75	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 125

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00071 Maint Aggregate (Veh Track Pad) Cubic Yard =====							
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	35.00	60.00	116.12	170.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				49.00	71.43	159.65	128.75
WEIGHTED AVERAGE FOR THE YEAR				170.00	100.62	126.34	90.08
===== 208-00075 Pre-fab Vehicle Track Pad Each =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	2.00	5000.00	4988.40	17500.00
STA0252-459			02/03/22	2.00	5000.00	16333.33	17000.00
C0762-055			02/17/22	2.00	3000.00	5387.48	4300.00
STR0141-031			02/17/22	2.00	2000.00	5600.00	11100.00
NHPP0063-063			02/24/22	2.00	3000.00	9875.00	1400.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	1.00	3000.00	5074.40	600.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	5.00	4600.00	7946.23	2700.00
C0761-239							
NHPP0703-472			03/10/22	1.00	10900.00	4581.50	5000.00
BRC040-057			03/17/22	4.00	5000.00	10297.28	423.11
STR092A-031			03/17/22	2.00	4000.00	11300.00	11300.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				23.00	4386.96	7931.13	6347.50
NH0504-911			04/07/22	8.00	4065.00	5125.00	7750.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	3.00	22892.42	22892.42	22892.42
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	15.00	7000.00	6215.42	1400.00
STA0712-019	SH 71: Frieight Improvements		05/12/22	8.00	3000.00	5023.67	5023.67
CM760-047	COLFAX AND QUAIL		05/12/22	1.00	4000.00	2202.60	500.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	4.00	6600.00	1857.50	800.00
C0852-120	Rehabilitation of Culvert by		05/26/22	2.00	5000.00	1500.00	1500.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	2.00	20000.00	9750.00	9750.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	4.00	6000.00	5317.20	1380.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				47.00	7119.09	5839.86	4757.16
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	4.00	23790.20	23790.20	23790.20
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	2.00	6000.00	2911.90	750.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	2.00	2500.00	11668.96	7500.00
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	2.00	4500.00	10866.67	4500.00
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	1.00	5000.00	5043.88	5556.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 126

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00075 Pre-fab Vehicle Track Pad Each =====							
ER0253-297	WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5000.00	7759.28	2300.00	
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	8712.09	2000.00	
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	12.00	5000.00	3345.51	100.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				28.00	7112.89	7467.45	4918.48
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22	2.00	6000.00	3623.55	8170.65	
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	5000.00	8600.00	2900.00	
C170A-002	CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	5000.00	6238.75	3125.00	
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	5.00	4500.00	7600.00	7600.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	4000.00	5061.92	9500.00	
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	4340.00	8527.77	19083.32	
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	4300.00	6401.00	5600.00	
C5502-097	US550 MP 117.28-126.06	11/17/22	10.00	3000.00	5206.57	2880.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	5000.00	3625.00	4750.00	
STA0711-021	SH71: REGION LINE NORTH	12/01/22	2.00	5300.00	4381.67	1200.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	2167.30	8011.34	5510.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	7.00	6000.00	7000.00	16500.00	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	5500.00	11139.56	4000.00	
STR0092-024	SH 9 North of Silverthorne	12/22/22	2.00	7000.00	11535.00	20470.00	
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22	2.00	6000.00	3627.08	1804.88	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	2500.00	3783.40	2500.00	
STA385A-016	SH 385 MP 97.76	12/22/22	2.00	2000.00	7712.50	18750.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				59.00	4215.57	6804.92	8059.39
WEIGHTED AVERAGE FOR THE YEAR				157.00	5626.60	6870.17	6282.51
===== 208-00082 Construction Mat Sq Foot =====							
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	18,827.00	7.27	7.27	7.27	
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPPR100-266	R1 ESSENTIAL REPAIRS	09/01/22	3,000.00	30.00	14.19	10.74	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				21,827.00	10.39	9.51	7.75
WEIGHTED AVERAGE FOR THE YEAR				21,827.00	10.39	9.51	7.75
===== 208-00090 Erosion Control (Curb Ramp) Each =====							
CR100-362		03/14/22	265.00	707.31	707.31	707.31	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				265.00	707.31	707.31	707.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 127

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00090 Erosion Control (Curb Ramp) Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	153.00	600.00	511.28	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		153.00	600.00	511.28	400.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	66.00	500.00	523.99	523.99
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	32.00	420.00	417.01	539.28
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		98.00	473.88	453.40	528.98
		WEIGHTED AVERAGE FOR THE YEAR		516.00	631.16	555.64	582.32
===== 208-00103 Removal and Disposal of Sediment (Labor) Hour =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	80.00	60.00	98.21	90.53
STR0505-050			01/13/22	10.00	60.00	98.00	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	70.00	78.13	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	600.00	100.00	102.04	62.00
NHPP1601-083			02/03/22	20.00	60.00	196.19	60.00
STA0252-459			02/03/22	10.00	50.00	175.07	72.00
C0762-055			02/17/22	150.00	50.00	67.21	85.00
STR0141-031			02/17/22	40.00	70.00	55.03	51.10
STR133A-051			02/17/22	20.00	35.00	79.33	43.00
NHPP0063-063			02/24/22	20.00	65.00	45.00	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	50.00	93.97	55.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	60.00	78.47	60.00
C0761-239							
NHPP0703-472			03/10/22	15.00	60.00	108.31	120.00
BRC040-057			03/17/22	20.00	100.00	88.72	52.89
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	70.00	50.46	20.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	100.00	78.50	100.00
STR092A-031			03/17/22	40.00	65.00	110.50	110.50
NHM765-007			03/31/22	100.00	50.00	74.62	57.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,235.00	78.46	93.21	66.88
NH0504-911			04/07/22	120.00	61.90	74.55	94.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 128

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00103	Removal and Disposal of Sediment (Labor)		Hour =====			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	80.00	240.22	240.22	240.22
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,080.00	55.00	58.54	50.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	72.00	101.83	80.98
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	20.00	50.00	82.50	65.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	60.00	70.00	49.74	49.74
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	10.00	65.00	91.75	48.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	40.00	66.00	109.67	49.00
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	68.00	84.60	87.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	60.00	70.00	55.50	60.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	125.00	50.00	50.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	100.00	90.00	90.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	30.00	75.00	106.00	120.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	10.00	55.00	55.00	65.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	30.00	55.00	144.54	144.54
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	144.00	95.00	61.00	45.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	60.00	77.00	75.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,838.00	69.56	64.69	66.06
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	120.00	241.71	241.71	241.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	60.00	100.00	61.00	65.52
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	68.00	65.33	60.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	70.00	54.43	66.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	20.00	60.00	57.17	45.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	70.00	139.58	294.99
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	49.37	116.25	116.25
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	55.00	69.00	46.01
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	100.00	100.00	54.60	63.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	10.00	100.00	65.71	80.39
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	160.00	75.00	66.26	50.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	120.00	31.32	5.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				614.00	114.98	74.14	96.38
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	40.00	90.00	56.60	48.80
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	50.00	48.65	51.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	60.00	65.40	81.20
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	63.00	57.75	65.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	40.00	103.75	100.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	10.00	90.00	122.50	170.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00103		Removal and Disposal of Sediment (Labor)		Hour =====			
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	8.00	100.00	73.44	43.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	80.00	70.00	64.45	45.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	224.00	60.00	53.00	53.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	11.00	63.00	76.85	157.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,000.00	70.00	68.74	73.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	50.75	51.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	80.00	153.54	70.00
C5502-097		US550 MP 117.28-126.06	11/17/22	104.00	100.00	55.58	50.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	94.00	80.00	75.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	69.10	52.90	70.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	60.00	59.00	53.61	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	70.00	56.00	60.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	50.00	84.58	180.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	90.00	53.50	40.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	60.00	52.33	44.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15.00	100.00	53.25	55.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	24.00	70.00	115.00	35.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	75.00	174.46	124.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	70.00	51.45	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	55.00	90.98	51.25
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	80.00	75.00	108.42	52.61
STR0092-024		SH 9 North of Silverthorne	12/22/22	40.00	120.00	49.35	48.70
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	60.00	112.25	119.74
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	80.00	60.00	47.34	44.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	100.00	53.44	43.75
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,856.00	69.70	71.87	73.62
		WEIGHTED AVERAGE FOR THE YEAR		8,543.00	74.19	73.93	72.66
===== 208-00105		Removal and Disposal of Sediment (Equip)		Hour =====			
STR0505-050			01/13/22	10.00	120.00	206.67	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	120.00	125.44	100.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	250.00	150.00	197.34	289.00
NHPP1601-083			02/03/22	20.00	150.00	281.01	130.00
STA0252-459			02/03/22	10.00	117.01	172.30	87.50
C0762-055			02/17/22	60.00	120.00	132.54	165.00
STR0141-031			02/17/22	40.00	135.00	114.80	89.40
NHPP0063-063			02/24/22	20.00	150.00	82.50	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	150.00	127.70	120.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	140.00	160.46	100.00
C0761-239							
NHPP0703-472			03/10/22	15.00	120.00	183.30	230.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 130

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00105	Removal and Disposal of Sediment (Equip)		Hour =====			
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	173.00	114.90	20.00
STR092A-031			03/17/22	40.00	140.00	154.00	154.00
NHM765-007			03/31/22	100.00	120.00	148.08	136.80
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		665.00	139.14	168.95	185.70
NH0504-911			04/07/22	120.00	131.43	126.80	123.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	80.00	125.40	125.40	125.40
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	540.00	105.00	163.43	100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	130.00	197.93	138.82
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	20.00	150.00	162.50	125.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	20.00	160.00	133.83	133.83
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	40.00	125.00	123.67	136.00
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	145.00	151.40	92.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	20.00	130.00	107.50	120.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	170.00	100.00	100.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	220.00	190.00	190.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	30.00	150.00	124.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	30.00	125.00	249.20	249.20
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	20.00	250.00	152.40	100.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	115.00	90.25	95.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,074.00	120.79	151.80	113.94
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	120.00	131.10	131.10	131.10
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	150.00	114.61	166.92
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	130.00	149.67	225.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	120.00	169.83	215.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	20.00	120.00	118.33	135.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	150.00	156.52	182.06
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	137.49	88.36	88.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	85.00	108.80	104.41
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	150.00	115.00	133.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	10.00	150.00	119.31	116.53
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	150.00	132.68	105.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	180.00	57.67	5.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		404.00	139.56	124.68	128.20
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	150.00	130.50	155.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00105		Removal and Disposal of Sediment (Equip)		Hour =====			
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	120.00	140.55	121.65
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	130.00	115.68	106.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	100.00	176.25	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	40.00	115.00	153.79	105.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	64.00	120.00	96.00	96.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	4.00	130.00	163.11	335.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	300.00	186.10	330.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	125.00	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	8.00	130.00	157.78	151.90
C5502-097		US550 MP 117.28-126.06	11/17/22	52.00	150.00	131.00	115.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	160.00	145.00	140.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	117.10	174.81	321.74
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	120.00	122.86	120.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	160.00	117.50	110.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	100.00	184.21	190.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	200.00	80.00	45.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	130.00	132.33	150.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	145.00	327.41	249.82
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	150.00	160.26	185.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	125.00	133.23	102.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	150.00	198.47	174.14
STR0092-024		SH 9 North of Silverthorne	12/22/22	12.00	120.00	150.50	111.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	95.00	157.20	124.99
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	80.00	120.00	83.84	117.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	150.00	107.38	112.50
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,800.00	174.75	160.38	196.89
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			3,943.00	150.44	156.93	165.69
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	20.00	150.00	605.00	605.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	150.00	219.31	172.07
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	200.00	176.49	100.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	120.00	152.75	192.91	152.00
NHPP1601-083			02/03/22	40.00	150.00	217.84	200.00
STA0252-459			02/03/22	200.00	150.00	279.20	301.50
C0762-055			02/17/22	240.00	125.00	161.89	140.00
STR0141-031			02/17/22	40.00	200.00	221.67	250.00
NHPP0063-063			02/24/22	20.00	160.00	82.50	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	150.00	167.70	180.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	150.00	207.52	100.00
C0761-239							

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 132

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00106							
		Sweeping (Sediment Removal)		Hour			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	40.00	160.00	197.87	165.74
BRC040-057			03/17/22	8.00	140.00	203.10	168.38
STR R500-171		Various locations on SH 141 a	03/17/22	60.00	280.00	131.85	20.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	300.00	194.50	271.00
STR092A-031			03/17/22	40.00	160.00	125.00	125.00
NHM765-007			03/31/22	200.00	150.00	291.23	285.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	20.00	200.00	234.50	315.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,158.00	157.38	212.69	205.41
NH0504-911			04/07/22	150.00	178.32	232.75	235.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	80.00	199.11	199.11	199.11
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,125.00	175.00	154.22	20.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	150.00	184.08	185.10
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	10.00	150.00	225.00	200.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	40.00	160.00	148.60	148.60
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	160.00	134.50	130.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	152.00	187.67	113.00
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	174.00	267.40	92.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	80.00	165.00	157.50	160.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	5.00	200.00	187.61	125.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	200.00	100.00	100.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	20.00	200.00	180.00	180.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	20.00	50.00	109.00	120.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	30.00	150.00	178.00	178.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	120.00	250.00	138.40	85.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	10.00	160.00	156.56	222.11
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	170.00	213.25	150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,908.00	177.66	161.22	78.71
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	120.00	202.59	202.59	202.59
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	50.00	200.00	190.45	143.52
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	165.00	220.67	225.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	130.00	180.63	180.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	200.00	200.00	151.00	120.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	150.00	145.18	158.04
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	254.13	103.37	103.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	10.00	200.00	113.73	113.73
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	85.00	203.71	114.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	200.00	220.94	200.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	250.00	142.33	175.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	160.00	148.20	99.96
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	320.00	150.00	185.08	190.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	150.00	168.05	120.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,064.00	173.08	179.13	163.71
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	16.00	205.00	147.50	250.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	175.00	244.20	400.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	175.00	235.17	230.50
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	160.00	160.81	177.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	110.00	212.50	105.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	80.00	150.00	163.27	150.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	224.00	150.00	134.00	134.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	66.00	160.00	149.86	250.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	180.00	170.00	181.32	198.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	16.00	124.00	175.39	186.18
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	137.50	150.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	150.00	191.40	160.00
C5502-097		US550 MP 117.28-126.06	11/17/22	52.00	170.00	238.74	95.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	20.00	200.00	219.50	255.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	176.00	150.00	200.67	170.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	160.00	210.00	160.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	120.00	100.00	194.60	190.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	200.00	295.00	165.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	50.00	160.00	143.33	180.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	200.00	210.95	175.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	40.00	170.00	290.06	206.11
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	180.00	178.39	152.00
NHM175-029		CANON CITY, CO	12/15/22	15.00	170.00	132.50	250.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	150.00	177.96	153.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	50.00	180.00	194.82	274.97
STR0092-024		SH 9 North of Silverthorne	12/22/22	30.00	200.00	154.00	157.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	180.00	180.46	176.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	150.00	307.38	117.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	160.00	231.67	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,775.00	157.70	185.13	176.94
		WEIGHTED AVERAGE FOR THE YEAR		5,905.00	166.86	180.53	148.78
===== 208-00107		Rem Trash		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	20.00	100.00	160.00	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 208-00107	Rem Trash			Hour =====			
MTCE R500-218			01/06/22	16.00	75.00	64.00	28.00
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	40.00	98.00	159.81	90.53
NH0504-910	US50B I-24-B MIN REP AT MP 40		01/13/22	10.00	100.00	106.69	50.00
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	60.00	40.00	159.67	160.00
NHPP1601-083			02/03/22	25.00	50.00	371.30	100.00
STA0252-459			02/03/22	100.00	90.00	222.76	123.00
C0762-055			02/17/22	40.00	70.00	135.83	100.00
STR0141-031			02/17/22	16.00	150.00	68.37	51.10
NHPP0063-063			02/24/22	20.00	80.00	87.50	40.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	40.00	100.00	79.15	90.00
NHPP0703-472			03/10/22	40.00	105.00	154.06	120.00
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	20.00	50.00	127.87	165.74
BRC040-057			03/17/22	10.00	100.00	101.72	52.89
STR R500-171	Various locations on SH 141 a		03/17/22	40.00	116.00	80.90	20.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	10.00	95.00	118.00	100.00
STR092A-031			03/17/22	40.00	100.00	242.00	242.00
NHM765-007			03/31/22	100.00	95.00	166.38	57.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				647.00	87.88	155.74	103.88
<hr/>							
NH0504-911			04/07/22	120.00	98.46	84.55	94.10
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	100.00	50.00	99.47	50.00
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	30.00	50.00	230.00	110.00
STA0712-019	SH 71: Frieght Improvements		05/12/22	20.00	100.00	68.84	68.84
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	20.00	105.00	132.67	48.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	30.00	110.00	65.50	80.00
STAR100-358	3 STRUCTURES IN REGION 1 METR		05/26/22	5.00	100.00	387.20	202.00
C0852-120	Rehabilitation of Culvert by		05/26/22	8.00	185.00	50.00	50.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	20.00	100.00	50.00	50.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	20.00	50.00	106.00	120.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS		06/02/22	3.00	90.00	130.00	140.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	20.00	100.00	124.60	124.60
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	30.00	150.00	103.80	45.00
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV		06/23/22	100.00	110.00	88.25	75.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				526.00	92.14	101.79	77.76
<hr/>							
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	80.00	108.00	87.67	75.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	40.00	100.00	66.75	66.00
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	32.00	100.00	92.83	45.00
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	50.00	200.00	116.50	95.00
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	24.00	183.28	194.10	194.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00107		Rem Trash		Hour =====			
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	10.00	200.00	173.69	173.69
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	15.00	100.00	406.07	113.21
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	20.00	100.00	61.93	85.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	60.00	100.00	119.82	197.04
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24.00	120.00	110.20	50.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	20.00	130.00	139.61	40.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		375.00	125.92	116.84	102.52
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	200.00	37.50	50.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10.00	150.00	48.65	51.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	120.00	98.93	141.80
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	86.00	68.23	70.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	50.00	124.25	95.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	10.00	80.00	127.50	180.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	40.00	100.00	97.42	45.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	40.00	70.00	53.00	53.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	650.00	175.00	128.05	230.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	8.00	77.00	75.79	84.36
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5.00	200.00	64.50	54.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	32.00	90.00	144.00	120.00
C5502-097		US550 MP 117.28-126.06	11/17/22	26.00	140.00	203.56	50.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	92.60	142.50	314.48
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	60.00	110.61	110.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	15.00	180.00	77.50	72.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	50.00	90.00	92.67	90.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15.00	150.00	52.25	55.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	10.00	100.00	135.16	146.32
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	10.00	200.00	142.01	90.42
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	10.00	100.00	156.67	35.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	40.00	120.00	116.96	124.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	130.00	130.45	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	100.00	95.98	51.25
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	50.00	115.00	147.55	220.71
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	200.00	100.50	150.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	75.00	123.67	162.87
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	90.00	72.67	44.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,659.00	125.35	115.34	157.66
		WEIGHTED AVERAGE FOR THE YEAR		3,207.00	112.41	121.03	127.63
===== 208-00146		Pre-fab Conc Washout Str (Type 2)		Each =====			
NHPP1601-083			02/03/22	1.00	1500.00	2977.08	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1500.00	2977.08	400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 136

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00146 Pre-fab Conc Washout Str (Type 2) Each =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	2200.00	650.00	800.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3.00	3000.00	971.20	525.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	2800.00	933.41	593.75
===== 208-00200 Erosion Control Management LUMP SUM =====							
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	2000.00	1617.46	977.60
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	2000.00	1617.46	977.60
===== 208-00207 Erosion Control Management Day =====							
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	2000.00	2379.27	3200.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	1500.00	1766.40	610.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	5.00	1400.00	3163.33	500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	1500.00	2573.48	865.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	1913.33	1965.89	776.68
===== 208-00207 Erosion Control Management Day =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5500.00	20525.00	1100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5500.00	20525.00	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5500.00	20525.00	1100.00
===== 208-00207 Erosion Control Management Day =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	30.00	300.00	295.74	75.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	500.00	561.64	720.00
NHPP1601-083			02/03/22	40.00	300.00	580.04	500.00
STA0252-459			02/03/22	200.00	270.11	307.83	197.00
C0762-055			02/17/22	30.00	400.00	321.77	400.00
NHPP0063-063			02/24/22	115.00	260.00	672.50	75.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	546.00	250.00	192.47	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 137

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00207 Erosion Control Management Day =====							
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	25.00	200.00	529.10	718.20
STR092A-031			03/17/22	32.00	200.00	450.00	450.00
NHM765-007			03/31/22	200.00	240.00	296.32	228.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,298.00	271.82	264.79	172.03
NH0504-911			04/07/22	140.00	279.88	97.00	144.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	40.00	1284.00	1284.00	1284.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	150.00	340.00	486.90	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	497.00	150.00	233.30	330.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	40.00	250.00	172.88	172.88
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	70.00	300.00	222.00	316.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	16.00	300.00	687.50	500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	15.00	150.00	1113.00	988.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	5.00	280.00	339.33	300.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	12.00	350.00	382.40	115.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				985.00	263.70	287.53	340.37
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	52.00	1234.62	1234.62	1234.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	322.00	203.33	200.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	174.00	110.00	175.57	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	120.00	250.00	173.33	100.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	7.00	300.00	685.56	1625.44
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	99.00	456.26	519.11	519.11
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	150.00	250.27	349.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	100.00	400.00	250.01	170.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	200.00	344.63	209.88
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	40.00	230.00	325.69	290.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	225.00	617.53	1100.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				807.00	320.09	316.80	383.59
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	140.00	400.00	404.88	914.65
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	40.00	240.00	481.33	842.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	30.00	300.00	300.00	100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00207	Erosion Control Management		Day	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	120.00	265.00	287.45	300.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	56.00	650.00	700.00	700.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	300.00	343.10	400.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	400.00	350.08	410.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	60.00	240.00	132.99	223.96
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	10.00	500.00	550.70	280.00
C5502-097		US550 MP 117.28-126.06	11/17/22	180.00	600.00	453.43	735.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	30.00	450.00	1042.50	1150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	52.00	354.00	760.64	507.55
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	180.00	189.80	301.40	110.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	60.00	250.00	500.00	450.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	61.00	200.00	340.86	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	80.00	250.00	354.14	266.60
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	42.00	300.00	725.34	651.15
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	30.00	250.00	338.67	500.00
STA385A-016		SH 385 MP 97.76	12/22/22	35.00	300.00	698.75	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,736.00	358.91	393.58	455.46
		WEIGHTED AVERAGE FOR THE YEAR		4,826.00	309.56	318.80	345.65
=====	208-00300	Temporary Berms		Lin Foot	=====		
NHPP1601-083			02/03/22	22,725.00	3.00	1.37	2.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,725.00	3.00	1.37	2.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	500.00	5.00	7.60	1.94
STA0712-019		SH 71: Frieght Improvements	05/12/22	22,962.00	3.00	0.51	0.51
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23,462.00	3.04	1.21	0.54
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,500.00	1.80	7.91	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,500.00	1.80	7.91	15.00
		WEIGHTED AVERAGE FOR THE YEAR		47,687.00	2.98	1.70	1.69
=====	208-00301	Temporary Diversion		Lin Foot	=====		
BRC040-057			03/17/22	175.00	120.00	195.96	261.84
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	120.00	195.96	261.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 139

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00301 Temporary Diversion Lin Foot =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	550.00	260.00	529.00	68.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		550.00	260.00	529.00	68.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	300.00	200.00	86.67	150.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	60.00	65.00	62.39	59.78
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		360.00	177.50	120.09	99.59
		WEIGHTED AVERAGE FOR THE YEAR		1,085.00	210.05	301.59	108.44
===== 208-00400 Water Control LUMP SUM =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	27164.11	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	30000.00	27164.11	1000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	2000.00	44061.62	7601.39
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	44061.62	7601.39
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	100000.00	164453.46	8360.38
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	300000.00	297793.58	313380.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	200000.00	231123.52	160870.57
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	15000.00	33560.82	15000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	70000.00	66786.78	29500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	50000.00	106152.48	53883.26

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00400 Water Control LUMP SUM =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	20000.00	88333.33	100000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	10000.00	44779.36	67575.30
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	10000.00	125000.00	100000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	40000.00	113500.00	75000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	30714.29	71943.23	62994.08
	WEIGHTED AVERAGE FOR THE YEAR			11.00	58818.18	80709.74	70118.28
===== 208-00520 Temp Stream Crossing LUMP SUM =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	703374.62	703374.62	703374.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	703374.62	703374.62	703374.62
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	545019.65	315000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	75000.00	545019.65	315000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	389187.31	584608.40	509187.31
===== 209-00000 Water M Gallon =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	395.41	1027.60	1027.60
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			48.00	395.41	1027.60	1027.60
	WEIGHTED AVERAGE FOR THE YEAR			48.00	395.41	1027.60	1027.60
===== 210-00001 Res Structure Each =====							
NHM765-007			03/31/22	2.00	300.00	5984.09	3990.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	12.00	5000.00	5937.50	4000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	4328.57	5946.82	3998.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 141

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00001 Res Structure Each =====							
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	5000.00	7533.06	7533.06
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	7533.06	7533.06
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	3.00	10000.00	1900.00	800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	10000.00	1900.00	800.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	5000.00	5874.73	1900.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	10000.00	3880.32	1535.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	8750.00	6061.12	4417.50
	WEIGHTED AVERAGE FOR THE YEAR			22.00	5936.36	5481.60	3850.75
===== 210-00009 Res Communications Cabinet Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	5000.00	1196.44	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	5000.00	1196.44	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	1196.44	1200.00
===== 210-00010 Res Mailbox Str Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	435.00	486.97	1000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	9.00	450.00	356.28	135.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15.00	444.00	408.56	481.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	500.00	552.09	378.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	500.00	552.09	378.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	447.50	414.08	474.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 142

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00011 Res Mailbox Str (Ty 1) Each =====							
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.00	350.00	637.48	533.50
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	500.00	375.50	351.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	380.00	613.67	497.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	380.00	613.67	497.00
===== 210-00012 Res Mailbox Str (Ty 2) Each =====							
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	1000.00	517.50	485.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	1000.00	517.50	485.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	517.50	485.00
===== 210-00013 Res Mailbox Str (Ty 3) Each =====							
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	3000.00	745.50	701.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	3000.00	745.50	701.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	745.50	701.00
===== 210-00035 Res Water Meter Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	3000.00	1622.04	1400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	3000.00	1622.04	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	1622.04	1400.00
===== 210-00050 Res Fire Hydrant Each =====							
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	5394.00	5579.44	5575.90
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5394.00	5579.44	5575.90
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5394.00	5579.44	5575.90

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 143

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00060 Res Marker Each =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2.00	400.00	445.00	500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	425.00	844.41	631.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	412.50	644.70	565.93
	WEIGHTED AVERAGE FOR THE YEAR			4.00	412.50	644.70	565.93
===== 210-00065 Res Monument (Ty 3A) Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	3.00	1000.00	1035.16	500.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	1000.00	2061.67	685.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	1000.00	1621.74	605.71
	WEIGHTED AVERAGE FOR THE YEAR			7.00	1000.00	1621.74	605.71
===== 210-00090 Res Delineator Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5.00	26.75	26.75	26.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	26.75	26.75	26.75
===== 210-00100 Res Trash Guard Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	1500.00	1260.38	1284.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	1500.00	1260.38	1284.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	1260.38	1284.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 144

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00473 Res TV Cameras Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	1880.00	2030.47	2100.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	1880.00	2030.47	2100.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	3852.00	3852.00	3852.00
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		1.00	3852.00	3852.00	3852.00
STAM420-001 BR2854-148 STM0091-046 2670703-487 NHPP0931-033		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1250.00	2254.60	3420.89
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	4000.00	1429.90	1420.00
		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	2000.00	585.19	690.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		3.00	2416.67	1423.74	1843.63
	WEIGHTED AVERAGE FOR THE YEAR			5.00	2596.40	1711.21	2296.58
===== 210-00474 Res Traf Contr Signal Head Each =====							
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	1000.00	2284.27	1000.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		2.00	1000.00	2284.27	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	2284.27	1000.00
===== 210-00475 Res CCTV Pole Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	7600.00	5106.34	4800.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	7600.00	5106.34	4800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	5500.00	17421.17	26389.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 145

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00475	Res CCTV Pole		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		3.00	5500.00	17421.17	26389.69
		WEIGHTED AVERAGE FOR THE YEAR		4.00	6025.00	13799.16	20992.27
=====	210-00476	Reset MVRD		Each	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	1000.00	1429.90	1420.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	1429.90	1420.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1429.90	1420.00
=====	210-00477	Reset Weather Station		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	7704.00	7704.00	7704.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		1.00	7704.00	7704.00	7704.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6000.00	27080.16	41050.63
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	27080.16	41050.63
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6852.00	23204.93	24377.32
=====	210-00479	Res Radio Com Antenna		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	940.00	1690.05	1800.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	940.00	1690.05	1800.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3.00	600.00	1030.81	792.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		3.00	600.00	1030.81	792.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 146

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00479		Res Radio Com Antenna		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	1200.00	2033.75	1895.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	1030.00	1537.44	2345.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1072.50	1661.52	2233.06
	WEIGHTED AVERAGE FOR THE YEAR			8.00	878.75	1374.08	1638.53
===== 210-00481		Reset DSRC (Roadside Unit)		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	3852.00	3852.00	3852.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	3852.00	3852.00	3852.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3852.00	3852.00	3852.00
===== 210-00750		Res Light Standard		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	12.00	2200.00	7583.91	7300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	2200.00	7583.91	7300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	2000.00	1396.75	1640.38
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	1000.00	2735.80	2534.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1500.00	2005.41	2087.19
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1800.00	1683.33	3200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1800.00	3166.97	2350.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2062.50	6134.49	5620.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 147

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00760 Res Luminaire Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	400.00	359.96	421.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	400.00	359.96	421.55
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	400.00	700.66	605.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	400.00	700.66	605.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	500.00	580.18	580.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	500.00	580.18	580.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	450.00	503.01	546.64
===== 210-00805 Res Overhead Sign Str Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4333.50	4333.50	4333.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	3500.00	23331.04	17993.11
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	3916.75	18581.65	11163.31
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	18000.00	16780.58	25412.30
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	2500.00	38608.90	40800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	10250.00	28907.42	33106.15
		WEIGHTED AVERAGE FOR THE YEAR		4.00	7083.38	25730.26	22134.73
===== 210-00810 Res Ground Sign Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	300.00	689.84	135.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 148

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00810 Res Ground Sign Each =====							
MTCER300-262			02/03/22	30.00	400.00	475.00	375.00
NHPP1601-083			02/03/22	63.00	400.00	455.79	500.00
STA0252-459			02/03/22	5.00	500.00	409.89	350.00
CR100-362			03/14/22	10.00	268.30	268.30	268.30
ER007A-035			03/15/22	3.00	663.00	709.45	709.45
STR092A-031			03/17/22	13.00	400.00	545.00	545.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				134.00	392.33	497.44	430.94
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	38.00	400.00	425.46	750.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	695.50	695.50	695.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	400.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	408.00	1046.67	640.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	450.00	604.21	604.21
WEIGHTED AVERAGE FOR THE SECOND QUARTER				46.00	428.04	450.32	724.73
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	518.42	518.42	518.42
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	400.00	735.00	450.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	500.00	669.54	605.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	430.00	492.50	625.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	400.00	348.92	274.26
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	14.00	700.00	676.96	531.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	480.00	611.04	96.55
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	30.00	350.00	297.55	223.63
WEIGHTED AVERAGE FOR THE THIRD QUARTER				63.00	466.47	399.41	373.10
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	500.00	633.67	701.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	10.00	400.00	648.07	694.20
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	300.00	507.75	355.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10.00	90.00	556.25	580.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	30.00	500.00	425.00	425.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	460.00	412.64	115.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	425.00	455.04	460.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	700.00	693.19	513.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6.00	350.00	467.50	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	394.00	597.10	410.90

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 149

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00810 Res Ground Sign Each =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	450.00	340.00	370.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	600.00	645.12	576.62
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5.00	600.00	247.01	341.01
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	300.00	635.87	615.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	17.00	550.00	304.16	373.38
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	400.00	390.51	325.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				122.00	435.47	469.35	466.04
WEIGHTED AVERAGE FOR THE YEAR				365.00	424.04	458.28	469.71
===== 210-00815 Res Sign Panel Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	240.00	99.91	37.20
NHPP1601-083			02/03/22	8.00	100.00	495.03	150.00
STA0252-459			02/03/22	2.00	271.58	254.52	225.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	150.00	166.93	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	250.00	1064.63	200.00
C0761-239							
NHPP0703-472			03/10/22	3.00	180.00	158.31	150.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				17.00	157.24	408.95	157.48
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	200.00	155.47	179.36
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	100.00	207.01	207.01
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	200.00	652.50	640.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	250.00	302.11	302.11
WEIGHTED AVERAGE FOR THE SECOND QUARTER				18.00	200.00	178.22	235.30
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	21.00	150.00	297.50	380.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	160.00	293.75	280.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				26.00	196.14	315.09	400.37
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	9.00	185.00	425.00	350.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 150

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00815 Res Sign Panel Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	12.00	50.00	645.25	600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	200.00	281.09	300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	175.00	366.58	350.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	150.00	452.56	477.69
MPR200-280		PUEBLO AREA	11/17/22	1.00	680.00	225.00	300.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	160.00	173.33	200.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	3.00	250.00	189.01	341.01
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	350.00	357.93	480.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	4.00	200.00	316.04	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			59.00	166.44	362.07	343.25
	WEIGHTED AVERAGE FOR THE YEAR			120.00	176.61	326.07	313.61
===== 210-00816 Res Sign Panel (Spec) Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	6367.50	8190.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	6000.00	6367.50	8190.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	6000.00	6367.50	8190.00
===== 210-00820 Res Var Mesg Sign Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	35310.00	35310.00	35310.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	35310.00	35310.00	35310.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	16000.00	27080.16	41050.63
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	16000.00	27080.16	41050.63
	WEIGHTED AVERAGE FOR THE YEAR			2.00	25655.00	28726.13	38180.32
===== 210-00825 Res Flashing Beacon Each =====							
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	5000.00	1350.00	1200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 151

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00825							
STAM420-001	Res Flashing Beacon	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	Each			
BR2854-148		INTERSECTION OF US 285 & SH 9		1.00	5000.00	4404.17	2517.69
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	5000.00	2877.09	1639.23
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5000.00	2877.09	1639.23
===== 210-00827							
	Res Pull Box			Each			
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22	23.00	440.00	553.31	522.35	
NHPP0063-063		02/24/22	5.00	700.00	2105.00	2500.00	
CR100-362		03/14/22	17.00	1032.55	1032.55	1032.55	
MP0503-098		03/24/22	1.00	2000.00	1245.00	780.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		46.00	721.16	760.31	931.47	
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	1.00	1500.00	824.63	970.09	
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	900.00	1296.50	800.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1200.00	942.60	885.05	
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	1000.00	1796.24	1500.00	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	5.00	850.00	2337.12	2002.27	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	875.00	2182.58	1918.56	
	WEIGHTED AVERAGE FOR THE YEAR		54.00	755.99	1023.25	1039.42	
===== 210-00830							
	Res Traf Sig Face			Each			
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	7.00	1000.00	554.35	392.75	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	1000.00	554.35	392.75	
	WEIGHTED AVERAGE FOR THE YEAR		7.00	1000.00	554.35	392.75	
===== 210-00831							
	Res Traf Sig Head			Each			
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	1000.00	1270.71	1270.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	1000.00	1270.71	1270.00	
	WEIGHTED AVERAGE FOR THE YEAR		6.00	1000.00	1270.71	1270.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 152

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00845		Res Traf Sig Cntrlr		Each	=====		
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	374.26	179.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	3000.00	374.26	179.50
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	374.26	179.50
===== 210-00846		Port Non-Intrus Traf Sens (Reset)		Each	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	286.00	1660.00	1182.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	286.00	1660.00	1182.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	286.00	1660.00	1182.00
===== 210-00848		Res Traf Sig Control+Cab		Each	=====		
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	7000.00	5927.36	5927.36
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	7000.00	5927.36	5927.36
	WEIGHTED AVERAGE FOR THE YEAR			1.00	7000.00	5927.36	5927.36
===== 210-00855		Res Traf Sig Control Cab		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5173.00	9163.09	8800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5173.00	9163.09	8800.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	300.00	5718.75	5995.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	300.00	5718.75	5995.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1924.33	7043.50	6930.00
===== 210-00858		Res Pedestal Pole		Each	=====		
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	1300.00	760.98	750.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1300.00	760.98	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 153

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00858 Res Pedestal Pole Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	750.00	858.02	810.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	3000.00	1937.10	2285.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1875.00	1217.71	1547.93
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1683.33	1126.36	1281.95
===== 210-00859 Mod Ped Push Button Each =====							
CR100-362			03/14/22	7.00	882.75	882.75	882.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	882.75	882.75	882.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	11.00	500.00	515.42	515.42
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	500.00	515.42	515.42
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	600.00	408.71	435.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	600.00	408.71	435.00
		WEIGHTED AVERAGE FOR THE YEAR		19.00	646.28	612.90	646.52
===== 210-00860 Res Ped Push Button Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	800.00	102.41	95.86
NHPP0063-063			02/24/22	1.00	1000.00	1527.00	2500.00
CR100-362			03/14/22	25.00	449.40	449.40	449.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	482.78	474.15	512.25
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	17.00	1200.00	472.16	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	1200.00	472.16	550.00
		WEIGHTED AVERAGE FOR THE YEAR		44.00	759.89	472.91	526.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 154

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00861 Reset Wiring LUMP SUM =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	4000.00	1742.69	1400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	1742.69	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	1742.69	1400.00
===== 210-00865 Res Ped Sig Head Each =====							
CR100-362			03/14/22	2.00	690.15	690.15	690.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	690.15	690.15	690.15
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	300.00	547.16	775.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	300.00	547.16	775.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	560.10	604.35	718.43
===== 210-00867 Res Fire Preempt Unit Each =====							
CM760-047		COLFAX AND QUAIL	05/12/22	2.00	873.00	1312.40	677.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	1000.00	1192.66	1192.66
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	936.50	1292.44	934.83
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	11.00	3000.00	1425.00	1200.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11.00	3000.00	1425.00	1200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2500.00	1270.71	1270.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2500.00	1270.71	1270.00
	WEIGHTED AVERAGE FOR THE YEAR			17.00	2455.65	1362.09	1145.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 155

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00882 Res Detector Each =====							
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	1000.00	1186.67	1186.67
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1000.00	1186.67	1186.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	2000.00	2587.40	3909.59
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	1000.00	1043.98	1320.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	1333.33	1558.45	2183.20
		WEIGHTED AVERAGE FOR THE YEAR		5.00	1200.00	1505.34	1784.59
===== 210-01000 Res Fence Lin Foot =====							
STR092A-031			03/17/22	31.00	25.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		31.00	25.00	115.00	115.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3,200.00	10.00	8.62	5.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,200.00	10.00	8.62	5.75
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	22.00	100.00	32.75	56.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	100.00	77.68	93.05
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	600.00	12.00	44.11	45.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		722.00	26.87	50.31	51.99
C5502-097		US550 MP 117.28-126.06	11/17/22	8,060.00	6.00	15.13	17.90
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	161.00	25.00	40.77	50.63
BR2854-148		INTERSECTION OF US 285 & SH 9					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 156

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01000	Res Fence		Lin Foot	=====		
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8,221.00	6.37	15.80	18.54
	WEIGHTED AVERAGE FOR THE YEAR			12,174.00	8.59	14.42	17.41
=====	210-01011	Res Gate		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	1000.00	492.91	448.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1000.00	492.91	448.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1000.00	492.91	448.00
=====	210-01050	Res C L Fence		Lin Foot	=====		
NHM765-007			03/31/22	101.00	30.00	52.14	45.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			101.00	30.00	52.14	45.60
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	50.00	55.87	79.61
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	50.00	55.87	79.61
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	156.00	22.20	55.91	69.73
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			156.00	22.20	55.91	69.73
	WEIGHTED AVERAGE FOR THE YEAR			307.00	29.29	54.84	63.40
=====	210-01130	Res Gd rail Ty 3		Lin Foot	=====		
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	30.00	29.06	27.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			100.00	30.00	29.06	27.22
	WEIGHTED AVERAGE FOR THE YEAR			100.00	30.00	29.06	27.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 157

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-01170	Res Gdrail Ty 7			Lin Foot	=====		
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS	05/26/22		100.00	550.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	550.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	550.00	350.00	350.00
===== 210-01180	Reset Guardrail (Special)			Lin Foot	=====		
STR R500-171	Various locations on SH 141 a	03/17/22		120.00	125.00	80.18	142.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	125.00	80.18	142.00
NH0504-911		04/07/22		212.00	100.00	35.15	35.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			212.00	100.00	35.15	35.30
	WEIGHTED AVERAGE FOR THE YEAR			332.00	109.04	55.83	73.87
===== 210-01190	Reset High-Tension Cable Barrier			Lin Foot	=====		
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		2,231.00	20.00	39.48	35.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,231.00	20.00	39.48	35.00
	WEIGHTED AVERAGE FOR THE YEAR			2,231.00	20.00	39.48	35.00
===== 210-01200	Res End Anchorage			Each	=====		
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22		2.00	2000.00	1715.78	1650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2000.00	1715.78	1650.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		2.00	1700.00	6123.81	6500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1700.00	6123.81	6500.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1850.00	3919.80	4075.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 158

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-01710 Res Valve Each =====							
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	380.12	2489.60	2787.96
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	380.12	2489.60	2787.96
	WEIGHTED AVERAGE FOR THE YEAR			1.00	380.12	2489.60	2787.96
===== 210-02804 Grinding: Sidwlk and/or Curb Ramp Repair Lin Foot =====							
CR100-362			03/14/22	200.00	65.54	65.54	65.54
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			200.00	65.54	65.54	65.54
	WEIGHTED AVERAGE FOR THE YEAR			200.00	65.54	65.54	65.54
===== 210-02900 Relay Riprap Cubic Yard =====							
NHPP 0761-238 C0761-239 CR100-362		I-76 DAHLIA TO YORK	03/10/22	120.00	48.00	68.65	35.00
			03/14/22	10.00	406.65	406.65	406.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			130.00	75.59	72.14	63.59
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	156.00	100.00	73.71	68.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			156.00	100.00	73.71	68.00
	WEIGHTED AVERAGE FOR THE YEAR			286.00	88.90	72.52	65.99
===== 210-03100 Replace Conc Pvmnt Sq Yard =====							
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2,071.00	180.00	229.29	161.58
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,071.00	180.00	229.29	161.58
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4,574.00	200.00	259.69	243.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-03100		Replace Conc Pvm		Sq Yard			
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	13,365.00	300.00	237.17	206.33
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			17,939.00	274.50	246.32	215.68
	WEIGHTED AVERAGE FOR THE YEAR			20,010.00	264.72	244.88	210.08
===== 210-04000		Adj Structure		Each			
NHM765-007			03/31/22	6.00	2000.00	5062.58	2661.47
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	2000.00	5062.58	2661.47
	WEIGHTED AVERAGE FOR THE YEAR			6.00	2000.00	5062.58	2661.47
===== 210-04010		Adj Manhole		Each			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	130.00	900.00	906.76	889.27
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000.00	1983.57	2500.00
STR0141-031			02/17/22	1.00	1500.00	3366.67	3100.00
NHPP0063-063			02/24/22	102.00	800.00	1725.00	1300.00
CR100-362			03/14/22	6.00	1097.62	1097.62	1097.62
STR092A-031			03/17/22	1.00	1100.00	1300.00	1300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			241.00	870.48	1151.98	1085.85
NH0504-911			04/07/22	4.00	1615.53	885.00	1220.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	1200.00	604.43	600.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	1200.00	1234.56	1811.38
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	900.00	586.67	660.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	68.00	1200.00	1009.04	1009.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			83.00	1216.41	1073.04	1097.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	13.00	2728.50	2728.50	2728.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	1100.00	1760.89	1800.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	1500.00	1750.00	2500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			18.00	2298.36	2306.85	2509.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 160

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04010	Adj Manhole			Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	2000.00	1677.21	1050.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	10.00	1500.00	2768.36	1360.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	2000.00	4690.43	2610.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	1200.00	2625.00	2750.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1300.00	1834.53	1684.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	1000.00	1143.80	1030.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1200.00	2600.00	1200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	14.00	1000.00	1175.48	994.49
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	975.00	1269.95	939.89
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	1000.00	1424.87	2560.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			52.00	1171.15	1664.91	1321.09
	WEIGHTED AVERAGE FOR THE YEAR			394.00	1048.27	1254.97	1184.30
===== 210-04011	Adj Manhole (Spec)			Each =====			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	3500.00	2998.90	2800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	3500.00	2998.90	2800.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3500.00	2998.90	2800.00
===== 210-04015	Modify Manhole			Each =====			
NHPP0063-063			02/24/22	1.00	3500.00	8650.00	15000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3500.00	8650.00	15000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	7019.67	7019.67	7019.67
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	4500.00	4136.88	2520.07
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	4919.95	4229.87	3270.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3.00	2500.00	1071.56	925.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	2500.00	1071.56	925.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 161

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04015 Modify Manhole Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3700.00	4425.59	4500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	3500.00	7896.11	5600.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	3500.00	5366.67	3100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	3540.00	6128.48	4880.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	3881.31	4702.12	4119.67
===== 210-04020 Modify Inlet Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	3500.00	3010.40	2500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3500.00	3010.40	2500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4000.00	3651.55	4880.26
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	4000.00	3651.55	4880.26
NHPP0702-414 FBR0702-423 NHPP0063-054		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	8195.41	8195.41	8195.41
		VAIL PASS AUX BE F-12-AT PHAS					
		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	3000.00	2308.95	1995.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	7545.98	6887.31	7420.36
IM025A-050 NHPP083A-046		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	5000.00	7633.33	4900.00
		SH83 RESURFACING STROH RD TO	12/08/22	1.00	5000.00	10834.22	9368.43
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	5000.00	8433.55	6389.48
	WEIGHTED AVERAGE FOR THE YEAR			13.00	6374.45	5659.57	6608.58
===== 210-04050 Adj Valve Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	76.00	460.00	507.45	723.02

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 162

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04050 Adj Valve Box Each =====							
STR0141-031			02/17/22	4.00	500.00	1933.33	1300.00
NHPP0063-063			02/24/22	97.00	500.00	1012.50	425.00
CR100-362			03/14/22	5.00	970.00	970.00	970.00
STR092A-031			03/17/22	18.00	500.00	900.00	900.00
NHM765-007			03/31/22	50.00	300.00	709.10	205.68
WEIGHTED AVERAGE FOR THE FIRST QUARTER				250.00	457.24	733.97	530.83
NH0504-911			04/07/22	2.00	1000.00	222.50	45.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	6.00	500.00	527.21	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	14.00	620.00	767.09	1172.70
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	110.00	500.00	800.19	800.19
WEIGHTED AVERAGE FOR THE SECOND QUARTER				132.00	520.30	753.87	825.98
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	700.00	680.89	1225.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	700.00	680.89	1225.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	600.00	1016.30	850.00
C5502-097		US550 MP 117.28-126.06	11/17/22	13.00	700.00	372.57	228.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	700.00	1214.75	2787.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	14.00	1300.00	653.40	600.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	64.00	750.00	450.62	688.72
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	1000.00	879.31	852.62
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	500.00	684.25	1225.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				116.00	801.72	551.83	737.30
WEIGHTED AVERAGE FOR THE YEAR				500.00	554.78	677.06	659.43
===== 210-04060 Adj Water Meter Each =====							
STR092A-031			03/17/22	1.00	2000.00	890.00	890.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1.00	2000.00	890.00	890.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 163

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04060 Adj Water Meter Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	700.00	522.69	450.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	700.00	522.69	450.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 11/03/22		1.00	1000.00	1928.03	850.00
C5502-097		US550 MP 117.28-126.06 11/17/22		9.00	700.00	646.24	25.40
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.00	730.00	774.42	107.86
	WEIGHTED AVERAGE FOR THE YEAR			12.00	833.33	762.66	201.55
===== 210-04200 Adj Gdrail Lin Foot =====							
STA0361-129		US 36: HYGIENE RD AND NELSON 12/22/22		1,000.00	20.00	10.56	10.76
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,000.00	20.00	10.56	10.76
	WEIGHTED AVERAGE FOR THE YEAR			1,000.00	20.00	10.56	10.76
===== 211-01200 Rock Anchor Lin Foot =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF 11/03/22		200.00	70.00	293.67	166.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			200.00	70.00	293.67	166.00
	WEIGHTED AVERAGE FOR THE YEAR			200.00	70.00	293.67	166.00
===== 211-01300 Rock Anchor Each =====							
C5502-111		US 550 MP 81 AND 89 RED MOUNT 10/27/22		22.00	2500.00	5800.00	6600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			22.00	2500.00	5800.00	6600.00
	WEIGHTED AVERAGE FOR THE YEAR			22.00	2500.00	5800.00	6600.00
===== 211-02270 Cement Grout Cubic Foot =====							
BRC040-057			03/17/22	1,121.00	40.00	36.74	19.96
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,121.00	40.00	36.74	19.96
	WEIGHTED AVERAGE FOR THE YEAR			1,121.00	40.00	36.74	19.96

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 164

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 211-02275 Cement Grout Cubic Yard =====							
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	8.00	1000.00	24300.00	32000.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		8.00	1000.00	24300.00	32000.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	1000.00	24300.00	32000.00
===== 211-03005 Dewatering LUMP SUM =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	10000.00	26353.44	1000.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	10000.00	26353.44	1000.00
FSA052A-057 NHPP0063-054		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	10000.00	13315.00	6344.00
		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	20000.00	54564.89	47500.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		2.00	15000.00	29814.95	26922.00
C170A-002 NHPP0343-048 BR012A-048		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	15000.00	8575.00	1000.00
		US 34 (MP 169.3-171.4)	11/01/22	1.00	2000.00	21343.75	38000.00
		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	20000.00	150000.00	150000.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		3.00	12333.33	41967.50	63000.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	12833.33	33894.67	40640.67
===== 211-04000 Monitor and Abandon of Instrument LUMP SUM =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	241526.82	241526.82	241526.82
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		1.00	241526.82	241526.82	241526.82
	WEIGHTED AVERAGE FOR THE YEAR			1.00	241526.82	241526.82	241526.82
===== 212-00006 Seeding (Native) Acre =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	1000.00	9776.72	9072.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 165

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00006 Seeding (Native) Acre =====							
NHPP0703-472			03/10/22	0.50	900.00	5242.64	4000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	12000.00	9665.50	10371.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.70	2500.00	6280.41	5634.83
===== 212-00007 Seeding (Native) (Hydraulic) Acre =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	8000.00	16970.12	25534.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			0.10	8000.00	16970.12	25534.80
	WEIGHTED AVERAGE FOR THE YEAR			0.80	3187.50	7705.70	8122.33
===== 212-00007 Seeding (Native) (Hydraulic) Acre =====							
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.07	30000.00	15396.30	8996.48
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			0.07	30000.00	15396.30	8996.48
	WEIGHTED AVERAGE FOR THE YEAR			0.07	30000.00	15396.30	8996.48
===== 212-00009 Seeding (Temporary) Acre =====							
BRC040-057			03/17/22	0.10	4000.00	11648.65	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.10	4000.00	11648.65	5000.00
===== 212-00022 Seeding (Riparian) Acre =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.40	1000.00	1333.33	1700.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	10000.00	6806.25	7759.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.53	1764.71	2143.83	2900.85
	WEIGHTED AVERAGE FOR THE YEAR			1.63	1901.84	2698.04	2999.41
===== 212-00022 Seeding (Riparian) Acre =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.64	2000.00	5366.67	5900.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	0.75	850.00	3329.83	2464.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.39	1379.50	4267.66	4046.31
	WEIGHTED AVERAGE FOR THE YEAR			1.39	1379.50	4267.66	4046.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 166

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00028 Seeding (Wetlands) Acre =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.05	6000.00	7116.67	7750.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.01	4000.00	76465.00	111145.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			0.06	5666.67	18674.72	24982.50
	WEIGHTED AVERAGE FOR THE YEAR			0.06	5666.67	18674.72	24982.50
===== 212-00032 Soil Conditioning Acre =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	3000.00	14528.66	18185.10
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	0.65	3000.00	10060.41	11000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	14500.00	15855.50	17401.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.85	4352.94	11215.83	12598.36
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	0.10	2700.00	3382.33	4000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.10	2700.00	3382.33	4000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	5000.00	7375.63	2752.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	10000.00	27113.44	32998.70
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			0.60	5833.33	10665.26	7793.53
	WEIGHTED AVERAGE FOR THE YEAR			1.55	4819.35	10516.51	10183.70
===== 212-00050 Sod Sq Foot =====							
NHPP0063-063			02/24/22	800.00	3.00	11.65	2.30
MP0503-098			03/24/22	10.00	20.00	27.50	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			810.00	3.21	11.85	2.58
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	3,592.00	5.00	4.74	5.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,592.00	5.00	4.74	5.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 167

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00050 Sod Sq Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		10,790.00	3.00	2.42	1.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10,790.00	3.00	2.42	1.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,500.00	4.00	3.50	3.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	180.00	1.60	13.02	19.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,680.00	3.74	6.59	5.18
		WEIGHTED AVERAGE FOR THE YEAR		16,872.00	3.51	3.79	2.66
===== 212-00700 Organic Fertilizer Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	7,600.00	0.50	0.78	1.20
NHPP1601-083			02/03/22	19,200.00	1.50	1.37	1.30
C0762-055			02/17/22	960.00	1.75	0.88	0.50
STR0141-031			02/17/22	200.00	3.00	3.42	6.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	75.00	10.00	6.48	8.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3,900.00	3.00	0.60	0.35
C0761-239							
BRC040-057			03/17/22	90.00	5.00	6.18	4.72
STR R500-171		Various locations on SH 141 a	03/17/22	30.00	2.00	4.34	2.00
STR092A-031			03/17/22	150.00	0.40	3.80	3.80
NHM765-007			03/31/22	30.00	10.00	13.50	35.69
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,235.00	1.50	0.99	1.24
NH0504-911			04/07/22	900.00	1.64	2.05	2.10
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	36.00	10.00	41.59	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11,200.00	0.36	0.36	0.36
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,260.00	1.40	0.76	0.95
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	900.00	3.00	1.83	1.65
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	9.00	1.40	26.50	22.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,700.00	2.00	1.37	0.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 168

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00700 Organic Fertilizer Pound =====							
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	1.60	107.80	80.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	610.00	2.00	2.63	3.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	150.00	50.00	12.00	12.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	270.00	2.00	2.65	2.30
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	21.00	1.00	8.00	7.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,746.00	1.20	1.11	1.30
WEIGHTED AVERAGE FOR THE SECOND QUARTER				18,806.00	1.34	1.24	0.99
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	11,840.00	0.35	0.35	0.35
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	60.00	4.50	2.69	2.60
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	300.00	2.00	5.80	5.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16.00	2.00	4.99	2.50
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	147.00	1.50	2.91	2.92
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	324.00	1.18	1.18	1.18
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,622.00	1.50	1.75	1.50
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	972.00	1.50	3.66	3.81
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,300.00	1.00	1.74	0.98
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	288.00	4.00	1.50	2.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				17,869.00	0.76	1.76	0.90
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	219.00	5.00	4.05	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	730.00	1.25	2.70	2.60
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	321.00	2.10	2.78	6.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	150.00	2.00	12.24	10.95
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,435.00	1.00	1.16	1.30
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10,771.00	1.55	2.25	2.25
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	900.00	2.00	1.46	2.30
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	249.00	1.00	1.85	1.71
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	180.00	5.00	2.78	3.30
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	420.00	4.00	1.97	1.35
C5502-097		US550 MP 117.28-126.06	11/17/22	15,015.00	1.50	0.79	0.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,518.00	1.00	1.46	2.08
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	90.00	1.60	9.32	10.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	150.00	5.00	25.00	40.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	15.00	7.00	2.15	0.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,012.00	1.00	0.90	0.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 169

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00700 Organic Fertilizer Pound =====							
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	78.00	5.00	8.72	12.93
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	912.00	2.50	1.76	0.60
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,884.00	2.00	1.42	0.78
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	234.00	3.00	2.80	3.63
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	3,250.00	1.50	1.77	1.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				42,533.00	1.59	1.55	1.62
WEIGHTED AVERAGE FOR THE YEAR				111,443.00	1.39	1.34	1.30
===== 212-00701 Compost (Mech App) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	162.50	50.00	74.23	125.00
C0762-055			02/17/22	384.00	105.00	42.21	30.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	17.00	100.00	189.25	220.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	211.00	50.00	56.35	39.00
C0761-239							
BRC040-057			03/17/22	10.00	100.00	110.88	107.50
NHM765-007			03/31/22	7.00	100.00	349.06	238.86
WEIGHTED AVERAGE FOR THE FIRST QUARTER				791.50	78.83	59.93	58.81
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	8.00	150.00	210.65	100.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	715.00	1.44	1.44	1.44
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	52.00	50.00	66.02	83.32
STA0712-019		SH 71: Frieight Improvements	05/12/22	142.00	35.00	97.11	97.11
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	2.00	43.00	222.25	210.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	132.00	326.20	362.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	198.00	45.00	77.65	90.00
C0852-120		Rehabilitation of Culvert by	05/26/22	35.00	100.00	53.00	53.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	59.00	100.00	75.00	69.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	5.00	55.00	67.33	50.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	379.00	36.00	45.05	40.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,596.00	26.47	46.66	37.52
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	572.00	89.00	89.00	89.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	13.00	100.00	54.21	52.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	32.00	115.70	105.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 170

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00701 Compost (Mech App) Cubic Yard =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11.10	150.00	80.00	80.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	342.00	69.55	69.55	69.55
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	32.50	65.00	109.34	88.51
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	14.00	150.00	112.62	150.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	423.00	45.00	54.06	64.26
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	314.00	50.00	63.70	55.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,725.60	67.65	63.49	73.08
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	60.00	75.00	135.18	130.55
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	70.00	60.00	78.24	71.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	791.00	30.00	42.81	40.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3,489.00	45.00	43.10	43.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	195.00	90.00	77.92	92.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	46.00	65.00	69.38	47.50
C5502-097		US550 MP 117.28-126.06	11/17/22	3,250.00	60.00	61.83	60.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	38.00	589.81	224.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	49.00	166.34	180.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	143.00	60.00	68.19	69.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	360.00	45.00	77.67	93.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	9.00	120.00	146.95	164.39
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	62.00	120.00	118.32	120.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	26.00	50.00	71.62	61.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	209.00	70.00	92.79	106.18
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	104.00	85.00	70.37	70.91
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				8,836.00	52.52	61.19	57.86
WEIGHTED AVERAGE FOR THE YEAR				12,949.10	52.94	59.95	57.46
===== 212-00702 Bio Soil Amd (Hyd App) Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20,150.00	2.00	1.26	1.70
NHPP1601-083			02/03/22	96,000.00	1.00	1.42	1.50
STA0252-459			02/03/22	2,240.00	1.00	1.64	1.18
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	650.00	1.00	1.66	1.50
C0761-239							
STR092A-031			03/17/22	1,750.00	0.90	5.45	5.45
WEIGHTED AVERAGE FOR THE FIRST QUARTER				120,790.00	1.17	1.40	1.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 171

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00702		Bio Soil Amd (Hyd App)		Pound =====			
NH0504-911			04/07/22	10,500.00	0.85	1.45	1.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10,500.00	0.92	0.92	0.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	180,600.00	1.50	1.07	0.86
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	260.00	1.50	2.99	4.05
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	10,850.00	0.85	1.95	1.85
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		212,710.00	1.41	1.11	0.95
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	21,000.00	0.93	0.93	0.93
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	355.00	1.34	1.34	1.34
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	8,750.00	1.30	1.43	1.43
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6,192.00	2.00	2.17	2.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2,625.00	2.00	4.14	6.82
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	385.00	3.00	2.03	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		39,307.00	1.28	2.06	1.62
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,750.00	2.00	5.02	7.08
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	2,905.00	1.60	2.11	2.08
C5502-097		US550 MP 117.28-126.06	11/17/22	175.00	2.00	3.87	2.55
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	17,500.00	2.00	1.70	2.50
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,750.00	4.00	8.83	16.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,250.00	2.00	1.29	1.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	19,355.00	2.00	1.35	1.40
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	7,350.00	2.00	2.58	1.30
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5,250.00	2.00	2.00	1.20
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	22,400.00	1.50	1.81	1.62
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	245.00	2.00	6.48	4.02
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	5,850.00	2.00	1.21	1.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2,250.00	1.50	1.75	2.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		92,030.00	1.89	1.89	2.05
		WEIGHTED AVERAGE FOR THE YEAR		464,837.00	1.43	1.37	1.39

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 172

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00703	Humate			Pound =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	375.00	4.00	1.38	2.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,850.00	40.00	0.87	1.00
NHPP1601-083			02/03/22	1,800.00	1.50	3.47	2.00
STA0252-459			02/03/22	128.00	1.00	1.11	0.74
C0762-055			02/17/22	480.00	2.00	1.33	0.75
STR0141-031			02/17/22	130.00	3.00	5.45	10.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	50.00	10.00	10.04	9.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,300.00	3.60	1.04	0.75
C0761-239							
BRC040-057			03/17/22	30.00	2.00	9.17	0.57
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	2.50	5.67	2.00
STR092A-031			03/17/22	100.00	1.00	4.35	4.35
NHM765-007			03/31/22	20.00	10.00	19.34	48.80
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6,283.00	13.57	1.53	1.74
NH0504-911			04/07/22	225.00	1.65	2.65	2.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	24.00	15.00	41.83	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,875.00	0.33	0.33	0.33
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3,870.00	0.85	0.74	0.43
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	420.00	1.50	0.67	0.72
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	900.00	20.00	1.56	1.46
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,433.00	1.50	1.28	1.28
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	6.00	1.50	29.40	11.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	233.00	2.00	2.95	0.85
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	3.50	142.40	119.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	458.00	2.00	4.25	5.00
C0852-120		Rehabilitation of Culvert by	05/26/22	120.00	5.00	3.00	3.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	150.00	17.00	12.00	12.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	180.00	5.00	2.75	2.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	13.00	2.50	8.67	7.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	873.00	1.50	1.53	1.90
WEIGHTED AVERAGE FOR THE SECOND QUARTER				10,783.00	2.99	1.29	1.38
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,770.00	0.46	0.46	0.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	30.00	10.00	4.41	2.60
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	150.00	3.00	10.25	8.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11.00	3.00	7.07	2.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00703		Humate		Pound =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	34.00	5.00	6.33	7.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	74.00	3.50	3.54	3.36
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	794.00	0.96	0.96	0.96
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	2.50	1.20	1.59
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	147.00	3.00	4.18	3.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	648.00	1.50	4.36	4.54
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	975.00	2.14	1.63	0.72
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	742.00	3.00	2.55	4.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,475.00	1.60	2.71	1.93
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	146.00	7.00	4.53	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	168.00	1.25	8.13	7.40
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	193.00	1.75	4.27	8.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	37.50	5.00	13.13	11.92
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	74.00	6.00	3.78	3.13
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,826.00	1.00	1.09	1.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8,060.00	1.75	2.50	2.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	450.00	3.00	3.34	3.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	63.00	1.60	85.33	2.99
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	120.00	3.50	3.50	4.40
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	105.00	4.00	2.67	2.60
C5502-097		US550 MP 117.28-126.06	11/17/22	10,010.00	1.75	1.01	0.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	381.00	1.00	2.77	1.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	45.00	1.50	16.77	20.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	100.00	10.00	11.00	7.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	740.00	5.00	1.73	1.60
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10.00	7.00	3.88	1.75
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	845.00	1.00	1.37	2.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	26.00	5.00	23.23	39.46
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	608.00	1.75	1.87	0.60
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	380.00	2.00	1.96	1.15
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1,923.00	2.00	1.82	1.07
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	112.00	5.00	3.22	3.79
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	98.00	2.25	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	480.00	1.00	3.33	2.81
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		27,000.50	1.89	2.00	1.78
		WEIGHTED AVERAGE FOR THE YEAR		49,541.50	3.58	1.84	1.70
===== 212-00704		Mycorrhizae		Pound =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	30.00	18.32	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 174

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00704	Mycorrhizae		Pound	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	270.00	50.00	7.88	2.50
NHPP1601-083			02/03/22	480.00	20.00	25.70	21.00
STA0252-459			02/03/22	12.80	15.00	26.40	13.50
C0762-055			02/17/22	28.00	20.00	22.34	16.00
BRC040-057			03/17/22	15.00	25.00	38.93	9.70
WEIGHTED AVERAGE FOR THE FIRST QUARTER				825.80	30.06	16.45	14.80
NH0504-911			04/07/22	60.00	23.50	13.15	11.30
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	280.00	11.56	11.56	11.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,032.00	17.50	11.19	9.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	76.00	20.00	12.19	12.19
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	62.00	19.00	23.00	14.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	18.00	43.25	50.00
C0852-120		Rehabilitation of Culvert by	05/26/22	12.00	30.00	18.00	18.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	25.00	81.00	75.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	45.00	197.00	13.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	47.00	23.00	24.35	30.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,603.00	17.18	12.66	11.92
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	296.00	11.30	11.30	11.30
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	40.00	91.75	26.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	8.00	19.00	195.33	125.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.40	18.00	21.67	20.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	30.00	40.88	38.88
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	43.00	26.75	26.75	26.75
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	35.00	24.27	23.06
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	37.00	50.00	23.57	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	60.00	25.00	20.84	14.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	46.00	20.00	21.28	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				515.40	18.92	24.35	17.75
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	9.00	23.00	26.88	45.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	10.00	12.00	44.21	45.82
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	50.00	60.75	70.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00704 Mycorrhizae Pound =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	101.00	20.00	20.05	21.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	435.00	20.00	22.10	22.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	24.00	25.00	19.68	29.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	17.00	21.00	22.01	17.02
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	14.00	50.00	20.85	46.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	17.07	18.39	3.89
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	17.00	139.99	120.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	50.00	15.00	14.80	15.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	46.00	20.00	14.33	17.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	13.00	50.00	73.07	85.13
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	34.00	25.00	14.57	12.30
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.10	75.00	19.24	21.99
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	26.00	35.00	26.85	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	27.00	30.00	27.38	37.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				923.10	21.81	21.55	21.78
WEIGHTED AVERAGE FOR THE YEAR				3,867.30	21.27	16.32	15.67
===== 212-00705 Elemental Sulfur Pound =====							
BRC040-057			03/17/22	3.00	20.00	52.50	10.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	20.00	52.50	10.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	948.00	1.50	1.03	1.03
C0852-120		Rehabilitation of Culvert by	05/26/22	36.00	15.00	3.00	3.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	20.00	22.50	21.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				992.00	2.14	1.44	1.26
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	880.00	0.71	0.71	0.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	29.00	20.00	9.56	8.68
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	2.00	7.75	4.24
WEIGHTED AVERAGE FOR THE THIRD QUARTER				939.00	1.35	2.04	1.07
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	3.00	100.00	141.22	220.43
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				3.00	100.00	141.22	220.43
WEIGHTED AVERAGE FOR THE YEAR				1,937.00	1.93	2.45	1.52

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 176

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00706		Seed (Native) Drill		Acre =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.50	3500.00	1189.93	1250.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	9.60	900.00	959.55	1300.00
C0762-055			02/17/22	3.00	1200.00	809.48	570.00
STR0141-031			02/17/22	0.65	5000.00	3375.00	1625.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3.25	2000.00	571.82	500.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.54	11283.00	7710.52	7710.52
WEIGHTED AVERAGE FOR THE FIRST QUARTER				20.54	2342.54	1031.08	1551.63
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10.00	4708.00	4708.00	4708.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.20	1400.00	1215.70	1190.28
STA0712-019		SH 71: Frieght Improvements	05/12/22	9.60	1000.00	738.88	738.88
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3.05	1200.00	1400.00	1600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	0.90	5000.00	2813.50	2600.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	0.10	1300.00	5712.67	7000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	5.82	1000.00	1053.10	1015.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				30.67	2362.90	1698.75	2263.74
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.30	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	0.50	1165.27	7064.00	12000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	0.05	2500.00	15482.31	15000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.17	3000.00	4300.00	5000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	5.25	722.25	722.25	722.25
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	0.50	3000.00	4510.24	960.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2.49	1700.00	1163.69	1431.22
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	5.90	2000.00	1199.78	1064.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.40	3000.00	1569.31	1600.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				27.56	1691.35	1445.49	1438.21
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.07	1900.00	1888.43	5000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	0.49	4000.00	4187.50	5000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.91	1050.00	1465.13	1200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	212-00706	Seed (Native) Drill		Acre	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	53.10	800.00	870.00	870.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	1608.85	1400.00
C5502-097		US550 MP 117.28-126.06	11/17/22	43.20	1000.00	914.89	831.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	0.60	1050.00	12182.50	10950.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	706.20	981.98	990.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	5.23	2000.00	1700.00	1800.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	0.94	1100.00	2657.93	2200.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.40	2500.00	1929.55	1025.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.20	1500.00	1241.43	1167.94
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.71	2000.00	2216.37	2461.22
STA385A-016		SH 385 MP 97.76	12/22/22	3.00	1000.00	2430.63	2687.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				130.85	1038.86	1364.14	1146.35
WEIGHTED AVERAGE FOR THE YEAR				209.62	1446.11	1350.98	1378.29
=====							
=====	212-00707	Seed (Native) Hyd)		Acre	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.60	1500.00	1290.84	1600.00
NHPP1601-083			02/03/22	24.00	1000.00	1581.32	1500.00
STA0252-459			02/03/22	0.64	800.00	4846.49	4925.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3.25	2000.00	891.42	1000.00
C0761-239							
STR092A-031			03/17/22	0.50	2000.00	1845.00	1845.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				34.99	1197.83	1388.28	1540.00
=====							
NH0504-911			04/07/22	3.00	5000.00	2175.00	2250.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3.00	2427.83	2427.83	2427.83
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	51.60	1400.00	1383.47	1382.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1800.00	1168.39	1003.33
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.50	4500.00	2400.00	2300.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.10	700.00	2390.00	1670.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				64.20	1667.34	1444.27	1494.99
=====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	3039.55	3039.55	3039.55
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.09	1141.33	1247.31	1247.31
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 178

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00707 Seed (Native) Hyd Acre =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.50	1800.00	1819.27	1727.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.55	2500.00	1409.87	1100.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	0.75	2500.00	1681.16	2266.10
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.10	6000.00	3488.81	1600.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10.99	2656.05	2029.29	2387.05
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	0.73	2000.00	3115.00	3500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	3000.00	6400.00	5650.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.63	2000.00	2049.67	2814.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	0.40	3000.00	2605.00	2900.00
C5502-097		US550 MP 117.28-126.06	11/17/22	0.05	2000.00	9200.33	10690.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1754.00	2418.01	3714.72
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	0.50	3000.00	10750.00	14000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.50	1200.00	1547.10	1560.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	0.30	1500.00	5093.53	3880.60
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.10	1250.00	3355.16	2650.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.50	2500.00	1558.61	1230.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	6.40	1500.00	1733.40	2096.65
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.30	3500.00	1948.62	2000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	0.50	1700.00	2993.00	3300.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				21.41	1840.96	2349.69	2942.72
WEIGHTED AVERAGE FOR THE YEAR				131.59	1653.32	1612.27	1817.01
===== 212-00708 Seed (Native) Brdcst Acre =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.40	15000.00	2337.03	3000.00
C0762-055			02/17/22	0.20	3000.00	1737.01	650.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	0.65	1000.00	2330.48	1500.00
BRC040-057			03/17/22	0.15	4000.00	11244.05	3522.00
STR R500-171		Various locations on SH 141 a	03/17/22	0.10	1620.00	4581.39	5000.00
NHM765-007			03/31/22	0.10	20000.00	11797.38	18319.33
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.60	9620.00	3100.76	3140.47
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	0.12	15000.00	12923.45	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 179

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00708	Seed (Native) Brdcst		Acres =====			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	4716.56	4716.56	4716.56
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	1500.00	1500.00
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	0.03	900.00	24286.78	5000.00
CM760-047		COLFAX AND QUAIL	05/12/22	0.01	4000.00	72837.40	58387.00
C0852-120		Rehabilitation of Culvert by	05/26/22	0.76	5000.00	1200.00	1200.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	0.75	6000.00	12500.00	12500.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	0.10	2000.00	11012.80	3275.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.77	5048.31	4732.48	4156.75
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.50	1424.28	1424.28	1424.28
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	0.20	5000.00	4219.89	4550.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.72	4000.00	5392.35	11127.06
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	0.50	3500.00	1532.00	1696.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	0.20	6000.00	1693.93	2200.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	0.60	4000.00	2264.70	1798.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.40	7000.00	1938.30	1600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.12	4084.02	2859.58	4051.42
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	0.84	2500.00	5677.67	6033.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	0.01	4000.00	112750.00	69000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	0.26	5000.00	2694.71	2900.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	0.50	2000.00	2600.00	2600.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.20	4238.00	1970.00	1610.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	0.20	3000.00	1715.00	2300.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	0.70	3400.00	3904.10	1575.00
C5502-097		US550 MP 117.28-126.06	11/17/22	6.80	2000.00	1152.85	1020.00
MPR200-280		PUEBLO AREA	11/17/22	0.20	1850.00	2250.00	3500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	0.03	2961.00	36163.81	29035.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	0.30	3400.00	6829.30	6000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	0.20	2500.00	1282.22	1290.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	0.05	10000.00	35377.50	39755.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	0.10	8000.00	9277.57	2432.70
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	15000.00	11044.65	13444.30
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	0.10	5000.00	6080.70	1461.40
STA385A-016		SH 385 MP 97.76	12/22/22	0.20	2000.00	4187.50	6250.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10.82	2587.47	2715.18	2495.69
		WEIGHTED AVERAGE FOR THE YEAR		21.31	4215.56	3032.41	3158.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 180

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00709 Seeding (Wetland) Drill Acre =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	0.10	2500.00	9434.76	9400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	0.05	5000.00	12028.27	15500.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.15	3333.33	10587.43	11433.33
===== 212-00710 Seeding (Wetland) Hydraulic Acre =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	0.59	11000.00	3106.50	7600.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.10	5000.00	10392.86	1230.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			0.69	10130.43	4162.49	6676.81
	WEIGHTED AVERAGE FOR THE YEAR			0.84	8916.67	5742.40	7526.19
===== 212-00710 Seeding (Wetland) Hydraulic Acre =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4000.00	5089.34	3535.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	5089.34	3535.39
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	5089.34	3535.39
===== 212-00711 Seeding (Wetland) Broadcast Acre =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	0.10	9000.00	9890.78	7500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.10	9000.00	9890.78	7500.00
===== 212-00711 Seeding (Wetland) Broadcast Acre =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	0.14	3705.41	3705.41	3705.41
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.14	3705.41	3705.41	3705.41
===== 212-00711 Seeding (Wetland) Broadcast Acre =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.62	3481.07	3481.07	3481.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 181

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00711 Seeding (Wetland) Broadcast Acre =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.01	6322.73	6955.00	6955.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			0.63	3526.18	3536.21	3536.21
	WEIGHTED AVERAGE FOR THE YEAR			0.87	4184.19	6789.29	4019.05
===== 212-01200 Landscape Restoration LUMP SUM =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	5000.00	18705.76	3384.42
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	18705.76	3384.42
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	20000.00	15878.96	5000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	10000.00	17800.05	17800.05
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	15000.00	16359.24	11400.03
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	10000.00	20410.01	5000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	34250.00	25000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	20000.00	27330.00	15000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	19740.54	11312.17
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	8000.00	8134.04	3069.09
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	9000.00	13937.29	7190.63
	WEIGHTED AVERAGE FOR THE YEAR			7.00	13285.71	18053.92	10080.82
===== 213-00002 Mulching (Weed Free Hay) Acre =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	3.90	1500.00	1471.92	1000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 182

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 213-00002		Mulching (Weed Free Hay)		Acre =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	0.20	2000.00	2937.56	5500.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.91	4000.00	903.77	1100.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	9800.00	7702.00	8144.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.11	2433.72	1346.72	1295.48
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7.00	1926.00	1926.00	1926.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	1926.00	1926.00	1926.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.80	1282.40	1282.40	1282.40
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.17	1500.00	4866.67	5500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.97	1291.72	1706.52	1463.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	0.84	3500.00	2860.00	2780.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.66	2900.00	1563.65	3250.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	0.49	4000.00	3068.75	3125.00
MPR200-280		PUEBLO AREA	11/17/22	0.20	2350.00	2250.00	3500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	5.23	1500.00	1300.00	1100.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	7000.00	9366.47	10470.94
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	0.10	5000.00	13546.40	10292.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.65	2247.28	1841.82	1696.92
		WEIGHTED AVERAGE FOR THE YEAR		25.73	2056.71	1649.95	1646.04
===== 213-00003		Mulching (Weed Free)		Acre =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	1000.00	8143.33	5756.90
NHPP1601-083			02/03/22	24.00	800.00	2370.48	2500.00
NHPP0703-472			03/10/22	0.50	602.00	3502.96	3100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.60	796.79	2461.24	2525.43
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	0.12	9000.00	11053.14	7500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00003 Mulching (Weed Free) Acre =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.20	750.00	1048.65	1159.13
C0852-120		Rehabilitation of Culvert by	05/26/22	0.10	5000.00	9400.00	9400.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	0.90	5000.00	1716.00	1600.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.32	3008.62	1644.63	2013.34
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.49	5000.00	3808.90	4526.69
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	5.25	668.75	668.75	668.75
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	3.00	1500.00	1785.67	1007.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	0.50	5000.00	2753.28	882.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.40	1000.00	1661.40	1500.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				13.64	1272.80	1708.44	1157.70
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	0.01	15000.00	88600.00	52000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2500.00	1192.92	850.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.20	736.00	5651.33	9554.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	0.60	600.00	1968.50	2050.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	0.03	662.40	28422.98	35158.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.50	1300.00	1013.88	1110.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	8000.00	14492.37	17677.80
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	0.94	2600.00	3131.86	2700.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.10	1000.00	1699.70	1625.22
STA385A-016		SH 385 MP 97.76	12/22/22	3.20	1000.00	1896.88	2187.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				14.68	1701.03	1778.60	1802.40
WEIGHTED AVERAGE FOR THE YEAR				55.24	1247.52	1996.89	1974.06
===== 213-00004 Mulching (Weed Free Straw) Acre =====							
BRC040-057			03/17/22	0.08	1500.00	13160.81	7439.00
STR R500-171		Various locations on SH 141 a	03/17/22	0.10	3300.00	4775.99	5000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				0.18	2500.00	9103.64	6084.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	8.40	1100.00	744.16	744.16
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8.40	1100.00	744.16	744.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 184

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00004 Mulching (Weed Free Straw) Acre =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.49	1900.00	1991.02	1647.03
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.49	1900.00	1991.02	1647.03
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.92	2000.00	1022.02	950.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	53.10	1000.00	875.00	875.00
C5502-097		US550 MP 117.28-126.06	11/17/22	43.20	900.00	1498.91	1530.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.40	2000.00	1946.73	1640.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.46	2500.00	3939.49	2149.96
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	5000.00	5856.81	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			107.08	1090.49	1298.44	1173.68
	WEIGHTED AVERAGE FOR THE YEAR			118.15	1110.38	1341.23	1160.60
===== 213-00006 Mulching (Weed Free) Ton =====							
NHPP0063-063			02/24/22	250.00	10.00	105.50	132.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			250.00	10.00	105.50	132.00
	WEIGHTED AVERAGE FOR THE YEAR			250.00	10.00	105.50	132.00
===== 213-00007 Mulching (Wood Strand) Acre =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	5000.00	15000.00	15000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5000.00	15000.00	15000.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.54	21849.14	21849.14	21849.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			0.54	21849.14	21849.14	21849.14
	WEIGHTED AVERAGE FOR THE YEAR			2.54	8582.10	15814.66	16456.12

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 185

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00008 Mulching (Wood Chip) Cubic Foot =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	245.00	2.50	10.07	9.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			245.00	2.50	10.07	9.00
	WEIGHTED AVERAGE FOR THE YEAR			245.00	2.50	10.07	9.00
===== 213-00011 Mulching (Hydraulic) Acre =====							
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	1.55	1600.00	3086.97	3300.00
2670703-497	I-70_GENESEE WILDLIFE XING		09/15/22	0.75	1600.00	3086.38	2896.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.30	1600.00	3086.65	3168.42
	WEIGHTED AVERAGE FOR THE YEAR			2.30	1600.00	3086.65	3168.42
===== 213-00012 Spray-on Mulch Blanket Acre =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	6.00	2000.00	4217.83	2600.00
C0762-055			02/17/22	3.00	3500.00	3768.58	2900.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	0.65	4500.00	6483.33	7000.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	0.29	4000.00	5475.05	5500.00
C0761-239							
STR092A-031			03/17/22	0.50	4700.00	4835.00	4835.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.44	2771.55	4265.98	3147.75
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	3.00	5605.73	5605.73	5605.73
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	51.60	4090.00	3799.39	3100.00
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	1.50	4000.00	7850.00	7700.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	0.75	17000.00	17500.00	17500.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	4.91	3768.00	4216.40	4000.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	0.10	1200.00	11012.80	3275.60
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			61.86	4287.62	3935.93	3579.37
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	6.00	5042.27	5042.27	5042.27

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00012		Spray-on Mulch Blanket		Acre =====			
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	4000.00	12922.64	18445.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.09	6955.00	6955.00	6955.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	0.20	7000.00	6566.90	7900.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	5.80	3500.00	3941.53	4272.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.60	6000.00	5827.11	4000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		13.69	4395.88	4583.19	5703.59
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	0.73	3000.00	7175.00	7500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	6000.00	8541.50	7950.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10.00	3250.00	3770.13	3700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	10.00	3500.00	4151.89	4400.00
C5502-097		US550 MP 117.28-126.06	11/17/22	0.05	7000.00	7183.41	9890.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.07	4070.00	5015.71	6104.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	0.50	5000.00	12750.00	16000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	0.50	5000.00	4598.58	4640.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.70	5000.00	5634.81	4400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.50	5000.00	4143.07	3691.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.60	5000.00	5520.91	5412.19
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.07	20000.00	15349.79	9228.45
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.30	5000.00	3869.88	3000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	0.50	5400.00	5010.67	5600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		34.02	3999.56	4429.40	4678.43
		WEIGHTED AVERAGE FOR THE YEAR		120.01	4086.42	4166.63	4095.70
===== 213-00016		Mulching Pelletized Matl(Waterless Appl)		Acre =====			
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.45	5400.00	6650.00	8000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.45	5400.00	6650.00	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		4.45	5400.00	6650.00	8000.00
===== 213-00061		Mulch Tackifier		Pound =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	40.00	3.20	16.44	16.38

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 187

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00061	Mulch Tackifier		Pound	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	5.00	4.68	5.00
NHPP1601-083			02/03/22	4,600.00	6.00	4.49	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	230.00	5.00	3.66	3.50
C0761-239							
NHPP0703-472			03/10/22	125.00	3.00	11.42	5.00
BRC040-057			03/17/22	10.00	5.00	48.01	28.05
STR R500-171		Various locations on SH 141 a	03/17/22	300.00	12.00	10.52	2.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	20.00	35.00	34.00	38.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				5,405.00	6.29	5.43	4.17
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	24.00	65.00	47.21	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,400.00	4.28	4.28	4.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	240.00	3.00	4.17	5.05
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,676.00	4.00	3.91	3.91
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	6.00	149.80	135.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	50.00	47.00	47.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	180.00	15.00	3.75	3.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3,543.00	5.28	5.32	4.78
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	700.00	5.68	5.68	5.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	34.00	5.00	4.00	5.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	98.00	5.00	8.88	10.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,050.00	3.16	3.16	3.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,000.00	5.00	3.23	2.93
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	20.00	6.79	4.70
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	100.00	25.00	5.76	10.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	490.00	3.60	3.57	3.41
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	878.00	4.00	5.29	6.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4,450.00	5.11	4.17	4.45
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	168.00	15.00	9.67	10.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,784.00	2.50	3.37	4.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10,624.00	4.00	4.00	4.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	722.00	2.20	3.77	3.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 188

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00061 Mulch Tackifier Pound =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	600.00	3.00	4.61	3.84
C5502-097		US550 MP 117.28-126.06	11/17/22	8,640.00	4.00	4.08	4.20
MPR200-280		PUEBLO AREA	11/17/22	40.00	11.00	27.50	45.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	120.00	5.00	7.05	3.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	65.00	2.30	10.83	5.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	5.00	5.02	5.10
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,046.00	5.00	3.63	3.40
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	28.00	15.00	27.84	38.68
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	40.00	20.00	8.89	4.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	15.00	17.69	28.17
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	188.00	4.00	4.97	4.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	400.00	3.00	3.03	2.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	420.00	5.00	4.93	4.24
STA385A-016		SH 385 MP 97.76	12/22/22	640.00	5.00	5.22	3.38
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				25,795.00	4.03	4.20	4.22
WEIGHTED AVERAGE FOR THE YEAR				39,193.00	4.57	4.40	4.29
===== 213-00066 Mulch (Paper Base) Acre =====							
C0762-055			02/17/22	2.00	2000.00	2038.78	1600.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	2000.00	2038.78	1600.00
WEIGHTED AVERAGE FOR THE YEAR				2.00	2000.00	2038.78	1600.00
===== 213-00067 Rock Mulch (Weed Free) Sq Foot =====							
NHPP0063-063			02/24/22	16,034.00	3.00	3.53	3.35
WEIGHTED AVERAGE FOR THE FIRST QUARTER				16,034.00	3.00	3.53	3.35
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		12,099.00	4.00	4.18	2.75
WEIGHTED AVERAGE FOR THE THIRD QUARTER				12,099.00	4.00	4.18	2.75
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	848.00	20.00	7.32	11.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				848.00	20.00	7.32	11.00
WEIGHTED AVERAGE FOR THE YEAR				28,981.00	3.91	3.96	3.32

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 189

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00070 Landscape Weed Barr Fabric Sq Yard =====							
NHPP0063-063			02/24/22	1,782.00	2.00	5.40	7.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,782.00	2.00	5.40	7.65
	WEIGHTED AVERAGE FOR THE YEAR			1,782.00	2.00	5.40	7.65
===== 213-00071 Vegetation Control Mat Sq Yard =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	67.00	50.00	86.01	133.03
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			67.00	50.00	86.01	133.03
	WEIGHTED AVERAGE FOR THE YEAR			67.00	50.00	86.01	133.03
===== 213-00150 Bonded Fiber Matrix Acre =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	6500.00	4356.87	5250.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	3000.00	3797.97	2900.00
NHM765-007			03/31/22	0.10	10000.00	14054.97	11142.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			21.10	3199.05	3867.67	3050.44
NH0504-911			04/07/22	3.00	3000.00	3890.00	3980.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20.00	4896.32	4896.32	4896.32
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	2956.00	3880.38	2700.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	0.20	3000.00	6069.40	6069.40
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.10	3400.00	6616.67	5350.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3.00	3000.00	3838.00	3675.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			39.30	3985.40	4334.37	4216.04
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	20.00	4545.68	4545.68	4545.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.50	3500.00	3784.15	3996.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			24.50	4353.62	4108.21	4444.72

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 190

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00150 Bonded Fiber Matrix Acre =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	18.00	4200.00	3800.00	3800.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.14	3100.00	8347.67	7543.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	0.50	5000.00	7913.00	4250.00
C5502-097		US550 MP 117.28-126.06	11/17/22	12.50	5000.00	6021.71	6470.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.40	3500.00	5266.67	4300.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3800.00	5438.76	4700.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	9.00	5000.00	5235.00	4068.76
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	0.50	5000.00	4471.00	4000.00
STA385A-016		SH 385 MP 97.76	12/22/22	0.60	5000.00	6075.00	4500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			44.64	4570.65	5358.42	4686.26
	WEIGHTED AVERAGE FOR THE YEAR			129.54	4128.64	4496.34	4231.47
===== 213-00151 Bonded Fiber Matrix Pound =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6,000.00	1.75	2.33	1.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6,000.00	1.75	2.33	1.80
	WEIGHTED AVERAGE FOR THE YEAR			6,000.00	1.75	2.71	1.85
===== 213-00300 Conc Landscape Border Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	3,902.00	39.29	48.17	48.17
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,902.00	39.29	48.17	48.17
	WEIGHTED AVERAGE FOR THE YEAR			3,902.00	39.29	48.17	48.17
===== 213-00610 Landscape Log Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	24.00	531.79	531.79	531.79
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	531.79	531.79	531.79
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	546.57	546.57	546.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 191

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00610		Landscape Log		Each =====			
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	546.57	546.57	546.57
	WEIGHTED AVERAGE FOR THE YEAR			36.00	536.72	536.72	536.72
===== 213-00700		Landscape Boulder		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	48.00	500.00	630.90	550.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	180.00	300.00	299.15	195.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			228.00	342.11	346.54	269.74
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	48.00	531.79	531.79	531.79
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	224.00	23.00	1150.00	650.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			272.00	112.79	1108.79	629.14
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	133.00	494.62	494.62	494.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	600.00	686.95	875.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			153.00	508.40	539.09	544.34
	WEIGHTED AVERAGE FOR THE YEAR			653.00	285.55	572.79	483.78
===== 213-00705		Landscape Boulder (Special)		Each =====			
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	130.00	400.00	451.67	130.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			130.00	400.00	451.67	130.00
	WEIGHTED AVERAGE FOR THE YEAR			130.00	400.00	451.67	130.00
===== 213-00800		Brush Fill		Cubic Yard =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	30.00	56.21	56.21	56.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 192

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00800		Brush Fill		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			30.00	56.21	56.21	56.21
	WEIGHTED AVERAGE FOR THE YEAR			30.00	56.21	56.21	56.21
===== 214-00000		Landscape Maintenance		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	31080.00	36920.98	36920.98
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	31080.00	36920.98	36920.98
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4500.00	13487.17	10245.22
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	4500.00	13487.17	10245.22
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17790.00	16834.86	23583.10
===== 214-00008		Extended Landscape Preservation		LUMP SUM	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	15000.00	22833.33	38000.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	50000.00	143666.93	170320.80
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	10000.00	90539.33	62000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	5000.00	24071.45	21581.86
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	20000.00	58726.18	72975.67
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	25000.00	36777.54	40000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	15000.00	24600.96	24800.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	10000.00	27996.73	16900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	16666.67	28777.03	27233.33
	WEIGHTED AVERAGE FOR THE YEAR			7.00	18571.43	45890.83	53371.81
===== 214-00205		Deciduous Tree (5 Gal)		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	500.00	169.14	7.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	500.00	169.14	7.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 193

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-00205 Deciduous Tree (5 Gal) Each =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	28.00	25.00	92.17	54.80
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			28.00	25.00	92.17	54.80
	WEIGHTED AVERAGE FOR THE YEAR			38.00	150.00	120.89	42.22
===== 214-00215 Deciduous Tree (1.5 In C) Each =====							
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	60.00	500.00	441.68	250.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			60.00	500.00	441.68	250.00
	WEIGHTED AVERAGE FOR THE YEAR			60.00	500.00	441.68	250.00
===== 214-00220 Deciduous Tree (2 In C) Each =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	665.00	798.43	798.43
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	665.00	798.43	798.43
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	650.00	821.09	987.13
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	650.00	821.09	987.13
	WEIGHTED AVERAGE FOR THE YEAR			12.00	660.00	815.43	861.33
===== 214-00222 Decid Tree (2 In Cal) (Furnish) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	250.00	613.11	719.16
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	250.00	613.11	719.16
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	24.00	500.00	539.17	565.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			24.00	500.00	539.17	565.00
	WEIGHTED AVERAGE FOR THE YEAR			29.00	456.90	560.92	591.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 194

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-00227 Furn Deciduous Tree (2.5 In C) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	9.00	1000.00	565.45	380.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	1000.00	565.45	380.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	1000.00	565.45	380.00
===== 214-00310 Deciduous Shrub (1 Gal) Each =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	15.00	48.14	39.33
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			30.00	15.00	48.14	39.33
	WEIGHTED AVERAGE FOR THE YEAR			30.00	15.00	48.14	39.33
===== 214-00506 Evergreen Tree (6 Ft) (B-B) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	550.00	728.03	866.23
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	550.00	728.03	866.23
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	5.00	660.00	782.83	730.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	660.00	782.83	730.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	605.00	746.30	798.12
===== 214-00507 Furn Evergreen Tree (6 Ft) (B-B) Each =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	24.00	470.00	535.40	620.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			24.00	470.00	535.40	620.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	470.00	535.40	620.00
===== 214-01009 Brush Windrow Lin Foot =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	340.00	9.10	24.56	56.29
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			340.00	9.10	24.56	56.29
	WEIGHTED AVERAGE FOR THE YEAR			340.00	9.10	24.56	56.29

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 195

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-01010 Brush Layer Cutting Each =====							
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	40.00	5.00	13.57	14.59
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	5.00	13.57	14.59
===== 214-01013 Live Willow Stakes Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	150.00	6.00	8.52	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		150.00	6.00	8.52	7.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	400.00	11.46	11.46	11.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,075.00	12.00	7.70	10.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,475.00	11.85	8.29	10.40
===== 214-01015 Willow Cuttings Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	352.00	12.00	7.18	7.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		352.00	12.00	7.18	7.00
		WEIGHTED AVERAGE FOR THE YEAR		1,977.00	11.44	8.06	9.53
===== 214-01015 Willow Cuttings Each =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1,081.00	10.00	9.17	10.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,081.00	10.00	9.17	10.00
		WEIGHTED AVERAGE FOR THE YEAR		1,081.00	10.00	9.17	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 196

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-01016 Live Willow Poles Each =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	18.00	100.00	72.10	130.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		18.00	100.00	72.10	130.00	
	WEIGHTED AVERAGE FOR THE YEAR		18.00	100.00	72.10	130.00	
===== 214-01228 Riprap Planting Pocket Each =====							
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT	08/25/22	78.00	200.00	58.33	20.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		78.00	200.00	58.33	20.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	63.00	20.00	201.77	205.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		63.00	20.00	201.77	205.00	
	WEIGHTED AVERAGE FOR THE YEAR		141.00	119.57	122.42	102.66	
===== 214-01401 Nursery Stock Container (DRC #10) Each =====							
NHPP0702-414 FBR0702-423	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,000.00	4.09	4.09	4.09	
	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,000.00	4.09	4.09	4.09	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	101.00	15.00	8.72	15.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101.00	15.00	8.72	15.00	
	WEIGHTED AVERAGE FOR THE YEAR		2,101.00	4.61	4.70	4.61	
===== 214-01403 Nursery Stock Container (DRC # 60) Each =====							
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	205.00	28.10	28.10	28.10	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 197

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-01403		Nursery Stock Container (DRC # 60)		Each	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	108.00	20.00	10.17	11.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			313.00	25.31	17.12	22.20
	WEIGHTED AVERAGE FOR THE YEAR			313.00	25.31	17.12	22.20
===== 214-01404		Nursery Stock Container (DRC # 180)		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	18.00	25.00	27.93	41.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	25.00	27.93	41.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	25.00	27.93	41.00
===== 214-01420		(SNC #1) Nursery Stock Container		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	30.00	22.00	81.90	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	22.00	81.90	220.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	79.00	30.00	46.24	18.45
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			79.00	30.00	46.24	18.45
	WEIGHTED AVERAGE FOR THE YEAR			109.00	27.80	57.72	73.92
===== 215-00600		Transplant Plug		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,000.00	13.64	13.64	13.64
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,000.00	13.64	13.64	13.64
	WEIGHTED AVERAGE FOR THE YEAR			1,000.00	13.64	13.64	13.64
===== 216-00021		Soil Reten Blanket (C1 1)		Sq Yard	=====		
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	340.00	5.00	6.33	7.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			340.00	5.00	6.33	7.00
	WEIGHTED AVERAGE FOR THE YEAR			340.00	5.00	6.33	7.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 198

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00022 Soil Reten Blanket (Cl 2) Sq Yard =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	595.00	5.00	4.92	5.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			595.00	5.00	4.92	5.00
	WEIGHTED AVERAGE FOR THE YEAR			595.00	5.00	4.92	5.00
===== 216-00041 Soil Reten Blanket (S/C) Sq Yard =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2,408.00	3.00	3.82	3.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1,492.00	4.00	3.34	3.27
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,900.00	3.38	3.68	3.54
	WEIGHTED AVERAGE FOR THE YEAR			3,900.00	3.38	3.68	3.54
===== 216-00042 Soil Retent Blanket (BioD S/C) Sq Yard =====							
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,210.00	10.00	3.08	3.47
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,210.00	10.00	3.08	3.47
	WEIGHTED AVERAGE FOR THE YEAR			1,210.00	10.00	3.08	3.47
===== 216-00070 Geocell Confinement Sys Sq Yard =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,250.00	30.00	34.34	31.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,250.00	30.00	34.34	31.00
	WEIGHTED AVERAGE FOR THE YEAR			1,250.00	30.00	34.34	31.00
===== 216-00101 Soil Reten Blanket (S-C) (PhotoD Cl 1) Sq Yard =====							
NHPP1601-083			02/03/22	5,704.00	3.50	4.59	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	21,975.00	3.20	2.51	2.50
C0761-239							
BRC040-057			03/17/22	150.00	5.00	5.28	2.83
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			27,829.00	3.27	2.64	2.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 199

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00101 Soil Reten Blanket (S-C) (PhotoD Cl 1) Sq Yard =====							
NH0504-911			04/07/22	1,500.00	2.41	3.85	4.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	19,000.00	2.43	2.43	2.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20,500.00	2.43	2.62	2.56

STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	70.00	3.00	25.03	9.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	3.00	25.03	9.00

STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	14,127.00	2.75	2.96	3.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,127.00	2.75	2.96	3.14
		WEIGHTED AVERAGE FOR THE YEAR		62,526.00	2.88	2.72	2.81
===== 216-00111 Soil Reten Blanket (Excel) (PhotoD Cl 1) Sq Yard =====							
NH0504-911			04/07/22	1,500.00	5.00	3.80	3.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,500.00	5.00	3.80	3.90
		WEIGHTED AVERAGE FOR THE YEAR		1,500.00	5.00	3.80	3.90
===== 216-00201 Soil Reten Blanket (S-C) (BioD Cl 1) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	48,320.00	2.50	2.26	1.50
C0762-055			02/17/22	970.00	5.00	2.76	3.00
STR0141-031			02/17/22	3,146.00	4.00	2.87	2.35
STR092A-031			03/17/22	2,420.00	4.00	2.35	2.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		54,856.00	2.70	2.29	1.61

2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,855.00	2.75	2.82	3.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 200

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00201		Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard			
STA0712-019		SH 71: Frieght Improvements	05/12/22	5,634.00	2.50	2.64	2.64
C0852-120		Rehabilitation of Culvert by	05/26/22	2,450.00	5.00	2.50	2.50
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	12.00	10.00	10.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	10.00	4.50	4.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4,405.00	3.00	3.33	3.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,484.00	3.09	2.97	2.92
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	21,780.00	3.66	3.66	3.66
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	968.00	5.50	4.95	6.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	986.00	2.41	2.41	2.41
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	400.00	10.00	4.43	3.23
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	240.00	7.00	5.60	4.70
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	7,289.00	4.00	4.28	5.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	5,550.00	4.00	3.66	2.67
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,390.00	5.00	2.83	2.43
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40,603.00	3.98	3.68	3.70
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	970.00	3.30	3.32	4.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	680.00	3.00	6.24	5.95
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,311.00	3.50	3.50	3.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,258.00	3.00	3.05	2.50
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2,904.00	3.50	3.20	2.60
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	3,388.00	4.00	2.99	3.10
C5502-097		US550 MP 117.28-126.06	11/17/22	6,888.00	3.50	3.96	4.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,460.00	3.90	3.76	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,000.00	3.00	5.25	6.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,981.00	3.50	2.75	2.70
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	242.00	5.00	7.38	9.75
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,878.00	3.00	3.43	2.80
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,917.00	4.00	4.63	4.40
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,500.00	4.00	3.75	4.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	12,300.00	2.50	3.86	4.60
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2,310.00	5.00	4.19	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	700.00	10.00	4.60	4.38
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		50,687.00	3.39	3.67	3.83
		WEIGHTED AVERAGE FOR THE YEAR		164,630.00	3.27	3.03	2.97

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 201

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00221 Soil Reten Blanket (C) (BioD Cl 1) Sq Yard =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10,619.00	3.00	3.47	3.55
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10,619.00	3.00	3.47	3.55
	WEIGHTED AVERAGE FOR THE YEAR			10,619.00	3.00	3.47	3.55
===== 216-00301 Turf Reinf Mat (Cl 1) Sq Yard =====							
NH0504-911			04/07/22	1,500.00	4.73	8.95	9.40
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,500.00	4.73	8.95	9.40
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	735.00	5.00	6.92	7.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			735.00	5.00	6.92	7.00
	WEIGHTED AVERAGE FOR THE YEAR			2,235.00	4.82	8.09	8.61
===== 216-00302 Turf Reinf Mat (Cl 2) Sq Yard =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	6.00	8.61	6.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	6.00	8.61	6.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,981.00	10.00	7.33	6.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,981.00	10.00	7.33	6.50
	WEIGHTED AVERAGE FOR THE YEAR			3,081.00	9.87	7.37	6.50
===== 216-00303 Turf Reinf Mat (Cl 3) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6,860.00	5.30	7.53	7.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,860.00	5.30	7.53	7.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 202

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00303		Turf Reinf Mat (Cl 3)		Sq Yard	=====		
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2,372.00	7.50	11.74	12.21
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,050.00	8.00	10.09	13.39
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,422.00	7.73	10.76	12.76
	WEIGHTED AVERAGE FOR THE YEAR			11,282.00	6.25	8.61	9.56
===== 216-00304		Turf Reinforcement Mat (Special)		Sq Yard	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	322.00	7.00	38.17	45.25
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			322.00	7.00	38.17	45.25
	WEIGHTED AVERAGE FOR THE YEAR			322.00	7.00	38.17	45.25
===== 217-00000		Herbicide Treatment		Sq Yard	=====		
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	500.00	10.00	3.72	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			500.00	10.00	3.72	4.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	10,000.00	1.50	0.72	0.72
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5.00	186.40	625.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10,001.00	1.50	0.81	0.78
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	13,552.00	1.00	0.43	0.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13,552.00	1.00	0.43	0.50
	WEIGHTED AVERAGE FOR THE YEAR			24,053.00	1.40	0.60	0.69
===== 217-00020		Herbicide Treatment		Hour	=====		
STA0252-459			02/03/22	60.00	150.00	179.56	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 203

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 217-00020		Herbicide Treatment		Hour =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	40.00	180.00	189.56	185.00
C0761-239							
CR100-362			03/14/22	100.00	144.34	144.34	144.34
BRC040-057			03/17/22	8.00	200.00	186.00	179.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	160.00	149.50	209.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		218.00	155.20	178.46	164.48
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	80.00	145.00	217.35	150.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	250.00	125.00	125.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	5.00	100.00	203.00	187.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		101.00	159.41	213.55	147.87
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	160.00	155.00	145.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	180.00	199.50	279.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	15.00	130.00	188.20	222.60
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	100.00	155.00	188.07	99.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	20.00	155.00	210.40	193.10
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		173.00	154.86	188.64	136.90
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	80.00	150.00	171.13	148.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	25.00	180.00	176.19	200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	140.00	212.90	246.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	150.00	678.37	650.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	16.00	175.00	156.04	141.08
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	150.00	159.46	143.50
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	200.00	116.49	111.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		313.00	157.00	190.45	202.29
		WEIGHTED AVERAGE FOR THE YEAR		805.00	156.35	190.78	171.17
===== 218-00000		Noxious Weed Management		LUMP SUM =====			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	10357.60	10357.60	10357.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10357.60	10357.60	10357.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 204

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 218-00000 Noxious Weed Management LUMP SUM =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	18837.89	18837.89	18837.89
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	18837.89	18837.89	18837.89

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	10000.00	11201.34	5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	11201.34	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	13065.16	11880.62	11398.50
===== 240-00000 Wildlife Biologist Hour =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	24.00	150.00	135.00	135.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	60.00	125.00	152.11	150.00
NHPP1601-083			02/03/22	40.00	140.00	259.90	240.00
STA0252-459			02/03/22	60.00	120.00	117.80	130.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	250.00	160.00	114.25	120.00
C0761-239							
NHPP0703-472			03/10/22	60.00	125.00	94.49	85.00
BRC040-057			03/17/22	40.00	200.00	152.50	135.00
STR R500-171		Various locations on SH 141 a	03/17/22	45.00	260.00	103.85	10.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			579.00	157.34	121.98	121.92

NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	16.00	107.00	107.00	107.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.00	126.00	120.96	90.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	120.00	98.85	95.41
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	130.00	138.33	140.00
CM760-047		COLFAX AND QUAIL	05/12/22	20.00	130.00	113.60	100.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	100.00	125.00	83.37	85.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	175.00	30.00	30.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	170.00	150.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	48.00	130.00	106.80	106.80
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	96.00	125.00	97.75	90.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			420.00	131.13	101.03	98.18

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 205

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00000		Wildlife Biologist		Hour =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	107.00	107.00	107.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	130.00	117.84	115.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	140.00	126.67	125.00
CI211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	150.00	170.00	220.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	140.00	191.48	259.44
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	75.00	85.00	95.40	95.40
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	60.00	140.00	132.07	127.20
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	20.00	110.00	140.87	140.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	20.00	120.00	130.37	113.59
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		259.00	117.71	129.71	123.46
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	20.00	150.00	150.13	148.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	30.00	150.00	190.00	190.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	16.00	135.00	126.41	140.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	140.00	121.47	135.00
C5502-097		US550 MP 117.28-126.06	11/17/22	40.00	130.00	233.29	242.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	10.00	150.00	220.00	190.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	185.00	130.62	94.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	24.00	200.00	200.00	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	120.00	146.67	130.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	150.00	186.05	90.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	24.00	130.00	182.49	254.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	150.00	365.54	1027.58
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	150.00	134.71	94.86
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		378.00	146.90	187.00	244.82
		WEIGHTED AVERAGE FOR THE YEAR		1,636.00	141.93	133.77	146.86
===== 240-00010		Rem of Nests		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	24.00	150.00	130.00	130.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	100.00	127.07	130.00
NHPP1601-083			02/03/22	10.00	150.00	399.74	125.00
STA0252-459			02/03/22	40.00	110.00	88.27	107.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	10.00	100.00	138.78	150.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	120.00	115.77	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 206

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00010 Rem of Nests Hour =====							
C0761-239							
NHPP0703-472			03/10/22	60.00	100.00	87.57	75.00
BRC040-057			03/17/22	40.00	115.00	181.00	53.00
STR R500-171		Various locations on SH 141 a	03/17/22	112.00	215.00	161.52	10.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				416.00	141.30	129.73	74.74
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	190.00	144.59	90.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	120.00	111.23	89.45
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	16.00	115.00	138.33	140.00
CM760-047		COLFAX AND QUAIL	05/12/22	20.00	120.00	101.00	94.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	100.00	80.00	69.26	53.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	170.00	150.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	48.00	120.00	106.80	106.80
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	96.00	80.00	194.75	95.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				428.00	114.49	130.88	100.38
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	140.00	126.89	115.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	120.00	213.33	135.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	75.00	75.00	175.97	175.97
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	60.00	160.00	235.36	198.09
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	10.00	100.00	101.12	120.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				195.00	116.03	193.05	167.35
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	120.00	298.57	185.70
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	16.00	150.00	183.69	142.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	125.00	153.56	140.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	40.00	140.00	98.96	105.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	10.00	91.80	144.22	182.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	300.00	100.00	150.52	148.68
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	150.00	133.81	88.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	24.00	160.00	270.50	111.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	20.00	120.00	369.14	343.27
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	130.00	144.58	150.80
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	150.00	92.99	89.28

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 207

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00010	Rem of Nests			Hour =====			
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22		20.00	100.00	114.07	142.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			528.00	115.22	151.32	146.23
	WEIGHTED AVERAGE FOR THE YEAR			1,567.00	122.04	143.32	118.07
===== 240-00017	Protect Migratory Birds			LUMP SUM =====			
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		1.00	9000.00	10220.45	3500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	9000.00	10220.45	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	9000.00	10220.45	3500.00
===== 240-00020	Netting			Sq Yard =====			
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22		4,500.00	10.00	7.08	4.00
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22		300.00	32.00	11.15	10.00
C0761-239							
BRC040-057		03/17/22		200.00	15.00	35.00	6.00
NHM765-007		03/31/22		20.00	10.00	41.85	57.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,020.00	11.51	9.12	4.65
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		178.00	8.50	15.51	12.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			178.00	8.50	15.51	12.00
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22		50.00	25.00	25.89	79.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	25.00	25.89	79.00
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22		200.00	35.00	13.30	9.90
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22		20.00	27.00	38.54	43.62
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		1,400.00	27.00	8.35	7.59

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 208

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00020 Netting Sq Yard =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	6,100.00	7.00	14.26	9.51
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	10.00	22.82	31.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7,820.00	11.39	12.88	9.61
	WEIGHTED AVERAGE FOR THE YEAR			13,068.00	11.45	11.35	8.01
===== 240-00100 Prairie Dog Mgmt LUMP SUM =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	10000.00	13672.35	15000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	13672.35	15000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	5000.00	17500.00	18000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5000.00	17500.00	18000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	28000.00	23036.31	25000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	28000.00	23036.31	25000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	14333.33	18259.41	19333.33
===== 250-00010 Envir Health/Safety Mngmt LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	10000.00	4864.84	3700.00
NHPP0063-063			02/24/22	1.00	5000.00	6075.00	7500.00
ER007A-035			03/15/22	1.00	43000.00	45000.00	45000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	19333.33	10184.28	18733.33
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	5000.00	4805.89	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 209

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	250-00010	Envir Health/Safety Mngmt		LUMP SUM	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	13750.00	15000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	10000.00	6449.31	11358.87
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	15000.00	37902.47	65000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	15000.00	12158.60	24714.72
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	38594.92	4400.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	10000.00	16800.03	5000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	42500.00	21068.09	4133.33
		WEIGHTED AVERAGE FOR THE YEAR		9.00	22555.56	14727.66	16745.89
=====	250-00050	Monitoring Technician		Hour	=====	=====	=====
NHPP0063-063			02/24/22	40.00	140.00	124.00	48.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	140.00	132.45	115.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		70.00	140.00	130.34	76.71
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	140.00	245.63	265.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	20.00	150.00	170.00	210.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	200.00	142.53	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	151.43	209.29	232.86
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,000.00	135.00	98.33	99.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	78.00	197.79	45.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,010.00	134.44	103.96	102.25
		WEIGHTED AVERAGE FOR THE YEAR		1,150.00	135.81	110.03	108.23
=====	250-00100	Environmental Health and Safety		LUMP SUM	=====	=====	=====
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	7850.00	13902.67	30000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7850.00	13902.67	30000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7850.00	13902.67	30000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 210

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00110 Health and Safety Officer Hour =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	200.00	108.79	150.00
NHPP0063-063			02/24/22	20.00	130.00	195.50	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	160.00	115.24	125.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	60.00	300.00	79.08	50.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				180.00	221.11	107.70	116.11
CM760-047		COLFAX AND QUAIL	05/12/22	16.00	130.00	117.40	107.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				16.00	130.00	117.40	107.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	150.00	180.27	265.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	150.00	187.50	245.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	200.00	161.44	150.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				58.00	158.62	178.02	242.41
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	650.00	150.00	121.12	120.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	200.00	226.52	125.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				660.00	150.76	126.25	125.47
WEIGHTED AVERAGE FOR THE YEAR				914.00	164.75	123.46	130.30
===== 250-00120 Material Sampling and Delivery Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	474.05	86.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	2000.00	474.05	86.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	10.00	200.00	250.98	150.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10.00	200.00	250.98	150.00
WEIGHTED AVERAGE FOR THE YEAR				12.00	500.00	325.34	139.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 211

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00200 Material Handling (Stockpile) Cubic Yard =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1,415.00	30.00	26.69	17.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		1,415.00	30.00	26.69	17.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 11/03/22		5,000.00	45.00	25.30	23.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		5,000.00	45.00	25.30	23.00
	WEIGHTED AVERAGE FOR THE YEAR			6,415.00	41.69	25.52	21.68
===== 250-00204 Materials Management Plan LUMP SUM =====							
ER007A-035			03/15/22	1.00	40550.00	40000.00	40000.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	40550.00	40000.00	40000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	40550.00	40000.00	40000.00
===== 250-00210 Solid Waste Disposal Cubic Yard =====							
NHPP1601-083			02/03/22	20.00	400.00	456.61	200.00
NHPP0063-063			02/24/22	85.00	100.00	189.00	155.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		105.00	157.14	239.97	163.57
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 11/03/22		5,000.00	80.00	74.01	43.50
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		5,000.00	80.00	74.01	43.50
	WEIGHTED AVERAGE FOR THE YEAR			5,105.00	81.59	76.30	45.97
===== 250-00224 Hazardous Waster Disposal (Radioactive) Cubic Yard =====							
NHPP0063-063			02/24/22	100.00	85.00	177.00	64.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		100.00	85.00	177.00	64.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 212

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00224		Hazardous Waster Disposal (Radioactive)		Cubic Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1,415.00	30.00	29.33	28.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,415.00	30.00	29.33	28.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		50.00	150.00	285.23	766.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	150.00	285.23	766.00
	WEIGHTED AVERAGE FOR THE YEAR			1,565.00	37.35	54.31	53.88
===== 304-01000		ABC (CL 1)		Ton	=====		
STR092A-031			03/17/22	6,091.39	30.00	38.00	38.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,091.39	30.00	38.00	38.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C 12/22/22		18,884.00	30.00	33.61	36.59
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18,884.00	30.00	33.61	36.59
	WEIGHTED AVERAGE FOR THE YEAR			24,975.39	30.00	33.88	36.93
===== 304-01005		ABC (CL 1)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT 01/13/22		20,654.00	25.00	65.09	67.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20,654.00	25.00	65.09	67.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 07/08/22		2,115.00	42.35	42.35	42.35
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,115.00	42.35	42.35	42.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 213

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-01005 ABC (CL 1) Cubic Yard =====							
C5502-097	US550 MP 117.28-126.06		11/17/22	34,089.00	45.00	52.15	54.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			34,089.00	45.00	52.15	54.20
	WEIGHTED AVERAGE FOR THE YEAR			56,858.00	37.64	58.49	58.41
===== 304-02000 ABC (CL 2) Ton =====							
NHPP1601-083			02/03/22	67,481.00	20.00	24.18	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			67,481.00	20.00	24.18	28.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22		4,000.29	60.00	41.00	37.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,000.29	60.00	41.00	37.00
	WEIGHTED AVERAGE FOR THE YEAR			71,481.29	22.24	25.12	28.50
===== 304-03000 ABC (CL 3) Ton =====							
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22		6,650.00	32.00	27.34	32.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6,650.00	32.00	27.34	32.50
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22		120.00	50.00	57.82	51.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			120.00	50.00	57.82	51.25
	WEIGHTED AVERAGE FOR THE YEAR			6,770.00	32.32	28.65	32.83
===== 304-03005 ABC (CL 3) Cubic Yard =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		266.00	30.00	94.80	75.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			266.00	30.00	94.80	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-03005 ABC (CL 3) Cubic Yard =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	329.00	65.00	46.01	43.80
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	225.00	30.00	327.50	410.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		554.00	50.79	134.16	192.53
		WEIGHTED AVERAGE FOR THE YEAR		820.00	44.04	115.24	154.40
===== 304-06000 ABC (CL 6) Ton =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	847.00	60.00	88.46	59.54
NHPP1601-083			02/03/22	31,010.00	20.00	25.18	29.00
STA0252-459			02/03/22	220.00	40.00	80.45	100.00
NHPP0063-063			02/24/22	3,281.00	30.00	51.90	70.00
NHPP0703-472			03/10/22	20.00	25.00	171.79	175.00
CR100-362			03/14/22	500.00	121.66	121.66	121.66
STR092A-031			03/17/22	4,568.53	32.00	39.00	39.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40,446.53	24.37	32.24	35.70
NH0504-911			04/07/22	896.00	40.00	37.50	35.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,840.00	55.00	58.57	32.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,708.00	55.37	55.37	55.37
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	37,707.00	26.00	25.70	22.69
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	34.00	150.00	168.76	107.52
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4,958.00	35.00	45.00	55.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	200.00	30.00	63.50	66.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	95.00	90.00	62.33	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	488.00	50.00	49.01	49.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		49,926.00	30.85	28.69	29.45
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	7,476.00	40.00	75.89	85.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	24.00	300.00	157.50	150.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	24.00	22.50	122.94	84.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,524.00	40.77	76.37	85.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 215

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06000 ABC (CL 6) Ton =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	40.00	214.43	66.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6,996.00	45.00	38.32	32.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5,428.00	50.00	40.85	41.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,928.00	35.00	83.75	71.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15,414.00	18.00	41.25	50.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2,000.20	65.00	68.00	40.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	144.00	80.00	294.00	410.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15,292.00	40.00	59.83	59.70
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	68.30	110.00	145.07	85.32
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,854.00	50.00	42.76	43.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	7,427.00	75.00	36.54	38.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				56,711.50	41.40	43.30	45.25
WEIGHTED AVERAGE FOR THE YEAR				154,608.03	33.51	37.25	40.08
===== 304-06007 ABC (CL 6) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	592.00	75.00	83.08	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,586.00	41.00	96.93	66.00
STR0141-031			02/17/22	691.00	40.00	104.75	76.25
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16,146.00	60.00	46.94	41.00
C0761-239							
ER007A-035			03/15/22	54.00	244.50	157.65	157.65
STR092A-031			03/17/22	484.00	70.00	70.00	70.00
NHM765-007			03/31/22	11,853.00	65.00	84.81	55.52
WEIGHTED AVERAGE FOR THE FIRST QUARTER				32,406.00	60.62	59.38	49.85
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,307.00	45.00	59.90	62.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	21,354.00	65.00	82.42	82.42
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	158.00	58.00	63.90	40.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6,083.00	60.00	62.39	48.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				30,902.00	61.84	67.66	73.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,706.00	98.08	98.08	98.08

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 216

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06007 ABC (CL 6) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	51.00	150.00	222.62	222.53
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	794.00	76.05	87.81	87.81
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,545.00	70.00	71.95	67.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	584.00	94.00	88.67	87.47
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,124.00	85.00	52.03	28.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	45.00	250.00	174.16	58.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				9,849.00	85.62	66.41	66.82
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	526.00	60.00	93.00	78.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	39.00	225.00	240.31	56.25
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9,545.00	100.00	102.00	102.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	164.00	49.00	142.98	102.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,091.00	70.00	112.39	82.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	544.00	70.00	137.40	107.20
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	688.00	70.00	73.63	46.15
C5502-097		US550 MP 117.28-126.06	11/17/22	12,725.00	60.00	57.90	54.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	64.40	531.73	221.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	62.00	74.00	165.00	100.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,093.00	45.00	55.55	52.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	61.00	330.00	410.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,443.00	43.19	77.83	55.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,388.00	68.00	80.61	72.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	101.00	150.00	150.58	122.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	226.50	70.00	100.94	122.33
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	533.00	65.00	108.00	130.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,264.00	60.00	115.96	70.83
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				38,484.50	69.68	79.26	73.44
WEIGHTED AVERAGE FOR THE YEAR				111,641.50	66.28	66.84	65.95
===== 304-06008 ABC (CL 6) (Spec) Cubic Yard =====							
NHPP0703-472			03/10/22	141.00	50.00	154.79	95.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				141.00	50.00	154.79	95.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	3,735.00	70.00	94.37	94.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 217

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06008	ABC (CL 6) (Spec)			Cubic Yard	=====	=====	=====
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC	05/12/22		3,470.00	60.00	51.65	42.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS	06/02/22		13.00	53.00	173.67	250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,218.00	65.16	66.99	69.47
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22		3,752.00	55.00	52.38	53.10
STA0711-021	SH71: REGION LINE NORTH	12/01/22		9,607.00	50.00	84.58	80.00
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22		440.00	80.00	92.65	108.91
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13,799.00	52.32	72.80	73.61
	WEIGHTED AVERAGE FOR THE YEAR			21,158.00	56.68	72.54	72.34
===== 304-06009	ABC (CL 6) (Spec)			Ton	=====	=====	=====
NHPP1601-083		02/03/22		8,585.00	22.00	22.90	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,585.00	22.00	22.90	25.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL	05/26/22		1,317.00	30.00	60.50	56.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,317.00	30.00	60.50	56.00
	WEIGHTED AVERAGE FOR THE YEAR			9,902.00	23.06	27.90	29.12
===== 304-07000	ABC (CL 7)			Ton	=====	=====	=====
STR092A-031		03/17/22		3,190.43	30.00	32.00	32.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,190.43	30.00	32.00	32.00
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS	10/13/22		231.82	40.00	127.23	81.70
NHPP0701-253	I-70 EAST OF DEBEQUE	10/27/22		3,360.00	35.00	39.50	40.70
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22		16,197.93	55.00	37.50	42.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22		1,307.00	35.00	46.35	69.11
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21,096.75	50.41	40.38	43.91
	WEIGHTED AVERAGE FOR THE YEAR			24,287.18	47.73	39.84	42.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 218

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-07005 ABC (CL 7) Cubic Yard =====							
STR0141-031			02/17/22	1,675.00	40.00	77.00	60.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,675.00	40.00	77.00	60.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4,021.00	75.00	68.28	80.90
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	174.00	80.00	96.15	81.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	679.00	80.00	121.00	117.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,874.00	75.88	74.72	85.93
	WEIGHTED AVERAGE FOR THE YEAR			6,549.00	66.70	75.32	79.30
===== 304-07009 ABC (CL 7) (Spec) Ton =====							
C0762-055			02/17/22	5,032.00	40.00	37.04	33.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,032.00	40.00	37.04	33.00
	WEIGHTED AVERAGE FOR THE YEAR			5,032.00	40.00	37.04	33.00
===== 304-08000 ABC (Shoulder Material) Ton =====							
ER007A-035			03/15/22	5,023.00	30.15	32.25	32.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,023.00	30.15	32.25	32.25
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	5,755.00	30.00	59.33	48.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,755.00	30.00	59.33	48.00
	WEIGHTED AVERAGE FOR THE YEAR			10,778.00	30.07	53.23	40.66
===== 304-08002 ABC (Shoulder Material) Cubic Yard =====							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	955.00	60.00	69.04	58.07
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			955.00	60.00	69.04	58.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 219

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-08002 ABC (Shoulder Material) Cubic Yard =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,299.00	60.00	91.40	98.20
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	65.00	180.67	152.01
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,399.00	60.36	95.16	98.51
	WEIGHTED AVERAGE FOR THE YEAR			2,354.00	60.21	89.43	86.52
===== 304-09000 ABC (Spec) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6,390.00	25.00	29.13	23.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,390.00	25.00	29.13	23.50
	WEIGHTED AVERAGE FOR THE YEAR			6,390.00	25.00	29.13	23.50
===== 304-09006 ABC (Spec) Sq Yard =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	25,870.00	3.00	4.01	3.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25,870.00	3.00	4.01	3.60
	WEIGHTED AVERAGE FOR THE YEAR			25,870.00	3.00	4.01	3.60
===== 304-09014 ABC (Spec) Ton =====							
NHPP1601-083			02/03/22	11,215.00	22.00	30.62	34.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11,215.00	22.00	30.62	34.00
	WEIGHTED AVERAGE FOR THE YEAR			11,215.00	22.00	30.62	34.00
===== 304-09102 ABC (RAP) Cubic Yard =====							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	323.00	60.00	42.62	66.24
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			323.00	60.00	42.62	66.24

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 220

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-09102 ABC (RAP) Cubic Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	138.00	156.81	156.81	156.81
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19,371.00	30.00	25.48	11.04
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,509.00	30.90	25.67	12.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	472.00	141.37	141.37	141.37
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	216.00	60.00	172.50	90.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		688.00	115.82	156.25	125.24
		WEIGHTED AVERAGE FOR THE YEAR		20,520.00	34.20	27.22	17.00
===== 306-01000 Reconditioning Sq Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	49,883.00	1.40	3.12	2.20
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		49,883.00	1.40	3.12	2.20
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	113.00	10.00	67.58	13.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		113.00	10.00	67.58	13.16
		WEIGHTED AVERAGE FOR THE YEAR		49,996.00	1.42	3.16	2.22
===== 310-00608 Full Depth Reclam. of HMA Pvm (0-8 in.) Sq Yard =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	172,383.00	3.50	1.72	2.71
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	65,200.00	4.00	4.50	3.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	58,857.00	6.00	5.13	7.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		296,440.00	4.11	2.40	3.63
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	16,466.00	5.00	10.98	4.65

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 221

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 310-00608	Full Depth Reclam. of HMA Pvm (0-8 in.)	Sq Yard	=====				
STA0711-021	SH71: REGION LINE NORTH	12/01/22	247,636.00	3.00	3.63	5.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		264,102.00	3.12	3.94	4.98	
	WEIGHTED AVERAGE FOR THE YEAR		560,542.00	3.64	3.04	4.26	
===== 310-00610	Full Depth Reclam. of HMA Pvm (8-12 in)	Sq Yard	=====				
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	16,432.00	3.00	4.40	2.40	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		16,432.00	3.00	4.40	2.40	
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	43,739.00	3.75	2.48	3.65	
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL	05/26/22	4,928.00	6.00	6.72	10.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		48,667.00	3.98	2.67	4.29	
STA0711-021	SH71: REGION LINE NORTH	12/01/22	11,499.00	3.50	4.66	6.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,499.00	3.50	4.66	6.00	
	WEIGHTED AVERAGE FOR THE YEAR		76,598.00	3.70	3.28	4.14	
===== 310-00614	Full Depth Reclam of HMA Pvm (12-16 in)	Sq Yard	=====				
NHPP1601-083		02/03/22	156,865.00	3.25	5.33	7.40	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		156,865.00	3.25	5.33	7.40	
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	41,166.00	4.50	4.53	7.33	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		41,166.00	4.50	4.53	7.33	
	WEIGHTED AVERAGE FOR THE YEAR		198,031.00	3.51	5.01	7.39	
===== 310-00700	Asphalt Emulsion Full Depth Reclamation	Sq Yard	=====				
NHPP1601-083		02/03/22	190,232.00	3.50	4.56	6.50	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		190,232.00	3.50	4.56	6.50	
	WEIGHTED AVERAGE FOR THE YEAR		190,232.00	3.50	4.56	6.50	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 222

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 310-00800 Process Cem Tr Full Depth Reclam Sq Yard =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	257,288.00	2.40	3.45	3.13
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			257,288.00	2.40	3.45	3.13
	WEIGHTED AVERAGE FOR THE YEAR			257,288.00	2.40	3.45	3.13
===== 310-00900 Hydraulic Cement Ton =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	5,019.00	165.00	228.60	240.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,019.00	165.00	228.60	240.00
	WEIGHTED AVERAGE FOR THE YEAR			5,019.00	165.00	228.60	240.00
===== 403-00720 HMA (Patching) (Asph) Ton =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	1,226.00	220.00	199.06	140.63
STR0505-050			01/13/22	6.00	250.00	1311.67	2000.00
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	55.00	230.00	391.90	446.67
STA0252-459			02/03/22	10.00	200.00	531.03	531.00
C0762-055			02/17/22	517.00	175.00	178.38	172.00
STR0141-031			02/17/22	610.00	400.00	311.67	265.00
NHPP0063-063			02/24/22	4,870.00	180.00	194.00	165.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	200.00	150.00	170.54	190.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	482.00	220.00	300.79	250.00
C0761-239							
NHPP0703-472			03/10/22	220.00	180.00	211.75	165.00
CR100-362			03/14/22	60.00	259.77	259.77	259.77
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	583.83	170.00	181.95	153.89
STR R500-171	Various locations on SH 141 a		03/17/22	356.00	350.00	511.52	462.00
NHM765-007			03/31/22	776.00	200.00	242.80	222.30
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,971.83	207.31	234.74	191.10
NH0504-911			04/07/22	755.00	150.00	193.25	166.50
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	471.00	275.00	265.81	300.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1,000.00	180.00	194.56	165.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	244.00	240.00	297.16	310.76
STA0712-019	SH 71: Frieght Improvements		05/12/22	346.00	175.00	222.54	222.54

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-00720	HMA (Patching) (Asph)		Ton =====			
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	500.00	185.00	157.50	150.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	50.00	200.00	256.00	318.00
CM760-047		COLFAX AND QUAIL	05/12/22	94.00	230.00	376.40	313.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	800.00	150.00	177.50	165.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	3.20	250.00	1799.67	1000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	454.00	190.00	174.75	174.75
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	50.00	350.00	251.32	241.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,767.20	186.81	217.21	195.45
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	31.00	369.39	369.39	369.39
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	750.00	358.68	378.04
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	60.00	325.00	405.00	325.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	509.00	400.00	341.26	275.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	151.00	400.00	262.50	185.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	554.31	762.42	762.42
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	27.00	300.00	710.00	400.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	208.00	260.00	250.06	232.85
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	22.00	300.00	345.20	358.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,016.00	363.33	302.94	265.89
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	400.00	640.33	308.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	225.00	220.00	288.00	224.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	223.20	300.00	300.50	220.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	89.00	250.00	378.20	277.78
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	200.00	225.00	210.00	210.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	164.00	230.00	522.19	530.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	140.00	500.00	558.28	590.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	92.00	350.00	401.00	460.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	500.00	300.00	178.50	167.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	226.00	220.00	281.20	279.56
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	163.00	250.00	267.00	240.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	172.00	161.10	274.22	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	35.00	200.00	385.00	430.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	338.00	350.00	429.00	508.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	350.00	312.15	325.75
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	800.00	450.00	346.50	270.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 224

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-00720 HMA (Patching) (Asph) Ton =====							
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	34.00	300.00	539.71	400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	258.00	250.00	212.02	136.80
STR0092-024		SH 9 North of Silverthorne	12/22/22	50.00	80.00	524.50	569.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	496.00	225.00	198.30	177.01
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	24.00	200.00	201.34	200.00
STA385A-016		SH 385 MP 97.76	12/22/22	175.00	300.00	336.53	261.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	208.85	280.00	310.00	400.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,688.05	300.91	290.35	278.76
WEIGHTED AVERAGE FOR THE YEAR				20,443.08	231.75	249.69	217.29
===== 403-00721 HMA (Patching) (Asph) Sq Yard =====							
STA0252-459			02/03/22	1,500.00	40.00	169.28	93.00
C0762-055			02/17/22	27,366.00	9.75	22.65	22.00
STR133A-051			02/17/22	100.00	300.00	114.67	130.00
STR092A-031			03/17/22	232.00	220.00	95.00	95.00
NHM765-007			03/31/22	37.00	100.00	101.29	85.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				29,235.00	14.08	28.87	26.67
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	79.00	150.00	141.57	134.71
WEIGHTED AVERAGE FOR THE THIRD QUARTER				79.00	150.00	141.57	134.71
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	279.00	95.00	92.00	92.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	130.00	108.70	116.11
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	640.00	27.00	149.42	96.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,022.00	100.00	101.25	77.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,041.00	77.90	125.69	83.37
WEIGHTED AVERAGE FOR THE YEAR				31,355.00	18.57	35.41	30.97
===== 403-00800 Emerg Pothole Rep Ton =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	255.00	324.96	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 225

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-00800	Emerg Pothole Rep		Ton	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	200.00	600.00	497.01	497.01
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			300.00	485.00	374.12	398.01
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	75.00	700.00	545.75	500.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	600.00	556.54	569.31
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			125.00	660.00	549.50	527.72
	WEIGHTED AVERAGE FOR THE YEAR			425.00	536.47	453.21	436.16
=====	403-09221	SMA (Fibers) (Asph)		Ton	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	11,980.30	128.00	149.37	132.48
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,642.00	140.00	198.43	185.00
C0761-239			03/10/22	40,588.00	135.00	136.91	125.00
NHPP0703-472							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			55,210.30	133.72	145.11	129.49
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,598.00	140.00	195.22	215.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,598.00	140.00	195.22	215.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,287.00	170.00	280.90	400.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4,469.00	220.00	171.42	181.11
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5,756.00	208.82	183.44	230.05
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,488.00	180.00	204.74	190.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	13,004.00	150.00	150.92	141.89
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8,236.00	150.00	243.97	191.94
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			22,728.00	151.96	176.38	163.18
	WEIGHTED AVERAGE FOR THE YEAR			86,292.30	143.72	157.68	147.65

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 226

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-09500 Furnish HMA Ton =====							
NH0504-911			04/07/22	750.00	70.00	102.65	75.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			750.00	70.00	102.65	75.30
	WEIGHTED AVERAGE FOR THE YEAR			750.00	70.00	102.65	75.30
===== 403-33741 HMA (Gr S) (75) (PG 64-22) Ton =====							
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	11,429.00	115.00	88.38	80.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	35,372.00	110.00	135.50	131.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			46,801.00	111.22	123.99	118.55
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,750.00	100.00	113.94	100.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	28,558.00	135.50	144.00	144.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	44,358.00	130.00	116.25	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			76,666.00	130.58	120.02	116.39
	WEIGHTED AVERAGE FOR THE YEAR			123,467.00	123.24	121.33	117.21
===== 403-33841 HMA (Gr S) (100) (PG 64-22) Ton =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2,353.00	110.00	105.62	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,353.00	110.00	105.62	100.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	9,246.00	90.00	113.28	110.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,509.00	85.00	102.74	140.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4,088.00	100.00	110.74	115.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16,843.00	91.39	110.16	117.46
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	914.00	150.00	147.68	150.28

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 227

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-33841		HMA (Gr S) (100) (PG 64-22)		Ton =====			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,754.00	120.00	127.95	126.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,668.00	130.28	135.41	134.32
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,874.00	130.00	129.89	135.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4,477.00	130.00	101.90	94.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,536.00	100.00	130.33	110.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,360.00	115.00	92.96	71.40
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			11,247.00	121.42	113.16	105.55
	WEIGHTED AVERAGE FOR THE YEAR			33,111.00	106.04	112.99	113.53
===== 403-34701		HMA (Gr SX) (75)		Ton =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40,335.00	100.00	108.42	105.00
STR0141-031			02/17/22	18,314.00	90.00	86.67	85.00
STR092A-031			03/17/22	22,713.91	78.00	72.00	72.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			81,362.91	91.61	101.18	91.29
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,839.00	162.98	162.98	162.98
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6,839.00	162.98	162.98	162.98
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	24,232.00	90.00	88.00	86.00
C5502-097		US550 MP 117.28-126.06	11/17/22	37,552.00	80.00	100.14	88.60
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	47,360.11	80.00	84.00	70.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15,776.00	80.00	120.00	107.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	12,337.00	90.00	104.22	99.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	15,247.00	125.00	115.00	105.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			152,504.11	86.90	98.07	86.80
	WEIGHTED AVERAGE FOR THE YEAR			240,706.02	90.65	100.04	90.48
===== 403-34721		HMA (Gr SX) (75) (PG 58-28)		Ton =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2,399.00	150.00	141.52	151.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 228

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34721	HMA (Gr SX) (75) (PG 58-28)			Ton =====			
NHPP1601-083			02/03/22	45,768.00	105.00	104.67	95.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	17,181.00	95.00	94.66	90.00
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	50,772.78	105.00	98.26	97.52
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			116,120.78	104.45	102.93	96.52
NH0504-911			04/07/22	440.00	100.00	175.25	100.50
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	2,698.00	190.37	190.37	190.37
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	5,129.00	240.00	169.33	168.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,267.00	216.35	172.60	171.71
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	1,360.00	226.41	226.41	226.41
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	2,352.00	140.00	171.14	207.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,712.00	171.66	180.07	214.11
STA207A-004	Resurfacing SH207A MANZANOLA		10/27/22	24,853.00	120.00	130.23	121.70
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF		11/03/22	1,771.00	170.00	199.40	203.19
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	9,988.00	150.00	222.77	225.00
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	4,662.00	100.00	153.33	160.00
BR012A-048	CO 12 STRUCTURE P-17-F AT MP		12/22/22	1,701.00	155.00	171.14	170.00
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	40,331.63	100.00	141.67	122.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			83,306.63	114.57	156.58	142.32
	WEIGHTED AVERAGE FOR THE YEAR			211,406.41	113.99	134.21	121.10
===== 403-34731	HMA (Gr SX) (75) (PG 58-34)			Ton =====			
ER007A-035			03/15/22	28,450.00	114.80	124.95	124.95
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28,450.00	114.80	124.95	124.95
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	6,689.00	155.00	236.22	245.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 229

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34731		HMA (Gr SX) (75) (PG 58-34)		Ton =====			
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6,689.00	155.00	236.22	245.00
	WEIGHTED AVERAGE FOR THE YEAR			35,139.00	122.45	178.88	147.80
===== 403-34741		HMA (Gr SX) (75) (PG 64-22)		Ton =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	16,337.00	85.00	112.05	108.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,223.00	60.00	129.51	145.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	9,395.00	130.00	140.77	140.77
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26,955.00	99.55	116.09	121.10
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	99.00	200.00	282.83	340.68
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,350.00	200.00	200.47	145.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,449.00	200.00	205.36	152.91
STA385A-016		SH 385 MP 97.76	12/22/22	2,659.00	190.00	173.81	172.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,659.00	190.00	173.81	172.22
	WEIGHTED AVERAGE FOR THE YEAR			32,063.00	114.72	125.38	127.77
===== 403-34751		HMA (Gr SX) (75) (PG 64-28)		Ton =====			
BRC040-057			03/17/22	177.00	200.00	322.00	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			177.00	200.00	322.00	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	610.00	90.00	147.81	155.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	16,168.00	130.00	155.78	155.78
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	33,402.00	120.00	104.63	103.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 230

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34751	HMA (Gr SX) (75) (PG 64-28)			Ton =====			
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL	05/26/22		35,336.00	120.00	148.00	139.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS	06/02/22		89.00	200.00	592.00	448.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR	06/09/22		7,927.00	135.00	130.57	138.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			93,532.00	122.88	131.04	129.36
FSA052A-057	SH52 BOX CULVERT EXTENSION (M	08/04/22		33.00	300.00	296.81	372.04
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22		4,240.00	165.85	165.85	165.85
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4,273.00	166.89	168.84	167.44
STA3852-015	US 385 HOLYOKE NORTH	10/27/22		24,781.00	151.25	153.00	153.00
NHPP0343-048	US 34 (MP 169.3-171.4)	11/01/22		120.00	120.00	499.69	530.00
STA0711-021	SH71: REGION LINE NORTH	12/01/22		45,310.00	150.00	126.33	108.00
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22		19,030.00	140.00	105.15	101.64
STA385A-016	SH 385 MP 97.76	12/22/22		1,582.00	210.00	182.95	177.78
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			90,823.00	149.25	123.22	120.72
	WEIGHTED AVERAGE FOR THE YEAR			188,805.00	136.63	127.27	126.22
===== 403-34771	HMA (Gr SX) (75) (PG 76-28)			Ton =====			
NH0504-911		04/07/22		95,923.00	90.00	110.00	101.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			95,923.00	90.00	110.00	101.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		1,250.00	150.00	136.05	112.00
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22		1,963.00	165.00	249.50	270.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		804.00	100.00	160.00	160.00
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22		1,618.00	220.00	266.30	254.60
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,635.00	168.19	134.95	118.86
	WEIGHTED AVERAGE FOR THE YEAR			101,558.00	94.34	120.09	106.49
===== 403-34801	HMA (Gr SX) (100)			Ton =====			
NHPP0063-063		02/24/22		16,484.00	65.00	102.00	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,484.00	65.00	102.00	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 231

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34801	HMA (Gr SX) (100)			Ton =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2,248.00	200.00	181.78	130.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,248.00	200.00	181.78	130.00
NHPP0701-253		I-70 EAST OF DEBEQUE 10/27/22		16,467.00	100.00	92.00	95.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		5,943.74	175.00	153.09	117.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			22,410.74	119.89	117.61	100.83
	WEIGHTED AVERAGE FOR THE YEAR			41,142.74	102.28	115.21	102.09
===== 403-34841	HMA (Gr SX) (100) (PG 64-22)			Ton =====			
NHM765-007			03/31/22	1,145.00	180.00	230.95	210.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,145.00	180.00	230.95	210.90
	WEIGHTED AVERAGE FOR THE YEAR			1,145.00	180.00	230.95	210.90
===== 403-34851	HMA (Gr SX) (100) (PG 64-28)			Ton =====			
C0762-055			02/17/22	30,038.00	115.00	113.55	108.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30,038.00	115.00	113.55	108.00
STM1151-038		SH115 MP 27 TO MP 38 04/21/22		32,043.00	96.00	119.29	115.00
2670703-479		I-70 BRIDGE OVER HARLAN 05/05/22		122.00	90.00	188.34	165.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32,165.00	95.98	119.60	115.19
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		2,053.00	150.00	145.57	143.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,053.00	150.00	145.57	143.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 232

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34851	HMA (Gr SX) (100) (PG 64-28)			Ton	=====		
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	29,324.00	135.00	106.63	97.65	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		29,324.00	135.00	106.63	97.65	
	WEIGHTED AVERAGE FOR THE YEAR		93,580.00	115.50	114.35	108.00	
===== 403-34871	HMA (Gr SX) (100) (PG 76-28)			Ton	=====		
NHPP1601-083		02/03/22	22,114.00	115.00	119.91	110.00	
C0762-055		02/17/22	14,402.00	115.00	116.70	111.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		36,516.00	115.00	118.09	110.39	
CM760-047	COLFAX AND QUAIL	05/12/22	31.00	167.50	472.60	544.00	
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN	06/09/22	23,343.00	85.00	102.03	102.03	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		23,374.00	85.11	104.47	102.62	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,902.00	150.00	176.45	184.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,652.00	110.00	145.22	140.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	760.00	100.00	166.67	170.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	18,988.00	122.00	96.81	77.15	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		23,302.00	122.72	107.80	93.36	
	WEIGHTED AVERAGE FOR THE YEAR		83,192.00	108.76	112.26	103.44	
===== 403-36621	HMA (Gr ST) (50) (PG 58-28)			Ton	=====		
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	11,201.00	100.00	102.63	99.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,201.00	100.00	102.63	99.00	
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22	27,635.77	120.00	143.83	133.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		27,635.77	120.00	143.83	133.00	
	WEIGHTED AVERAGE FOR THE YEAR		38,836.77	114.23	131.95	123.19	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 233

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	403-36701	HMA (Gr ST) (75)		Ton	=====		
STR0141-031			02/17/22	8,729.00	95.00	86.42	78.25
STR092A-031			03/17/22	9,260.72	88.00	74.00	74.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,989.72	91.40	83.17	76.06
<hr/>							
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	27,531.46	85.00	89.50	79.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	11,238.00	90.00	122.50	108.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		38,769.46	86.45	99.07	87.41
		WEIGHTED AVERAGE FOR THE YEAR		56,759.18	88.02	94.08	83.81
<hr/>							
=====	403-40000	HMA Safety Edge		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	360.00	2.50	23.10	20.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		360.00	2.50	23.10	20.00
<hr/>							
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	12,962.00	0.75	1.72	1.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12,962.00	0.75	1.72	1.70
		WEIGHTED AVERAGE FOR THE YEAR		13,322.00	0.80	2.63	2.19
<hr/>							
=====	408-01100	Joint Sealant		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	164.00	25.00	34.66	55.31
C0762-055			02/17/22	299.00	30.00	35.97	37.00
NHPP0703-472			03/10/22	995.00	25.00	26.39	20.00
BRC040-057			03/17/22	228.00	30.00	51.75	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,686.00	26.56	32.32	28.48
<hr/>							
NH0504-911			04/07/22	608.00	27.00	37.75	35.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 234

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 408-01100		Joint Sealant		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	268.00	26.00	38.83	40.49
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		876.00	26.69	38.37	37.03
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	104.00	20.14	20.14	20.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	616.00	25.00	40.79	44.86
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	448.00	26.00	23.13	28.40
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,168.00	24.95	29.48	36.35
C5502-097		US550 MP 117.28-126.06	11/17/22	145.00	40.00	31.67	41.10
STA0711-021		SH71: REGION LINE NORTH	12/01/22	121.00	26.00	38.83	42.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	812.00	50.00	26.39	51.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	306.00	40.00	25.58	21.15
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	101.00	40.00	52.98	80.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,485.00	44.33	28.45	45.12
		WEIGHTED AVERAGE FOR THE YEAR		5,215.00	31.28	31.37	36.42
===== 409-01010		CC Matl (Ty I)		Ton			
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	2,289.37	145.00	255.92	124.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,289.37	145.00	255.92	124.00
		WEIGHTED AVERAGE FOR THE YEAR		2,289.37	145.00	255.92	124.00
===== 409-01015		CC Matl (Ty I)		Sq Yard			
STR133A-051			02/17/22	285,117.00	1.00	1.58	1.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		285,117.00	1.00	1.58	1.50
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	568,140.00	1.60	3.01	2.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 235

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	409-01015	CC Matl (Ty I)		Sq Yard	=====		
STR0092-024		SH 9 North of Silverthorne	12/22/22	266,778.00	1.50	1.65	1.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			834,918.00	1.57	2.61	1.96
	WEIGHTED AVERAGE FOR THE YEAR			1,120,035.00	1.42	2.40	1.87
=====	409-02030	CC Matl (Ty I) (Special)		Sq Yard	=====		
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	173,835.00	3.00	4.43	4.43
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			173,835.00	3.00	4.43	4.43
	WEIGHTED AVERAGE FOR THE YEAR			173,835.00	3.00	4.43	4.43
=====	409-09000	Micro-Surfacing Seal Coat		Ton	=====		
STR0505-050			01/13/22	5,897.00	230.00	230.00	175.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,897.00	230.00	230.00	175.00
NH0504-911			04/07/22	1,154.00	250.00	280.00	300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,154.00	250.00	280.00	300.00
NHM175-029		CANON CITY, CO	12/15/22	4,198.00	230.00	260.00	220.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,198.00	230.00	260.00	220.00
	WEIGHTED AVERAGE FOR THE YEAR			11,249.00	232.05	242.93	204.62
=====	411-03342	Asph Cem (PG 64-28)		Ton	=====		
STR092A-031			03/17/22	1,160.00	750.00	868.00	868.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,160.00	750.00	868.00	868.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1,229.00	1000.00	844.98	817.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,229.00	1000.00	844.98	817.00
	WEIGHTED AVERAGE FOR THE YEAR			2,389.00	878.61	850.49	841.76

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 236

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-03345 Asph Cem (PG 76-28) Ton =====						
NHPP0063-063		02/24/22	989.10	600.00	642.50	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		989.10	600.00	642.50	500.00

NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP 08/18/22		154.00	1300.00	1066.82	510.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		154.00	1300.00	1066.82	510.00

NHPP0701-253	I-70 EAST OF DEBEQUE	10/27/22	989.00	1000.00	765.00	600.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	236.25	600.00	1072.71	875.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,225.25	922.87	864.48	653.02
	WEIGHTED AVERAGE FOR THE YEAR		2,368.35	812.55	792.15	579.82
===== 411-03352 Asph Cem (PG 58-28) Ton =====						
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,392.00	500.00	650.28	630.00
STR0141-031		02/17/22	593.00	550.00	551.67	540.00
STR092A-031		03/17/22	878.03	700.00	623.00	623.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,863.03	571.69	629.55	609.21

NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	410.00	1069.89	1069.89	1069.89
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		410.00	1069.89	1069.89	1069.89

STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	272.00	1000.00	737.50	745.00
C5502-097	US550 MP 117.28-126.06	11/17/22	1,024.00	600.00	731.21	711.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,873.30	900.00	625.00	700.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	764.00	1000.00	621.50	668.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 237

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-03352	Asph Cem (PG 58-28)			Ton =====			
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22		295.00	750.00	698.97	680.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,228.30	841.38	672.39	698.38
	WEIGHTED AVERAGE FOR THE YEAR			7,501.33	750.94	660.18	684.65
===== 411-03354	Asph Cem (PG 64-22)			Ton =====			
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP 08/18/22			181.00	900.00	930.34	445.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			181.00	900.00	930.34	445.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22		120.37	450.00	882.63	705.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			120.37	450.00	882.63	705.00
	WEIGHTED AVERAGE FOR THE YEAR			301.37	720.27	903.11	548.85
===== 411-03355	Asph Cem (PG 58-34)			Ton =====			
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		1,037.00	600.00	838.84	826.00
STR0141-031		02/17/22		1,099.00	750.00	658.33	660.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,136.00	677.18	768.67	740.59
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22		1,155.00	1200.00	837.00	837.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22		2,840.15	1000.00	700.00	800.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22		947.00	1200.00	698.50	742.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22		445.00	900.00	820.68	800.00
STR0092-024	SH 9 North of Silverthorne	12/22/22		915.00	900.00	753.50	751.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6,302.15	1045.13	748.79	790.95
	WEIGHTED AVERAGE FOR THE YEAR			8,438.15	951.99	756.31	778.20
===== 411-10216	Emul Asph (CRS-2P)			Gallon =====			
STR133A-051		02/17/22		111,196.00	2.70	3.07	2.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			111,196.00	2.70	3.07	2.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 238

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-10216	Emul Asph (CRS-2P)			Gallon	=====		
MTCE 072A-045	SH 72B MP 37.00 TO MP 45.3 NE	07/07/22		86,918.00	3.50	0.75	0.75
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			86,918.00	3.50	0.75	0.75
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS	10/13/22		71,503.00	3.00	4.35	3.70
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22		221,580.00	3.40	4.00	3.25
STR0092-024	SH 9 North of Silverthorne	12/22/22		104,043.00	2.70	3.50	3.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			397,126.00	3.14	4.10	3.57
	WEIGHTED AVERAGE FOR THE YEAR			595,240.00	3.11	3.76	3.06
===== 411-10253	Emul Asph (CSS-1H)			Gallon	=====		
STR133A-051		02/17/22		18,818.00	2.60	3.88	3.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18,818.00	2.60	3.88	3.65
MTCE 072A-045	SH 72B MP 37.00 TO MP 45.3 NE	07/07/22		11,255.00	3.80	0.75	0.75
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11,255.00	3.80	0.75	0.75
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS	10/13/22		12,101.00	4.00	3.67	2.15
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22		37,487.00	4.20	4.53	3.25
STR0092-024	SH 9 North of Silverthorne	12/22/22		17,607.00	4.00	3.05	3.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			67,195.00	4.11	4.20	3.04
	WEIGHTED AVERAGE FOR THE YEAR			97,268.00	3.78	4.02	2.92
===== 411-10255	Emul Asph (SS)			Gallon	=====		
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22		7,904.00	3.80	6.35	2.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 239

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10255	Emul Asph (SS)		Gallon =====			
STR0505-050			01/13/22	10,679.00	4.00	4.58	5.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	374.00	6.00	8.24	6.56
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	14,899.00	4.00	2.65	2.30
NHPP1601-083			02/03/22	39,759.00	5.00	3.34	2.00
STR0141-031			02/17/22	12,266.00	5.00	3.00	2.50
NHPP0063-063			02/24/22	16,437.00	4.00	2.88	2.50
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20,159.00	3.00	3.36	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,248.00	6.00	4.07	3.75
C0761-239							
NHPP0703-472			03/10/22	16,217.00	4.00	6.36	3.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	20,688.00	3.00	3.00	3.00
STR092A-031			03/17/22	20,655.00	3.00	2.75	2.75
NHM765-007			03/31/22	251.00	7.00	10.81	9.12
WEIGHTED AVERAGE FOR THE FIRST QUARTER				181,536.00	3.96	3.86	2.75
NH0504-911			04/07/22	33,917.00	3.51	5.10	8.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,115.00	2.68	2.68	2.68
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	41,407.00	3.50	5.60	5.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,586.00	3.50	5.18	12.25
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3,021.00	3.00	6.67	9.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	26,660.00	3.50	3.13	3.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	16,424.00	5.00	3.52	3.52
WEIGHTED AVERAGE FOR THE SECOND QUARTER				126,130.00	3.68	5.06	5.62
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,175.00	2.68	2.68	2.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,605.00	5.00	3.90	3.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2,240.00	8.10	8.82	9.09
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6,020.00	5.32	7.44	5.15
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	7,737.00	4.50	3.55	3.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	14,562.00	5.00	5.37	6.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	468.00	5.00	10.02	9.90
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	445.00	5.00	8.60	5.81
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	12,573.00	4.00	3.60	3.00
C5502-097		US550 MP 117.28-126.06	11/17/22	11,901.00	5.00	4.35	4.30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	411-10255	Emul Asph (SS)		Gallon	=====		
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,444.00	4.00	10.25	10.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10,000.00	3.50	11.70	7.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	25,143.00	3.50	3.33	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	51,492.00	5.00	3.50	4.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,168.00	25.00	5.37	5.80
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,692.00	3.00	5.50	5.50
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	19,264.00	5.00	3.65	4.30
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	348.00	5.00	12.25	5.49
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8,161.00	3.00	5.75	4.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6,810.00	5.00	5.19	4.37
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,640.00	4.00	6.60	4.20
NHM175-029		CANON CITY, CO	12/15/22	12,555.00	4.00	6.25	4.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	14,633.00	5.00	3.95	4.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3,473.00	4.00	8.13	8.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	9,240.00	6.00	3.63	3.25
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	438.00	4.00	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,773.00	6.00	10.78	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	45,498.00	3.60	3.25	4.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		262,458.00	4.48	4.61	4.38
		WEIGHTED AVERAGE FOR THE YEAR		576,144.00	4.15	4.53	4.15
=====							
=====	411-90040	Recycling Agent		Gallon	=====		
NHPP1601-083			02/03/22	627,765.00	1.75	3.58	3.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		627,765.00	1.75	3.58	3.30
		WEIGHTED AVERAGE FOR THE YEAR		627,765.00	1.75	3.58	3.30
=====							
=====	412-00000	Furn Conc Pvmt		Cubic Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	18,267.00	130.00	142.15	110.29
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,267.00	130.00	142.15	110.29
		WEIGHTED AVERAGE FOR THE YEAR		18,267.00	130.00	142.15	110.29
=====							
=====	412-00050	Pl Conc Pvmt		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	66,685.00	12.00	31.49	30.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		66,685.00	12.00	31.49	30.07
		WEIGHTED AVERAGE FOR THE YEAR		66,685.00	12.00	31.49	30.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 241

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00190 Conc Pvmnt (Patching) Sq Yard =====							
STA0252-459			02/03/22	1,606.00	160.00	451.85	493.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,606.00	160.00	451.85	493.50
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	658.00	200.00	148.35	115.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	10.00	150.00	132.52	132.52
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			668.00	199.25	148.27	115.26
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,636.00	125.00	145.19	145.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	74.00	110.00	210.41	282.80
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	15.00	225.00	561.15	290.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	150.00	609.71	515.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,730.00	125.30	148.71	153.22
	WEIGHTED AVERAGE FOR THE YEAR			4,004.00	151.55	220.79	283.37
===== 412-00600 Conc Pvmnt (6 In) Sq Yard =====							
NHPP0063-063			02/24/22	238.00	150.00	168.10	275.00
STR092A-031			03/17/22	46.00	300.00	160.00	160.00
NHM765-007			03/31/22	1,181.00	70.00	96.88	81.82
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,465.00	90.22	105.93	115.66
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	136.00	100.00	131.32	131.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			136.00	100.00	131.32	131.32
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	451.00	100.00	75.20	83.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			451.00	100.00	75.20	83.00
	WEIGHTED AVERAGE FOR THE YEAR			2,052.00	93.02	99.07	109.52

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 242

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00700 Conc Pvmnt (7 In) Sq Yard =====						
NH0504-911		04/07/22	1,139.00	110.00	104.40	103.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,139.00	110.00	104.40	103.80
	WEIGHTED AVERAGE FOR THE YEAR		1,139.00	110.00	104.40	103.80
===== 412-00800 Conc Pvmnt (8 In) Sq Yard =====						
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22	40.00	45.00	105.99	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	45.00	105.99	90.00
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	85,051.00	48.00	64.26	54.79
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		85,051.00	48.00	64.26	54.79
C1211-099 SHE2873-193	SH 121 NORTH SGA SIGNALS	08/25/22	323.00	300.00	161.00	170.00
	US 287 & CO 52 INTERSECTION I	09/15/22	7,846.00	85.00	105.95	73.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		8,169.00	93.50	106.70	77.32
TRG0253-264 C5502-097 STAM420-001 BR2854-148 STM0091-046 2670703-487	I-25 AND SH 119 PARK-N-RIDE	10/27/22	288.00	85.00	121.76	105.00
	US550 MP 117.28-126.06	11/17/22	168.00	250.00	178.27	182.00
	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	380.00	51.40	138.08	135.75
	INTERSECTION OF US 285 & SH 9					
	ADA RAMP IMPROVEMENTS - FAIRP					
	I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,698.00	110.00	158.43	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,534.00	108.32	152.51	146.32
	WEIGHTED AVERAGE FOR THE YEAR		96,794.00	54.04	71.61	60.05
===== 412-00801 Conc Pvmnt (8 In) (Spec) Sq Yard =====						
2670403-065	US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,352.00	150.00	108.05	108.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,352.00	150.00	108.05	108.00
	WEIGHTED AVERAGE FOR THE YEAR		1,352.00	150.00	108.05	108.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 243

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00805 Conc Pvmt (8 In) (Fast Track) Sq Yard =====						
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	387.00	150.00	232.03	124.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		387.00	150.00	232.03	124.00

2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	141.00	190.00	203.35	170.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		141.00	190.00	203.35	170.00
	WEIGHTED AVERAGE FOR THE YEAR		528.00	160.68	225.35	136.28
===== 412-00850 Conc Pvmt (8-1/2 In) Sq Yard =====						
NHM765-007		03/31/22	38,372.00	90.00	90.56	74.63
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		38,372.00	90.00	90.56	74.63
	WEIGHTED AVERAGE FOR THE YEAR		38,372.00	90.00	90.56	74.63
===== 412-00900 Conc Pvmt (9 In) Sq Yard =====						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	12,878.00	100.00	142.85	155.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		12,878.00	100.00	142.85	155.00
	WEIGHTED AVERAGE FOR THE YEAR		12,878.00	100.00	142.85	155.00
===== 412-00901 Conc Pvmt (9 In) (Spec) Sq Yard =====						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	382.00	130.00	213.91	170.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		382.00	130.00	213.91	170.00
	WEIGHTED AVERAGE FOR THE YEAR		382.00	130.00	213.91	170.00
===== 412-00920 Conc Pvmt (9 In) (Fast Track) Sq Yard =====						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	420.00	300.00	158.21	175.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		420.00	300.00	158.21	175.00
	WEIGHTED AVERAGE FOR THE YEAR		420.00	300.00	158.21	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 244

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-01000 Conc Pvmt (10 In) Sq Yard =====						
CR100-362		03/14/22	95.00	337.59	337.59	337.59
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		95.00	337.59	337.59	337.59

IM025A-050	I25-MP103.9 - INTERSECTION DR 12/01/22		282.00	150.00	265.00	240.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		282.00	150.00	265.00	240.00
	WEIGHTED AVERAGE FOR THE YEAR		377.00	197.27	272.33	264.59
===== 412-01020 Conc Pvmt (10 In) (Fast Track) Sq Yard =====						
IM025A-050	I25-MP103.9 - INTERSECTION DR 12/01/22		556.00	250.00	281.67	250.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		556.00	250.00	281.67	250.00
	WEIGHTED AVERAGE FOR THE YEAR		556.00	250.00	281.67	250.00
===== 412-01050 Conc Pvmt (10-1/2 In) Sq Yard =====						
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22	68,317.00	90.00	80.55	78.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		68,317.00	90.00	80.55	78.00
	WEIGHTED AVERAGE FOR THE YEAR		68,317.00	90.00	80.55	78.00
===== 412-01100 Conc Pvmt (11 In) Sq Yard =====						
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	4,534.00	100.00	134.58	124.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	152.00	150.00	116.38	125.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,686.00	101.62	134.35	124.03
	WEIGHTED AVERAGE FOR THE YEAR		4,686.00	101.62	134.35	124.03
===== 412-01150 Conc Pvmt (11-1/2 In) Sq Yard =====						
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	420.00	310.00	199.92	200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		420.00	310.00	199.92	200.00
	WEIGHTED AVERAGE FOR THE YEAR		420.00	310.00	199.92	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 245

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-01200 Conc Pvmnt (12 In) Sq Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	63.00	200.00	596.18	310.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,689.00	120.00	143.41	132.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,752.00	121.34	147.25	134.99
	WEIGHTED AVERAGE FOR THE YEAR			3,752.00	121.34	147.25	134.99
===== 412-02000 Conc Safety Edge Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	4,871.00	6.00	5.03	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,871.00	6.00	5.03	4.00
	WEIGHTED AVERAGE FOR THE YEAR			4,871.00	6.00	5.03	4.00
===== 412-05000 Partial Depth Repair of Conc Pvmnt Sq Foot =====							
STA0252-459			02/03/22	330.00	300.00	236.07	163.60
C0762-055			02/17/22	1,000.00	50.00	121.19	120.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,330.00	112.03	143.98	130.82
	WEIGHTED AVERAGE FOR THE YEAR			1,330.00	112.03	143.98	130.82
===== 412-05002 Full Depth Repair of Conc Pavement Sq Foot =====							
STA0252-459			02/03/22	330.00	180.00	321.10	240.00
C0762-055			02/17/22	246,294.00	8.75	10.84	11.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			246,624.00	8.98	11.15	11.31
	WEIGHTED AVERAGE FOR THE YEAR			246,624.00	8.98	11.15	11.31
===== 412-05100 Poly Slab Jacking Pound =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1,247.00	8.00	18.82	19.93
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,247.00	8.00	18.82	19.93
	WEIGHTED AVERAGE FOR THE YEAR			1,247.00	8.00	18.82	19.93

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 246

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-14000 Sawing and Sealing Joints Lin Foot =====							
STA0252-459			02/03/22	381,522.90	1.80	2.33	2.50
C0762-055			02/17/22	292,140.00	1.90	2.19	2.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			673,662.90	1.84	2.26	2.39
	WEIGHTED AVERAGE FOR THE YEAR			673,662.90	1.84	2.26	2.39
===== 412-15000 Routing and Sealing Cracks Lin Foot =====							
STA0252-459			02/03/22	1,056.55	28.00	21.93	11.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,056.55	28.00	21.93	11.25
	WEIGHTED AVERAGE FOR THE YEAR			1,056.55	28.00	21.93	11.25
===== 412-15060 Rep Conc Cr (Stitch) Each =====							
STA0252-459			02/03/22	493.00	35.70	88.67	119.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			493.00	35.70	88.67	119.00
	WEIGHTED AVERAGE FOR THE YEAR			493.00	35.70	88.67	119.00
===== 420-00000 Geomembrane Sq Yard =====							
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22		2,700.00	20.65	20.65	20.65
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22		6,320.00	14.00	9.66	8.90
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9,020.00	15.99	10.39	12.42
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22		1,423.00	29.26	29.26	29.26
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,423.00	29.26	29.26	29.26
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		1,354.00	15.00	12.03	11.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 247

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00000							
		Geomembrane		Sq Yard			
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,492.00	14.00	12.82	7.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	525.00	10.00	17.00	18.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,371.00	13.86	12.91	9.52
		WEIGHTED AVERAGE FOR THE YEAR		15,814.00	16.46	11.72	12.95
===== 420-00102							
		Geotextile (Er Cont) (CL 1)		Sq Yard			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	145.00	10.00	10.48	6.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	245.00	8.60	21.67	24.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		390.00	9.12	16.23	17.40
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	224.00	116.87	116.87	116.87
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		224.00	116.87	116.87	116.87
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	63.00	9.00	11.65	6.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	6.86	3.68	3.68
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	77.00	15.00	17.15	10.44
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	71.00	15.00	16.86	18.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,006.00	5.00	13.64	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,241.00	6.43	13.97	18.29
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	36.00	20.00	16.45	14.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,838.00	6.00	6.37	4.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,874.00	6.18	6.54	4.32
		WEIGHTED AVERAGE FOR THE YEAR		4,729.00	11.73	11.39	14.40
===== 420-00103							
		Geotextile (Er Cont) (CL 2)		Sq Yard			
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	225.00	25.00	13.92	9.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		225.00	25.00	13.92	9.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 248

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00103 Geotextile (Er Cont) (CL 2) Sq Yard =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	31.00	5.00	25.44	22.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			31.00	5.00	25.44	22.00
	WEIGHTED AVERAGE FOR THE YEAR			256.00	22.58	16.07	10.57
===== 420-00112 Geotextile (Drain) (CL 1) Sq Yard =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	275.10	10.00	12.65	3.63
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	201.20	5.00	13.79	3.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			476.30	7.89	13.13	3.58
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	106.00	7.00	13.58	3.95
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			106.00	7.00	13.58	3.95
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	428.00	5.00	7.12	10.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,215.00	3.90	5.83	4.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	49.00	10.00	5.53	6.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	31.00	100.00	70.31	40.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,723.00	6.08	7.28	6.20
	WEIGHTED AVERAGE FOR THE YEAR			2,305.30	6.49	8.87	5.55
===== 420-00113 Geotextile (Drain) (CL 2) Sq Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	22.00	20.00	33.51	44.00
C0761-239			03/17/22	310.00	10.00	11.63	13.50
BRC040-057							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			332.00	10.66	14.35	15.52
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,400.00	8.77	8.77	8.77
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,400.00	8.77	8.77	8.77

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 249

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00113 Geotextile (Drain) (CL 2) Sq Yard =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	954.00	8.84	8.84	8.84
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3,012.00	4.00	3.23	2.75
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,966.00	5.16	3.99	4.21
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	147.00	20.00	5.08	5.08
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,985.00	6.50	4.76	5.30
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,132.00	6.98	4.76	5.29
	WEIGHTED AVERAGE FOR THE YEAR			9,830.00	6.63	5.39	5.70
===== 420-00114 Geotextile (Drain) (CL 3) Sq Yard =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	59.00	3.50	57.55	22.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			59.00	3.50	57.55	22.83
	WEIGHTED AVERAGE FOR THE YEAR			59.00	3.50	57.55	22.83
===== 420-00132 Geotextile (Separator) (CL 1) Sq Yard =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,000.00	5.00	7.65	7.65
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,500.00	5.00	4.63	3.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,500.00	5.00	5.13	4.33
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	14,866.00	3.50	3.79	2.50
STA0711-021		SH71: REGION LINE NORTH	12/01/22	275.00	10.00	5.63	6.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15,141.00	3.62	3.83	2.64
	WEIGHTED AVERAGE FOR THE YEAR			18,641.00	3.88	3.89	2.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 250

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00133 Geotextile (Separator) (CL 2) Sq Yard =====							
NHPP1601-083			02/03/22	1,505.00	10.00	10.45	6.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,505.00	10.00	10.45	6.00
===== 420-00134 Geotextile (Separator) (CL 3) Sq Yard =====							
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	335.00	10.00	10.00	10.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			335.00	10.00	10.00	10.00
	WEIGHTED AVERAGE FOR THE YEAR			1,840.00	10.00	10.36	6.73
===== 420-00134 Geotextile (Separator) (CL 3) Sq Yard =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	298.00	5.00	2.09	2.30
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			298.00	5.00	2.09	2.30
	WEIGHTED AVERAGE FOR THE YEAR			298.00	5.00	2.09	2.30
===== 420-00200 Geotextile (Weed Barrier) Sq Yard =====							
NHPP0703-472			03/10/22	1,685.00	7.00	6.00	2.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,685.00	7.00	6.00	2.65
	WEIGHTED AVERAGE FOR THE YEAR			1,685.00	7.00	6.00	2.65
===== 420-00300 Geotextile (Reinforcement) Sq Yard =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	639.00	5.00	10.18	12.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			639.00	5.00	10.18	12.25
===== 420-00300 Geotextile (Reinforcement) Sq Yard =====							
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	578.00	10.00	21.63	28.89
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			578.00	10.00	21.63	28.89

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 251

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00300	Geotextile (Reinforcement)			Sq Yard	=====		
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22		866.00	4.00	5.20	7.10
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			866.00	4.00	5.20	7.10
	WEIGHTED AVERAGE FOR THE YEAR			2,083.00	5.97	11.03	14.73
===== 420-00510	Geotextile (Cr Reduc) (H D)			Sq Yard	=====		
NHPP1601-083		02/03/22		267.00	45.00	38.97	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			267.00	45.00	38.97	40.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22		315.00	65.00	38.00	44.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			315.00	65.00	38.00	44.00
	WEIGHTED AVERAGE FOR THE YEAR			582.00	55.82	38.44	42.16
===== 501-00200	Steel Sheet Pile (Ty II)			Sq Foot	=====		
NHPP0343-048	US 34 (MP 169.3-171.4)	11/01/22		27,040.00	75.00	52.62	42.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			27,040.00	75.00	52.62	42.00
	WEIGHTED AVERAGE FOR THE YEAR			27,040.00	75.00	52.62	42.00
===== 502-00100	Drill Hole Fac Pile Driving			Lin Foot	=====		
2670703-497	I-70_GENESEE WILDLIFE XING	09/15/22		247.00	144.00	234.17	27.39
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			247.00	144.00	234.17	27.39
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		2,354.00	40.00	43.45	13.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,354.00	40.00	43.45	13.00
	WEIGHTED AVERAGE FOR THE YEAR			2,601.00	49.88	67.88	14.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 252

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 502-00460	File Tip			Each	=====		
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	14.00	250.00	273.07	350.00	
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22	37.00	200.00	188.11	300.00	
C0761-239							
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5	03/11/22	64.00	257.75	133.75	133.75	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				115.00	238.23	193.85	213.57
<hr/>							
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	26.00	210.00	268.29	185.00	
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	46.00	210.00	249.92	209.54	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				72.00	210.00	255.80	200.68
<hr/>							
2670703-497	I-70_GENESEE WILDLIFE XING	09/15/22	24.00	230.00	304.64	159.03	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				24.00	230.00	304.64	159.03
<hr/>							
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	44.00	243.10	382.10	260.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	200.00	210.00	160.00	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	18.00	200.00	472.55	500.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				66.00	228.73	375.68	298.50
WEIGHTED AVERAGE FOR THE YEAR				277.00	227.91	271.17	229.23
<hr/>							
===== 502-00500	CJP Splice			Each	=====		
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1500.00	1098.57	1600.00	
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	664.57	1289.84	1289.84	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				10.00	831.66	1183.58	1351.87
<hr/>							
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	26.00	1300.00	862.23	1.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 253

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-00500	CJP Splice			Each =====			
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22		4.00	1500.00	1215.16	1899.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			30.00	1326.67	917.23	254.11
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		4.00	2000.00	832.29	1000.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		4.00	1000.00	404.00	310.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	1500.00	1302.11	184.44
	WEIGHTED AVERAGE FOR THE YEAR			48.00	1252.43	1107.79	365.55
===== 502-02000	Dynamic Load Testing			LUMP SUM =====			
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		1.00	32000.00	3828.44	5300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	32000.00	3828.44	5300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	32000.00	3828.44	5300.00
===== 502-02010	Dynamic Pile Test			Each =====			
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		2.00	3000.00	3670.86	2500.00
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22		2.00	3000.00	3658.49	4049.05
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	3000.00	3664.11	3274.53
2670703-497	I-70_GENESEE WILDLIFE XING	09/15/22		4.00	2900.00	4254.39	3066.90
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	2900.00	4254.39	3066.90
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		6.00	5000.00	4536.87	3710.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		1.00	3000.00	4166.67	4500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	4714.29	4503.22	3822.86
	WEIGHTED AVERAGE FOR THE YEAR			15.00	3773.33	4196.86	3475.05

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-02012 Static Pile Load Test Each =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1.00	10000.00	15076.27	12000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	15076.27	12000.00
STM1151-038 2670703-479	SH115 MP 27 TO MP 38		04/21/22	1.00	15000.00	15658.96	8000.00
	I-70 BRIDGE OVER HARLAN		05/05/22	1.00	3000.00	28242.49	42964.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	9000.00	22522.70	25482.49
	WEIGHTED AVERAGE FOR THE YEAR			3.00	9333.33	19387.36	20988.32
===== 502-11057 Steel Pile (HP 10x57) Lin Foot =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	37.00	100.00	206.20	106.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			37.00	100.00	206.20	106.00
	WEIGHTED AVERAGE FOR THE YEAR			37.00	100.00	206.20	106.00
===== 502-11274 Steel Pile (HP 12x74) Lin Foot =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	360.00	100.00	211.28	210.00
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1,258.00	86.00	134.50	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,618.00	89.11	146.15	202.22
	WEIGHTED AVERAGE FOR THE YEAR			1,618.00	89.11	147.88	200.47
===== 502-11284 Steel Pile (HP 12x84) Lin Foot =====							
BR012A-048	CO 12 STRUCTURE P-17-F AT MP		12/22/22	320.00	160.00	307.94	275.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			320.00	160.00	307.94	275.00
	WEIGHTED AVERAGE FOR THE YEAR			320.00	160.00	307.94	275.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 255

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-11489 Steel Pile (HP 14x89) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	3,200.00	152.31	160.83	160.83
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,200.00	152.31	160.83	160.83
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,274.00	150.00	125.61	150.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,928.00	110.00	175.80	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,202.00	125.92	157.98	150.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,008.00	140.00	156.15	110.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,008.00	140.00	156.15	110.25
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,482.00	135.00	149.83	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,482.00	135.00	154.71	151.64
		WEIGHTED AVERAGE FOR THE YEAR		9,892.00	138.17	156.80	149.93
===== 502-14117 Steel Pile (HP 14x117) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	110.00	150.00	333.33	290.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		110.00	150.00	211.34	265.67
		WEIGHTED AVERAGE FOR THE YEAR		110.00	150.00	211.34	265.67
===== 503-00018 Drilled Shaft (18 In) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	16.00	320.00	279.99	210.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	320.00	279.99	210.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 256

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00018 Drilled Shaft (18 In) Lin Foot =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5.00	250.00	360.63	400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	330.00	151.61	179.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	303.33	193.41	252.91
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	350.00	421.39	365.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	20.00	350.00	397.50	395.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	350.00	409.45	380.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	300.00	371.25	305.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	32.00	400.00	218.51	520.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	25.00	370.00	474.86	595.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	300.00	239.87	222.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		92.00	353.80	308.01	454.31
		WEIGHTED AVERAGE FOR THE YEAR		163.00	344.91	302.79	393.56
===== 503-00024 Drilled Shaft (24 In) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	9.00	360.00	1136.12	1300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8.00	350.00	455.98	410.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	355.29	736.77	881.18
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	500.00	454.30	534.14
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	113.00	500.00	1107.50	650.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		122.00	500.00	981.53	641.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 257

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00024 Drilled Shaft (24 In) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	23.00	1300.00	446.08	690.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,847.00	600.00	285.00	230.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,870.00	605.61	288.40	233.69
	WEIGHTED AVERAGE FOR THE YEAR			3,009.00	599.91	315.05	253.88
===== 503-00030 Drilled Shaft (30 In) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	329.00	420.00	400.98	350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			329.00	420.00	400.98	350.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	697.00	600.48	600.48	600.48
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			697.00	600.48	600.48	600.48
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	300.00	412.01	412.01	412.01
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			300.00	412.01	412.01	412.01
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	141.00	400.00	575.00	450.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			141.00	400.00	575.00	450.00
	WEIGHTED AVERAGE FOR THE YEAR			1,467.00	502.19	454.28	491.30
===== 503-00036 Drilled Shaft (36 In) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	19.00	580.00	508.44	465.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 258

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	503-00036	Drilled Shaft (36 In)		Lin Foot	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		19.00	580.00	508.44	465.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	32.00	650.00	759.31	720.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,161.00	350.00	304.03	225.00
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	430.00	508.60	473.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	76.00	450.00	743.17	743.17
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1,299.00	365.09	322.65	273.24
<hr/>							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	19.00	700.00	785.93	680.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	86.00	600.00	740.00	680.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		105.00	618.10	748.31	680.00
<hr/>							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	900.00	807.87	830.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	38.00	800.00	925.00	1000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,321.00	800.00	679.69	675.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	16.00	400.00	604.65	640.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	38.00	750.00	1069.71	990.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	38.00	700.00	724.10	612.20
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		1,547.00	798.38	698.85	698.43
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			2,970.00	601.10	496.29	510.32
<hr/>							
=====	503-00042	Drilled Shaft (42 In)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	17.00	600.00	772.63	550.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	19.00	1500.00	1477.00	1618.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		36.00	1075.00	926.46	1113.67
<hr/>							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17.00	600.00	596.79	704.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 259

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	503-00042	Drilled Shaft (42 In)		Lin Foot	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	18.00	554.00	1233.33	1200.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	34.00	500.00	1935.50	800.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	538.72	1156.64	880.78
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	19.00	615.88	615.88	615.88
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
CI2111-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	700.00	807.50	750.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		36.00	655.60	738.81	679.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	21.00	450.00	922.50	1190.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	450.00	922.50	1190.00
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		162.00	672.37	1003.62	927.82
=====	503-00048	Drilled Shaft (48 In)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	52.00	1200.00	1328.51	1450.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	36.00	880.00	787.18	600.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	69.00	1750.00	1506.00	1540.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		157.00	1368.34	1136.95	1294.65
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	31.00	725.00	879.46	800.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	66.00	700.00	669.63	792.05
CM760-047		COLFAX AND QUAIL	05/12/22	42.00	555.00	673.80	604.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	32.00	750.00	2139.00	850.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	300.00	700.00	914.38	728.76
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		471.00	692.11	862.11	739.43
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	188.00	1012.24	1012.24	1012.24

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 260

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00048 Drilled Shaft (48 In) Lin Foot =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	21.00	1000.00	1052.23	910.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	210.00	800.00	840.00	760.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	84.00	750.00	649.69	124.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				503.00	879.33	792.67	754.33
===== 503-00054 Drilled Shaft (54 In) Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	477.00	700.00	868.33	1010.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	700.00	1100.00	1250.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	127.00	660.00	1016.01	1161.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	337.00	400.00	717.19	480.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	900.00	1666.09	2090.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	36.00	850.00	935.05	836.80
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,040.00	611.17	861.72	899.26
WEIGHTED AVERAGE FOR THE YEAR				2,171.00	745.62	876.87	859.60
===== 503-00054 Drilled Shaft (54 In) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	424.00	900.00	757.82	435.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				424.00	900.00	757.82	435.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	21.00	900.00	1125.00	850.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				21.00	900.00	1125.00	850.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	210.00	650.00	963.75	1005.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	640.00	1155.00	1310.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	106.00	500.00	901.83	940.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				337.00	602.20	946.20	1003.56
WEIGHTED AVERAGE FOR THE YEAR				782.00	771.66	828.21	691.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 261

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00060 Drilled Shaft (60 In) Lin Foot =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	33.00	2100.00	2030.00	1984.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			33.00	2100.00	2030.00	1984.00
	WEIGHTED AVERAGE FOR THE YEAR			33.00	2100.00	2030.00	1984.00
===== 503-00072 Drilled Shaft (72 In) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	122.00	1000.00	1775.00	1600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			122.00	1000.00	1907.87	2247.74
	WEIGHTED AVERAGE FOR THE YEAR			122.00	1000.00	1907.87	2247.74
===== 503-00310 CSL Testing Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	7.00	2800.00	3559.35	2500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	2800.00	3559.35	2500.00
NHPP0702-413 2670703-479		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8.00	1163.63	1163.63	1163.63
		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	3000.00	1745.93	3470.61
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			17.00	2135.83	1670.79	2384.97
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	6805.76	6805.76	6805.76
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	6805.76	6805.76	6805.76
STU0252-457 STAM420-001		I-25:ALAMEDA RIVER PH 2.0	11/03/22	62.00	4000.00	2109.70	4100.00
		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	1100.00	2664.88	885.86

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 262

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00310	CSL Testing		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9.00	4500.00	2673.00	2960.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	4500.00	2300.00	3600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101.00	3385.15	2347.58	3204.96
		WEIGHTED AVERAGE FOR THE YEAR		137.00	3499.84	2514.73	3382.59
=====	503-01080	M Pile (8 In)		Lin Foot	=====		
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4,512.00	400.00	228.11	252.60
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,512.00	400.00	228.11	252.60
		WEIGHTED AVERAGE FOR THE YEAR		4,512.00	400.00	228.11	252.60
=====	503-01100	M Pile (10 In)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,090.00	167.00	261.78	270.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,090.00	167.00	261.78	270.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	726.00	150.00	340.00	280.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		726.00	150.00	340.00	280.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,304.00	300.00	655.07	640.32
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,304.00	300.00	655.07	640.32
		WEIGHTED AVERAGE FOR THE YEAR		4,120.00	206.10	366.25	388.97
=====	503-02000	Verification Test Pile		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	22000.00	29607.63	21500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	22000.00	29607.63	21500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 263

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-02000 Verification Test Pile Each =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	3.00	4000.00	31002.26	4506.77
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	50000.00	17243.91	28000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	22400.00	26768.92	13904.06
	WEIGHTED AVERAGE FOR THE YEAR			11.00	22181.82	28749.42	18047.30
===== 504-04420 Precast Panel Facing Sq Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	13,344.00	61.85	61.85	61.85
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	22,490.00	50.00	54.24	52.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35,834.00	54.41	54.92	55.67
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,167.00	71.12	71.12	71.12
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5,167.00	71.12	71.12	71.12
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7,787.00	56.00	50.86	44.24
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10,901.00	50.00	54.13	38.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,825.00	45.00	88.00	79.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21,513.00	51.52	56.10	45.64
	WEIGHTED AVERAGE FOR THE YEAR			62,514.00	54.80	55.71	53.50
===== 504-05000 Wire Mesh Facing Sq Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	213.00	63.44	63.44	63.44
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			213.00	63.44	63.44	63.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 264

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 504-05000 Wire Mesh Facing Sq Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	4,354.00	29.36	29.36	29.36
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4,354.00	29.36	29.36	29.36
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	7,787.00	12.00	28.51	35.05
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7,787.00	12.00	28.51	35.05
	WEIGHTED AVERAGE FOR THE YEAR			12,354.00	19.01	28.82	33.53
===== 504-06300 Ground Nail Lin Foot =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	210.00	75.00	548.50	532.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			210.00	75.00	548.50	532.00
	WEIGHTED AVERAGE FOR THE YEAR			210.00	75.00	548.50	532.00
===== 504-06406 Soil Nail Lin Foot =====							
NHPP0702-413 NHC540-017		VAIL PASS AUX PHASE 1 CAP 2 R2 CHAINUP STA @ KENOSHA/HOOS	04/18/22 05/12/22	16,159.00 2,008.00	74.10 65.00	74.10 89.33	74.10 83.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18,167.00	73.09	78.24	75.08
NHPP0702-414 FBR0702-423 2670403-065		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS US40_FLOYD HILL ROUNDABOUTS	07/08/22 09/15/22	57,565.00 7,337.00	45.56 70.00	45.56 83.92	45.56 54.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			64,902.00	48.32	56.17	46.51
	WEIGHTED AVERAGE FOR THE YEAR			83,069.00	53.74	60.98	52.76

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 265

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-06410	Verification Testing		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	6.00	4815.00	4815.00	4815.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	535.00	3733.33	3200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	2675.00	4003.75	4007.50
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	3782.45	3782.45	3782.45
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	2000.00	3420.33	2136.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	3425.96	3627.26	3453.16
		WEIGHTED AVERAGE FOR THE YEAR		32.00	3144.35	3801.02	3661.04
=====	506-00012	Riprap (Special)		Each	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	500.00	1765.30	1170.89
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	500.00	1765.30	1170.89
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	1765.30	1170.89
=====	506-00020	Place Riprap		Cubic Yard	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	37.00	250.00	111.69	80.08
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		37.00	250.00	111.69	80.08
		WEIGHTED AVERAGE FOR THE YEAR		37.00	250.00	111.69	80.08
=====	506-00030	Grouted Riprap		Cubic Yard	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	47.00	500.00	402.08	543.74
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		47.00	500.00	402.08	543.74
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	67.00	700.00	310.00	230.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		67.00	700.00	310.00	230.00
		WEIGHTED AVERAGE FOR THE YEAR		114.00	617.54	347.96	359.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 266

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00035 Grouted Riprap Sq Yard =====							
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	56.00	80.00	283.20	395.93
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			56.00	80.00	283.20	395.93
	WEIGHTED AVERAGE FOR THE YEAR			56.00	80.00	283.20	395.93
===== 506-00050 Slope Mattress Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	388.00	100.00	315.78	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			388.00	100.00	315.78	250.00
	WEIGHTED AVERAGE FOR THE YEAR			388.00	100.00	315.78	250.00
===== 506-00100 Riprap (Gabions) Cubic Yard =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS	20 05/06/22	2,087.00	350.00	312.50	170.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,087.00	350.00	312.50	170.00
	WEIGHTED AVERAGE FOR THE YEAR			2,087.00	350.00	312.50	170.00
===== 506-00206 Riprap (6 In) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	51.00	150.00	194.97	93.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			51.00	150.00	194.97	93.75
NH0504-911 NHPP0702-413 STA0712-019		VAIL PASS AUX PHASE 1 CAP 2 SH 71: Frieight Improvements	04/07/22 04/18/22 05/12/22	307.00 41.00 4.00	150.00 92.32 300.00	125.50 92.32 489.86	131.00 92.32 489.86
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			352.00	144.99	125.65	130.57
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	94.96	94.96	94.96

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 267

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00206 Riprap (6 In) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	17.00	300.00	352.09	325.31
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	28.00	170.00	198.05	110.18
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		95.00	153.77	207.15	140.67

NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	325.00	150.00	180.07	125.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		325.00	150.00	180.07	125.00
		WEIGHTED AVERAGE FOR THE YEAR		823.00	148.29	171.91	127.26
===== 506-00209 Riprap (9 In) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	164.00	160.00	192.88	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		164.00	160.00	192.88	150.00

NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	71.00	92.32	92.32	92.32
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	12.00	150.00	240.49	154.41
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.90	215.00	175.30	124.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		183.90	163.39	173.45	113.75

NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	66.00	94.96	94.96	94.96
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	106.00	90.00	266.67	200.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	42.00	200.00	399.39	345.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	140.00	500.00	500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	32.00	160.00	149.50	139.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	29.00	150.00	200.65	201.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		277.00	122.59	237.04	192.18

NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	18.00	190.00	396.49	505.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 268

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00209 Riprap (9 In) Cubic Yard =====							
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	74.00	175.00	210.00	210.00	
C5502-097	US550 MP 117.28-126.06	11/17/22	51.00	200.00	291.60	325.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	19.00	300.00	180.20	170.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	33.00	150.00	235.00	180.00	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	6.00	500.00	616.33	680.00	
STR0092-024	SH 9 North of Silverthorne	12/22/22	66.00	400.00	593.50	687.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				267.00	249.51	340.77	366.08
WEIGHTED AVERAGE FOR THE YEAR				891.90	175.88	236.11	223.15
===== 506-00212 Riprap (12 In) Cubic Yard =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	185.00	200.00	149.27	124.00	
NHPP1601-083		02/03/22	123.00	250.00	244.80	240.00	
C0762-055		02/17/22	12.00	200.00	196.04	200.00	
BRC040-057		03/17/22	146.00	200.00	494.75	665.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				466.00	213.20	275.45	326.07
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	32.00	92.32	92.32	92.32	
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	448.50	160.00	154.49	89.20	
STA0712-019	SH 71: Frieight Improvements	05/12/22	120.00	300.00	236.49	236.49	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				600.50	184.37	157.77	118.80
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	94.96	94.96	94.96	
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
STR0711-022	SH 71 OVER THE ARKANSAS	08/04/22	245.00	135.00	307.67	200.00	
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	994.00	160.00	284.22	245.00	
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22	12.00	265.24	233.46	233.46	
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	574.00	300.00	225.95	278.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,841.00	200.44	270.55	247.92
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	57.00	130.00	184.95	150.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00212 Riprap (12 In) Cubic Yard =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	26.00	120.00	156.86	189.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	23.00	100.00	263.33	260.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	26.00	150.00	313.33	190.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			132.00	126.74	202.63	184.76
	WEIGHTED AVERAGE FOR THE YEAR			3,039.50	196.02	235.42	231.65
===== 506-00218 Riprap (18 In) Cubic Yard =====							
NHPP1601-083			02/03/22	143.00	260.00	242.45	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			143.00	260.00	242.45	250.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	46.00	350.00	218.31	269.66
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			46.00	350.00	218.31	269.66
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,115.00	150.00	137.09	134.00
C5502-097		US550 MP 117.28-126.06	11/17/22	70.00	300.00	255.10	249.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3,067.00	85.00	94.86	130.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	39.00	120.00	266.67	270.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	576.00	225.00	111.00	73.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	610.00	155.00	183.05	140.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6,477.00	127.80	115.74	129.31
	WEIGHTED AVERAGE FOR THE YEAR			6,666.00	132.17	118.00	132.87
===== 506-00224 Riprap (24 In) Cubic Yard =====							
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	151.00	200.00	243.81	332.55
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			151.00	200.00	243.81	332.55
	WEIGHTED AVERAGE FOR THE YEAR			151.00	200.00	243.81	332.55

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 270

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00409 Soil Riprap (9 In) Cubic Yard =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	19.00	160.00	185.02	160.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	160.00	185.02	160.00
	WEIGHTED AVERAGE FOR THE YEAR			19.00	160.00	212.15	244.33
===== 506-00412 Soil Riprap (12 In) Cubic Yard =====							
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	36.00	150.00	172.67	120.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	47.00	300.00	401.29	235.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			83.00	234.94	279.05	185.12
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	106.00	110.00	157.10	111.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			106.00	110.00	157.10	111.00
	WEIGHTED AVERAGE FOR THE YEAR			189.00	164.87	180.56	143.55
===== 506-00418 Soil Riprap (18 In) Cubic Yard =====							
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	146.00	150.00	159.76	110.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	445.00	125.00	134.42	123.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			591.00	131.18	146.25	119.79
	WEIGHTED AVERAGE FOR THE YEAR			591.00	131.18	146.25	119.79
===== 506-00606 In-Channel Boulder Grouted (24 In) Cubic Yard =====							
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	1,243.00	400.00	625.67	478.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,243.00	400.00	625.67	478.00
	WEIGHTED AVERAGE FOR THE YEAR			1,243.00	400.00	625.67	478.00
===== 506-00612 Matrix Riprap (12 In) Cubic Yard =====							
NHPPR100-266	R1 ESSENTIAL REPAIRS		09/01/22	38.00	250.00	517.19	376.58
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			38.00	250.00	517.19	376.58
	WEIGHTED AVERAGE FOR THE YEAR			38.00	250.00	517.19	376.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 271

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00700 Void-Filled Riprap Cubic Yard =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	93.00	200.00	347.00	130.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		93.00	200.00	347.00	130.00
===== 506-01020 Geogrid Reinforce Sq Yard =====							
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	43.00	200.00	339.19	408.26
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		43.00	200.00	339.19	408.26
		WEIGHTED AVERAGE FOR THE YEAR		136.00	200.00	343.60	217.98
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	223.00	5.00	18.06	8.00
STR092A-031			03/17/22	1,000.00	5.00	3.15	3.15
NHM765-007			03/31/22	16,566.00	5.00	6.70	8.62
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,789.00	5.00	6.88	8.30
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,556.00	10.00	3.54	3.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,556.00	10.00	3.54	3.25
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	866.00	5.00	6.37	8.60
C5502-097		US550 MP 117.28-126.06	11/17/22	894.00	15.00	3.91	4.60
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	100.00	5.00	14.45	4.03
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,860.00	9.81	5.93	6.43
		WEIGHTED AVERAGE FOR THE YEAR		25,205.00	6.46	6.26	7.05
===== 507-00000 Conc S and D Pave Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	1000.00	1294.40	500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 272

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	507-00000	Conc S and D Pave		Cubic Yard	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	6.50	1200.00	1126.28	1900.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		31.50	1041.27	1245.01	788.89
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	66.00	800.00	832.55	887.71
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		66.00	800.00	832.55	887.71
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	46.00	800.00	1076.76	885.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		46.00	800.00	1076.76	885.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	2000.00	11830.00	13000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	36.00	1000.00	1240.88	690.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	55.00	750.00	1250.00	1600.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		92.00	861.41	1456.36	1279.38
	WEIGHTED AVERAGE FOR THE YEAR			235.50	856.26	1300.86	1163.39
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	208.00	800.00	829.17	660.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		208.00	800.00	829.17	660.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7.00	2274.15	2274.15	2274.15
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		7.00	2274.15	2274.15	2274.15
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4888.61	4888.61	4888.61

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 273

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 507-00100 Conc S and D Pave (Reinf) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		25.00	500.00	915.34	850.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			26.00	668.79	993.25	1005.33

STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	101.00	1000.00	1358.29	770.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			101.00	1000.00	1182.59	1005.51
	WEIGHTED AVERAGE FOR THE YEAR			342.00	879.26	947.88	869.84
===== 507-00400 Asphalt S and D Pave (Asph) Ton =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.50	250.00	231.24	198.40
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.50	250.00	231.24	198.40

STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	46.00	212.00	313.33	325.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			46.00	212.00	313.33	325.00

STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	390.00	1308.00	544.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	390.00	1308.00	544.00
	WEIGHTED AVERAGE FOR THE YEAR			71.50	227.51	286.49	284.68
===== 507-00550 Concrete Lined Ditch Lin Foot =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	25.00	869.00	253.33	160.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	869.00	253.33	160.00

IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	81.00	100.00	141.67	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			81.00	100.00	141.67	150.00
	WEIGHTED AVERAGE FOR THE YEAR			106.00	281.37	168.00	152.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 274

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 508-90000 Paint Existing Structure LUMP SUM =====							
NH0504-911			04/07/22	1.00	45000.00	87500.00	75000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	45000.00	87500.00	75000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	87500.00	75000.00
===== 509-00000 Str Steel Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	541,937.00	4.25	4.63	4.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			541,937.00	4.25	4.63	4.90
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,400.00	4.00	2.88	2.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,400.00	4.00	2.88	2.50
	WEIGHTED AVERAGE FOR THE YEAR			543,337.00	4.25	4.63	4.89
===== 509-00001 Str Steel (Galv) Pound =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2,401.00	17.00	12.86	2.41
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,401.00	17.00	12.86	2.41
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	14,638.00	15.00	9.00	9.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	530.00	40.00	83.70	85.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	70.00	20.00	180.25	75.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15,238.00	15.89	11.28	12.14
	WEIGHTED AVERAGE FOR THE YEAR			17,639.00	16.04	11.66	10.82
===== 509-08100 Provide Temporary Support LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	80000.00	37203.85	17091.22
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	80000.00	37203.85	17091.22
	WEIGHTED AVERAGE FOR THE YEAR			1.00	80000.00	37203.85	17091.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 275

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 509-50000 Cor Steel Br Plank Sq Foot =====							
STAR100-358		3 STRUCTURES IN REGION 1	05/26/22	33,359.00	54.00	36.04	32.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33,359.00	54.00	36.04	32.00

STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	38,835.00	38.00	49.13	49.13
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			38,835.00	38.00	49.13	49.13
	WEIGHTED AVERAGE FOR THE YEAR			72,194.00	45.39	39.70	41.21
===== 509-90001 Paint Existing Structure Each =====							
NH0504-911			04/07/22	32.00	1000.00	4250.00	2500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32.00	1000.00	4250.00	2500.00
	WEIGHTED AVERAGE FOR THE YEAR			32.00	1000.00	4250.00	2500.00
===== 512-00101 Bearing Device (Type I) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	5000.00	5057.94	6100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	5000.00	5057.94	6100.00

STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	24.00	3000.00	2355.33	4300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	3000.00	2355.33	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			28.00	3285.71	2942.85	4557.14
===== 512-00102 Bearing Device (Type II) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	16.00	2100.00	7095.67	7900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	2100.00	7095.67	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2100.00	7095.67	7900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 276

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 512-00103 Bearing Device (Type III) Each =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	6.00	14314.30	14314.30	14314.30
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	14314.30	14314.30	14314.30
	WEIGHTED AVERAGE FOR THE YEAR			6.00	14314.30	14314.30	14314.30
===== 512-00120 Bearing Repair Corbel Each =====							
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	20000.00	20883.37	16940.74
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	20000.00	20883.37	16940.74
	WEIGHTED AVERAGE FOR THE YEAR			4.00	20000.00	20883.37	16940.74
===== 513-00600 Bridge Drain Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	5000.00	13666.78	10637.83
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	13666.78	10637.83
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	13666.78	10637.83
===== 513-00690 Bridge Drain (Spec) Each =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	16644.64	16644.64	16644.64
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	16644.64	16644.64	16644.64
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	5000.00	6033.33	6000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	5000.00	6033.33	6000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	7328.93	6849.59	8128.93
===== 513-00691 Inst Bridge Drain (Spec) Each =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3.00	150.00	1133.01	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	150.00	1133.01	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	150.00	1133.01	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 277

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 514-00000 Pipe Railing Lin Foot =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		676.00	50.00	246.72	210.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			676.00	50.00	246.72	210.00
C5502-097	US550 MP 117.28-126.06	11/17/22		46.00	400.00	390.06	384.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		249.00	230.00	327.72	428.38
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			295.00	256.51	335.30	421.46
	WEIGHTED AVERAGE FOR THE YEAR			971.00	112.74	268.98	274.24
===== 514-00048 Ped Railing (48 In) Lin Foot =====							
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22		50.00	300.00	475.00	500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	300.00	475.00	500.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	300.00	475.00	500.00
===== 514-00054 Ped Railing (54 In) Lin Foot =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22		150.00	250.00	600.24	680.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			150.00	250.00	600.24	680.00
	WEIGHTED AVERAGE FOR THE YEAR			150.00	250.00	600.24	680.00
===== 514-00100 Hand Rail Lin Foot =====							
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22		290.00	142.31	134.86	134.86
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			290.00	142.31	134.86	134.86
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		16.00	300.00	392.68	330.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	300.00	392.68	330.00
	WEIGHTED AVERAGE FOR THE YEAR			306.00	150.56	213.81	145.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 278

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 514-00200 Pedestrian Railing (Steel) Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,279.00	304.98	304.98	304.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,279.00	304.98	304.98	304.98
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	491.00	344.54	344.54	344.54
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		491.00	344.54	344.54	344.54
		WEIGHTED AVERAGE FOR THE YEAR		1,770.00	315.95	315.95	315.95
===== 514-00201 Ped Railing (Steel) (Spec) Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	445.00	500.00	348.82	277.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,280.00	100.00	133.60	130.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,725.00	203.19	178.11	167.92
		WEIGHTED AVERAGE FOR THE YEAR		1,725.00	203.19	178.11	167.92
===== 514-02150 Inst Anchor Bolt Each =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	196.00	170.00	238.00	225.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		196.00	170.00	238.00	225.00
		WEIGHTED AVERAGE FOR THE YEAR		196.00	170.00	238.00	225.00
===== 515-00120 Waterproofing (Membrane) Sq Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	147.00	40.00	45.93	41.11
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,839.00	21.00	23.57	21.00
NHPP1601-083			02/03/22	12.00	26.00	303.95	60.00
C0762-055			02/17/22	1,610.00	25.00	25.71	35.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3,126.00	22.00	21.15	19.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 279

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00120	Waterproofing (Membrane)		Sq Yard	=====	=====	=====
C0761-239							
BRC040-057			03/17/22	469.00	30.00	38.75	30.00
STR R500-171		Various locations on SH 141 a	03/17/22	1,271.00	15.50	30.41	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,474.00	21.77	24.18	24.85
NH0504-911			04/07/22	4,217.00	24.00	25.00	20.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	363.00	27.00	39.85	40.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,606.00	22.00	16.99	19.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	796.00	30.00	16.64	16.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,982.00	24.08	21.07	20.41
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,374.00	26.06	26.06	26.06
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	122.00	42.00	39.97	56.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	553.00	28.89	27.36	27.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,850.00	24.00	24.72	22.83
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,899.00	26.01	25.39	25.80
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,935.00	20.00	28.17	41.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,944.00	25.00	22.40	19.00
C5502-097		US550 MP 117.28-126.06	11/17/22	116.00	40.00	47.78	43.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,646.00	36.00	24.03	27.22
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	387.00	23.44	29.33	32.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	471.00	16.00	39.50	33.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,771.00	25.00	18.15	18.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	20.00	27.67	25.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4,693.00	25.00	23.34	27.67
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	573.00	40.00	30.36	35.00
STA385A-016		SH 385 MP 97.76	12/22/22	295.00	50.00	69.86	194.44
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17,931.00	25.88	24.48	28.99
		WEIGHTED AVERAGE FOR THE YEAR		44,286.00	24.42	23.99	26.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 280

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00400	Concrete Sealer		Sq Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,175.00	21.00	20.31	17.00
NHPP1601-083			02/03/22	887.00	30.00	57.74	50.00
C0762-055			02/17/22	338.00	175.00	30.11	37.00
STR R500-171		Various locations on SH 141 a	03/17/22	699.00	23.00	36.72	51.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	65.00	50.00	206.00	150.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,164.00	41.01	32.62	38.63
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	881.00	22.72	22.72	22.72
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	9,252.00	12.00	10.91	6.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				10,133.00	12.93	11.19	7.45
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,499.00	24.46	24.46	24.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	100.00	23.00	18.30	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6,599.00	24.44	24.19	24.39
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,357.00	20.00	19.36	13.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	244.00	20.00	37.08	50.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	286.00	20.00	18.39	17.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,887.00	20.00	20.61	18.39
WEIGHTED AVERAGE FOR THE YEAR				21,783.00	21.11	17.44	18.06
=====	515-00402	Furnish Concrete Sealer (HMWM Resin)		Gallon	=====		
BRC040-057			03/17/22	274.00	100.00	94.25	101.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				274.00	100.00	94.25	101.00
WEIGHTED AVERAGE FOR THE YEAR				274.00	100.00	94.25	101.00
=====	515-00404	Place Concrete Sealer (HMWM Resin)		Sq Foot	=====		
BRC040-057			03/17/22	20,486.00	2.00	1.75	1.55
WEIGHTED AVERAGE FOR THE FIRST QUARTER				20,486.00	2.00	1.75	1.55
WEIGHTED AVERAGE FOR THE YEAR				20,486.00	2.00	1.75	1.55

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 281

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-00000 Brdg Compress Joint Sealer Lin Foot =====							
C0762-055			02/17/22	100.00	100.00	290.15	375.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	100.00	290.15	375.00

STM1151-038		SH115 MP 27 TO MP 38	04/21/22	148.00	240.00	72.30	135.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		148.00	240.00	72.30	135.00

NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	724.00	115.00	93.42	87.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	552.00	300.00	170.50	161.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	120.00	150.00	136.53	143.06
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,396.00	191.16	115.93	121.08
		WEIGHTED AVERAGE FOR THE YEAR		1,644.00	190.01	122.88	137.78
===== 518-00100 Waterstop Lin Foot =====							
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	8.50	216.67	240.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	8.50	80.52	75.56
		WEIGHTED AVERAGE FOR THE YEAR		20.00	8.50	80.52	75.56
===== 518-00106 Waterstop (6 In) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	267.00	20.00	17.65	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		267.00	20.00	17.65	15.00
		WEIGHTED AVERAGE FOR THE YEAR		267.00	20.00	17.65	15.00
===== 518-01001 Br Expan Joint (Asphaltic Plug) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	181.00	200.00	388.68	275.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 282

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-01001 Br Expan Joint (Asphaltic Plug) Lin Foot =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	80.00	200.00	282.90	300.00
BRC040-057			03/17/22	120.00	250.00	513.25	320.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				381.00	215.75	409.85	294.42

NH0504-911			04/07/22	192.00	300.00	352.00	374.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				192.00	300.00	352.00	374.00

STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	151.00	380.00	367.77	303.30
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	510.00	300.00	310.66	315.32
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	252.00	220.00	191.33	200.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				913.00	291.15	305.57	290.66
WEIGHTED AVERAGE FOR THE YEAR				1,486.00	272.96	343.53	300.93
===== 518-01004 Br Expan Device (0-4 In) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	124.00	325.00	486.27	355.00
NHPP1601-083			02/03/22	68.00	400.00	931.22	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	440.00	380.00	400.32	350.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	103.00	604.00	496.22	482.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				735.00	403.96	434.15	373.97

STM1151-038		SH115 MP 27 TO MP 38	04/21/22	154.00	300.00	306.58	375.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	268.00	300.00	318.64	340.09
WEIGHTED AVERAGE FOR THE SECOND QUARTER				422.00	300.00	314.74	352.83

NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	104.00	628.12	628.12	628.12
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 283

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-01004	Br Expan Device (0-4 In)			Lin Foot			
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	80.00	380.00	167.17	100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			184.00	520.24	306.52	398.50
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	167.00	450.00	390.03	304.00
STR064A-010	SH 64 AND SH 13 AT MEEKER		11/10/22	50.00	500.00	616.00	625.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	200.00	260.00	232.49	278.26
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	46.00	350.00	471.67	480.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			463.00	363.39	374.69	354.88
	WEIGHTED AVERAGE FOR THE YEAR			1,804.00	381.09	386.22	366.00
===== 518-01060	Br Expan Device (Gland) (0-4 In)			Lin Foot			
BRC040-057			03/17/22	104.00	350.00	163.25	320.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			104.00	350.00	163.25	320.00
NH0504-911			04/07/22	140.00	310.00	161.25	142.50
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV		06/23/22	190.00	26.32	134.00	115.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			330.00	146.67	141.34	126.67
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	362.00	400.00	66.50	60.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			362.00	400.00	75.76	68.61
	WEIGHTED AVERAGE FOR THE YEAR			796.00	288.44	113.52	120.56
===== 518-01250	Br Expan Cover Plate			Lin Foot			
BRC040-057			03/17/22	2.00	500.00	2731.75	2100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	500.00	2731.75	2100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 284

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-01250 Br Expan Cover Plate Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	103.00	300.00	326.06	407.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			103.00	300.00	326.06	407.00
	WEIGHTED AVERAGE FOR THE YEAR			105.00	303.81	386.77	439.25
===== 518-02030 Polyester Conc End Dam Cubic Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	156.00	129.25	129.25	129.25
	WEIGHTED AVERAGE FOR THE THIRD QUARTER	VAIL PASS AUX BE F-12-AT PHAS		156.00	129.25	129.25	129.25
	WEIGHTED AVERAGE FOR THE YEAR			156.00	129.25	129.25	129.25
===== 518-03000 Saw and Seal Br Joint Lin Foot =====							
NHPP1601-083			02/03/22	120.00	50.00	119.31	100.00
BRC040-057			03/17/22	104.00	35.00	60.00	35.00
STR R500-171		Various locations on SH 141 a	03/17/22	52.00	56.00	52.31	45.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			276.00	45.48	76.05	65.14
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	112.00	35.00	42.50	75.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			112.00	35.00	42.50	75.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	100.00	83.02	85.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			40.00	100.00	83.02	85.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	152.00	60.00	50.10	52.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 285

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-03000 Saw and Seal Br Joint Lin Foot =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	151.00	35.00	53.77	43.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,325.00	50.00	25.60	33.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	100.00	100.00	32.35	33.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	186.00	25.00	59.73	70.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	178.00	45.00	39.50	44.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	182.00	100.00	88.50	129.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,274.00	53.44	34.05	46.52
	WEIGHTED AVERAGE FOR THE YEAR			2,702.00	52.55	38.86	50.18
===== 518-03100 Rapid Cure Silicone Jt Seal Lin Foot =====							
BRC040-057			03/17/22	79.00	100.00	58.25	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			79.00	100.00	58.25	50.00
	WEIGHTED AVERAGE FOR THE YEAR			79.00	100.00	58.25	50.00
===== 519-02000 Corner Monuments Each =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	4.00	445575.86	619235.21	619235.21
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	445575.86	619235.21	619235.21
	WEIGHTED AVERAGE FOR THE YEAR			4.00	445575.86	619235.21	619235.21
===== 519-03000 Thin Bonded Epoxy Overlay Sq Yard =====							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	11.00	300.00	389.58	455.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11.00	300.00	389.58	455.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	300.00	389.58	455.00
===== 519-03035 Place Thin Bond Overlay (Poly Conc) Sq Yard =====							
STA0252-459			02/03/22	42.00	60.00	827.23	965.00
BRC040-057			03/17/22	15,526.00	30.00	38.40	28.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15,568.00	30.08	40.00	31.13

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 286

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 519-03035 Place Thin Bond Overlay (Poly Conc) Sq Yard =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,247.00	55.00	79.59	73.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	13,654.00	50.00	61.69	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,901.00	50.42	63.52	66.59
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4,417.00	70.00	120.56	74.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4,480.00	90.00	67.65	72.30
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,897.00	80.07	102.75	73.14
		WEIGHTED AVERAGE FOR THE YEAR		39,366.00	49.08	60.72	54.04
===== 519-03055 Furnish Thin Bond Overlay (Poly Conc) Cubic Foot =====							
STA0252-459			02/03/22	92.00	240.00	469.45	569.30
BRC040-057			03/17/22	11,650.00	105.00	133.13	158.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,742.00	106.06	135.11	161.72
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	702.00	175.00	174.99	167.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	9,819.00	120.00	112.80	71.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,521.00	123.67	117.90	77.41
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	9,995.00	145.00	137.87	111.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	3,360.00	220.00	135.25	149.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13,355.00	163.87	137.50	120.69
		WEIGHTED AVERAGE FOR THE YEAR		35,618.00	132.94	130.53	121.43
===== 601-01000 Conc CL B Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	1000.00	1541.24	2090.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 287

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	601-01000	Conc CL B		Cubic Yard	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	52.00	763.44	689.33	689.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		77.00	840.25	1290.96	1144.09
<hr/>							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.10	1500.00	2033.07	1750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.10	1500.00	2033.07	1750.00
<hr/>							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	5.00	1400.00	2622.67	1900.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	283.00	1000.00	871.93	1037.79
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	17.00	1500.00	1381.77	885.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	220.00	1100.00	952.50	438.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		525.00	1061.90	942.90	789.71
<hr/>							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	27.00	1400.00	2363.20	1277.78
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9.00	1300.00	875.00	875.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	12.70	1600.00	1714.65	1100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	3000.00	2230.50	1450.00
C5502-097		US550 MP 117.28-126.06	11/17/22	54.70	2200.00	2348.10	1890.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	1406.00	1708.57	904.97
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	4000.00	1378.99	1300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		133.40	1843.36	2074.92	1476.72
		WEIGHTED AVERAGE FOR THE YEAR		742.50	1183.51	1158.61	961.99
<hr/>							
=====	601-01025	Conc CL B (Misc)		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	105.00	2005.37	2005.37	2005.37
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	25.00	900.00	760.99	526.58
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		130.00	1792.80	1273.38	1720.99
		WEIGHTED AVERAGE FOR THE YEAR		130.00	1792.80	1273.38	1720.99

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 288

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03000 Conc CL D Cubic Yard =====							
NHPP1601-083			02/03/22	103.00	800.00	2262.00	1800.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	348.00	789.55	832.54	832.54
WEIGHTED AVERAGE FOR THE FIRST QUARTER				451.00	791.94	1364.07	1053.49
STA0712-019		SH 71: Frieight Improvements	05/12/22	49.00	1200.00	2929.17	2929.17
WEIGHTED AVERAGE FOR THE SECOND QUARTER				49.00	1200.00	2929.17	2929.17
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	165.00	1200.00	1296.67	1200.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	51.90	1982.66	2091.71	1535.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	68.00	1400.00	631.36	625.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				284.90	1390.31	1282.70	1123.83
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	11.90	6000.00	12250.00	12500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	346.00	110.00	971.11	665.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	3000.00	1490.18	1260.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	1000.00	2366.67	1200.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	54.00	1500.00	2473.15	2136.65
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	2500.00	6890.00	1780.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				443.90	591.26	1475.73	1214.46
WEIGHTED AVERAGE FOR THE YEAR				1,228.80	874.45	1447.47	1204.57
===== 601-03025 Conc CL D (Misc) (C) Cubic Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	244.00	1564.83	1564.83	1564.83
WEIGHTED AVERAGE FOR THE SECOND QUARTER				244.00	1564.83	1564.83	1564.83
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	113.00	1424.55	1424.55	1424.55

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 289

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03025 Conc CL D (Misc) (C) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			113.00	1424.55	1424.55	1424.55
	WEIGHTED AVERAGE FOR THE YEAR			357.00	1520.43	1520.43	1520.43
===== 601-03030 Conc CL D (Box) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	132.50	1000.00	1505.55	1000.14
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			132.50	1000.00	1505.55	1000.14
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	39.00	1500.00	1921.93	1750.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			39.00	1500.00	1921.93	1750.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	85.00	1200.00	1527.75	1024.71
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	133.00	983.04	894.50	894.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			218.00	1067.64	1310.68	945.27
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	962.00	750.00	1013.85	700.00
C5502-097		US550 MP 117.28-126.06	11/17/22	95.60	2000.00	1768.07	2320.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	86.00	1100.00	1391.67	1500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	66.00	1000.00	1700.00	1700.00
STA385A-016		SH 385 MP 97.76	12/22/22	351.00	1000.00	1526.25	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,560.60	912.66	1132.62	1065.55
	WEIGHTED AVERAGE FOR THE YEAR			1,950.10	947.67	1186.46	1061.35
===== 601-03040 Conc CL D (Bridge) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	661.10	1515.00	2003.96	1720.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 290

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03040	Conc CL D (Bridge)		Cubic Yard	=====		
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22	40.00	1200.00	1105.87	820.00
C0761-239						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		701.10	1497.03	1924.69	1668.65
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	263.00	1791.95	1791.95	1791.95
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	82.20	1300.00	1186.49	1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		345.20	1674.81	1422.75	1603.37
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,773.00	1439.41	1439.41	1439.41
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	18.70	3000.00	2873.77	1450.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,791.70	1455.70	1469.04	1439.52
NHPP0701-253	I-70 EAST OF DEBEQUE	10/27/22	1.00	6000.00	14010.00	15000.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,869.00	1000.00	1056.67	860.00
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	7.00	3000.00	562.00	570.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	106.00	1250.00	1821.02	1100.00
BR2854-148	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	115.00	1000.00	2266.67	1900.00
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	94.50	2000.00	2250.00	1800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,192.50	1043.85	1159.58	937.05
	WEIGHTED AVERAGE FOR THE YEAR		6,030.50	1255.02	1383.38	1209.53
===== 601-03050	Conc CL D (Wall)		Cubic Yard	=====		
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	23.00	1602.28	1602.28	1602.28
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	41.00	1500.00	1848.99	1750.00
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	39.00	950.00	1225.33	529.86
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		103.00	1314.59	1520.83	1255.02
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	1868.56	1868.56	1868.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 291

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03050 Conc CL D (Wall) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	14.00	1100.00	1453.49	1000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				21.00	1356.19	1536.50	1289.52
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	82.00	850.00	1317.28	950.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	46.00	1800.00	1789.93	1300.00
C5502-097		US550 MP 117.28-126.06	11/17/22	24.00	1900.00	1797.59	1820.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	285.00	1250.00	1210.12	1100.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	71.00	800.00	1391.62	1200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	25.00	1100.00	2616.67	3000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				533.00	1198.22	1358.94	1229.04
WEIGHTED AVERAGE FOR THE YEAR				657.00	1221.51	1386.56	1235.05
===== 601-03056 Conc CL DF Cubic Yard =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	203.00	1350.00	1027.92	1164.77
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	856.00	900.00	1084.25	827.60
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,059.00	986.26	1079.05	892.23
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	681.00	1050.00	1380.57	900.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	493.00	1200.00	1400.00	1400.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	169.60	2500.00	2150.00	1800.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,343.60	1288.07	1300.30	1176.88
WEIGHTED AVERAGE FOR THE YEAR				2,402.60	1155.04	1204.09	1088.52
===== 601-03057 Conc CL DR Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	119.00	2640.00	1368.83	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 292

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03057 Conc CL DR Cubic Yard =====							
NHPP1601-083			02/03/22	10.00	2500.00	4057.53	2000.00
C0762-055			02/17/22	12.00	2500.00	5317.92	6500.00
BRC040-057			03/17/22	26.00	2100.00	2889.50	2180.00
STR R500-171		Various locations on SH 141 a	03/17/22	23.00	3850.00	3426.14	2975.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				190.00	2696.37	2018.87	1863.18
NH0504-911			04/07/22	48.00	2016.00	3135.00	2970.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	23.00	2300.00	1799.99	2250.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				71.00	2108.00	2407.39	2736.76
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.10	6000.00	4173.74	3400.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.10	6000.00	4173.74	3400.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	72.00	2400.00	2283.99	2100.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	2000.00	3508.33	3600.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	28.00	3000.00	2580.00	2160.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	260.00	2500.00	2367.95	1712.90
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				368.00	2507.61	2508.31	1974.96
WEIGHTED AVERAGE FOR THE YEAR				630.10	2525.60	2318.55	2023.57
===== 601-03540 Conc CL DT (Deck Topping) Cubic Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	68.00	3000.00	1365.26	1280.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				68.00	3000.00	1365.26	1280.00
WEIGHTED AVERAGE FOR THE YEAR				68.00	3000.00	1365.26	1280.00
===== 601-04550 Conc CL G Cubic Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,521.00	1200.00	1018.94	1030.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 293

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-04550 Conc CL G Cubic Yard =====							
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1,521.00	1200.00	1018.94	1030.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	481.40	990.00	979.29	1100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	958.00	600.00	1111.77	850.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1,439.40	730.43	1072.67	933.61
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	475.00	1100.00	716.67	670.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,958.00	850.00	1134.00	990.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		2,433.00	898.81	1080.97	927.53
	WEIGHTED AVERAGE FOR THE YEAR			5,393.40	938.81	1054.89	958.05
===== 601-06020 Conc (Patching) (Polymer) Cubic Yard =====							
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	3400.00	2922.84	4300.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	3400.00	2922.84	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3400.00	2922.84	4300.00
===== 601-06100 Conc (Patching) Cubic Yard =====							
NHM765-007			03/31/22	1.00	3500.00	4649.60	11730.60
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	3500.00	4649.60	11730.60
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.10	5000.00	5025.51	3000.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		0.10	5000.00	5025.51	3000.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	64.00	6000.00	6388.80	5322.60
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		64.00	6000.00	6388.80	5322.60
	WEIGHTED AVERAGE FOR THE YEAR			65.10	5960.06	6346.95	5417.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 294

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-06102 Concrete (Patching) Cubic Foot =====							
BRC040-057			03/17/22	8.00	325.00	904.25	1975.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		8.00	325.00	904.25	1975.00
NH0504-911			04/07/22	76.00	300.00	1035.00	870.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	48.00	500.00	517.23	450.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		124.00	377.42	718.00	707.42
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	149.00	1000.00	789.32	130.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		149.00	1000.00	789.32	130.00
NHPP0705-088	I-70 AGATE STRUCTURE REHAB		10/27/22	30.00	400.00	876.62	850.00
STA0711-021	SH71: REGION LINE NORTH		12/01/22	11.00	320.00	860.00	850.00
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	42.30	120.00	811.00	900.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		83.30	247.25	864.81	892.60
	WEIGHTED AVERAGE FOR THE YEAR			364.30	601.14	787.57	545.01
===== 601-06150 Conc (Patching) Sq Foot =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	200.00	150.00	96.83	25.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		200.00	150.00	96.83	25.00
	WEIGHTED AVERAGE FOR THE YEAR			200.00	150.00	96.83	25.00
===== 601-06300 Cement Grout Cubic Foot =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	1000.00	1169.20	800.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	1000.00	1169.20	800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 295

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-06300 Cement Grout Cubic Foot =====							
C0852-120		Rehabilitation of Culvert by	05/26/22	2,916.00	52.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,916.00	52.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE YEAR			2,917.00	52.32	61.51	25.15
===== 601-07000 Conc Retaining Wall Sq Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	550.00	800.00	60.75	56.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			550.00	800.00	60.75	56.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,550.00	33.60	132.50	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,550.00	33.60	132.50	100.00
	WEIGHTED AVERAGE FOR THE YEAR			2,100.00	234.32	113.71	88.48
===== 601-10250 Slab Jacking Pound =====							
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	4,800.00	8.50	17.33	14.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4,800.00	8.50	17.33	14.00
	WEIGHTED AVERAGE FOR THE YEAR			4,800.00	8.50	17.33	14.00
===== 601-10310 Fly Ash Slurry Cubic Yard =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	739.42	739.42	739.42
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	739.42	739.42	739.42
	WEIGHTED AVERAGE FOR THE YEAR			7.00	739.42	739.42	739.42
===== 601-10400 Drilled Hole Each =====							
STA0252-459			02/03/22	100.00	80.00	129.00	93.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	80.00	129.00	93.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	80.00	129.00	93.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 296

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-13001 Str Conc Stain (Special) Sq Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	628.00	21.38	21.38	21.38
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		628.00	21.38	21.38	21.38
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,223.00	109.42	109.42	109.42
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,223.00	109.42	109.42	109.42
		WEIGHTED AVERAGE FOR THE YEAR		1,851.00	79.55	79.55	79.55
===== 601-25735 Precast Deck Panel (3.5 In) Sq Yard =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,416.00	139.14	139.14	139.14
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,416.00	139.14	139.14	139.14
		WEIGHTED AVERAGE FOR THE YEAR		2,416.00	139.14	139.14	139.14
===== 601-40300 Struct Conc Coating Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,175.00	15.00	19.15	21.00
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	4,097.00	19.00	15.59	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,272.00	18.11	16.13	12.45
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,589.00	18.00	19.05	13.09
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,589.00	18.00	19.05	13.09
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	382.00	15.00	18.81	13.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 297

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-40300	Struct Conc Coating		Sq Yard	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	79.00	35.00	23.22	13.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			461.00	18.43	19.56	13.00
	WEIGHTED AVERAGE FOR THE YEAR			7,322.00	18.11	16.86	12.62
=====	601-40301	Struct Conc Coating		Sq Foot	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	194.00	12.00	5.07	1.10
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			194.00	12.00	5.07	1.10
	WEIGHTED AVERAGE FOR THE YEAR			194.00	12.00	5.07	1.10
=====	601-40302	Struct Conc Coating (Anti-Graf)		Sq Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,284.00	3.00	2.88	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,284.00	3.00	2.88	4.00
NH0504-911 NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/07/22 04/18/22	5,600.00 28,262.00	4.00 2.68	10.20 2.68	18.00 2.68
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33,862.00	2.90	4.81	5.21
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	19,291.00	2.50	2.05	2.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			19,291.00	2.50	2.05	2.00
	WEIGHTED AVERAGE FOR THE YEAR			55,437.00	2.76	3.14	4.05
=====	601-40400	Struct Conc Stain		Sq Yard	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	415.00	44.10	48.65	48.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			415.00	44.10	48.65	48.65

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 298

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	601-40400	Struct Conc Stain		Sq Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2,133.00	40.56	40.56	40.56
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	7,048.00	22.00	12.93	14.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,181.00	26.31	14.26	20.55
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,827.00	43.61	43.61	43.61
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,600.00	50.00	19.57	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,427.00	44.99	32.75	38.52
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,696.00	25.00	21.96	25.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,147.00	15.00	14.04	13.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,340.00	26.00	26.11	36.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,181.00	30.00	13.32	13.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,895.00	14.00	13.33	13.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,259.00	22.77	18.04	18.63
		WEIGHTED AVERAGE FOR THE YEAR		28,282.00	30.07	18.05	24.92
<hr/>							
=====	601-51005	Galvanic Anodes		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,125.00	40.00	38.37	33.00
C0762-055			02/17/22	280.00	44.00	30.41	35.00
BRC040-057			03/17/22	550.00	30.00	68.38	61.50
STR R500-171		Various locations on SH 141 a	03/17/22	476.00	33.00	30.89	38.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,431.00	37.75	41.39	38.43
NH0504-911			04/07/22	1,955.00	30.00	29.15	33.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 299

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	601-51005	Galvanic Anodes		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	320.00	40.00	28.47	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,275.00	31.41	28.95	30.02
<hr/>							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	30.00	50.00	48.22	35.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	50.00	48.22	35.00
<hr/>							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,700.00	39.78	29.71	31.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	275.00	33.40	44.28	44.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1,140.00	45.00	36.50	44.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,300.00	35.00	36.44	31.88
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,415.00	39.41	32.43	34.61
		WEIGHTED AVERAGE FOR THE YEAR		11,151.00	37.30	35.62	34.85
<hr/>							
=====	602-00000	Reinf Steel		Pound	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	17,371.00	3.00	1.73	1.65
C0762-055			02/17/22	280.00	4.00	7.42	9.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	64,145.00	1.15	1.40	1.40
BRC040-057			03/17/22	600.00	2.00	5.94	3.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		82,396.00	1.56	1.70	1.50
<hr/>							
NH0504-911			04/07/22	2,155.00	2.00	6.50	6.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	66,202.00	1.87	1.87	1.87
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	32,751.00	1.25	1.71	1.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		101,108.00	1.67	1.84	1.84
<hr/>							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	140,740.00	1.81	1.81	1.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 602-00000 Reinf Steel Pound =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2,229.00	2.00	16.79	3.80
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4,480.00	5.00	2.42	2.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				147,449.00	1.91	2.69	1.85
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,205.00	2.10	5.36	5.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	815.00	10.00	35.00	30.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	3,620.00	2.00	4.35	3.23
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	206,770.00	1.50	1.72	1.70
C5502-097		US550 MP 117.28-126.06	11/17/22	22,105.00	2.00	2.43	3.25
STA0711-021		SH71: REGION LINE NORTH	12/01/22	155.00	2.80	4.84	5.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,229.00	3.00	1.88	1.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	16,122.00	2.00	1.90	1.80
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	8,100.00	4.00	3.47	1.93
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	10,025.00	2.00	3.55	4.94
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	13,221.00	3.00	1.86	2.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				285,367.00	1.77	2.08	1.98
WEIGHTED AVERAGE FOR THE YEAR				616,320.00	1.76	2.07	1.88
===== 602-00020 Reinf Steel (Epoxy) Pound =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	26,600.00	2.00	2.60	2.53
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	163,271.00	2.00	1.86	1.80
NHPP1601-083			02/03/22	9,863.00	5.00	3.97	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	316,162.00	1.60	1.65	1.35
C0761-239							
BRC040-057			03/17/22	395.00	2.00	7.93	4.20
STR R500-171		Various locations on SH 141 a	03/17/22	3,432.00	5.00	3.71	3.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				519,723.00	1.83	1.77	1.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	36,366.00	3.85	3.85	3.85
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	99,633.00	1.80	1.82	1.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	363,735.00	1.50	1.70	1.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	8,307.00	2.60	3.01	3.01
WEIGHTED AVERAGE FOR THE SECOND QUARTER				508,041.00	1.75	1.75	1.73
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	323,170.00	2.88	2.88	2.88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 602-00020 Reinf Steel (Epoxy) Pound =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	27,691.00	3.00	3.19	3.32
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,030.00	4.00	3.38	3.50
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11,269.00	4.00	5.08	3.85
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	3,717.00	7.00	3.23	1.95
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	13,522.00	1.52	1.70	1.70
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	25,941.00	6.00	3.34	2.53
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	54,110.00	4.00	2.58	2.80
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	145,149.00	1.80	1.97	1.90
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24,735.00	3.00	2.85	1.64
WEIGHTED AVERAGE FOR THE THIRD QUARTER				630,334.00	2.88	2.42	2.59
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	45.00	8.00	26.80	28.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,444.00	2.50	5.90	6.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	339,023.00	2.00	2.08	1.90
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	188.00	2.50	6.16	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	456,270.00	1.70	2.14	2.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	500.00	4.00	2.70	2.75
C5502-097		US550 MP 117.28-126.06	11/17/22	18,640.00	2.75	3.15	4.30
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	164,162.00	2.00	2.17	2.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	14,715.00	2.00	2.76	3.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	547,743.00	1.50	2.11	1.80
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	787.00	4.00	8.50	13.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	169,300.00	2.00	2.17	2.50
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	209.00	7.00	5.62	5.25
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	47,519.00	3.50	2.53	3.00
STA385A-016		SH 385 MP 97.76	12/22/22	58,265.00	2.00	3.76	3.23
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	39.00	2.50	8.91	10.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,819,849.00	1.82	2.20	2.05
WEIGHTED AVERAGE FOR THE YEAR				3,477,947.00	2.01	2.07	2.04
===== 602-00030 Reinf (FRP) (Surface) M Kip Foot =====							
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	96.00	4500.00	5332.91	3956.81
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				96.00	4500.00	5332.91	3956.81
WEIGHTED AVERAGE FOR THE YEAR				96.00	4500.00	5332.91	3956.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 302

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 602-00060 Reinf Steel Splice Each =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	99.00	896.03	230.00
	WEIGHTED	AVERAGE FOR THE THIRD	QUARTER	20.00	99.00	896.03	230.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	99.00	896.03	230.00
===== 602-00210 Welded Wire Fabric Sq Yard =====							
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	41.00	50.00	213.72	200.00
	WEIGHTED	AVERAGE FOR THE FOURTH	QUARTER	41.00	50.00	213.72	200.00
		WEIGHTED AVERAGE FOR THE YEAR		41.00	50.00	213.72	200.00
===== 603-00025 Culvert Lining (24 Inch) (Special) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	612.00	300.00	326.98	382.00
	WEIGHTED	AVERAGE FOR THE FIRST	QUARTER	612.00	300.00	326.98	382.00
		WEIGHTED AVERAGE FOR THE YEAR		612.00	300.00	326.98	382.00
===== 603-00047 Prepare Culvert Pipe (48 In) Lin Foot =====							
C0852-120		Rehabilitation of Culvert by	05/26/22	990.00	200.00	35.00	35.00
	WEIGHTED	AVERAGE FOR THE SECOND	QUARTER	990.00	200.00	35.00	35.00
		WEIGHTED AVERAGE FOR THE YEAR		990.00	200.00	35.00	35.00
===== 603-00049 Culvert Lining (48 Inch) (Special) Lin Foot =====							
C0852-120		Rehabilitation of Culvert by	05/26/22	990.00	500.00	485.00	485.00
	WEIGHTED	AVERAGE FOR THE SECOND	QUARTER	990.00	500.00	485.00	485.00
		WEIGHTED AVERAGE FOR THE YEAR		990.00	500.00	485.00	485.00
===== 603-00054 Culvert Lining (54 In) Lin Foot =====							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	391.00	1000.00	1115.00	1050.00
	WEIGHTED	AVERAGE FOR THE FOURTH	QUARTER	391.00	1000.00	1115.00	1050.00
		WEIGHTED AVERAGE FOR THE YEAR		391.00	1000.00	1115.00	1050.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 303

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-00084 Culvert Lining (84 In) Lin Foot =====							
NHPP0701-253	I-70 EAST OF DEBEQUE		10/27/22	415.00	200.00	343.00	335.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			415.00	200.00	343.00	335.00
	WEIGHTED AVERAGE FOR THE YEAR			415.00	200.00	343.00	335.00
===== 603-01125 12 In RCP (CIP) Lin Foot =====							
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP 08/18/22			481.00	150.00	77.43	67.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			481.00	150.00	77.43	67.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	138.00	125.00	202.99	230.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM 12/15/22			163.00	150.00	106.39	128.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			301.00	138.54	143.90	174.76
	WEIGHTED AVERAGE FOR THE YEAR			782.00	145.59	112.37	108.48
===== 603-01155 15 In RCP (CIP) Lin Foot =====							
NHPP0063-063			02/24/22	607.00	225.00	201.60	305.00
NHM765-007			03/31/22	1,034.00	97.00	197.54	234.49
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,641.00	144.35	198.68	260.57
C5502-097	US550 MP 117.28-126.06		11/17/22	119.00	350.00	150.79	107.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	264.00	128.50	205.76	213.77
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			383.00	197.32	191.87	180.60
	WEIGHTED AVERAGE FOR THE YEAR			2,024.00	154.37	197.00	245.44
===== 603-01180 18 In RCP Lin Foot =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	365.00	125.00	127.50	151.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			365.00	125.00	127.50	151.64
	WEIGHTED AVERAGE FOR THE YEAR			365.00	125.00	127.50	151.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 304

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01185 18 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	332.00	109.00	170.68	183.45
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			332.00	109.00	170.68	183.45
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	283.00	160.00	211.89	189.89
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	149.00	200.00	138.07	74.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			432.00	173.80	189.38	149.92
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	244.00	200.00	109.99	120.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	16.00	140.00	290.00	230.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	874.00	200.00	159.60	158.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	80.00	130.00	156.48	151.50
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	13.00	140.00	300.24	267.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,227.00	194.02	156.74	152.11
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	489.00	135.00	253.73	310.00
C5502-097		US550 MP 117.28-126.06	11/17/22	733.00	200.00	171.24	117.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3,155.00	135.00	160.10	125.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	114.00	300.00	231.12	230.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	83.00	200.00	132.85	162.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,574.00	150.71	162.45	149.22
	WEIGHTED AVERAGE FOR THE YEAR			6,565.00	158.21	164.29	151.22
===== 603-01240 24 In RCP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	457.00	100.00	212.02	265.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			457.00	100.00	212.02	265.04
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	140.00	210.00	244.87	215.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			140.00	210.00	244.87	215.22
	WEIGHTED AVERAGE FOR THE YEAR			597.00	125.80	219.72	253.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 305

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01245 24 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	828.00	125.00	196.68	203.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		828.00	125.00	196.68	203.55
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	32.00	170.00	306.39	250.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	170.00	306.39	250.75
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,464.00	275.00	155.68	135.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	69.00	210.00	260.08	192.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,087.00	160.00	173.16	168.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,620.00	225.58	169.73	150.19
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	20.00	150.00	289.33	150.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	92.00	150.00	130.00	130.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	192.00	175.00	237.51	267.00
C5502-097		US550 MP 117.28-126.06	11/17/22	403.00	250.00	185.83	137.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	746.00	170.00	230.37	219.82
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	7.00	400.00	298.29	590.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	52.00	200.00	421.19	507.16
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,512.00	192.57	237.77	221.91
		WEIGHTED AVERAGE FOR THE YEAR		4,992.00	198.54	197.76	183.35
===== 603-01305 30 In RCP (CIP) Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	424.00	300.00	146.59	160.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		424.00	300.00	146.59	160.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	41.00	250.00	180.00	180.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 306

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01305 30 In RCP (CIP) Lin Foot =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	369.00	235.00	273.41	252.42
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			410.00	236.50	270.88	245.18
	WEIGHTED AVERAGE FOR THE YEAR			834.00	268.78	226.32	201.87
===== 603-01365 36 In RCP (CIP) Lin Foot =====							
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	24.00	350.00	621.80	347.32
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,507.00	325.00	287.73	250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	379.00	250.00	297.17	260.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	284.00	600.00	242.89	212.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,194.00	347.91	280.70	247.87
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	35.00	400.00	230.00	230.00
C5502-097		US550 MP 117.28-126.06	11/17/22	42.00	400.00	352.52	231.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	529.00	228.00	305.60	266.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	27.00	420.00	257.03	303.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			633.00	257.11	304.77	263.99
	WEIGHTED AVERAGE FOR THE YEAR			2,827.00	327.58	287.61	251.48
===== 603-01420 42 In RCP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	51.00	240.00	314.29	396.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			51.00	240.00	314.29	396.15
	WEIGHTED AVERAGE FOR THE YEAR			51.00	240.00	314.29	396.15
===== 603-01425 42 In RCP (CIP) Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	258.00	350.00	516.17	445.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 307

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01425	42 In RCP (CIP)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	480.00	300.00	390.75	348.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		738.00	317.48	423.83	381.91
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	473.00	295.00	393.27	375.73
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	21.00	400.00	344.94	382.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		494.00	299.46	391.22	376.00
		WEIGHTED AVERAGE FOR THE YEAR		1,232.00	310.26	407.44	379.54
=====	603-01485	48 In RCP (CIP)		Lin Foot	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	120.00	375.00	524.93	462.11
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	22.00	450.00	380.34	402.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		142.00	386.62	502.53	452.80
		WEIGHTED AVERAGE FOR THE YEAR		142.00	386.62	502.53	452.80
=====	603-01545	54 In RCP (CIP)		Lin Foot	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	32.00	750.00	420.00	420.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	980.00	500.00	607.13	450.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,012.00	507.91	605.61	449.05
		WEIGHTED AVERAGE FOR THE YEAR		1,012.00	507.91	605.61	449.05
=====	603-01785	78 In RCP (CIP)		Lin Foot	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	136.00	500.00	573.44	750.31
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		136.00	500.00	573.44	750.31
		WEIGHTED AVERAGE FOR THE YEAR		136.00	500.00	573.44	750.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 308

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-02185 23x14 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	368.00	140.00	200.93	209.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			368.00	140.00	200.93	209.70
===== 603-02240 30x19 In RCP Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		61.00	200.00	302.18	260.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			61.00	200.00	302.18	260.00
C5502-097		US550 MP 117.28-126.06	11/17/22	34.00	300.00	212.20	184.00
STA385A-016		SH 385 MP 97.76	12/22/22	64.00	300.00	276.25	250.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			98.00	300.00	258.00	227.10
	WEIGHTED AVERAGE FOR THE YEAR			527.00	176.70	221.62	218.76
===== 603-02245 30x19 In RCP (CIP) Lin Foot =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	66.00	250.00	328.75	328.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			66.00	250.00	328.75	328.75
	WEIGHTED AVERAGE FOR THE YEAR			66.00	250.00	328.75	328.75
===== 603-02245 30x19 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	18.00	145.00	356.00	350.61
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	145.00	356.00	350.61
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	305.00	180.00	246.49	170.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			305.00	180.00	246.49	170.00
STA385A-016		SH 385 MP 97.76	12/22/22	80.00	350.00	326.88	312.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			80.00	350.00	326.88	312.50
	WEIGHTED AVERAGE FOR THE YEAR			403.00	212.18	263.15	206.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 309

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-02270 34x22 In RCP Lin Foot =====							
NHM765-007			03/31/22	310.00	150.00	289.31	277.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			310.00	150.00	289.31	277.12
	WEIGHTED AVERAGE FOR THE YEAR			310.00	150.00	289.31	277.12
===== 603-02305 38x24 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	82.00	186.00	290.92	283.06
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			82.00	186.00	290.92	283.06
C5502-097	US550 MP 117.28-126.06		11/17/22	164.00	320.00	254.71	214.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			164.00	320.00	254.71	214.00
	WEIGHTED AVERAGE FOR THE YEAR			246.00	275.33	266.78	237.02
===== 603-02365 45x29 In RCP (CIP) Lin Foot =====							
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP 08/18/22			152.00	350.00	659.12	570.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			152.00	350.00	659.12	570.00
C5502-097	US550 MP 117.28-126.06		11/17/22	19.00	400.00	350.24	324.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			19.00	400.00	350.24	324.00
	WEIGHTED AVERAGE FOR THE YEAR			171.00	355.56	610.35	542.67
===== 603-02485 60x38 In. RCP (CIP) Lin Foot =====							
STA385A-016	SH 385 MP 97.76		12/22/22	60.00	400.00	600.00	750.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			60.00	400.00	600.00	750.00
	WEIGHTED AVERAGE FOR THE YEAR			60.00	400.00	600.00	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 310

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-05012 12 In RCES Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3.00	1200.00	1098.54	950.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	1200.00	1098.54	950.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1200.00	1098.54	950.00
===== 603-05015 15 In RCES Each =====							
C5502-097		US550 MP 117.28-126.06 11/17/22		1.00	4000.00	1565.58	859.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	1565.58	859.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	1565.58	859.00
===== 603-05018 18 In RCES Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK 03/10/22		2.00	1400.00	1620.34	1900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1400.00	1620.34	1900.00
STM1151-038		SH115 MP 27 TO MP 38 04/21/22		2.00	1600.00	2043.02	2269.98
2670703-479		I-70 BRIDGE OVER HARLAN 05/05/22		1.00	1500.00	2072.74	2197.49
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR 06/09/22		6.00	1000.00	1782.50	1470.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	1188.89	1876.99	1728.61
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 07/08/22		5.00	1774.82	1774.82	1774.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS 08/25/22		2.00	2100.00	2135.00	1770.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS 09/15/22		2.00	2000.00	2773.59	3070.00
2670703-497		I-70 GENESEE WILDLIFE XING 09/15/22		1.00	1800.00	2606.33	1698.73
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		2.00	1000.00	2915.96	2438.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	1739.51	2567.40	2094.07
C5502-097		US550 MP 117.28-126.06 11/17/22		29.00	1800.00	1696.21	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 311

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-05018 18 In RCES Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1600.00	2618.61	3338.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	2500.00	2220.40	2420.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3000.00	2261.45	1400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			33.00	1887.88	1800.37	1226.02
	WEIGHTED AVERAGE FOR THE YEAR			56.00	1726.32	1933.99	1516.88
===== 603-05024 24 In RCES Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1700.00	4510.18	2500.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	1600.00	1948.63	2100.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1650.00	2933.84	2300.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	17.00	1500.00	2246.16	2481.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			17.00	1500.00	2246.16	2481.15
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	1988.82	1988.82	1988.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	1600.00	1840.94	1590.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	2500.00	2985.35	3240.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	1600.00	3529.10	2650.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	1839.66	2983.17	2242.52
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9.00	2500.00	2600.00	2600.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	2000.00	3092.92	3278.77
C5502-097		US550 MP 117.28-126.06	11/17/22	9.00	2000.00	1941.43	1360.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	1700.00	2749.19	3564.22
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	2547.80	1640.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 312

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-05024	24 In RCES			Each =====			
NHPP0502-090	SH 50 MP 134.6-136	GUNNISON C	12/22/22	2.00	2500.00	3304.58	5761.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			28.00	2185.71	2557.56	2619.58
	WEIGHTED AVERAGE FOR THE YEAR			56.00	1896.03	2521.19	2509.56
===== 603-05030	30 In RCES			Each =====			
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	1.00	2416.82	2416.82	2416.82
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	2416.82	2416.82	2416.82
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	4.00	3000.00	3000.00	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	3000.00	3000.00	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	2883.36	2883.36	2883.36
===== 603-05036	36 In RCES			Each =====			
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	4.00	3800.00	3600.00	3600.00
C5502-097	US550 MP 117.28-126.06		11/17/22	1.00	2600.00	2892.85	2350.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	1.00	2500.00	3795.18	2964.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	3383.33	3478.12	3285.67
	WEIGHTED AVERAGE FOR THE YEAR			6.00	3383.33	3478.12	3285.67
===== 603-05042	42 In RCES			Each =====			
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1.00	2700.00	3342.19	3674.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2700.00	3342.19	3674.15
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	1.00	3000.00	3614.95	3125.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 313

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05042	42 In RCES		Each =====			
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	3200.00	4274.16	4580.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	3100.00	4010.48	3852.50
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2966.67	3676.33	3793.05
=====	603-05048	48 In RCES		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	4000.00	4100.00	4100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	4000.00	4100.00	4100.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	4100.00	4100.00
=====	603-05054	54 In RCES		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	4500.00	4900.00	4900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	4500.00	4900.00	4900.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4500.00	4900.00	4900.00
=====	603-05118	23x14 In RCES		Each =====			
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	4000.00	2463.90	2250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	4000.00	2463.90	2250.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	4000.00	2390.42	1820.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	2390.42	1820.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	2443.86	2035.00
=====	603-05124	30x19 In RCES		Each =====			
STA0712-019		SH 71: Frieght Improvements	05/12/22	2.00	3000.00	5174.75	5174.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 314

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05124	30x19 In RCES		Each	=====	=====	=====
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	10.00	1500.00	2406.19	2050.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	1750.00	2512.67	2570.79
	WEIGHTED AVERAGE FOR THE YEAR			12.00	1750.00	2512.67	2570.79
=====	603-05130	38x24 In RCES		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	5000.00	3479.83	2850.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	3479.83	2850.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	3479.83	2850.00
=====	603-05136	45x29 In RCES		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	7000.00	4221.84	3730.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	7000.00	4221.84	3730.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	7000.00	4221.84	3730.00
=====	603-10060	6 In CSP		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	150.00	192.41	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20.00	150.00	192.41	220.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	150.00	192.41	220.00
=====	603-10120	12 In CSP		Lin Foot	=====	=====	=====
NHM765-007			03/31/22	60.00	200.00	122.96	57.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			60.00	200.00	122.96	57.75
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.00	95.00	139.71	177.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	95.00	139.71	177.64
	WEIGHTED AVERAGE FOR THE YEAR			84.00	170.00	129.66	92.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 315

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10150 15 In CSP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	96.00	105.00	153.76	178.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		96.00	105.00	153.76	178.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	112.00	500.00	154.06	120.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	104.00	190.00	124.33	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		216.00	350.74	143.42	110.37
		WEIGHTED AVERAGE FOR THE YEAR		312.00	275.13	147.09	131.33
===== 603-10180 18 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	40.00	125.00	235.03	130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	125.00	235.03	130.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	866.00	135.00	141.34	190.98
STA0712-019		SH 71: Frieght Improvements	05/12/22	48.00	80.00	137.13	137.13
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	160.00	175.00	125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		944.00	133.00	141.98	186.15
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	38.00	120.00	140.88	157.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		38.00	120.00	140.88	157.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	26.00	125.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		26.00	125.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE YEAR		1,048.00	132.02	143.33	181.18

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 316

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10240 24 In CSP Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	141.00	150.00	217.04	350.00
NHPP1601-083			02/03/22	304.00	150.00	333.89	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		445.00	150.00	271.15	302.18
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	152.00	150.00	238.03	406.71
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	150.00	180.00	203.33	140.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	18.00	140.00	202.50	300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		320.00	163.50	224.47	275.69
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	7.00	150.00	293.96	345.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	150.00	293.96	345.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	18.00	350.00	441.71	453.22
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	300.00	349.33	339.82
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	135.00	350.00	137.40	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		160.00	347.81	225.52	234.60
		WEIGHTED AVERAGE FOR THE YEAR		932.00	188.59	246.04	281.80
===== 603-10300 30 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	60.00	150.00	342.41	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	150.00	342.41	300.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	23.00	300.00	437.46	412.61
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		23.00	300.00	437.46	412.61
		WEIGHTED AVERAGE FOR THE YEAR		83.00	191.57	388.93	331.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 317

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10360 36 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	112.00	200.00	393.63	350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			112.00	200.00	393.63	350.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	30.00	200.00	257.78	308.89
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			30.00	200.00	257.78	308.89
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8.00	300.00	375.00	375.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	136.00	240.00	181.67	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			144.00	243.33	185.38	162.50
	WEIGHTED AVERAGE FOR THE YEAR			286.00	221.82	258.18	251.28
===== 603-10420 42 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	32.00	200.00	487.76	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			32.00	200.00	487.76	500.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	15.00	250.00	386.61	571.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15.00	250.00	386.61	571.64
	WEIGHTED AVERAGE FOR THE YEAR			47.00	215.96	433.18	522.86
===== 603-10480 48 In CSP Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	70.00	434.44	434.44	434.44
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			70.00	434.44	434.44	434.44
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	400.00	575.73	623.08
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20.00	400.00	575.73	623.08
	WEIGHTED AVERAGE FOR THE YEAR			90.00	426.79	517.55	476.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 318

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10720 72 In CSP Lin Foot =====							
NHPP0502-090	SH 50 MP 134.6-136	GUNNISON C	12/22/22	79.00	600.00	676.95	790.56
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			79.00	600.00	676.95	790.56
	WEIGHTED AVERAGE FOR THE YEAR			79.00	600.00	676.95	790.56
===== 603-15036 36 In Equiv CSP A Lin Foot =====							
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	20.00	200.00	190.00	190.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20.00	200.00	190.00	190.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	200.00	190.00	190.00
===== 603-30012 12 In SES Each =====							
NHM765-007			03/31/22	2.00	400.00	949.67	388.82
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	400.00	949.67	388.82
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	2.00	750.00	666.66	1271.28
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	750.00	666.66	1271.28
	WEIGHTED AVERAGE FOR THE YEAR			4.00	575.00	772.79	830.05
===== 603-30015 15 In SES Each =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	2.00	800.00	703.69	1289.76
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	800.00	703.69	1289.76
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	6.00	400.00	884.40	1320.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	400.00	884.40	1320.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	500.00	839.22	1312.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 319

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-30018 18 In SES Each =====							
NHPP1601-083			02/03/22	2.00	200.00	2171.90	650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	200.00	2171.90	650.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	440.00	768.67	1335.78
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	700.00	1042.61	1042.61
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	626.00	1558.33	925.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	529.20	907.77	1194.99
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	600.00	1676.67	430.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	600.00	1676.67	430.00
	WEIGHTED AVERAGE FOR THE YEAR			13.00	484.00	1071.40	1052.30
===== 603-30024 24 In SES Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	650.00	1156.37	550.00
NHPP1601-083			02/03/22	32.00	200.00	1488.73	800.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	500.00	1908.15	600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			39.00	265.38	1489.25	760.26
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	900.00	876.13	1450.59
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	5.00	880.00	2316.67	2000.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	1000.00	1232.50	1165.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	907.14	1302.68	1606.01
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	1000.00	1977.62	3499.98
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	1000.00	1977.62	3499.98
	WEIGHTED AVERAGE FOR THE YEAR			54.00	445.37	1438.37	1030.26

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 320

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-30030 30 In SES Each =====							
NHPP1601-083			02/03/22	4.00	200.00	2435.84	1200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	200.00	2435.84	1200.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2500.00	1515.28	909.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	1200.00	2596.48	3991.86
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	2066.67	2006.73	1936.62
	WEIGHTED AVERAGE FOR THE YEAR			7.00	1000.00	2187.41	1515.69
===== 603-30036 36 In SES Each =====							
NHPP1601-083			02/03/22	14.00	300.00	2514.39	2000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	300.00	2514.39	2000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	1530.00	1611.02	2070.86
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1530.00	1611.02	2070.86
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	1800.00	1800.00	1800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1800.00	1800.00	1800.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	603.33	2252.83	1985.65
===== 603-30042 42 In SES Each =====							
NHPP1601-083			02/03/22	2.00	500.00	4571.59	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	500.00	4571.59	3000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2000.00	2504.52	2881.90
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2000.00	2504.52	2881.90
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1000.00	3423.21	2960.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 321

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-31336 36 In Equiv Arch SES Each =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	2000.00	2000.00	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2000.00	2000.00	2000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	2000.00	2000.00
===== 603-50006 6 In Plastic Pipe Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	47.24	47.24	47.24
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35.00	47.24	47.24	47.24
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	8.00	300.00	115.17	100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	300.00	115.17	100.00
	WEIGHTED AVERAGE FOR THE YEAR			43.00	94.27	68.55	57.06
===== 603-50015 15 In Plastic Pipe Lin Foot =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	153.92	111.30	111.30
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			48.00	153.92	111.30	111.30
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	114.00	110.00	278.72	430.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			114.00	110.00	278.72	430.00
	WEIGHTED AVERAGE FOR THE YEAR			162.00	123.01	258.11	335.57
===== 603-50018 18 In Plastic Pipe Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	27.00	125.00	198.33	210.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			27.00	125.00	198.33	210.00
	WEIGHTED AVERAGE FOR THE YEAR			27.00	125.00	198.33	210.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 322

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-50024 24 In Plastic Pipe Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	50.00	150.00	230.00	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	150.00	230.00	200.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	150.00	230.00	200.00
===== 603-50030 30 In Plastic Pipe Lin Foot =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	125.00	500.00	209.94	116.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			125.00	500.00	209.94	116.00
	WEIGHTED AVERAGE FOR THE YEAR			125.00	500.00	209.94	116.00
===== 603-61120 12 In Flexible Pipe Lin Foot =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	58.00	93.00	103.37	108.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			58.00	93.00	103.37	108.00
	WEIGHTED AVERAGE FOR THE YEAR			58.00	93.00	103.37	108.00
===== 603-61180 18 In Flexible Pipe Lin Foot =====							
NHPP1601-083			02/03/22	25.00	150.00	242.39	112.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	150.00	242.39	112.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	150.00	242.39	112.00
===== 603-70503 5x3 Ft CBC (Precast) Lin Foot =====							
STA0712-019		SH 71: Frieght Improvements	05/12/22	60.00	1000.00	1591.97	1591.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	1000.00	1591.97	1591.97
	WEIGHTED AVERAGE FOR THE YEAR			60.00	1000.00	1591.97	1591.97
===== 603-70804 8x4 Ft CBC (Precast) Lin Foot =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	56.00	1800.00	2199.17	2516.67
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			56.00	1800.00	2199.17	2516.67
	WEIGHTED AVERAGE FOR THE YEAR			56.00	1800.00	2199.17	2516.67

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 323

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-71204 12x4 Ft CBC (Precast) Lin Foot =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	198.00	2000.00	3578.51	3578.51
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			198.00	2000.00	3578.51	3578.51
	WEIGHTED AVERAGE FOR THE YEAR			198.00	2000.00	3578.51	3578.51
===== 603-71209 12x8 Ft CBC (Precast) (Inst Only) Lin Foot =====							
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG 08/31/22 US 6/US 34 TIMBER BRIDGE REPL		68.00	1879.59	1505.64	1505.64
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			68.00	1879.59	1505.64	1505.64
	WEIGHTED AVERAGE FOR THE YEAR			68.00	1879.59	1505.64	1505.64
===== 603-72007 20x8 Ft CBC (Precast) (Inst Only) Lin Foot =====							
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG 08/31/22 US 6/US 34 TIMBER BRIDGE REPL		150.00	2036.79	1529.69	1529.69
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			150.00	2036.79	1529.69	1529.69
	WEIGHTED AVERAGE FOR THE YEAR			150.00	2036.79	1529.69	1529.69
===== 603-82006 6 In Duct Iron Pipe Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	146.00	120.00	310.79	402.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			146.00	120.00	310.79	402.00
	WEIGHTED AVERAGE FOR THE YEAR			146.00	120.00	310.79	402.00
===== 604-00305 Inlet Ty C (5 Ft) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	7.00	5000.00	5983.78	4800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	5000.00	5983.78	4800.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	13.00	7424.15	7424.15	7424.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 324

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-00305 Inlet Ty C (5 Ft) Each =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	3500.00	5792.28	5000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	7000.00	7724.41	5566.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	5100.00	8397.00	8088.31
WEIGHTED AVERAGE FOR THE THIRD QUARTER				22.00	6209.73	7135.44	6624.28
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	5000.00	6674.01	4500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	8000.00	4956.77	3390.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7.00	5000.00	7934.06	7029.64
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	10000.00	6928.40	4850.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	8000.00	5633.71	4160.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				15.00	6133.33	6975.19	6038.68
WEIGHTED AVERAGE FOR THE YEAR				44.00	5991.23	6786.97	6130.26
===== 604-00310 Inlet Ty C (10 Ft) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	7000.00	7478.01	5500.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	7000.00	7478.01	5500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	6500.00	6456.76	5600.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	6500.00	6456.76	5600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	7000.00	9978.36	10286.35
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	5500.00	8300.00	8000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	6625.00	9642.69	9714.76
WEIGHTED AVERAGE FOR THE YEAR				9.00	6722.22	8312.87	7395.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 325

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-00505 Inlet Ty D (5 Ft) Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	9058.43	9058.43	9058.43
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	6700.00	5631.84	7013.49
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	7373.84	5885.67	7597.76
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	9010.17	9010.17	9010.17
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	5500.00	8989.69	7800.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	7500.00	10209.36	7211.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	6000.00	9442.25	9500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10.00	8207.12	9351.78	8758.22
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	6500.00	8271.05	5700.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6187.00	10592.26	8881.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	6343.50	9044.79	7290.53
		WEIGHTED AVERAGE FOR THE YEAR		19.00	7703.95	7645.31	8176.19
===== 604-00510 Inlet Ty D (10 Ft) Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	10649.59	10649.59	10649.59
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	8000.00	8476.04	12194.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	9766.39	9097.05	11164.56
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	8000.00	9806.34	8500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	13000.00	13356.11	7758.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	9666.67	11327.67	8252.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6500.00	12383.15	12419.91

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 326

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-00510	Inlet Ty D (10 Ft)		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	6500.00	12383.15	12419.91
	WEIGHTED AVERAGE FOR THE YEAR			7.00	9257.03	10694.76	10095.94
=====	604-00515	Inlet Ty D (15 Ft)		Each	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	15000.00	17679.53	10235.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	15000.00	17679.53	10235.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	17679.53	10235.00
=====	604-13005	Inlet Ty 13 (5 Ft)		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	5500.00	5427.47	4700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5500.00	5427.47	4700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5500.00	5427.47	4700.00
=====	604-16005	Inlet Ty 16 (5 Ft)		Each	=====		
NHM765-007			03/31/22	15.00	4500.00	9889.48	6972.35
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	4500.00	9889.48	6972.35
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	5500.00	7641.80	5077.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5500.00	7641.80	5077.49
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	5000.00	6478.48	5600.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	8000.00	9999.65	8000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9.00	7333.33	9436.26	7466.67

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 327

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-16005 Inlet Ty 16 (5 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	6500.00	10554.82	9805.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	6500.00	10500.00	10200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	6500.00	10531.33	10002.53
	WEIGHTED AVERAGE FOR THE YEAR			30.00	5683.33	9584.09	7398.35
===== 604-16010 Inlet Ty 16 (10 Ft) Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	7000.00	8892.22	7700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	7000.00	8892.22	7700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	8000.00	11286.22	9500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	12000.00	18420.83	27001.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	9333.33	14140.07	15333.67
	WEIGHTED AVERAGE FOR THE YEAR			4.00	8750.00	13265.42	13425.25
===== 604-16505 Inlet Ty 16 (D) (5 Ft) Each =====							
NHM765-007			03/31/22	4.00	8200.00	11408.03	9419.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	8200.00	11408.03	9419.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	8000.00	10684.35	13000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12609.05	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	8064.00	13650.60	14256.92
BR2854-148		INTERSECTION OF US 285 & SH 9					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 328

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-16505	Inlet Ty 16 (D) (5 Ft)		Each	=====		
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	8438.40	12483.01	13154.15
	WEIGHTED AVERAGE FOR THE YEAR			9.00	8332.44	12114.44	11494.42
=====	604-16510	Inlet Ty 16 (D) (10 Ft)		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	13000.00	12806.38	11100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	13000.00	12806.38	11100.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS 12/01/22 INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		6.00	15000.00	16467.31	18400.51
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	15000.00	16467.31	18400.51
	WEIGHTED AVERAGE FOR THE YEAR			7.00	14714.29	16185.70	17357.58
=====	604-16605	Inlet Ty 16 (T) (5 Ft)		Each	=====		
NHM765-007			03/31/22	16.00	10000.00	14205.26	11991.63
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	10000.00	14205.26	11991.63
STU0252-457 IM025A-050		I-25:ALAMEDA RIVER PH 2.0 11/03/22 I25-MP103.9 - INTERSECTION DR 12/01/22		2.00 1.00	15000.00 10000.00	22994.07 19466.67	16900.00 22900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	13333.33	21818.27	18900.00
	WEIGHTED AVERAGE FOR THE YEAR			19.00	10526.32	15407.31	13082.43
=====	604-16610	Inlet Ty 16 (T) (10 Ft)		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 11/03/22		1.00	20000.00	21746.22	17700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	20000.00	21746.22	17700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	21746.22	17700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 329

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19005 Inlet Spec (5 Ft) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	19191.85	9500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	19191.85	9500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	19191.85	9500.00
===== 604-19010 Inlet Spec (10 Ft) Each =====							
NHPP0063-063			02/24/22	3.00	7500.00	10145.00	4500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	7500.00	10145.00	4500.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	7500.00	10145.00	4500.00
===== 604-19035 Inlet Spec (35 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	36452.93	19319.67
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	36452.93	19319.67
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	36452.93	19319.67
===== 604-19105 Inlet Ty R L5 (5 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	10000.00	7816.88	7402.01
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	7816.88	7402.01
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		16.00	6500.00	11305.96	9800.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS 09/15/22		4.00	8000.00	11524.05	8053.00
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		1.00	6500.00	9202.65	8300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			21.00	6785.71	11105.90	9395.81
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	8000.00	9420.85	9000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 330

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19105 Inlet Ty R L5 (5 Ft) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	7500.00	10616.76	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	7010.00	9219.11	9301.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	7500.00	9666.67	9100.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				19.00	7139.47	9329.40	9300.83
WEIGHTED AVERAGE FOR THE YEAR				41.00	7028.05	9929.02	9303.16
===== 604-19110 Inlet Ty R L5 (10 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	12000.00	11752.68	13735.85
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	12000.00	11752.68	13735.85
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	13.00	8000.00	15095.99	13000.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	10000.00	17665.67	9724.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				15.00	8266.67	15577.80	12563.20
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	13038.08	12200.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	14.00	8550.00	12058.25	13671.45
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	9000.00	12433.33	10500.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				20.00	8785.00	12198.52	12890.02
WEIGHTED AVERAGE FOR THE YEAR				36.00	8658.33	13140.15	12777.34
===== 604-19115 Inlet Ty R L5 (15 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	10525.00	19374.67	23899.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2.00	10525.00	19374.67	23899.01
WEIGHTED AVERAGE FOR THE YEAR				2.00	10525.00	19374.67	23899.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 331

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19205		Inlet Ty R L10 (5 Ft)		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	12000.00	17143.30	14800.00
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		1.00	9500.00	11026.02	9100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	11166.67	13472.93	12900.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		2.00	11000.00	12879.18	12000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	11000.00	12879.18	12000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	11100.00	13107.54	12540.00
===== 604-19210		Inlet Ty R L10 (10 Ft)		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	12000.00	21551.13	18600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	12000.00	21551.13	18600.00
IM025A-050		I25-MP103.9 - INTERSECTION DR 12/01/22		1.00	12000.00	17533.33	14600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	12000.00	17533.33	14600.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	12000.00	19140.45	16600.00
===== 604-19305		Inlet Ty R L15 (5 Ft)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		2.00	13000.00	16213.91	19000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR 12/01/22		1.00	13000.00	22133.33	18400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	13000.00	17148.55	18800.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	13000.00	17148.55	18800.00
===== 604-19310		Inlet Ty R L15 (10 Ft)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		1.00	12774.00	22949.10	17392.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 332

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19310	Inlet Ty R L15 (10 Ft)		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	12774.00	22949.10	17392.57
	WEIGHTED AVERAGE FOR THE YEAR			1.00	12774.00	22949.10	17392.57
=====	604-19712	Inlet Spec (Trench) (12 In)		Lin Foot	=====		
NHPP0063-063			02/24/22	45.00	400.00	454.50	460.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	400.00	454.50	460.00
	WEIGHTED AVERAGE FOR THE YEAR			45.00	400.00	454.50	460.00
=====	604-20000	Outlet Structure		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	2279.10	2279.10	2279.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	2279.10	2279.10	2279.10
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	3866.27	3866.27	3866.27
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	15000.00	11218.14	9700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	6649.70	6807.02	5324.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	30000.00	21892.71	9500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	30000.00	21892.71	9500.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	9571.52	15737.39	4941.52
=====	604-25000	Vane Grate Inlet Spec		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	6000.00	15114.39	14223.04

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 333

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-25000	Vane Grate Inlet Spec		Each =====			
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	12000.00	19750.00	22000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	8000.00	15776.62	16815.36
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	10000.00	21131.48	18500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	8240.00	17363.00	26300.54
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	9000.00	10353.13	10000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	9246.67	18410.19	19683.51
		WEIGHTED AVERAGE FOR THE YEAR		9.00	8831.11	17292.92	18727.46
=====	604-25005	Vane Grate Inlet (5 Ft)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	5500.00	8418.43	7881.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5500.00	8418.43	7881.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	15141.41	15141.41	15141.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	6000.00	5313.10	4600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	10570.71	8589.20	9870.71
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4040.00	8869.60	9451.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	6000.00	12100.00	8800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	5346.67	10807.84	9017.14
		WEIGHTED AVERAGE FOR THE YEAR		8.00	7977.85	9551.10	9301.91
=====	604-25007	Vane Grate Inlet Spec (D) (5 Ft)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	10000.00	9053.39	7000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	9053.39	7000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	9053.39	7000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 334

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-25010 Vane Gate Inlet (10 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	7000.00	10090.46	9431.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	10090.46	9431.98
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	17101.53	17101.53	17101.53
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	8500.00	7838.79	6800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	12800.77	10926.37	11950.77
		WEIGHTED AVERAGE FOR THE YEAR		5.00	11640.61	10508.42	11447.01
===== 604-25025 Vane Gate Inlet (25 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	20000.00	26089.21	37500.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	20000.00	26089.21	37500.85
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	26089.21	37500.85
===== 604-26005 Vane Gate Inlet (D) (5 Ft) Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	7153.33	3900.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	9000.00	7153.33	3900.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	10000.00	8194.76	7100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	10000.00	8194.76	7100.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	9666.67	7500.47	6033.33
===== 604-30000 MH Slab Base (Spec) Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	10000.00	3404.35	2950.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	10000.00	3404.35	2950.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 335

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-30000 MH Slab Base (Spec) Each =====							
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	5000.00	18916.80	10211.87
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	18916.80	10211.87
	WEIGHTED AVERAGE FOR THE YEAR			6.00	9166.67	8575.16	4160.31
===== 604-30005 MH Slab Base (5 Ft) Each =====							
NHM765-007			03/31/22	12.00	5000.00	9262.28	7122.80
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	5000.00	9262.28	7122.80
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	5500.00	5306.43	7500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	5500.00	5306.43	7500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	5800.00	8723.50	6500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	5813.06	5040.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	5272.00	8469.83	7096.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	6428.80	8324.96	6446.74
	WEIGHTED AVERAGE FOR THE YEAR			21.00	5435.43	7880.12	7033.68
===== 604-30010 MH Slab Base (10 Ft) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	7000.00	7676.11	6400.00
NHM765-007			03/31/22	5.00	6600.00	13081.71	11008.24
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	6714.29	10919.47	9691.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5.00	11512.80	11512.80	11512.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 336

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30010	MH Slab Base (10 Ft)		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	6200.00	10408.75	7560.08
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	10627.33	10910.59	10854.01
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4.00	10388.56	10388.56	10388.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	7500.00	8828.45	6006.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	19.00	5500.00	6078.20	5250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6.00	10000.00	12637.69	7282.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	6000.00	8242.23	9300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	7095.45	8367.06	6447.13
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	7000.00	10497.89	8300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	8000.00	20935.19	17500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10.00	6300.00	10471.20	11015.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	7500.00	12800.00	7900.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	9000.00	18449.63	12356.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	7190.48	13157.18	11234.17
		WEIGHTED AVERAGE FOR THE YEAR		66.00	7406.34	11040.04	8824.54
=====	604-30015	MH Slab Base (15 Ft)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	9494.19	9100.00
C0761-239							
NHM765-007			03/31/22	2.00	8000.00	19782.45	23352.16
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	8333.33	13903.44	18601.44
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	8500.00	12059.36	13872.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	8500.00	12059.36	13872.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	16764.35	16764.35	16764.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 337

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-30015 MH Slab Base (15 Ft) Each =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5.00	12000.00	7986.95	6900.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	3.00	12000.00	25520.56	10870.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	12529.37	16315.94	9319.37

STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	8000.00	15349.74	18039.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	8000.00	14607.89	16431.68
		WEIGHTED AVERAGE FOR THE YEAR		17.00	10486.14	14803.76	13094.96
===== 604-30020 MH Slab Base (20 Ft) Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	18984.15	18984.15	18984.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	18984.15	18984.15	18984.15

STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	18627.14	23380.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	18627.14	23380.32
		WEIGHTED AVERAGE FOR THE YEAR		3.00	15989.43	18746.15	20449.54
===== 604-31005 MH Box Base (5 Ft) Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	15000.00	5999.29	5200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	15000.00	5999.29	5200.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	15000.00	5999.29	5200.00
===== 604-31015 MH Box Base (15 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	22000.00	32586.40	37947.02

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 338

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-31015	MH Box Base (15 Ft)		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		6.00	22000.00	30159.77	35298.01
		WEIGHTED AVERAGE FOR THE YEAR		6.00	22000.00	30159.77	35298.01
=====	604-31020	MH Box Base (20 Ft)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	22000.00	36087.69	35000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		8.00	22000.00	35744.16	35555.56
		WEIGHTED AVERAGE FOR THE YEAR		8.00	22000.00	35744.16	35555.56
=====	604-39000	MH Spec		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8.00	18190.00	18190.00	18190.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		8.00	18190.00	18190.00	18190.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	20736.60	20736.60	20736.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		6.00	20736.60	20736.60	20736.60
		WEIGHTED AVERAGE FOR THE YEAR		14.00	19281.40	19281.40	19281.40
=====	604-39050	MH (TMS)		Each	=====		
NHM765-007			03/31/22	2.00	10000.00	19843.90	17841.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	10000.00	19843.90	17841.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	7600.00	11572.04	11152.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		5.00	7600.00	11572.04	11152.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	8285.71	13173.04	13063.14

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 339

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-83108 8 In PPS (PVC) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	660.00	75.00	167.40	195.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		660.00	75.00	167.40	195.00
		WEIGHTED AVERAGE FOR THE YEAR		660.00	75.00	164.96	180.13
===== 605-00040 4 In PP Underdrain Lin Foot =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	168.00	40.00	58.50	50.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		168.00	40.00	58.50	50.00
		WEIGHTED AVERAGE FOR THE YEAR		168.00	40.00	58.50	50.00
===== 605-00060 6 In PP Underdrain Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	51.00	12.22	12.22	12.22
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		51.00	12.22	12.22	12.22
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	52.00	19.66	19.66	19.66
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		52.00	19.66	19.66	19.66
		WEIGHTED AVERAGE FOR THE YEAR		103.00	15.98	15.98	15.98
===== 605-00061 6 In PP Underdrain (Special) Lin Foot =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,060.00	60.00	30.24	34.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		1,060.00	60.00	30.24	34.00
		WEIGHTED AVERAGE FOR THE YEAR		1,060.00	60.00	30.24	34.00
===== 605-01020 2 In Hor Drain Lin Foot =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,792.00	67.44	67.44	67.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 340

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-01020	2 In Hor Drain		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		2,792.00	67.44	67.44	67.44
		WEIGHTED AVERAGE FOR THE YEAR		2,792.00	67.44	67.44	67.44
=====	605-01030	3 In Hor Drain		Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,265.00	85.11	85.11	85.11
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		5,265.00	85.11	85.11	85.11
		WEIGHTED AVERAGE FOR THE YEAR		5,265.00	85.11	85.11	85.11
=====	605-82100	Pipe Edge Drain		Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,036.00	71.26	71.26	71.26
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		1,036.00	71.26	71.26	71.26
		WEIGHTED AVERAGE FOR THE YEAR		1,036.00	71.26	71.26	71.26
=====	605-83000	Geocomp Drain		Sq Yard	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	32.00	87.10	115.22	115.22
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		32.00	87.10	115.22	115.22
		WEIGHTED AVERAGE FOR THE YEAR		32.00	87.10	115.22	115.22
=====	605-83002	Geocomp Drain (w/ Pipe)		Sq Yard	=====		
NH0504-911			04/07/22	68.00	40.00	54.30	53.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	210.00	44.79	44.79	44.79
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	127.00	30.00	87.29	46.58
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		405.00	39.35	75.19	46.83
		WEIGHTED AVERAGE FOR THE YEAR		405.00	39.35	75.19	46.83

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 341

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 605-84000 Subsurface Drain Outlet Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	618.00	25.99	25.99	25.99
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		618.00	25.99	25.99	25.99
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	284.00	48.64	48.64	48.64
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		284.00	48.64	48.64	48.64
		WEIGHTED AVERAGE FOR THE YEAR		902.00	33.12	33.12	33.12
===== 605-84100 Subsurface Drain Outlet Str Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	1838.72	1838.72	1838.72
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1838.72	1838.72	1838.72
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1878.18	1878.18	1878.18
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1878.18	1878.18	1878.18
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1858.45	1858.45	1858.45
===== 606-00301 Gdrail Ty 3 (6-3) Lin Foot =====							
C0762-055			02/17/22	1,175.00	30.00	36.83	38.00
STR092A-031			03/17/22	2,525.00	45.00	42.00	42.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,700.00	40.24	38.63	40.73
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	325.00	40.00	77.46	85.28
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	462.50	38.00	55.00	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		787.50	38.83	70.23	70.43

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 342

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00301 Gd rail Ty 3 (6-3) Lin Foot =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,587.50	40.00	48.13	43.40
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	200.00	30.00	58.96	57.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	387.50	47.50	81.50	82.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	550.00	41.00	45.00	44.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,762.00	45.00	42.03	34.10
STR0092-024		SH 9 North of Silverthorne	12/22/22	5,716.00	50.00	56.10	52.20
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				11,203.00	46.46	50.10	47.20
WEIGHTED AVERAGE FOR THE YEAR				15,690.50	44.61	49.50	46.84
===== 606-00302 Gd rail Ty 3 (31 In MGS) Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	800.00	60.00	51.79	51.94
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,530.00	40.00	51.83	52.00
NHPP1601-083			02/03/22	10,812.50	40.00	38.50	38.00
STA0252-459			02/03/22	5,250.00	36.00	37.96	32.60
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2,167.00	50.00	41.34	43.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	10,803.00	40.00	38.72	37.50
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	14,475.00	30.00	42.26	38.51
WEIGHTED AVERAGE FOR THE FIRST QUARTER				49,837.50	37.43	41.56	39.47
NH0504-911			04/07/22	7,200.00	27.41	43.00	43.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	21,800.00	32.00	35.04	29.40
STA0712-019		SH 71: Frieght Improvements	05/12/22	3,438.00	35.00	39.01	39.01
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	425.00	30.00	61.00	57.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	768.00	35.00	68.47	68.47
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	3,913.00	42.00	49.46	45.91
WEIGHTED AVERAGE FOR THE SECOND QUARTER				37,544.00	32.48	37.16	35.72
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	109.42	109.42	109.42
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	387.50	50.00	67.16	73.77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	606-00302	Gd rail Ty 3 (31 In MGS)		Lin Foot	=====		
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	400.00	53.60	84.37	84.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	150.00	50.00	56.90	38.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1,775.00	45.00	50.13	47.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	3,975.00	40.00	50.22	51.12
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	125.00	50.00	71.54	75.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6,862.50	43.56	51.45	53.86
<hr/>							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10,593.00	50.00	35.40	37.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	581.25	60.00	57.21	54.83
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	150.00	129.53	114.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,750.00	50.00	43.72	41.15
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,275.00	55.00	40.25	41.00
C5502-097		US550 MP 117.28-126.06	11/17/22	8,081.25	50.00	38.87	36.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,350.00	30.00	43.92	52.88
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	400.00	50.00	60.00	60.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,164.00	50.00	42.42	42.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10,968.00	55.00	38.30	32.60
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,681.00	40.00	41.33	40.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	456.00	80.00	58.41	46.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1,450.00	50.00	53.32	54.85
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	650.00	50.00	41.65	44.29
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	150.00	55.00	90.80	126.00
STA385A-016		SH 385 MP 97.76	12/22/22	200.00	35.00	67.92	46.67
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1,187.50	40.00	50.33	66.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				43,987.00	50.63	41.73	39.75
WEIGHTED AVERAGE FOR THE YEAR				138,231.00	40.59	41.12	39.28
<hr/>							
=====	606-00305	Gd rail Ty 3 (Spec)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	914.00	60.00	54.92	55.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,584.00	52.00	45.43	41.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,498.00	54.93	47.94	46.12
<hr/>							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	7.00	80.00	81.67	79.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				7.00	80.00	81.67	79.00
WEIGHTED AVERAGE FOR THE YEAR				2,505.00	55.00	47.98	46.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 344

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00350 Gdrail Ty 3 (D) (6-3) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	564.00	58.00	67.83	69.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			564.00	58.00	67.83	69.00

NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	300.00	100.00	106.30	112.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			300.00	100.00	106.30	112.00

2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	125.00	100.00	58.75	58.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			125.00	100.00	58.75	58.00
	WEIGHTED AVERAGE FOR THE YEAR			989.00	76.05	70.87	80.65
===== 606-00710 Gdrail Ty 7 (Sty CA) Lin Foot =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	494.00	300.00	248.00	280.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			494.00	300.00	248.00	280.00

STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	520.00	400.00	151.50	165.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	563.00	50.00	504.00	208.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,083.00	218.05	334.75	187.35
	WEIGHTED AVERAGE FOR THE YEAR			1,577.00	243.72	307.57	216.38
===== 606-00910 Guardrail Type 9 (Style CA) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	803.00	150.00	213.02	165.00
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1,414.00	140.00	116.85	90.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 345

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00910	Guardrail Type 9 (Style CA)		Lin Foot	=====		
NHPP0703-472			03/10/22	584.00	160.00	1461.79	440.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,801.00	147.04	316.58	184.48
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2,743.00	125.00	171.89	150.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,235.00	110.00	117.79	120.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,978.00	116.88	140.19	133.77
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,295.00	197.39	197.39	197.39
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,295.00	197.39	197.39	197.39
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	211.00	100.00	217.38	190.00
C5502-097		US550 MP 117.28-126.06	11/17/22	331.00	400.00	287.69	351.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			542.00	283.21	243.42	288.32
	WEIGHTED AVERAGE FOR THE YEAR			10,616.00	143.15	203.49	162.80
=====	606-00915	Guardrail Type 9 (Style CG)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8,760.00	155.00	117.08	96.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,760.00	155.00	117.08	96.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,597.00	237.64	237.64	237.64
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,597.00	237.64	237.64	237.64
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	370.00	300.00	196.85	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			370.00	300.00	196.85	150.00
	WEIGHTED AVERAGE FOR THE YEAR			10,727.00	172.30	121.70	118.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 346

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00916 Guardrail Type 9 (Style CA) (Special) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	575.00	175.00	382.21	320.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			575.00	175.00	382.21	320.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	304.00	150.00	279.72	325.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			304.00	150.00	279.72	325.00
	WEIGHTED AVERAGE FOR THE YEAR			879.00	166.35	342.43	321.73
===== 606-00917 Guardrail Type 9 (Style CG) (Special) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	186.00	150.00	298.65	235.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			186.00	150.00	298.65	235.00
	WEIGHTED AVERAGE FOR THE YEAR			186.00	150.00	298.65	235.00
===== 606-00930 Guardrail Type 9 (Style CD) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	596.00	175.00	174.53	155.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			596.00	175.00	174.53	155.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	410.00	160.00	144.61	120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			410.00	160.00	144.61	120.00
	WEIGHTED AVERAGE FOR THE YEAR			1,006.00	168.89	163.63	140.74
===== 606-00931 Guardrail Type 9 (Style CD) (Special) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	175.00	299.38	370.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 347

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00931	Guardrail Type 9 (Style CD) (Special)		Lin Foot	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			80.00	175.00	299.38	370.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	35.00	220.00	299.67	200.84
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35.00	220.00	299.67	200.84
	WEIGHTED AVERAGE FOR THE YEAR			115.00	188.70	299.45	318.52
=====	606-00940	Guardrail Type 9 (Style CE)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	676.00	225.00	516.12	570.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	521.00	170.00	241.76	180.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,197.00	201.06	364.62	400.25
C5502-097		US550 MP 117.28-126.06	11/17/22	1,042.00	400.00	392.08	502.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,042.00	400.00	392.08	502.00
	WEIGHTED AVERAGE FOR THE YEAR			2,239.00	293.64	372.66	447.60
=====	606-01320	End Anchor Ty 3B		Each	=====		
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	4200.00	4582.92	4366.67
STR0092-024		SH 9 North of Silverthorne	12/22/22	2.00	6000.00	7500.00	2240.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	4500.00	2721.93	2531.65
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	4757.14	4677.45	3496.90
	WEIGHTED AVERAGE FOR THE YEAR			7.00	4757.14	4677.45	3496.90
=====	606-01340	End Anchor Ty 3D		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	1800.00	2077.86	1600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 348

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01340		End Anchor Ty 3D		Each =====			
STA0252-459			02/03/22	3.00	920.00	1515.33	1418.00
C0762-055			02/17/22	2.00	2000.00	1758.28	1400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	1800.00	1170.05	1100.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	1675.56	1624.95	1408.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2200.00	1851.05	1280.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	3.00	1300.00	2142.76	2142.76
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	2000.00	3076.00	3784.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	15.00	2000.00	2028.06	1891.12
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21.00	1909.52	2114.98	2078.24
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	2000.00	3140.17	4600.52
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	5.00	1600.00	1790.48	1795.84
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	1714.29	1988.00	2597.18
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	11.00	2000.00	1830.00	1560.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	2458.13	2680.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	1800.00	1279.21	1270.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	9.00	2000.00	1900.00	2100.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	1700.00	1333.33	1300.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	2000.00	3098.94	2843.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		30.00	1940.00	1649.82	1661.54
		WEIGHTED AVERAGE FOR THE YEAR		76.00	1848.16	1756.68	1785.06
===== 606-01370		Transition Ty 3G		Each =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	3000.00	12442.37	6145.29
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	7.00	2800.00	5232.74	5400.00
NHPP1601-083			02/03/22	8.00	4000.00	4520.46	4200.00
C0762-055			02/17/22	4.00	3000.00	3845.15	3900.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	12.00	3000.00	4178.98	4000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01370	Transition Ty 3G		Each =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	11.00	3200.00	4726.44	4500.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2100.00	7179.33	6750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	3155.56	4879.66	4536.56
NH0504-911			04/07/22	13.00	3000.00	3975.00	3950.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	37.00	3300.00	3979.09	3375.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	3200.00	4193.14	4732.34
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	3300.00	6750.00	7000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	3500.00	5005.38	5005.38
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		61.00	3244.26	4103.65	3908.91
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	7776.98	7776.98	7776.98
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4.00	5000.00	5267.45	4900.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	4.00	3500.00	5897.79	6401.85
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	5000.00	6507.46	7150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	4959.45	5839.01	6173.76
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4.00	5000.00	3954.50	3809.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	4000.00	4800.00	5300.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3000.00	4481.24	4700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	8.00	7000.00	4695.00	4800.00
C5502-097		US550 MP 117.28-126.06	11/17/22	9.00	8000.00	4878.07	4540.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	3050.00	4584.20	5509.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	3400.00	4120.00	4000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	15.00	4000.00	5775.00	6000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	5000.00	3990.10	3950.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	26.00	4500.00	4188.00	3861.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	2750.00	4100.00	3900.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	5000.00	5571.72	4745.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	3000.00	3949.50	3140.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	41.00	7000.00	8385.00	4970.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3300.00	4676.19	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 350

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01370	Transition Ty 3G		Each =====			
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	4.00	3500.00	3625.00	4000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			137.00	5341.24	5369.06	4602.28
	WEIGHTED AVERAGE FOR THE YEAR			254.00	4433.87	4912.89	4494.71
=====	606-01371	Transition Ty 3G (Spec)		Each =====			
STR092A-031			03/17/22	4.00	4000.00	5000.00	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	4000.00	5000.00	5000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	9.00	5000.00	5307.50	5500.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	12.00	5000.00	2440.00	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21.00	5000.00	3668.93	4071.43
	WEIGHTED AVERAGE FOR THE YEAR			25.00	4840.00	3784.67	4220.00
=====	606-01372	Transition Type GR9-GR3		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	1800.00	8086.92	8800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	5000.00	6555.57	5900.00
C0761-239							
NHPP0703-472			03/10/22	2.00	3500.00	7092.16	6750.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	2742.86	7525.56	7800.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	6000.00	8104.64	3000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	6500.00	10087.37	21228.78
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	6107.14	8593.53	6906.17
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4353.81	4353.81	4353.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	4353.81	4353.81	4353.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 351

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01372 Transition Type GR9-GR3 Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	10000.00	8707.94	4410.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10000.00	8707.94	4410.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	5377.24	8247.34	6852.51
===== 606-01380 Transition Ty 3H Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5.00	1800.00	2342.83	2500.00
C0762-055			02/17/22	2.00	1500.00	1554.55	1700.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	1800.00	1723.39	1600.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	1762.50	1858.01	1893.75
NH0504-911			04/07/22	8.00	2000.00	1630.00	1560.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	1585.00	1793.12
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	2111.11	1617.73	1585.90
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	1800.00	2757.93	2656.83
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	1800.00	2757.93	2656.83
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4.00	2000.00	1607.50	1725.00
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	3000.00	2948.96	2740.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1950.00	2158.46	2585.27
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	2500.00	1584.38	1590.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	3500.00	1925.00	1560.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1350.00	1866.67	1800.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	2000.00	2452.30	1960.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21.00	2480.95	1952.41	1904.81
	WEIGHTED AVERAGE FOR THE YEAR			50.00	2130.00	1975.37	1904.06

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01381		Transition Ty 3H (Spec)		Each	=====		
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	1605.00	1340.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	5000.00	1605.00	1340.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	1605.00	1340.00
===== 606-01385		Transition Ty 3J		Each	=====		
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	4000.00	2435.92	3000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	3000.00	2602.71	2605.42
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	3500.00	2502.64	2802.71
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	1900.00	1748.70	1597.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	2000.00	3335.50	1936.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	1912.50	1834.47	1639.38
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3500.00	2382.52	2200.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	3500.00	2382.52	2200.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	5.00	2500.00	2466.67	2500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2200.00	4068.57	3300.00
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	3000.00	3385.60	3150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	2600.00	3642.82	4548.42
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	2000.00	3475.00	3800.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	2500.00	4325.00	4500.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2500.00	3996.73	4452.36
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	3000.00	5540.00	2180.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	2200.00	4512.91	3704.03
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20.00	2615.00	3720.78	3141.16
	WEIGHTED AVERAGE FOR THE YEAR			32.00	2550.00	2950.93	2685.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 353

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01390 End Anchor Ty 3K Each =====							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	2000.00	1996.65	1993.29
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	1996.65	1993.29
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	2400.00	2222.92	1849.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	1.00	1800.00	2007.54	2007.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	2325.00	2216.93	1868.82
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	5.00	2000.00	3000.00	3200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	2200.00	3505.76	3000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	2300.00	3064.50	2850.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1900.00	3282.87	3753.49
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	2300.00	2845.00	3200.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	2500.00	3065.00	3200.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2200.00	3528.40	3673.72
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	3000.00	6725.00	2950.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	2100.00	3141.12	2979.08
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	2323.81	3595.19	3140.94
		WEIGHTED AVERAGE FOR THE YEAR		30.00	2313.33	3072.27	2763.45
===== 606-01400 Transition Type BR10M-GR3 Each =====							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	8.00	7000.00	16320.00	13800.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	4000.00	8826.67	7680.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	12165.50	7800.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	7000.00	6938.05	5450.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	2360.00	5456.07	4831.84
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	5000.00	7683.33	8000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4.00	3500.00	10050.00	10000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	5000.00	7933.33	6300.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3600.00	4584.80	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		40.00	5096.00	8941.08	8053.68
		WEIGHTED AVERAGE FOR THE YEAR		40.00	5096.00	8941.08	8053.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 354

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01402 Transition Type BR10B-GR3 Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	4000.00	5261.58	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	4000.00	5261.58	1000.00

2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	14000.00	8302.83	5200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	14000.00	8302.83	5200.00

STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	4.00	10000.00	17635.00	18000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	16.00	16000.00	7637.50	4000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	14800.00	9637.00	6800.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	13142.86	8199.24	5742.86
===== 606-01403 Transition Type BR9-GR9 Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	3200.00	5801.75	5050.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	3200.00	5801.75	5050.30

NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	4353.81	4353.81	4353.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	4353.81	4353.81	4353.81
		WEIGHTED AVERAGE FOR THE YEAR		10.00	3430.76	5743.83	4911.00
===== 606-01407 Transition Type BR9-GR3 Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	2000.00	10190.78	9400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	2400.00	6872.91	6000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	2200.00	8149.02	7700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 355

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01407 Transition Type BR9-GR3 Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	8975.76	8975.76	8975.76
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	8.00	5100.00	8968.50	6147.77
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9.00	5530.64	8968.63	6461.99

2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	7000.00	10984.57	6980.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	7000.00	8616.02	7990.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	4541.70	8587.15	7347.12
===== 606-01460 Median Terminal Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	12000.00	12125.55	11000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	12000.00	12125.55	11000.00

NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	12000.00	16276.01	16900.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	12000.00	16276.01	16900.00

2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	12000.00	10461.55	10400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	12000.00	10461.55	10400.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	12000.00	12612.72	13800.00
===== 606-02003 End Anchor (Nonflared) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	4000.00	4104.47	3892.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 356

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-02003	End Anchor (Nonflared)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	3800.00	5192.97	5600.00
NHPP1601-083			02/03/22	36.00	4000.00	4163.70	4800.00
STA0252-459			02/03/22	11.00	3800.00	4001.67	3384.00
C0762-055			02/17/22	2.00	3000.00	3585.46	3500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	4000.00	4825.95	7000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	3600.00	4297.67	4000.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	23.00	4500.00	4777.83	3555.65
STR092A-031			03/17/22	10.00	5000.00	6000.00	6000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				98.00	4154.08	4394.83	4480.26
NH0504-911			04/07/22	43.00	3300.00	3765.00	3630.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	76.00	3200.00	3510.42	3152.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4000.00	4351.30	4904.88
STA0712-019		SH 71: Frieight Improvements	05/12/22	19.00	3600.00	3281.75	3281.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	9.00	4000.00	4946.04	4946.04
WEIGHTED AVERAGE FOR THE SECOND QUARTER				149.00	3338.93	3590.58	3438.39
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	7942.73	7942.73	7942.73
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	5000.00	5981.64	6899.37
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	24.00	5000.00	4592.50	3760.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	7.00	5000.00	5618.00	5250.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	5000.00	5851.41	5913.43
WEIGHTED AVERAGE FOR THE THIRD QUARTER				39.00	5150.91	5276.50	4623.79
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	18.00	4200.00	5083.33	4350.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3500.00	4538.25	4750.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	3725.00	4727.18	3981.55
C5502-097		US550 MP 117.28-126.06	11/17/22	20.00	5000.00	4225.00	3930.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	4600.00	7950.00	8200.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	3600.00	4479.38	5384.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	22.00	6000.00	7150.00	7000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	4100.00	3490.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-02003 End Anchor (Nonflared) Each =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	3700.00	3766.67	3700.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	6000.00	4988.96	4090.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	4400.00	3890.34	3550.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	19.00	5000.00	5074.50	5131.89
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	3700.00	4142.07	4372.34
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3800.00	4691.39	5000.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	3500.00	4387.50	4000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	3700.00	4388.33	6000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				130.00	4631.92	4936.75	4986.78
WEIGHTED AVERAGE FOR THE YEAR				416.00	4104.89	4349.72	4303.47
===== 606-02005 End Anchor (Flared) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	3200.00	4969.40	5500.00
C0762-055			02/17/22	2.00	3200.00	3936.13	4000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	16.00	4000.00	5024.59	7200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	3600.00	4500.03	4200.00
C0761-239							
STR092A-031			03/17/22	6.00	4000.00	7800.00	7800.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				33.00	3745.45	5038.60	6612.12
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3500.00	4686.87	5283.21
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	4000.00	3952.67	3952.67
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	3500.00	6550.00	7600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	3000.00	5451.50	4924.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	3.00	4000.00	5501.40	5501.40
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	14.00	4000.00	4191.95	3908.89
WEIGHTED AVERAGE FOR THE SECOND QUARTER				25.00	3820.00	4803.17	4828.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4.00	5031.73	2498.45	2498.45
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	3700.00	5814.22	5821.42
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5000.00	6346.65	6810.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				7.00	4832.42	5072.00	4205.03
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	11.00	5000.00	4500.00	5100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 358

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-02005 End Anchor (Flared) Each =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	12.00	6500.00	4500.00	4750.00
C5502-097		US550 MP 117.28-126.06	11/17/22	6.00	6000.00	4708.53	4380.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	7.00	3500.00	4250.00	4400.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	31.00	5000.00	4270.00	3515.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	6000.00	5414.79	4495.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	13.00	4200.00	4236.45	3885.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	21.00	5100.00	5687.31	5634.45
STR0092-024		SH 9 North of Silverthorne	12/22/22	31.00	6000.00	8670.00	5340.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	6.00	6000.00	4908.62	4831.10
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			139.00	5310.79	5392.51	4645.35
	WEIGHTED AVERAGE FOR THE YEAR			204.00	4858.47	5266.94	4967.68
===== 606-10200 Brdg Rail (Spec) Lin Foot =====							
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	91.00	200.00	124.50	130.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			91.00	200.00	124.50	130.00
	WEIGHTED AVERAGE FOR THE YEAR			91.00	200.00	124.50	130.00
===== 606-10700 Brdg Rail Ty 7 Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	29.00	240.00	311.64	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			29.00	240.00	311.64	200.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	100.00	244.19	170.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			378.00	100.00	244.19	170.00
	WEIGHTED AVERAGE FOR THE YEAR			407.00	109.98	251.56	172.14
===== 606-10705 Brdg Rail Ty 7 (Spec) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	15.00	150.00	464.35	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	150.00	464.35	250.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	150.00	464.35	250.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 359

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-10900 Brdg Rail Ty 9 Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	940.00	150.00	435.54	366.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	435.00	420.00	412.34	370.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,375.00	235.42	425.67	367.27

2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	275.00	428.41	430.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	275.00	428.41	430.00

NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,206.00	430.48	430.48	430.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	630.00	330.00	392.75	442.02
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,836.00	396.00	400.85	434.44

2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	450.00	374.62	260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		378.00	450.00	356.93	325.70
		WEIGHTED AVERAGE FOR THE YEAR		3,939.00	334.38	400.77	384.82
===== 606-10905 Brdg Rail Ty 9 (Spec) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	300.00	672.49	625.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	300.00	672.49	625.00
		WEIGHTED AVERAGE FOR THE YEAR		350.00	300.00	672.49	625.00
===== 606-11010 Brdg Rail Ty 10R Lin Foot =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	920.00	230.00	221.24	320.73

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 360

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-11010	Brdg Rail Ty 10R		Lin Foot	=====		
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	49.00	210.00	860.00	900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			969.00	228.99	243.15	350.02
	WEIGHTED AVERAGE FOR THE YEAR			969.00	228.99	243.15	350.02
=====	606-11035	Brdg Rail Ty 10 MASH		Lin Foot	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	302.00	240.00	324.78	440.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			302.00	240.00	324.78	440.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	445.00	500.00	480.87	490.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	500.00	300.25	279.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	306.00	400.00	389.78	554.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	980.00	330.00	307.67	270.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	248.00	250.00	525.11	650.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,027.00	372.13	379.10	407.99
	WEIGHTED AVERAGE FOR THE YEAR			2,329.00	354.99	368.37	412.14
=====	606-11037	Brdg Rail Ty 10R MASH		Lin Foot	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	617.00	400.00	231.00	240.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	220.00	500.00	256.67	240.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	88.00	400.00	502.50	520.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			925.00	423.78	262.27	266.64
	WEIGHTED AVERAGE FOR THE YEAR			925.00	423.78	262.27	266.64
=====	606-21010	End Anchor (High-Tens Cab Bar)		Each	=====		
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	3500.00	13821.85	15000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	3500.00	12717.05	13000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3500.00	12717.05	13000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 361

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-00000 Line Post Each =====							
C5502-097	US550 MP 117.28-126.06	US550 MP 117.28-126.06	11/17/22	524.00	15.00	69.97	30.90
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	300.00	80.00	53.99	67.05
BR2854-148	INTERSECTION OF US 285 & SH 9	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP	ADA RAMP IMPROVEMENTS - FAIRP					
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	CO 12 STRUCTURE P-17-F AT MP	12/22/22	88.00	10.00	22.70	15.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				912.00	35.90	60.64	41.26
WEIGHTED AVERAGE FOR THE YEAR				912.00	35.90	60.64	41.26
===== 607-00005 End Post Each =====							
STA0252-459			02/03/22	32.00	320.00	705.92	656.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				32.00	320.00	705.92	656.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS	I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	42.00	1300.00	1100.00	1100.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				42.00	1300.00	1100.00	1100.00
FSA052A-057	SH52 BOX CULVERT EXTENSION (M	SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	400.00	441.47	487.50
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	400.00	441.47	487.50
C5502-097	US550 MP 117.28-126.06	US550 MP 117.28-126.06	11/17/22	81.00	1100.00	571.84	494.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	40.00	285.00	433.77	540.14
BR2854-148	INTERSECTION OF US 285 & SH 9	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP	ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487	I-70 BRIDGES OVER WARD ROAD-	I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	1000.00	292.97	290.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	SH 50 MP 134.6-136 GUNNISON C	12/22/22	8.00	800.00	802.02	693.69
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	500.00	433.41	350.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				141.00	829.08	520.63	502.76
WEIGHTED AVERAGE FOR THE YEAR				217.00	841.20	586.21	640.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 362

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-00010 Corner and Line Br Post Each =====						
STA0252-459		02/03/22	258.00	360.00	897.00	811.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		258.00	360.00	897.00	811.00

FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	110.00	1600.00	1450.00	1450.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		110.00	1600.00	1450.00	1450.00

FSA052A-057	SH52 BOX CULVERT EXTENSION (M	08/04/22	3.00	500.00	506.37	520.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	500.00	506.37	520.00

C5502-097	US550 MP 117.28-126.06	11/17/22	33.00	1200.00	690.52	580.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	800.00	401.59	400.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22	8.00	800.00	977.42	832.43
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	11.00	1000.00	416.34	250.00
STA385A-016	SH 385 MP 97.76	12/22/22	4.00	500.00	735.56	722.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		59.00	1040.68	700.06	553.19
	WEIGHTED AVERAGE FOR THE YEAR		430.00	771.58	914.97	937.06
===== 607-00015 End Post (Spec) Each =====						
C5502-097	US550 MP 117.28-126.06	11/17/22	42.00	1200.00	1113.80	968.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		42.00	1200.00	1113.80	968.00
	WEIGHTED AVERAGE FOR THE YEAR		42.00	1200.00	1113.80	968.00
===== 607-00020 Corner and Line Br Post (Spec) Each =====						
C5502-097	US550 MP 117.28-126.06	11/17/22	53.00	1500.00	1585.13	1440.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		53.00	1500.00	1585.13	1440.00
	WEIGHTED AVERAGE FOR THE YEAR		53.00	1500.00	1585.13	1440.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 363

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-01000 Fence BW MP Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,420.00	5.00	5.77	4.06
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,420.00	5.00	5.77	4.06
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	12.00	11.36	15.60
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	312.00	34.24	35.85	35.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		432.00	28.06	22.73	30.23
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	195.00	10.00	18.08	9.25
C5502-097		US550 MP 117.28-126.06	11/17/22	2,284.00	6.00	5.84	5.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,180.00	7.00	8.67	6.38
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,500.00	5.00	9.91	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	5.00	8.77	8.06
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,659.00	6.14	8.24	8.18
		WEIGHTED AVERAGE FOR THE YEAR		8,511.00	7.07	7.72	8.61
===== 607-01050 Fence Wire MP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	12.00	17.58	16.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		200.00	12.00	17.58	16.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	12.00	17.58	16.00
===== 607-11200 Fence CW MP Lin Foot =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	14,467.00	6.00	8.37	7.45
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,467.00	6.00	8.37	7.45
		WEIGHTED AVERAGE FOR THE YEAR		14,467.00	6.00	8.37	7.45
===== 607-11300 Fence CW TWP Lin Foot =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5,400.00	5.00	4.37	5.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 364

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11300	Fence CW TWP		Lin Foot	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,400.00	5.00	4.37	5.45
	WEIGHTED AVERAGE FOR THE YEAR			5,400.00	5.00	4.37	5.45
=====	607-11350	Fence Deer		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	28,000.00	25.00	25.48	26.00
STA0252-459			02/03/22	58,249.00	7.86	13.33	10.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			86,249.00	13.42	18.73	15.28
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	28,098.00	33.00	32.00	32.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28,098.00	33.00	32.00	32.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	28,675.00	22.00	27.68	27.13
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			28,675.00	22.00	27.68	27.13
C5502-097		US550 MP 117.28-126.06	11/17/22	10,503.00	30.00	28.68	22.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10,503.00	30.00	28.68	22.80
	WEIGHTED AVERAGE FOR THE YEAR			153,525.00	19.74	23.05	21.07
=====	607-11360	Fence Deer (Spec)		Lin Foot	=====		
STA0252-459			02/03/22	580.00	10.90	18.05	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			580.00	10.90	18.05	14.00
	WEIGHTED AVERAGE FOR THE YEAR			580.00	10.90	18.05	14.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 365

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11455 Fence Wood Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		43.00	150.00	96.89	75.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			43.00	150.00	96.89	75.00
	WEIGHTED AVERAGE FOR THE YEAR			43.00	150.00	96.89	75.00
===== 607-11525 Fence (Plastic) Lin Foot =====							
MTCE R500-218			01/06/22	500.00	6.00	4.38	2.75
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	210.00	4.00	4.62	6.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,830.00	5.00	5.38	6.00
NHPP1601-083			02/03/22	900.00	3.00	6.85	4.00
STA0252-459			02/03/22	5,000.00	3.03	2.78	1.88
NHPP0063-063			02/24/22	200.00	3.50	8.10	12.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,500.00	5.00	3.98	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,390.00	6.00	4.62	5.00
C0761-239							
CR100-362			03/14/22	100.00	6.72	6.72	6.72
STR R500-171		Various locations on SH 141 a	03/17/22	400.00	4.00	2.92	0.50
STR092A-031			03/17/22	500.00	5.00	4.85	4.85
NHM765-007			03/31/22	3,000.00	6.00	3.07	2.85
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20,530.00	4.68	4.39	3.96
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5,600.00	2.13	2.13	2.13
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,000.00	2.50	5.90	10.39
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	245.00	3.50	3.98	2.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	600.00	4.00	6.42	4.25
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	200.00	6.00	3.00	3.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	250.00	5.00	7.00	7.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,895.00	2.55	4.32	3.51
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,300.00	3.00	3.00	3.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	280.00	5.00	9.13	13.50
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1,000.00	6.00	3.55	5.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1,820.00	5.00	8.50	11.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11525		Fence (Plastic)		Lin Foot	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	5.00	5.99	6.22
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3,156.00	9.10	7.59	7.59
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	400.00	4.00	3.82	4.05
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	300.00	6.00	6.82	10.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	200.00	5.00	4.13	4.30
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	250.00	4.50	5.09	4.54
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	8.00	5.01	2.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3,225.00	5.00	4.66	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		16,131.00	5.21	5.24	5.72
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	500.00	3.25	97.97	4.90
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,500.00	5.00	4.02	6.30
C5502-097		US550 MP 117.28-126.06	11/17/22	4,461.00	5.00	6.06	6.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2,085.00	3.00	4.55	5.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	500.00	3.50	6.36	5.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	965.00	4.00	4.01	4.70
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,000.00	4.00	3.20	4.10
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,550.00	4.00	4.84	3.67
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	100.00	5.00	4.93	2.56
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	8,345.00	4.00	2.93	2.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	4.00	5.15	3.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	115.00	5.00	6.97	4.55
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	5.00	6.17	6.67
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24,071.00	4.23	5.83	4.34
		WEIGHTED AVERAGE FOR THE YEAR		68,627.00	4.40	5.06	4.46
===== 607-11530		Fence (Spec)		Lin Foot	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	358.00	789.04	804.77	804.77
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		358.00	789.04	804.77	804.77
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	120.00	53.00	152.91	143.12
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		120.00	53.00	152.91	143.12
		WEIGHTED AVERAGE FOR THE YEAR		478.00	604.26	347.71	638.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11560 Debris Barrier Sq Foot =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	3,680.00	150.00	218.15	195.27
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,680.00	150.00	218.15	195.27
	WEIGHTED AVERAGE FOR THE YEAR			3,680.00	150.00	218.15	195.27
===== 607-11580 Fence (Temp) Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,450.00	6.00	7.15	4.06
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,450.00	6.00	7.15	4.06
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG 08/31/22 US 6/US 34 TIMBER BRIDGE REPL		136.00	34.24	35.85	35.85
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			136.00	34.24	35.85	35.85
STU0252-457 SHE0242-087		I-25:ALAMEDA RIVER PH 2.0 11/03/22 US 24 SAFETY IMPRVMENTS, E OF 11/03/22		860.00 179.00	10.00 20.00	20.20 6.12	27.00 4.37
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,039.00	11.72	16.16	20.13
	WEIGHTED AVERAGE FOR THE YEAR			2,625.00	9.73	9.94	13.09
===== 607-11937 Fence Metal (36 In) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	724.00	506.10	549.78	549.78
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			724.00	506.10	549.78	549.78
	WEIGHTED AVERAGE FOR THE YEAR			724.00	506.10	549.78	549.78
===== 607-15144 Fence Concrete (Noise) (144 In) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,336.00	460.00	497.89	420.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,336.00	460.00	497.89	420.00
	WEIGHTED AVERAGE FOR THE YEAR			1,336.00	460.00	497.89	420.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 368

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-32000 Fence Picket Snow Lin Foot =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,800.00	10.00	10.66	5.15
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,800.00	10.00	10.66	5.15
	WEIGHTED AVERAGE FOR THE YEAR			1,800.00	10.00	10.66	5.15
===== 607-52900 Line Post (CL) Each =====							
NHM765-007			03/31/22	4.00	105.00	269.07	285.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	105.00	269.07	285.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	105.00	57.30	55.88
===== 607-52905 End Post (CL) Each =====							
NHM765-007			03/31/22	3.00	275.00	533.31	570.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	275.00	533.31	570.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	275.00	211.64	224.12
===== 607-53137 Fence CL (Spec) (36 In) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	435.00	44.00	83.64	80.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			435.00	44.00	83.64	80.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	80.00	74.97	83.37
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			350.00	80.00	74.97	83.37
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	630.00	65.00	82.66	79.34
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			630.00	65.00	82.66	79.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 369

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-53137	Fence CL (Spec) (36 In)			Lin Foot	=====		
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	165.00	110.00	170.85	170.00	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	487.00	70.00	71.34	86.88	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	374.00	90.00	85.44	85.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	245.00	85.00	80.67	77.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,271.00	83.97	87.68	95.21	
	WEIGHTED AVERAGE FOR THE YEAR		2,686.00	72.53	83.50	87.48	
===== 607-53160	Fence CL (60 In)			Lin Foot	=====		
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	249.00	80.00	36.12	36.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		249.00	80.00	36.12	36.00	
	WEIGHTED AVERAGE FOR THE YEAR		249.00	80.00	36.12	36.00	
===== 607-53172	Fence CL (72 In)			Lin Foot	=====		
ER0502-092	US 50 MP 204 EB MONARCH TRUCK	08/29/22	50.00	80.00	117.90	58.71	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		50.00	80.00	117.90	58.71	
	WEIGHTED AVERAGE FOR THE YEAR		50.00	80.00	117.90	58.71	
===== 607-55110	Safety Rail (Cable)			Lin Foot	=====		
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	152.00	70.00	71.99	66.00	
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	1,000.00	50.00	52.13	58.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,152.00	52.64	54.36	59.06	
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	174.00	230.00	117.56	125.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 370

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-55110		Safety Rail (Cable)		Lin Foot			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	160.00	30.00	107.42	110.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			334.00	134.19	113.86	117.81
	WEIGHTED AVERAGE FOR THE YEAR			1,486.00	70.97	68.93	72.26
===== 607-55200		Rock Anchor		Lin Foot			
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	770.00	150.00	340.00	330.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			770.00	150.00	340.00	330.00
	WEIGHTED AVERAGE FOR THE YEAR			770.00	150.00	340.00	330.00
===== 607-60001		Pedest Gate (Spec)		Each			
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	550.00	1599.73	1505.05
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	550.00	1599.73	1505.05
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	1622.84	1450.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2000.00	1622.84	1450.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1275.00	1606.66	1477.53
===== 607-60002		Game Ramp		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	14.00	13000.00	20452.70	24000.00
STA0252-459			02/03/22	31.00	8000.00	8851.67	9155.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	9555.56	13833.70	13773.44
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	14.00	9600.00	14600.27	17109.23
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			14.00	9600.00	14600.27	17109.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 371

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-60002		Game Ramp		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	15000.00	14238.94	13070.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	15000.00	14238.94	13070.00
	WEIGHTED AVERAGE FOR THE YEAR			61.00	9744.26	14124.17	14515.97
===== 607-60004		4 Ft Gate Walk		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	1500.00	883.11	935.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	1500.00	883.11	935.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1500.00	883.11	935.00
===== 607-60008		Game Ramp (Special)		Each	=====		
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	9.00	20000.00	19000.00	19000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	20000.00	19000.00	19000.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	20000.00	19000.00	19000.00
===== 607-60109		8 Foot Gate (Spec)		Each	=====		
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	2400.00	3087.05	3038.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	2400.00	3087.05	3038.50
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2400.00	3087.05	3038.50
===== 607-60111		10 Ft Gate (Spec)		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	2500.00	2625.11	1570.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	2500.00	2625.11	1570.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2500.00	2625.11	1570.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 372

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-60114 14 Ft Gate Each =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	1600.00	1661.39	1573.20
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	1600.00	1661.39	1573.20
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	2500.00	2248.67	744.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	1700.00	2166.67	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2100.00	2207.67	1122.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1766.67	1757.79	1422.80
===== 607-60116 16 Ft Gate Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2500.00	2213.03	2500.00
STA0252-459			02/03/22	1.00	3072.00	3117.00	2750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2786.00	2552.02	2625.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	2500.00	1470.44	2565.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2500.00	1547.80	1926.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2643.00	1834.72	2125.71
===== 607-60117 16 Ft Gate (Spec) Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	2800.00	4591.83	2590.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2800.00	4591.83	2590.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2800.00	4591.83	2590.00
===== 607-60120 20 Ft Gate Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2500.00	2519.88	2800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	2519.88	2800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 373

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-60120	20 Ft Gate			Each	=====		
C5502-097	US550 MP 117.28-126.06	11/17/22	1.00	3000.00	3925.51	1190.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	3000.00	3925.51	1190.00	
	WEIGHTED AVERAGE FOR THE YEAR		2.00	2750.00	3046.99	1995.00	
===== 607-60121	20 Ft Gate (Spec)			Each	=====		
C5502-097	US550 MP 117.28-126.06	11/17/22	4.00	3500.00	6580.07	2670.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	3500.00	6580.07	2670.00	
	WEIGHTED AVERAGE FOR THE YEAR		4.00	3500.00	6580.07	2670.00	
===== 607-60320	20 Ft Gate Twin			Each	=====		
FSA052A-057	SH52 BOX CULVERT EXTENSION (M 08/04/22		1.00	1000.00	1255.87	1560.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1000.00	1255.87	1560.00	
	WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1255.87	1560.00	
===== 607-60620	Road Closure Gate			Each	=====		
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1700.00	23864.66	23000.00	
ER007A-035		03/15/22	4.00	38760.00	41473.00	41473.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	26406.67	28895.61	35315.33	
2670403-065	US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	15000.00	38818.53	35300.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	15000.00	38818.53	35300.00	
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	2.00	30000.00	45000.00	45000.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 374

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60620	Road Closure Gate		Each =====			
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	1.00	16300.00	72666.67	70000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	25433.33	61600.00	53333.33
	WEIGHTED AVERAGE FOR THE YEAR			10.00	24974.00	37681.55	40719.20
=====	608-00000	Conc Sidewalk		Sq Yard =====			
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	210.00	75.00	114.28	97.33
STA0252-459			02/03/22	15.00	250.00	200.88	350.00
CR100-362			03/14/22	1,509.00	214.76	214.76	214.76
STR092A-031			03/17/22	223.00	90.00	124.00	124.00
NHM765-007			03/31/22	600.00	65.00	99.60	60.76
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,557.00	157.47	144.00	161.86
NH0504-911			04/07/22	694.00	93.00	91.90	91.80
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	1,281.00	120.00	121.90	79.00
CM760-047	COLFAX AND QUAIL		05/12/22	73.00	120.00	118.40	148.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,048.00	110.85	114.23	85.80
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	212.00	150.00	80.50	71.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			212.00	150.00	80.50	71.00
STA207A-004	Resurfacing SH207A MANZANOLA		10/27/22	99.00	175.00	142.07	136.20
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA		10/27/22	169.40	85.00	191.00	132.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	2,950.00	40.00	63.81	58.00
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	317.00	120.00	125.00	125.00
C5502-097	US550 MP 117.28-126.06		11/17/22	29.00	200.00	131.70	102.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	121.00	77.00	93.22	89.86
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	550.00	80.00	105.67	75.00
NHPP0021-041	SH2 RESURFACING MLK TO 52ND		12/01/22	119.90	115.00	98.54	128.14
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,355.30	59.85	72.32	72.79
	WEIGHTED AVERAGE FOR THE YEAR			9,172.30	100.53	86.90	100.48

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 375

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00006 Conc Sidewalk (6 In) Sq Yard =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	882.00	80.00	76.49	77.00	
NHPP0063-063		02/24/22	140.00	120.00	119.70	175.00	
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22	124.00	70.00	71.83	70.00	
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,146.00	83.80	77.81	88.21	
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	628.00	75.00	118.03	83.50	
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN	06/09/22	216.00	85.00	95.17	95.17	
WEIGHTED AVERAGE FOR THE SECOND QUARTER			844.00	77.56	116.79	86.49	
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,147.00	70.00	81.75	65.00	
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22	644.00	90.00	143.00	150.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,791.00	74.61	95.88	84.61	
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,089.00	80.00	75.23	67.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,486.00	80.00	66.88	73.00	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,650.00	70.00	79.81	89.86	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	193.00	110.00	128.64	80.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	100.00	90.00	104.59	101.18	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	163.00	80.00	83.24	69.70	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,681.00	78.29	76.48	77.39	
WEIGHTED AVERAGE FOR THE YEAR			10,462.00	77.86	83.42	81.23	
===== 608-00010 Conc Curb Ramp Sq Yard =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22	2,411.00	140.00	197.88	180.93	
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	18.00	200.00	178.66	190.00	
NHPP0063-063		02/24/22	122.00	200.00	157.50	200.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 376

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00010 Conc Curb Ramp Sq Yard =====							
CR100-362			03/14/22	3,397.00	278.80	278.80	278.80
STR092A-031			03/17/22	502.00	180.00	216.00	216.00
NHM765-007			03/31/22	486.00	200.00	230.76	297.08
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6,936.00	216.29	218.77	239.90
NH0504-911			04/07/22	306.00	195.00	206.60	243.20
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,922.00	200.00	178.60	155.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	142.00	180.00	233.67	266.51
CM760-047		COLFAX AND QUAIL	05/12/22	68.00	229.00	228.00	282.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,555.00	200.00	162.64	162.64
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,993.00	199.52	183.22	167.69
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	667.00	60.00	239.32	150.00
CI211-099		SH 121 NORTH SGA SIGNALS	08/25/22	662.00	220.00	192.50	175.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	156.00	230.00	194.50	162.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,485.00	149.19	210.40	162.41
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	154.00	250.00	312.67	328.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	100.00	290.00	270.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	521.00	200.00	237.44	210.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,004.00	230.00	200.00	200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	242.00	185.00	177.52	215.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	866.00	250.00	284.01	338.61
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	153.00	150.00	246.67	200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	241.30	275.00	179.09	191.58
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	253.00	175.00	221.92	224.84
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	494.00	250.00	167.37	140.45
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,088.30	222.09	233.98	232.93
WEIGHTED AVERAGE FOR THE YEAR				17,502.30	207.17	213.43	211.10
===== 608-00012 Curb Ramp (Spec) Sq Yard =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	312.00	150.00	297.75	295.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 377

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00012	Curb Ramp (Spec)		Sq Yard	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	105.00	250.00	252.00	252.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		417.00	175.18	294.20	284.17
		WEIGHTED AVERAGE FOR THE YEAR		417.00	175.18	294.20	284.17
=====	608-00015	Detectable Warnings		Sq Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	430.00	96.00	114.55	112.30
STR0505-050			01/13/22	6.00	100.00	1175.00	1000.00
NHPP0063-063			02/24/22	30.00	75.00	58.60	75.00
CR100-362			03/14/22	140.00	103.97	103.97	103.97
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		606.00	96.84	121.90	117.32
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	12.00	100.00	88.44	82.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	100.00	88.44	82.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	32.00	125.00	92.50	120.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	125.00	92.50	120.00
		WEIGHTED AVERAGE FOR THE YEAR		650.00	98.29	120.39	116.80
=====	608-00017	Curb Ramp (Temp Perpendicular)		Each	=====		
NHPP0063-063			02/24/22	2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	964.00	1400.00
=====	608-00018	Curb Ramp (Temp Parallel) (Single)		Each	=====		
NHPP0063-063			02/24/22	2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	964.00	1400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 378

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00026 Conc Bikeway (6 In) Sq Yard =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	1,150.00	90.00	96.79	78.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,150.00	90.00	96.79	78.00
	WEIGHTED AVERAGE FOR THE YEAR			1,150.00	90.00	96.79	78.00
===== 608-00350 Conc Sidewalk (C) Sq Yard =====							
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	55.00	300.00	103.51	101.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			55.00	300.00	103.51	101.00
	WEIGHTED AVERAGE FOR THE YEAR			55.00	300.00	103.51	101.00
===== 608-01600 Aggregate Walkway Sq Yard =====							
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	84.00	75.00	68.00	65.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			84.00	75.00	68.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			84.00	75.00	68.00	65.00
===== 608-10000 Sidewalk Drain Lin Foot =====							
NH0504-911			04/07/22	5.00	400.00	802.00	854.00
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	10.00	500.00	524.76	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15.00	466.67	594.07	518.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	466.67	594.07	518.00
===== 608-10010 Sidewalk Drain Each =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	1.00	2500.00	5803.33	3600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	2500.00	5803.33	3600.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2500.00	5803.33	3600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 379

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-20004 Curb and Gutter Ty 2 (Sect II-M) (Spec) Lin Foot =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	176.00	80.00	100.24	53.95
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			176.00	80.00	100.24	53.95
	WEIGHTED AVERAGE FOR THE YEAR			176.00	80.00	100.24	53.95
===== 609-20010 Curb Ty 2 B Lin Foot =====							
NHPP0063-063			02/24/22	35,832.00	15.00	28.50	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			35,832.00	15.00	28.50	28.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	518.00	55.00	44.58	41.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			518.00	55.00	44.58	41.00
NHPP0063-054 C1211-099		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,175.00	30.00	32.09	27.00
		SH 121 NORTH SGA SIGNALS	08/25/22	214.00	40.00	32.50	30.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,389.00	31.54	32.15	27.46
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,105.00	52.00	68.50	51.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	272.00	31.38	45.31	33.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	50.00	74.74	37.47
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,383.00	47.94	60.90	47.57
	WEIGHTED AVERAGE FOR THE YEAR			39,122.00	17.28	30.30	28.84
===== 609-20011 Curb Ty 2 M Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	86.00	50.00	45.88	44.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			86.00	50.00	45.88	44.64
	WEIGHTED AVERAGE FOR THE YEAR			86.00	50.00	45.88	44.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 380

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21010 C and G Ty 2 I-B Lin Foot =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	378.00	50.00	37.56	36.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	100.00	30.00	38.74	28.00
C0761-239							
CR100-362			03/14/22	421.00	58.30	58.30	58.30
NHM765-007			03/31/22	5.00	40.00	98.44	157.32
WEIGHTED AVERAGE FOR THE FIRST QUARTER				904.00	51.60	40.95	46.17
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	650.00	30.00	39.15	29.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	2,906.00	35.00	54.21	54.21
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3,556.00	34.09	45.58	49.60
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	5,980.00	25.00	26.76	22.00
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	700.00	45.00	36.50	35.00
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	1,732.00	50.00	31.02	24.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				8,412.00	31.81	28.69	23.49
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	2,620.00	30.00	39.29	35.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	687.00	50.00	36.09	33.50
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	458.00	30.00	41.94	31.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	440.00	37.00	50.80	44.28
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	172.00	32.00	50.78	70.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	1,149.00	32.00	41.67	35.00
NHPP083A-046	SH83 RESURFACING STROH RD TO		12/08/22	258.00	45.00	56.98	49.96
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	355.00	40.00	42.47	32.00
NHPP0931-033	SH93:US6 TO 58TH RESURFACING		12/15/22	307.00	30.00	48.23	41.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				6,446.00	34.17	41.10	36.84
WEIGHTED AVERAGE FOR THE YEAR				19,318.00	33.94	37.92	33.82
===== 609-21011 C and G Ty 2 I-M Lin Foot =====							
FSA3921-019	SH 392 AND WCR 55 ISLANDS		06/02/22	41.00	33.00	123.33	90.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				41.00	33.00	123.33	90.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 381

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21011 C and G Ty 2 I-M Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		140.00	30.00	31.42	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		527.00	30.00	36.69	25.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		667.00	30.00	36.26	26.05
===== 609-21013 C and G Ty 2 I-M (Spec) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR 12/01/22		634.00	30.00	46.00	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		634.00	30.00	46.00	35.00
		WEIGHTED AVERAGE FOR THE YEAR		1,342.00	30.09	41.61	32.23
===== 609-21020 C and G Ty 2 II-B Lin Foot =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS 09/15/22		578.00	50.00	36.46	32.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		578.00	50.00	36.46	32.00
		WEIGHTED AVERAGE FOR THE YEAR		578.00	50.00	36.46	32.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA 01/06/22		387.00	36.00	54.51	44.92
NHPP1601-083		02/03/22		912.00	50.00	80.11	80.00
NHPP0063-063		02/24/22		1,218.00	40.00	38.85	45.00
NHPP 0761-238		I-76 DAHLIA TO YORK 03/10/22		140.00	35.00	41.52	28.00
C0761-239							
CR100-362		03/14/22		473.00	71.36	71.36	71.36
STR092A-031		03/17/22		271.00	60.00	81.50	81.50
NHM765-007		03/31/22		8,167.00	32.00	42.79	39.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,568.00	36.70	45.87	45.48
NH0504-911		04/07/22		2,720.00	32.00	44.85	49.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT 04/14/22		2,426.00	50.00	52.02	41.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 382

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21020 C and G Ty 2 II-B Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,096.00	36.00	42.22	30.50
CM760-047		COLFAX AND QUAIL	05/12/22	82.00	42.50	59.40	57.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	76.00	40.00	54.21	54.21
WEIGHTED AVERAGE FOR THE SECOND QUARTER				6,400.00	39.74	46.95	43.26
NHPP063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,544.00	30.00	32.77	22.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	947.00	50.00	38.50	35.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4,439.00	50.00	33.91	28.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10,930.00	39.86	33.76	25.56
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	567.00	75.00	50.17	49.50
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	148.00	40.00	95.94	44.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,191.00	30.00	40.73	35.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	374.00	95.00	95.00	95.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,107.00	40.54	74.84	83.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,072.00	55.00	39.65	41.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	553.00	36.00	63.63	52.25
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9,712.00	35.00	45.45	49.49
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,959.00	40.00	47.33	35.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	66.40	75.00	62.73	96.03
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	121.00	65.00	60.11	56.21
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	170.00	42.00	49.47	37.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	784.00	50.00	48.23	41.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				22,824.40	39.25	45.50	46.37
WEIGHTED AVERAGE FOR THE YEAR				51,722.40	38.87	44.04	41.39
===== 609-21021 C and G Ty 2 II-M Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,006.00	55.82	55.82	55.82
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3,006.00	55.82	55.82	55.82
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	412.00	50.00	41.73	29.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 383

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21021	C and G Ty 2 II-M		Lin Foot	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,448.00	38.00	31.32	25.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,860.00	39.28	31.91	25.43
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	55.00	35.00	67.45	92.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	48.00	45.00	56.31	51.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	110.00	35.00	56.27	49.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	108.00	35.00	60.00	35.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			321.00	36.50	60.82	52.25
	WEIGHTED AVERAGE FOR THE YEAR			7,187.00	46.07	36.12	39.34
=====	609-21023	C and G Ty 2 II-B (Spec)		Lin Foot	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	108.00	80.00	149.23	49.90
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	10.00	75.00	96.60	81.19
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			118.00	79.58	146.90	52.55
	WEIGHTED AVERAGE FOR THE YEAR			118.00	79.58	146.90	52.55
=====	609-21100	C and G Ty 2 Variable		Lin Foot	=====		
BRC040-057			03/17/22	120.00	50.00	54.75	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	50.00	54.75	50.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	50.00	54.75	50.00
=====	609-21110	C & G Ty 2 I-B (Spec)		Lin Foot	=====		
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	66.00	70.00	93.48	74.95
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			66.00	70.00	93.48	74.95
	WEIGHTED AVERAGE FOR THE YEAR			66.00	70.00	93.48	74.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 384

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21900 C and G Ty 2 (Spec) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	384.00	50.00	72.00	75.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			384.00	50.00	72.00	75.00
	WEIGHTED AVERAGE FOR THE YEAR			384.00	50.00	72.00	75.00
===== 609-23000 Gutter (Special) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	144.00	100.00	60.97	44.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			144.00	100.00	60.97	44.00
	WEIGHTED AVERAGE FOR THE YEAR			144.00	100.00	60.97	44.00
===== 609-24002 Gutter Ty 2 (2 Ft) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	750.00	30.00	26.34	24.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			750.00	30.00	26.34	24.50
	WEIGHTED AVERAGE FOR THE YEAR			750.00	30.00	26.34	24.50
===== 609-24004 Gutter Ty 2 (4 Ft) Lin Foot =====							
STR092A-031			03/17/22	3.00	170.00	240.50	240.50
NHM765-007			03/31/22	213.00	53.00	98.24	34.05
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			216.00	54.63	98.90	36.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,039.00	40.00	60.75	84.72
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,039.00	40.00	60.75	84.72
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	95.00	50.00	125.50	136.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			95.00	50.00	125.50	136.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 385

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-24004 Gutter Ty 2 (4 Ft) Lin Foot =====							
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1,180.00	39.20	51.42	44.28
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,180.00	39.20	51.42	44.28
	WEIGHTED AVERAGE FOR THE YEAR			2,530.00	41.25	60.65	63.70
===== 609-24005 Gutter Ty 2 (5 Ft) Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	35.00	40.00	63.24	77.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			35.00	40.00	63.24	77.00
	WEIGHTED AVERAGE FOR THE YEAR			35.00	40.00	63.24	77.00
===== 609-24006 Gutter Ty 2 (6 Ft) Lin Foot =====							
NHPP0063-063			02/24/22	36.00	70.00	124.80	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	70.00	124.80	200.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	85.00	89.00	89.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			55.00	85.00	89.00	89.00
STA207A-004 IM025A-050		Resurfacing SH207A MANZANOLA I25-MP103.9 - INTERSECTION DR	10/27/22 12/01/22	50.00 109.00	125.00 80.00	101.85 165.00	70.55 120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			159.00	94.15	145.14	104.45
	WEIGHTED AVERAGE FOR THE YEAR			250.00	88.66	137.60	114.81
===== 609-24008 Gutter Ty 2 (8 Ft) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	145.00	100.00	102.95	110.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 386

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-24008	Gutter Ty 2 (8 Ft)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	32.00	80.00	80.88	105.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			177.00	96.38	101.27	109.10
	WEIGHTED AVERAGE FOR THE YEAR			177.00	96.38	101.27	109.10
=====	609-40010	Curb Ty 4 B		Lin Foot	=====		
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	220.00	41.20	30.45	23.45
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			220.00	41.20	30.45	23.45
	WEIGHTED AVERAGE FOR THE YEAR			220.00	41.20	30.45	23.45
=====	609-40100	Curb Ty 4 Variable		Lin Foot	=====		
BRC040-057			03/17/22	120.00	50.00	58.00	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	50.00	58.00	50.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	50.00	58.00	50.00
=====	609-40120	Curb Median Special		Sq Yard	=====		
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	18.00	200.00	118.67	118.67
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	200.00	118.67	118.67
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	20.00	120.00	152.00	129.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20.00	120.00	152.00	129.00
	WEIGHTED AVERAGE FOR THE YEAR			38.00	157.89	146.92	124.11
=====	609-60011	Curb Ty 6 M		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	254.00	30.00	50.25	118.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 387

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-60011 Curb Ty 6 M Lin Foot =====						
NHPP1601-083		02/03/22	1,125.00	8.00	23.95	25.00
STA0252-459		02/03/22	30.00	40.00	99.72	160.00
C0762-055		02/17/22	4,648.00	15.00	14.40	18.00
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22	1,250.00	16.00	30.98	53.00
C0761-239						
BRC040-057		03/17/22	100.00	40.00	62.50	50.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,407.00	15.06	22.37	29.41
NH0504-911		04/07/22	349.00	25.00	18.30	21.60
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	8,079.00	17.00	10.44	9.90
WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,428.00	17.33	10.57	10.38
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22	360.00	42.80	42.80	42.80
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245	ALONG I-76 & RAMPS MILEPOST 9	09/01/22	75.00	70.00	161.50	195.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER			435.00	47.49	77.71	69.04
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	536.00	30.00	25.28	11.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	563.00	10.00	77.00	21.00
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22	27.00	21.00	102.33	150.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,126.00	19.78	46.31	19.33
WEIGHTED AVERAGE FOR THE YEAR			17,396.00	17.28	17.92	20.53
===== 609-60900 Curb Ty 6 M Special Lin Foot =====						
STR0711-022	SH 71 OVER THE ARKANSAS	08/04/22	1,783.00	25.00	15.00	13.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,783.00	25.00	15.00	13.00
WEIGHTED AVERAGE FOR THE YEAR			1,783.00	25.00	15.00	13.00
===== 609-71000 Curb (Special) Lin Foot =====						
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5	03/11/22	1,600.00	46.88	54.36	54.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 388

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-71000 Curb (Special) Lin Foot =====							
NHM765-007			03/31/22	103.00	45.00	57.27	21.14
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,703.00	46.77	54.83	52.35
	WEIGHTED AVERAGE FOR THE YEAR			1,703.00	46.77	54.83	52.35
===== 610-00020 Median Cover (Pattern Conc) Sq Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	55.00	30.00	43.83	22.00
NHM765-007			03/31/22	478.00	13.00	16.61	17.67
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			533.00	14.75	20.99	18.12
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,924.00	25.00	17.16	15.25
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	9,643.00	16.00	24.09	24.09
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15,567.00	19.42	18.64	20.73
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5,491.00	20.00	24.00	24.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	13,895.00	22.00	20.82	14.20
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			19,386.00	21.43	21.49	16.98
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	13,220.00	25.00	14.79	18.15
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	337.00	22.00	24.82	20.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4,145.00	25.00	13.57	11.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			17,702.00	24.94	14.88	16.57
	WEIGHTED AVERAGE FOR THE YEAR			53,188.00	21.95	17.96	17.95
===== 610-00024 Median Cover (4 In Pattern Conc) Sq Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11,594.00	15.00	9.95	8.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11,594.00	15.00	9.95	8.00
	WEIGHTED AVERAGE FOR THE YEAR			11,594.00	15.00	9.95	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 389

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 610-00026 Median Cover (6 In Pattern Conc) Sq Foot =====							
NHPP0063-063			02/24/22	23,417.00	10.00	11.35	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23,417.00	10.00	11.35	12.00
	WEIGHTED AVERAGE FOR THE YEAR			23,417.00	10.00	11.35	12.00
===== 610-00030 Median Cover Matl (Conc) Sq Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	523.00	9.00	23.41	19.96
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,800.00	13.00	13.02	10.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	11,308.00	13.10	12.33	12.33
CR100-362			03/14/22	25.00	375.27	375.27	375.27
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13,656.00	13.59	13.85	12.98
NH0504-911			04/07/22	150.00	13.73	115.35	30.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5,989.00	16.00	18.68	12.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	105.00	25.00	54.67	24.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6,244.00	16.10	20.85	12.65
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,682.00	12.00	10.47	9.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,646.00	15.00	13.54	11.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,328.00	13.48	12.76	9.99
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,063.00	35.00	34.00	34.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,530.00	20.00	13.78	15.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,337.00	13.00	16.53	16.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5,835.00	20.00	20.10	19.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4,267.00	16.00	17.33	19.53
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11,091.00	10.00	26.00	17.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	610-00030	Median Cover Matl (Conc)		Sq Foot	=====	=====	=====
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	3.30	35.00	107.87	385.99
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	397.00	20.00	21.49	24.98
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,258.00	18.00	13.23	9.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			28,781.30	15.63	20.47	17.80
	WEIGHTED AVERAGE FOR THE YEAR			52,009.30	15.01	18.57	15.42
=====	610-00055	Median Cover Matl (Stone)		Sq Foot	=====	=====	=====
CR100-362			03/14/22	180.00	24.45	24.45	24.45
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			180.00	24.45	24.45	24.45
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	75.00	30.00	37.70	37.10
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,504.00	3.00	14.90	4.70
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,579.00	4.28	15.98	6.24
	WEIGHTED AVERAGE FOR THE YEAR			1,759.00	6.35	16.29	8.10
=====	610-00110	Median Edging		Lin Foot	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	263.00	50.00	144.33	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			263.00	50.00	144.33	100.00
	WEIGHTED AVERAGE FOR THE YEAR			263.00	50.00	144.33	100.00
=====	611-00013	12 Ft Deer Gd		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	45000.00	61261.49	38900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	45000.00	61261.49	38900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	61261.49	38900.00
=====	611-00017	16 Ft Deer Gd		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	44700.00	76972.31	109198.99
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	44700.00	76972.31	109198.99
	WEIGHTED AVERAGE FOR THE YEAR			1.00	44700.00	76972.31	109198.99

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 391

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 611-00021 20 Ft Deer Guard Each =====							
C5502-097	US550 MP 117.28-126.06		11/17/22	5.00	55000.00	101470.61	64830.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	55000.00	101470.61	64830.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	55000.00	101470.61	64830.00
===== 611-00029 28 Ft Deer Gd Each =====							
STA0252-459			02/03/22	2.00	75000.00	128599.33	2500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	75000.00	128599.33	2500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	75000.00	128599.33	2500.00
===== 611-00041 40 Ft Deer Gd Each =====							
2670703-497	I-70_GENESEE WILDLIFE XING		09/15/22	3.00	125400.00	166436.12	237704.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	125400.00	166436.12	237704.50
	WEIGHTED AVERAGE FOR THE YEAR			3.00	125400.00	166436.12	237704.50
===== 612-00001 Delin (Ty I) Each =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	4.00	40.00	124.63	25.00
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	143.00	26.00	22.05	17.00
NHPP1601-083			02/03/22	324.00	40.00	34.81	23.00
STR0141-031			02/17/22	235.00	40.00	28.67	26.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	359.00	20.00	20.11	20.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	350.00	28.00	66.33	33.00
C0761-239							
NHPP0703-472			03/10/22	550.00	30.00	33.81	26.00
CR100-362			03/14/22	50.00	31.49	31.49	31.49
STR092A-031			03/17/22	845.00	35.00	29.00	29.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,860.00	31.77	40.82	26.29
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	34.00	50.00	79.31	50.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00001 Delin (Ty I) Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	241.00	20.00	21.70	20.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	25.00	44.60	51.68
STA0712-019		SH 71: Frieight Improvements	05/12/22	61.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	160.00	25.00	30.35	25.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	56.00	30.00	29.00	29.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				560.00	24.87	30.15	33.84
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	19.00	25.00	172.50	245.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	48.00	35.00	68.50	40.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	49.00	50.00	39.88	27.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	98.00	23.00	89.07	24.99
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	9.00	30.00	58.86	50.29
WEIGHTED AVERAGE FOR THE THIRD QUARTER				223.00	31.97	81.56	48.43
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	50.00	31.47	32.40
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	130.00	25.00	23.50	24.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	200.00	40.00	25.30	26.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	30.00	26.93	28.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	21.00	50.00	57.35	31.05
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	100.00	25.00	45.15	65.00
C5502-097		US550 MP 117.28-126.06	11/17/22	289.00	20.00	33.76	25.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	27.00	24.00	27.10	29.20
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4,630.00	50.00	27.38	26.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	27.00	50.00	37.21	43.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	40.00	41.50	45.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	25.00	27.67	28.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	30.00	49.22	22.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	72.00	30.00	38.44	27.70
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	29.00	30.00	39.98	34.15
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	92.00	30.00	49.58	35.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	16.00	30.00	42.74	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5,740.00	46.01	29.75	26.98
WEIGHTED AVERAGE FOR THE YEAR				9,383.00	40.07	35.82	27.67
===== 612-00002 Delin (Ty II) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	89.00	28.00	24.45	21.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00002	Delin (Ty II)		Each =====			
NHPP1601-083			02/03/22	53.00	30.00	80.87	26.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	127.00	20.00	21.21	21.00
NHPP0703-472			03/10/22	150.00	32.00	36.26	28.00
STR092A-031			03/17/22	35.00	30.00	30.00	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		454.00	27.47	32.13	24.59
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	171.00	25.00	22.55	21.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	24.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	40.00	34.20	29.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	27.00	25.36	30.87
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	33.00	35.00	62.98	55.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		33.00	35.00	62.98	55.64
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	60.00	35.93	37.80
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	200.00	286.31	25.25
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	30.00	47.75	68.00
C5502-097		US550 MP 117.28-126.06	11/17/22	113.00	30.00	36.72	27.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6.00	24.00	33.50	32.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	35.00	60.00	45.48	53.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	45.00	46.00	50.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	36.00	88.93	111.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	40.00	49.91	23.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	29.00	30.00	42.47	30.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	37.00	35.00	45.76	35.57
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	92.00	35.00	54.75	39.04
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		408.00	37.41	48.92	38.10
		WEIGHTED AVERAGE FOR THE YEAR		1,120.00	31.22	38.67	31.90
=====	612-00003	Delin (Ty III)		Each =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	40.00	140.35	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00003	Delin (Ty III)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	31.00	25.71	22.00
NHPP1601-083			02/03/22	129.00	35.00	55.66	28.00
STR0141-031			02/17/22	18.00	50.00	31.67	30.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	50.00	20.00	23.38	23.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	50.00	72.00	38.00
C0761-239							
NHPP0703-472			03/10/22	50.00	34.00	39.80	32.00
CR100-362			03/14/22	10.00	33.79	33.79	33.79
STR092A-031			03/17/22	58.00	40.00	31.00	31.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				347.00	34.23	41.73	28.32
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	33.00	30.00	27.87	39.03
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	32.00	57.74	66.95
STA0712-019		SH 71: Frieght Improvements	05/12/22	18.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	18.00	45.00	39.00	33.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	7.00	40.00	32.63	32.63
WEIGHTED AVERAGE FOR THE SECOND QUARTER				82.00	33.20	38.82	53.36
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	50.00	110.21	126.49
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	39.00	25.00	172.50	245.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	35.00	78.99	46.96
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	4.00	46.00	97.13	34.08
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	12.00	35.00	68.11	60.99
WEIGHTED AVERAGE FOR THE THIRD QUARTER				59.00	29.64	116.91	182.54
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	70.00	41.07	43.20
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	40.00	50.00	27.35	28.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	30.00	132.63	115.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	6.00	50.00	61.60	41.80
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	35.00	49.75	71.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	35.00	39.68	28.10
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	284.00	60.00	32.00	34.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	35.00	52.78	62.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	50.00	50.00	55.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	6.00	45.00	51.86	24.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	9.00	30.00	49.96	33.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 395

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00003	Delin (Ty III)		Each =====			
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	7.00	40.00	49.72	36.99
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	37.00	40.00	57.91	42.76
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	8.00	35.00	55.27	70.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			520.00	52.13	40.86	37.49
	WEIGHTED AVERAGE FOR THE YEAR			1,008.00	43.11	46.17	43.86
=====	612-00021	Delin (Ty I) (Barrier)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	75.00	104.92	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	75.00	104.92	130.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	31.00	81.86	81.86	81.86
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			31.00	81.86	81.86	81.86
	WEIGHTED AVERAGE FOR THE YEAR			37.00	80.75	93.20	89.67
=====	612-00031	Delin (Ty I) (Extra Ht)		Each =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	43.00	54.57	54.57	54.57
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			43.00	54.57	54.57	54.57
	WEIGHTED AVERAGE FOR THE YEAR			43.00	54.57	54.57	54.57
=====	612-00032	Delin (Ty II) (Extra Ht)		Each =====			
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	50.00	1000.00	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	50.00	1000.00	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	50.00	1000.00	1500.00
=====	612-00033	Delin (Ty III) (Extra Ht)		Each =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	41.00	60.03	60.03	60.03

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 396

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== FBR0702-423	612-00033	Delin (Ty III) (Extra Ht) VAIL PASS AUX BE F-12-AT PHAS		Each =====			
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			41.00	60.03	60.03	60.03
	WEIGHTED AVERAGE FOR THE YEAR			41.00	60.03	60.03	60.03
===== STA207A-004	612-00036	Delin (Flex) (Sq Base) Resurfacing SH207A MANZANOLA	10/27/22	410.00	66.00	88.95	85.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			410.00	66.00	88.95	85.85
	WEIGHTED AVERAGE FOR THE YEAR			410.00	66.00	88.95	85.85
===== STA207A-004 STA385A-016	612-00037	Delin (Flex) (Flat Mount) Resurfacing SH207A MANZANOLA SH 385 MP 97.76	10/27/22 12/22/22	67.00 15.00	78.50 60.00	78.00 87.14	53.00 75.56
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			82.00	75.12	80.10	57.13
	WEIGHTED AVERAGE FOR THE YEAR			82.00	75.12	80.10	57.13
===== CR100-362	612-00039	Delin (Flex) (Surf Mount)		Each =====			
			03/14/22	5.00	60.43	60.43	60.43
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	60.43	60.43	60.43
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	90.00	87.31	87.31	87.31
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			90.00	87.31	87.31	87.31
MPR200-280		PUEBLO AREA	11/17/22	16.00	80.00	70.00	65.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	80.00	70.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			111.00	85.05	81.89	82.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 397

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00041 Delin (Flex) (Ty I) Each =====							
ER007A-035			03/15/22	1,372.00	133.62	143.00	143.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,372.00	133.62	143.00	143.00
NH0504-911			04/07/22	378.00	73.40	69.50	72.00
STA0712-019	SH 71: Frieight Improvements		05/12/22	16.00	100.00	207.01	207.01
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	200.00	20.00	101.67	80.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			594.00	56.14	85.17	78.33
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	15.00	70.00	91.68	61.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			15.00	70.00	91.68	61.00
NHPP083A-046	SH83 RESURFACING STROH RD TO		12/08/22	43.00	70.00	164.48	69.95
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	516.00	63.00	101.00	80.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			559.00	63.54	104.34	79.23
	WEIGHTED AVERAGE FOR THE YEAR			2,540.00	99.70	110.32	113.36
===== 612-00042 Delin (Flex) (Ty II) Each =====							
ER007A-035			03/15/22	6.00	137.70	147.50	147.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	137.70	147.50	147.50
NH0504-911			04/07/22	186.00	86.45	81.80	83.60
STA0712-019	SH 71: Frieight Improvements		05/12/22	7.00	100.00	207.01	207.01
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	60.00	20.00	104.00	81.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			253.00	71.07	90.52	86.40

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 398

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00042 Delin (Flex) (Ty II) Each =====							
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22		87.00	75.00	134.10	71.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			87.00	75.00	134.10	71.20
	WEIGHTED AVERAGE FOR THE YEAR			346.00	73.21	101.24	83.64
===== 612-00043 Delin (Flex) (Ty III) Each =====							
ER007A-035		03/15/22		272.00	137.70	147.50	147.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			272.00	137.70	147.50	147.50
NH0504-911		04/07/22		136.00	81.06	87.30	89.60
STA0712-019	SH 71: Frieght Improvements	05/12/22		4.00	100.00	207.01	207.01
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22		20.00	20.00	105.67	82.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			160.00	73.90	92.00	91.59
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22		47.00	80.00	159.73	72.45
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22		50.00	84.00	109.33	84.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			97.00	82.06	128.75	78.40
	WEIGHTED AVERAGE FOR THE YEAR			529.00	108.20	120.24	117.92
===== 612-00052 Reflector Each =====							
STA0252-459		02/03/22		600.00	47.00	76.58	65.00
C0762-055		02/17/22		240.00	12.00	29.73	47.00
NHPP0703-472		03/10/22		648.00	18.00	53.86	18.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,488.00	28.73	57.17	41.63
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22		50.00	20.00	6.45	5.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 399

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00052	Reflector		Each =====			
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	800.00	29.00	15.00	5.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			850.00	28.47	14.50	5.03
	WEIGHTED AVERAGE FOR THE YEAR			2,338.00	28.63	46.89	28.32
=====	612-00060	Reflector (Median Barrier)		Each =====			
STA0252-459			02/03/22	300.00	41.91	119.23	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			300.00	41.91	119.23	100.00
	WEIGHTED AVERAGE FOR THE YEAR			300.00	41.91	119.23	100.00
=====	612-00070	Reflector Strip (4 In)		Each =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	231.00	65.48	65.48	65.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			231.00	65.48	65.48	65.48
	WEIGHTED AVERAGE FOR THE YEAR			231.00	65.48	65.48	65.48
=====	612-00075	Reflector Strip (6 In)		Each =====			
NHPP0703-472			03/10/22	264.00	40.00	85.48	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			264.00	40.00	85.48	90.00
	WEIGHTED AVERAGE FOR THE YEAR			264.00	40.00	85.48	90.00
=====	612-00081	Delin (PM) (Ty I)		Each =====			
C0762-055			02/17/22	12.00	75.00	83.24	65.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	75.00	83.24	65.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	8.00	89.24	89.35	89.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 400

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00081 Delin (PM) (Ty I) Each =====							
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	89.24	89.35	89.35
	WEIGHTED AVERAGE FOR THE YEAR			20.00	80.70	84.12	74.74
===== 612-00083 Delin (PM) (Ty III) Each =====							
C0762-055			02/17/22	4.00	80.00	90.27	70.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	80.00	90.27	70.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG 08/31/22		2.00	88.91	94.16	94.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	88.91	94.16	94.16
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		6.00	80.00	108.13	127.53
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	80.00	108.13	127.53
	WEIGHTED AVERAGE FOR THE YEAR			12.00	81.48	100.66	102.79
===== 612-00101 Delin (Drv Conc Inst) (Ty I) Each =====							
C0762-055			02/17/22	470.00	130.00	136.51	205.00
ER007A-035			03/15/22	458.00	163.20	174.60	174.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			928.00	146.39	143.97	190.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS 06/02/22		7.00	140.00	79.00	86.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	140.00	79.00	86.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 401

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00101 Delin (Drv Conc Inst) (Ty I) Each =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	320.00	100.00	125.00	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	138.00	135.00	97.40	95.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			458.00	110.55	106.14	115.96
	WEIGHTED AVERAGE FOR THE YEAR			1,393.00	134.57	132.22	165.13
===== 612-00102 Delin (Drv Conc Inst) (Ty II) Each =====							
ER007A-035			03/15/22	25.00	168.30	180.00	180.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	168.30	180.00	180.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	13.00	160.00	135.00	135.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	140.00	150.00	107.00	105.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			153.00	150.85	107.51	107.55
	WEIGHTED AVERAGE FOR THE YEAR			178.00	153.30	109.97	117.72
===== 612-00103 Delin (Drv Conc Inst) (Ty III) Each =====							
C0762-055			02/17/22	4.00	135.00	143.73	225.00
ER007A-035			03/15/22	91.00	173.40	185.50	185.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			95.00	171.78	179.25	187.16
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	44.00	175.00	140.00	140.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	20.00	150.00	116.00	115.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			64.00	167.19	123.33	132.19
	WEIGHTED AVERAGE FOR THE YEAR			159.00	169.93	147.17	165.03
===== 612-00111 Delin (Drv) (Ty I) Each =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	356.00	105.00	102.50	120.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			356.00	105.00	102.50	120.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 402

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00111 Delin (Drv) (Ty I) Each =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	15.00	153.01	153.01	153.01
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			15.00	153.01	153.01	153.01
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	87.00	112.00	124.35	105.91
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	354.00	86.00	79.83	98.00
STA385A-016		SH 385 MP 97.76	12/22/22	12.00	90.00	118.33	133.33
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			453.00	91.10	91.73	100.46
	WEIGHTED AVERAGE FOR THE YEAR			824.00	98.23	95.66	109.86
===== 612-00112 Delin (Drv) (Ty II) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	105.00	129.43	111.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	105.00	129.43	111.21
	WEIGHTED AVERAGE FOR THE YEAR			24.00	105.00	129.43	111.21
===== 612-00113 Delin (Drv) (Ty III) Each =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	110.00	110.00	130.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	110.00	110.00	130.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	152.26	160.50	160.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	152.26	160.50	160.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 403

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00113 Delin (Drv) (Ty III) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	113.00	137.32	116.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	89.00	86.33	110.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	90.00	119.58	133.33
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		28.00	96.21	115.37	120.27
		WEIGHTED AVERAGE FOR THE YEAR		32.00	100.58	116.00	123.39
===== 612-00260 Loc Mark (Fib Opt) (Dome) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	120.00	276.27	230.00
NHM765-007			03/31/22	10.00	150.00	462.81	416.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	136.67	356.22	333.39
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	44.00	120.00	336.17	370.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	260.00	84.00	106.67	115.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	21.00	100.00	265.00	213.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		325.00	89.91	161.51	155.86
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	87.31	87.31	87.31
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	130.00	275.62	283.98
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	97.98	219.13	136.48
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	130.00	124.73	130.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	125.00	289.52	439.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 404

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00260	Loc Mark (Fib Opt) (Dome)			Each =====			
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		1.00	100.00	257.61	260.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	126.67	148.06	192.47
	WEIGHTED AVERAGE FOR THE YEAR			359.00	93.57	172.33	165.76
===== 612-00270	Loc Mark (Util) (Flat Slat)			Each =====			
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		3.00	100.00	244.67	260.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS	06/02/22		4.00	100.00	130.50	205.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	100.00	204.96	228.57
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		5.00	100.00	124.98	132.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		71.00	36.10	353.58	537.57
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			76.00	40.30	325.36	510.89
	WEIGHTED AVERAGE FOR THE YEAR			83.00	45.34	317.38	487.08
===== 612-01080	Barrier Striping (6 In)			Lin Foot =====			
STA0252-459		02/03/22		8,600.00	2.50	5.84	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,600.00	2.50	5.84	4.00
	WEIGHTED AVERAGE FOR THE YEAR			8,600.00	2.50	5.84	4.00
===== 613-00075	3/4 In Elec Cond			Lin Foot =====			
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		725.00	10.00	29.81	29.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			725.00	10.00	29.81	29.00
	WEIGHTED AVERAGE FOR THE YEAR			725.00	10.00	29.81	29.00
===== 613-00100	1 In Elec Cond			Lin Foot =====			
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	01/06/22		2,050.00	40.00	155.00	155.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 405

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00100	1 In Elec Cond		Lin Foot	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	397.00	22.00	36.88	30.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,447.00	37.08	83.21	134.72
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	330.00	24.00	28.92	34.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			330.00	24.00	28.92	34.04
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	646.00	10.00	11.64	12.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	340.00	20.00	35.00	25.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			986.00	13.45	15.49	16.48
	WEIGHTED AVERAGE FOR THE YEAR			3,763.00	29.74	43.90	94.91
=====	613-00102	1 In Elec Cond (GRC) (Special)		Lin Foot	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	50.00	50.00	58.33	35.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			50.00	50.00	58.33	35.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	50.00	58.33	35.00
=====	613-00200	2 In Elec Cond		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,600.00	25.00	79.13	80.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	175.00	24.00	45.18	46.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,775.00	24.90	74.08	76.65
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	266.00	20.00	56.46	38.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20,832.00	32.10	32.10	32.10
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5,550.00	17.00	28.21	30.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 406

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-00200	2 In Elec Cond			Lin Foot	=====	=====	=====
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	1,915.00	25.00	21.24	24.75
CM760-047	COLFAX AND QUAIL		05/12/22	174.00	20.00	28.60	41.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28,737.00	28.53	28.59	31.31
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	700.00	39.59	39.59	39.59
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	3,100.00	25.00	28.43	25.00
2670403-065	US40 FLOYD HILL ROUNDABOUTS		09/15/22	4,550.00	30.00	58.76	53.00
2670703-497	I-70 GENESEE WILDLIFE XING		09/15/22	630.00	24.00	28.42	28.40
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8,980.00	28.60	45.33	40.56
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	6,905.00	20.00	21.03	22.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	1,338.00	35.00	40.93	41.00
C5502-097	US550 MP 117.28-126.06		11/17/22	58.00	30.00	95.90	216.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	434.00	25.60	37.32	40.51
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	755.00	35.00	29.81	29.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9,490.00	23.63	23.41	27.27
	WEIGHTED AVERAGE FOR THE YEAR			48,982.00	27.46	31.75	33.87
===== 613-00206	2 In Elec Cond (Bored)			Lin Foot	=====	=====	=====
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	265.00	30.00	110.21	106.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	725.00	24.00	44.91	31.00
C0761-239							
NHM765-007			03/31/22	1,500.00	40.00	44.38	39.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,490.00	34.28	52.15	44.34
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	55,890.00	11.00	29.21	30.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	1,840.00	25.00	21.20	24.75
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	325.00	33.00	55.33	56.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 407

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00206	2 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	606.00	19.00	25.20	24.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	545.00	50.00	63.50	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	210.00	15.00	27.57	27.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		59,416.00	12.01	29.08	30.19
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	250.00	98.23	98.23	98.23
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4,535.00	50.00	28.43	25.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2,025.00	25.00	28.50	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	470.00	32.00	26.42	26.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,280.00	43.54	29.17	29.02
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8,355.00	20.00	22.63	19.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,473.00	25.00	25.41	26.60
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,880.00	29.00	24.00	22.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,956.00	45.00	56.11	60.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	50.00	63.64	62.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	320.00	25.00	36.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	345.00	35.00	42.69	26.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	115.00	27.00	33.19	31.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,544.00	25.76	28.71	26.77
		WEIGHTED AVERAGE FOR THE YEAR		83,730.00	17.80	29.72	29.91
=====	613-00207	2 In Elec Cond (Bridge) (Spec)		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	360.00	50.00	115.94	130.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		360.00	50.00	115.94	130.00
		WEIGHTED AVERAGE FOR THE YEAR		360.00	50.00	115.94	130.00
=====	613-00300	3 In Elec Cond		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	674.00	35.00	32.11	33.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 408

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00300	3 In Elec Cond		Lin Foot	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	108.00	21.50	46.60	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		782.00	33.14	34.11	37.56
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	50.00	36.71	32.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,789.00	30.00	58.40	59.07
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,829.00	30.44	58.27	58.48
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	60.00	30.00	45.63	48.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	233.00	25.00	36.23	39.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		293.00	26.02	39.43	41.10
		WEIGHTED AVERAGE FOR THE YEAR		2,904.00	30.72	51.51	51.09
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====		
NHPP0063-063			02/24/22	6,100.00	25.00	26.60	28.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	900.00	45.92	49.14	49.14
NHM765-007			03/31/22	6,150.00	42.00	47.03	42.18
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13,150.00	34.38	39.19	36.08
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,020.00	30.00	26.72	31.50
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,160.00	36.00	62.00	68.00
CM760-047		COLFAX AND QUAIL	05/12/22	606.00	19.50	29.00	28.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	430.00	30.00	27.57	27.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,216.00	30.14	33.54	40.64
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3,935.00	28.00	32.00	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 409

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	550.00	40.00	140.80	127.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	940.00	30.00	31.20	32.10
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,425.00	29.56	43.54	43.82
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2,855.00	12.00	26.38	21.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,490.00	58.00	35.96	37.77
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	43.00	200.00	200.00	200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	780.00	33.00	24.75	23.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	586.00	30.00	56.11	60.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,500.00	40.00	39.00	26.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,260.00	35.00	49.38	33.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	420.00	27.00	35.30	33.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9,934.00	32.52	37.40	31.00
		WEIGHTED AVERAGE FOR THE YEAR		32,725.00	32.47	38.10	36.41
=====	613-00400	4 In Elec Cond		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	40.00	45.91	46.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	40.00	45.91	46.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	40.00	45.91	46.00
=====	613-00408	4 In Elec Cond (Bored)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,600.00	15.00	39.00	38.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,600.00	15.00	39.00	38.00
		WEIGHTED AVERAGE FOR THE YEAR		1,600.00	15.00	39.00	38.00
=====	613-00607	6 In Elec Cond (Brdg) (Spec)		Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,264.00	45.48	45.48	45.48

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 410

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00607	6 In Elec Cond (Brdg) (Spec)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,264.00	45.48	45.48	45.48
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	433.00	20.00	189.47	180.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			433.00	20.00	189.47	180.00
	WEIGHTED AVERAGE FOR THE YEAR			1,697.00	38.98	136.39	79.80
=====	613-01075	3/4 In Elec Cond (P)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,210.00	25.00	6.77	7.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,210.00	25.00	6.77	7.00
	WEIGHTED AVERAGE FOR THE YEAR			1,210.00	25.00	6.77	7.00
=====	613-01100	1 In Elec Cond (P)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	397.00	15.00	22.46	30.00
C0761-239		I-25 EXPRESS LANES SEGMENT 5	03/11/22	720.00	30.61	32.76	32.76
NHPP0253-275							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,117.00	25.06	24.36	31.78
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	15.00	28.92	34.04
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	279.00	25.00	20.67	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	220.00	15.00	35.00	40.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			599.00	19.66	26.66	28.29
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	290.00	25.00	25.34	22.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			290.00	25.00	25.34	22.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 411

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-01100	1 In Elec Cond (P)			Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	420.00	30.00	24.43	26.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	238.00	70.00	60.00	60.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	160.00	30.00	39.86	40.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	15.00	21.00	21.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			858.00	40.40	28.11	37.81
	WEIGHTED AVERAGE FOR THE YEAR			2,864.00	28.52	26.32	31.87
===== 613-01150	1-1/2 In Elec Cond (P)			Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	310.00	35.00	9.02	10.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			310.00	35.00	9.02	10.00
	WEIGHTED AVERAGE FOR THE YEAR			310.00	35.00	9.02	10.00
===== 613-01200	2 In Elec Cond (P)			Lin Foot	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	90.00	25.00	175.00	175.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	5.00	91.17	86.03
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,250.00	25.00	80.13	80.00
STA0252-459			02/03/22	20.00	30.81	34.40	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,402.00	6.00	28.87	33.50
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2,300.00	27.55	29.48	29.48
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	60.00	60.00	59.50	56.00
NHM765-007			03/31/22	4,532.00	20.00	44.38	39.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,704.00	21.06	49.95	46.70
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	914.00	20.00	38.53	41.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	545.00	16.00	35.74	42.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	29,377.00	35.00	24.17	19.50
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	270.00	25.00	58.00	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	130.00	10.00	32.36	32.36
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			31,236.00	34.04	25.44	20.93

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 412

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-01200	2 In Elec Cond (P)			Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	19,865.00	28.38	28.38	28.38
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	505.00	25.00	26.00	25.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	5,202.00	10.00	52.85	53.39
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	130.00	40.00	37.70	39.59
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			25,702.00	24.65	43.81	33.43
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,839.00	15.00	22.00	21.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7,300.00	20.00	23.19	24.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,260.00	25.00	45.21	45.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	160.00	25.00	22.50	19.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7,233.00	25.00	30.78	33.36
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	985.00	30.00	34.03	33.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	30.00	24.33	23.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	495.00	40.00	34.61	26.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	150.00	32.00	38.73	36.90
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20,522.00	23.25	26.68	28.99
	WEIGHTED AVERAGE FOR THE YEAR			88,164.00	27.21	32.55	29.58
===== 613-01250	2-1/2 In Elec Cond (P)			Lin Foot	=====		
NHM765-007			03/31/22	33,120.00	22.00	43.80	42.18
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			33,120.00	22.00	43.80	42.18
	WEIGHTED AVERAGE FOR THE YEAR			33,120.00	22.00	43.80	42.18
===== 613-01300	3 In Elec Cond (P)			Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	150.00	20.00	57.28	54.08
NHPP0063-063			02/24/22	4,045.00	20.00	21.05	22.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,195.00	20.00	23.55	23.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 413

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-01300 3 In Elec Cond (P) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	680.00	18.00	43.32	51.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	390.00	26.00	39.56	39.56
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,070.00	20.92	42.99	46.83
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	250.00	28.00	29.50	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	120.00	40.00	54.71	63.13
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		370.00	31.89	44.38	40.74
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,839.00	17.00	23.25	23.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7,290.00	28.00	33.24	35.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	370.00	35.00	53.03	53.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	180.00	24.00	23.00	20.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	136.00	20.00	36.23	39.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,020.00	20.00	32.33	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	140.00	40.00	39.36	33.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	275.00	40.00	54.80	54.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	268.00	20.00	32.39	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,518.00	25.85	32.66	32.45
		WEIGHTED AVERAGE FOR THE YEAR		17,153.00	24.24	32.45	31.32
===== 613-01400 4 In Elec Cond (P) Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,890.00	35.00	65.14	65.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	326.00	43.00	51.75	56.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,216.00	36.18	62.64	63.68
		WEIGHTED AVERAGE FOR THE YEAR		2,216.00	36.18	62.64	63.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 414

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-01600		6 In Elec Cond (P)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	756.00	50.00	116.04	116.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			756.00	50.00	116.04	116.00
	WEIGHTED AVERAGE FOR THE YEAR			756.00	50.00	116.04	116.00
===== 613-04020		Hanger System		LUMP SUM	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	21400.00	21400.00	21400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	21400.00	21400.00	21400.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	116724.27	116724.27	116724.27
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	116724.27	116724.27	116724.27
	WEIGHTED AVERAGE FOR THE YEAR			2.00	53174.76	53174.76	53174.76
===== 613-04100		Elect System Mods		LUMP SUM	=====		
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	15000.00	14564.50	25500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	14564.50	25500.00
TRG0253-264 STAM420-001 BR2854-148 STM0091-046		I-25 AND SH 119 PARK-N-RIDE US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	10/27/22 12/01/22	1.00 1.00	10000.00 3500.99	579.99 19776.93	1500.00 21447.71
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	6750.50	6978.97	11473.86
	WEIGHTED AVERAGE FOR THE YEAR			3.00	9500.33	8062.62	16149.24
===== 613-04120		1 In Elec Cond (Liquidtight Flx Met)		Lin Foot	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	80.00	42.00	33.00	32.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	42.00	33.00	32.00
	WEIGHTED AVERAGE FOR THE YEAR			80.00	42.00	33.00	32.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 415

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-05606 6 In Wide Cable Tray Lin Foot =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4,000.00	20.00	140.00	140.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,000.00	20.00	140.00	140.00
	WEIGHTED AVERAGE FOR THE YEAR			4,000.00	20.00	140.00	140.00
===== 613-07000 Pull Box (Spec) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1000.00	2205.74	2000.00
NHPP0063-063			02/24/22	2.00	1000.00	1780.00	2500.00
CR100-362			03/14/22	3.00	1096.75	1096.75	1096.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	1041.46	1909.86	1755.75
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	1037.00	3566.67	3200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	1037.00	3566.67	3200.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	15.00	15861.68	15861.68	15861.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	9.00	800.00	1446.32	1300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			24.00	10213.55	7998.75	10401.05
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	6.00	2500.00	1702.41	1100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	2500.00	1702.41	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			41.00	6623.50	4419.59	6861.35
===== 613-07001 Type One Pull Box Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	1000.00	1527.02	1400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 416

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07001 Type One Pull Box Each =====							
NHPP0063-063			02/24/22	74.00	1000.00	1046.00	1100.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	800.00	1623.75	1400.00
C0761-239							
CR100-362			03/14/22	7.00	1508.70	1508.70	1508.70
NHM765-007			03/31/22	50.00	850.00	1901.97	1710.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				140.00	964.72	1496.31	1357.58
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	900.00	1630.46	950.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	950.00	1642.92	1600.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	13.00	1200.00	1168.69	1168.69
WEIGHTED AVERAGE FOR THE SECOND QUARTER				20.00	1107.50	1501.11	1254.65
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	69.00	1500.00	1078.33	1150.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	2000.00	1583.79	1540.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	7.00	950.00	1075.00	1400.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	1500.00	1978.10	1856.20
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	6.00	1000.00	1302.56	1120.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				85.00	1425.29	1097.20	1189.68
WEIGHTED AVERAGE FOR THE YEAR				245.00	1136.17	1258.23	1290.92
===== 613-07002 Type Two Pull Box Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	16.00	1800.00	1938.23	1900.00
STA0252-459			02/03/22	2.00	1354.43	1985.00	2645.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	10.00	1545.92	1508.92	1508.92
CR100-362			03/14/22	20.00	1599.65	1599.65	1599.65
NHM765-007			03/31/22	36.00	1324.00	2187.27	1966.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				84.00	1507.44	2010.16	1828.17
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	6.00	1400.00	1663.79	1050.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	12.00	1100.00	1788.10	1700.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	21.00	1750.00	1390.11	1644.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 417

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07002 Type Two Pull Box Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	74.00	1200.00	2833.33	2500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			113.00	1302.21	2209.83	2179.03
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	2728.50	2728.50	2728.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	1300.00	1396.32	1200.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	36.00	2000.00	3098.53	2727.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			76.00	1781.95	2476.85	2084.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	7.00	900.00	1425.00	1050.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	41.00	1900.00	1361.61	1450.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10.00	4000.00	4350.00	4350.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	1745.63	1700.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	7.00	2685.00	2300.00	1610.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	1095.00	1987.69	2144.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11.00	1200.00	1366.67	1600.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	2700.00	2133.78	1650.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			87.00	2041.15	1510.95	1828.21
	WEIGHTED AVERAGE FOR THE YEAR			360.00	1629.95	1966.03	1992.36
===== 613-07003 Type Three Pull Box Each =====							
NHPP0063-063			02/24/22	1.00	1400.00	2175.00	3000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	12.00	2000.00	2505.81	1700.00
C0761-239							
CR100-362			03/14/22	10.00	1968.80	1968.80	1968.80
MP0503-098			03/24/22	2.00	1400.00	2299.00	2600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	1915.52	2444.57	1931.52
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	16.00	1300.00	2101.72	1100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	1300.00	2101.72	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 418

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07003 Type Three Pull Box Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	1300.00	1632.44	1700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	2314.05	2300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3000.00	2451.07	2302.14
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13.00	1700.00	1794.93	1977.09
	WEIGHTED AVERAGE FOR THE YEAR			54.00	1681.26	2170.40	1696.11
===== 613-07004 Type Four Pull Box Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	1800.00	3429.72	3200.00
NHPP0063-063			02/24/22	18.00	1500.00	2090.00	2200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	1800.00	3583.20	2550.00
C0761-239							
CR100-362			03/14/22	3.00	1674.55	1674.55	1674.55
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			33.00	1624.96	2943.63	2476.47
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	1700.00	2736.32	1700.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	46.00	1500.00	3200.65	3100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	3000.00	2634.47	3085.70
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	2000.00	2349.60	2402.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	6.00	1800.00	3296.31	3296.31
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			69.00	1800.00	3028.08	3033.75
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2200.00	4238.94	3700.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	2000.00	2212.50	2500.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	1800.00	2676.71	2480.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			23.00	1982.61	2522.93	2600.87
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	12.00	1200.00	2404.00	1895.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07004 Type Four Pull Box Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	2500.00	3023.91	3200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1700.00	4093.01	4100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	3.00	1675.00	2770.00	2190.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	11.00	1500.00	4277.50	4647.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	10000.00	3504.31	3400.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3200.00	4429.17	4158.33
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	3200.00	3875.79	3300.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	3000.00	3144.25	2780.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				49.00	2165.82	3250.30	3141.33
WEIGHTED AVERAGE FOR THE YEAR				174.00	1893.96	3039.96	2901.14
===== 613-07005 Type Five Pull Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	2800.00	2589.20	2443.37
NHPP0063-063			02/24/22	6.00	2000.00	2615.00	3000.00
CR100-362			03/14/22	3.00	1915.30	1915.30	1915.30
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	3.00	7400.00	5187.00	7874.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				13.00	3288.15	3144.19	3831.64
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2500.00	3771.09	3699.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	2300.00	3102.03	3652.58
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2500.00	3158.80	3049.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	5.00	2600.00	6472.75	6472.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				9.00	2511.11	3860.65	5157.43
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2500.00	5635.24	4900.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	2400.00	2909.50	3295.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	2400.00	3563.13	3389.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				7.00	2414.29	3430.24	3537.71
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	2000.00	6199.90	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 420

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07005 Type Five Pull Box Each =====							
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	2400.00	3340.00	2910.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	2533.00	5829.04	6315.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3500.00	5199.17	4400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	6000.00	6511.22	6540.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			14.00	2880.93	5969.42	5679.65
	WEIGHTED AVERAGE FOR THE YEAR			43.00	2850.67	4814.27	4662.96
===== 613-07010 Pull Box (Surf Mtd) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	1000.00	365.01	429.41
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	1000.00	365.01	429.41
	WEIGHTED AVERAGE FOR THE YEAR			10.00	1000.00	365.01	429.41
===== 613-07011 Pull Box (11"x18"x12") Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	1100.00	1602.92	1600.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	500.00	1078.80	1369.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	1000.00	1547.00	1240.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	1025.00	1544.95	1490.75
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	3000.00	1638.61	1600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	62.00	1500.00	1878.66	2025.62
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			70.00	1671.43	1857.47	1976.98
	WEIGHTED AVERAGE FOR THE YEAR			82.00	1576.83	1808.13	1905.82
===== 613-07023 Pull Box (24"x36"x24") Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	22.00	1400.00	4466.67	3900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 421

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07023		Pull Box (24"x36"x24")		Each =====			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	11.00	1500.00	3305.00	2655.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33.00	1433.33	4176.25	3485.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5.00	3492.48	3492.48	3492.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	1800.00	4883.62	4943.38
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	3008.91	4517.53	3907.02
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	13.00	2100.00	3771.96	3800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	1620.00	3187.12	3455.46
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			22.00	1903.64	3594.46	3646.40
	WEIGHTED AVERAGE FOR THE YEAR			62.00	1778.10	3928.13	3594.90
===== 613-07034		Pull Box (24"x36"x18")		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	1500.00	2554.74	2600.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	1500.00	2554.74	2600.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	1500.00	2292.75	2125.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	1500.00	3023.91	3200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	1500.00	2824.50	2739.29
	WEIGHTED AVERAGE FOR THE YEAR			11.00	1500.00	2740.20	2688.64
===== 613-07040		Pull Box (30"x48"x24")		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	3500.00	4005.00	4005.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3500.00	4005.00	4005.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 422

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07040		Pull Box (30"x48"x24")		Each	=====		
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	2000.00	4218.50	3300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2000.00	4218.50	3300.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	2600.00	5834.76	5871.40
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2600.00	5834.76	5871.40
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	1900.00	3496.50	3140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	1900.00	3496.50	3140.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	2257.14	4320.01	3699.49
===== 613-07060		Pull Box (18"x30"x18") Deep		Each	=====		
NHM765-007			03/31/22	3.00	1200.00	2891.00	2599.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1200.00	2891.00	2599.20
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1200.00	2891.00	2599.20
===== 613-07195		Proof Conduit		Lin Foot	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	5,975.00	3.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,975.00	3.00	17.00	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	700.00	5.00	7.00	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		700.00	5.00	7.00	8.00
		WEIGHTED AVERAGE FOR THE YEAR		6,675.00	3.21	15.10	16.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 423

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-10000 Wiring LUMP SUM =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	50000.00	210000.00	210000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	52000.00	6396.06	6028.53
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	82184.01	72000.00
STA0252-459			02/03/22	1.00	6500.00	1863.00	2444.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	54332.23	130000.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	63823.47	56551.69	56551.69
NHM765-007			03/31/22	1.00	255000.00	297975.47	267900.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				7.00	66046.21	81489.17	106417.75
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	102055.69	97000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	40000.00	36815.42	36282.23
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	310000.00	217666.67	203000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	10000.00	20351.40	12537.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	40000.00	55038.00	34000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	50000.00	30565.75	30565.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				6.00	91666.67	73934.99	68897.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	70000.00	71422.84	75000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	120000.00	120000.00	90000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	10000.00	117011.77	101000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	20000.00	82076.44	81420.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	25000.00	22080.16	15865.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				5.00	49000.00	72044.85	72657.07
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	20000.00	63690.00	41000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	107500.00	80415.90	80000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	25232.62	18000.00	18000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	150000.00	55912.72	55000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	25000.00	30750.00	39500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	250000.00	224525.00	225000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	20000.00	9481.41	9100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 424

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	613-10000	Wiring		LUMP SUM	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	40000.00	51666.67	50000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	10000.00	14481.50	13562.99
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	20000.00	30342.62	26500.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	5000.00	5139.71	2500.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	17292.88	10880.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	62710.20	61256.54	50080.23
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		30.00	66856.65	69735.42	70085.08
=====							
=====	613-13000	Luminaire (LED) (Spec)		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	2017.35	2382.39	2382.39
NHM765-007			03/31/22	46.00	1500.00	1711.78	1539.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		54.00	1576.64	1748.52	1663.95
=====							
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	5000.00	1041.20	1075.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	5000.00	1041.20	1075.00
=====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	1250.00	1217.33	1035.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	1250.00	1217.33	1035.00
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		62.00	1776.43	1606.97	1585.37
=====							
=====	613-13005	Lumin (Spec) (LED) (Step) (Light)		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	58.00	864.29	999.03	999.03
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		58.00	864.29	999.03	999.03
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		58.00	864.29	999.03	999.03
=====							
=====	613-13006	Lumin (LED) (6,000 Lumens)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	43.00	1200.00	1622.53	1700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 425

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13006	Lumin (LED) (6,000 Lumens)		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	3500.00	3700.00	3700.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	16.00	9000.00	3166.38	3030.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			60.00	3318.33	1918.02	2088.00
	WEIGHTED AVERAGE FOR THE YEAR			60.00	3318.33	1918.02	2088.00
=====	613-13008	Lumin (LED) (8,000 Lumens)		Each =====			
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	1000.00	839.06	839.06
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	1000.00	839.06	839.06
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	33.00	1300.00	1158.12	1000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			33.00	1300.00	1158.12	1000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	11.00	800.00	1173.25	1015.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	1000.00	1578.55	1650.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	4.00	1305.00	1187.50	1025.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	43.00	1000.00	1178.42	1280.91
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	1250.00	1171.45	880.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	1000.00	1410.26	1260.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			80.00	1000.25	1314.26	1279.93
	WEIGHTED AVERAGE FOR THE YEAR			117.00	1084.79	1277.71	1185.90
=====	613-13010	Lumin(LED) (10,000 Lumens)		Each =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	1500.00	1266.68	1100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			29.00	1500.00	1266.68	1100.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	13.00	700.00	800.00	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13.00	700.00	800.00	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			42.00	1252.38	1079.05	1130.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 426

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-13011 Lumin (LED) (11,000 Lumens) Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	54.00	815.00	1066.67	1100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			54.00	815.00	1066.67	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			54.00	815.00	1066.67	1100.00
===== 613-13012 Lumin (LED) (12,000 Lumens) Each =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	750.00	900.00	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	750.00	900.00	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	750.00	900.00	1200.00
===== 613-13014 Lumin (LED) (14,000 Lumens) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	18.00	200.00	1100.00	1100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			18.00	200.00	1100.00	1100.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	24.00	1900.00	4006.93	4200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	1500.00	3310.55	3300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			31.00	1809.68	3938.27	3996.77
	WEIGHTED AVERAGE FOR THE YEAR			49.00	1218.37	3527.92	2932.65
===== 613-13016 Lumin (LED) (16,000 Lumens) Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1000.00	1037.23	950.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	1000.00	1037.23	950.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	1000.00	1037.23	950.00
===== 613-13025 Lumin (LED) (25,000 Lumens) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	800.00	1906.87	1800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	800.00	1906.87	1800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 427

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-13025		Lumin (LED) (25,000 Lumens)		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	3500.00	1376.63	1620.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	3500.00	1376.63	1620.75
	WEIGHTED AVERAGE FOR THE YEAR			15.00	2420.00	1566.00	1692.45
===== 613-13060		Lumin (LED) (1300 Lumin)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	18.00	950.00	1124.46	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	950.00	1124.46	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	950.00	1124.46	1200.00
===== 613-13065		Lumin (LED) (5400 Lumen)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	3000.00	3950.51	4200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			26.00	3000.00	3950.51	4200.00
	WEIGHTED AVERAGE FOR THE YEAR			26.00	3000.00	3950.51	4200.00
===== 613-13100		Luminare Mounting Support System		LUMP SUM	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	50000.00	18833.47	8500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	50000.00	18833.47	8500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	50000.00	18833.47	8500.00
===== 613-15000		Floodlight		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	24.00	1942.86	2314.70	2314.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	1942.86	2314.70	2314.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 428

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-15000	Floodlight			Each	=====		
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22		8.00	1500.00	1700.00	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	1500.00	1700.00	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			32.00	1832.15	2007.35	2111.03
===== 613-15050	Spot Light			Each	=====		
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5	03/11/22		4.00	1942.86	2314.70	2314.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1942.86	2314.70	2314.70
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1942.86	2314.70	2314.70
===== 613-20000	Inst Light Std + Lumin			Each	=====		
NHM765-007		03/31/22		4.00	1000.00	2599.36	2337.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1000.00	2599.36	2337.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1000.00	2599.36	2337.00
===== 613-20200	Inst Lumin			Each	=====		
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22		1.00	300.00	700.66	605.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	300.00	700.66	605.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	300.00	700.66	605.00
===== 613-30005	Light Std + Lumin (Pedest)			Each	=====		
STAM420-001 BR2854-148 STM0091-046	US 285 AT HWY 9C IMPROVEMENTS	12/01/22		21.00	6000.00	7137.50	7745.01
	INTERSECTION OF US 285 & SH 9						
	ADA RAMP IMPROVEMENTS - FAIRP						
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21.00	6000.00	7137.50	7745.01
	WEIGHTED AVERAGE FOR THE YEAR			21.00	6000.00	7137.50	7745.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 429

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-30300 Light Std Alum (30 Ft) Each =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	15.00	2400.00	4466.67	4100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15.00	2400.00	4466.67	4100.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	2400.00	4466.67	4100.00
===== 613-32180 Light Std Steel (18 Ft) Each =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	5000.00	6422.12	5800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	5000.00	6422.12	5800.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	5000.00	6422.12	5800.00
===== 613-32300 Light Std Steel (30 Ft) Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	3000.00	8866.67	10100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	3000.00	8866.67	10100.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	6000.00	4498.20	3900.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	26.00	7000.00	7935.61	7200.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			55.00	6472.73	6469.65	5460.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	35.00	3500.00	3950.39	4289.54
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			35.00	3500.00	3950.39	4289.54
	WEIGHTED AVERAGE FOR THE YEAR			96.00	5171.88	5416.76	5323.27
===== 613-32350 Light Std Steel (35 Ft) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	10000.00	7938.66	7900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 430

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-34120 Light Std Metal (12 Ft) Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	1500.00	1904.23	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			26.00	1500.00	1904.23	2000.00
	WEIGHTED AVERAGE FOR THE YEAR			26.00	1500.00	1904.23	2000.00
===== 613-34300 Light Std Metal (30 Ft) Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	1800.00	2812.50	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	1800.00	2812.50	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1800.00	2812.50	3000.00
===== 613-34302 Light Std Metal (30 Ft) (2) Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	1900.00	2990.43	3200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	1900.00	2990.43	3200.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	1900.00	2990.43	3200.00
===== 613-34303 Light Std Metal (30 Ft) (2) (Spec) Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	24.00	10000.00	11766.67	12300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	10000.00	11766.67	12300.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	10000.00	11766.67	12300.00
===== 613-34350 Light Std Metal (35 Ft) Each =====							
NHM765-007			03/31/22	46.00	4500.00	4913.42	4417.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			46.00	4500.00	4913.42	4417.50
	WEIGHTED AVERAGE FOR THE YEAR			46.00	4500.00	4913.42	4417.50
===== 613-34400 Light Std Metal (40 Ft) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	5000.00	6896.96	7000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	5000.00	6896.96	7000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 431

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-34400 Light Std Metal (40 Ft) Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	4200.00	4432.47	4100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	4200.00	4432.47	4100.00

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	2100.00	5106.39	5400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	2100.00	5106.39	5400.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	3256.67	5099.95	5136.67
===== 613-40000 Conc Foundation Pad Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5600.00	4075.79	3800.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2.00	3157.15	3275.52	3275.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	3971.43	3847.14	3450.35

2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	5000.00	361.65	425.48
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	6.00	3000.00	19875.00	19000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	2500.00	2483.33	700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	3300.00	8591.33	11625.10

NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	8000.00	4238.94	3700.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3500.00	6805.58	6200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	5000.00	6163.92	5366.67

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2800.00	600.82	800.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	700.00	1775.00	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 432

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-40000 Conc Foundation Pad Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	5176.58	3300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	2450.00	1549.76	1850.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	3485.72	5435.67	7505.10
===== 613-40010 Light Std Foundation Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	3000.00	4981.37	4500.00
NHPP0063-063			02/24/22	59.00	1700.00	1145.00	1200.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	32.00	624.49	620.17	620.17
NHM765-007			03/31/22	50.00	2500.00	5103.62	4588.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			147.00	1791.05	3242.24	2361.02
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1600.00	6013.88	6250.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	2470.58	2914.21
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	3000.00	4116.67	3850.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			42.00	2633.33	4742.30	4456.29
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	2500.00	2842.62	2500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	26.00	4000.00	7554.20	7000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			55.00	3209.09	5544.85	4627.27
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	30.00	2600.00	3878.84	4100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	2000.00	5624.61	5600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	56.00	6000.00	9344.75	9500.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	17.00	2500.00	2333.33	3100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			110.00	4277.27	6084.44	6790.00
	WEIGHTED AVERAGE FOR THE YEAR			354.00	2883.85	5031.56	4337.95
===== 613-40012 Light Std Foundation Spec Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	5000.00	1867.58	2195.47
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	5000.00	1867.58	2195.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 433

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-40012		Light Std Foundation Spec		Each	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	6000.00	8136.53	7600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	6000.00	8136.53	7600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	2200.00	3051.60	3500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		26.00	2200.00	3051.60	3500.00
		WEIGHTED AVERAGE FOR THE YEAR		41.00	3395.12	3231.92	3945.46
===== 613-40020		Transformer Base Alum		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	700.00	1200.00	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	700.00	1200.00	1100.00
STA3852-015 IM025A-050		US 385 HOLYOKE NORTH	10/27/22	2.00	2500.00	2000.00	2000.00
		I25-MP103.9 - INTERSECTION DR	12/01/22	13.00	700.00	933.33	1100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	940.00	985.37	1220.00
		WEIGHTED AVERAGE FOR THE YEAR		45.00	780.00	1132.82	1140.00
===== 613-50010		Photoel Cell		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	1136.85	1200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	1136.85	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1136.85	1200.00
===== 613-50100		Lighting Ctrl Center		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	12816.88	7300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 434

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-50100	Lighting Ctrl Center		Each	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	9000.00	12816.88	7300.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	9200.00	10730.04	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	9200.00	10730.04	11000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	12000.00	12268.64	11000.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	8500.00	21676.24	18500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	9666.67	19324.34	16000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	38000.00	46599.41	50000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	12700.99	20607.22	22341.37
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	25350.50	37935.35	36170.69
	WEIGHTED AVERAGE FOR THE YEAR			7.00	13985.86	23212.25	19805.91
=====	613-50105	Lighting Ctrl Center (Pedestal Only)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	25000.00	13888.92	14500.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	10000.00	12705.57	8500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	17500.00	13494.47	11500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17500.00	13494.47	11500.00
=====	613-50106	Light Cont Center (Spec)		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	12000.00	9900.00	7700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	12000.00	9900.00	7700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 435

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-50106		Light Cont Center (Spec)		Each	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	8000.00	16400.00	21200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	8000.00	16400.00	21200.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	10666.67	12066.67	12200.00
===== 613-50109		Meter Power Pedestal		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2.00	12480.61	14098.89	14098.89
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	12480.61	14098.89	14098.89
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	8000.00	10190.04	11000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4000.00	8116.62	9496.69
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	8000.00	11000.00	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	6857.14	9548.58	10570.48
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	7000.00	9126.02	7900.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	7000.00	9126.02	7900.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6000.00	12639.43	13702.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	6000.00	12639.43	13702.71
	WEIGHTED AVERAGE FOR THE YEAR			11.00	7814.66	10028.09	11253.99
===== 613-50132		2-Plex Recept. (W/Box & Cover)		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	12.00	838.78	824.34	824.34
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	838.78	824.34	824.34
	WEIGHTED AVERAGE FOR THE YEAR			12.00	838.78	824.34	824.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 436

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-50150 Secondary Serv Pedestal Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	4000.00	7853.75	6195.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12245.71	12200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	8875.00	9562.50	6625.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	6175.00	8829.83	7482.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	6175.00	8829.83	7482.00
===== 613-50210 Temporary Lighting LUMP SUM =====							
C0762-055			02/17/22	1.00	125000.00	58186.61	32000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	125000.00	58186.61	32000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	125000.00	58186.61	32000.00
===== 613-50350 Power Transformer LUMP SUM =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	6000.00	3633.33	2900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	6000.00	3633.33	2900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	6000.00	3633.33	2900.00
===== 613-50365 Transformer Base Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	400.00	445.21	500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15.00	400.00	445.21	500.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	400.00	445.21	500.00
===== 613-60700 Troubleshooting Hour =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	100.00	135.00	330.00	330.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	135.00	330.00	330.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	60.00	150.00	197.50	175.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	150.00	197.50	175.00
	WEIGHTED AVERAGE FOR THE YEAR			160.00	140.63	257.73	271.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 437

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-70400 Lumin HPS (400 W) Each =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	4.00	1500.00	5517.59	5500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1500.00	5517.59	5500.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1500.00	5517.59	5500.00
===== 613-80010 Ballast Un Each =====							
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5		03/11/22	2.00	2653.06	2798.39	2798.39
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2653.06	2798.39	2798.39
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2653.06	2798.39	2798.39
===== 613-80130 Service Meter Cabinet Each =====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	3.00	6500.00	11250.04	11000.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	3.00	4000.00	7957.00	6900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	5250.00	10309.17	8950.00
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	2.00	8000.00	8500.00	8500.00
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	1.00	1500.00	9576.80	8700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	5833.33	9146.08	8566.67
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	3.00	6000.00	12639.43	13702.71
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
NHPP0931-033	SH93:US6 TO 58TH RESURFACING		12/15/22	1.00	5000.00	11815.28	10100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	5750.00	12433.39	12802.03
	WEIGHTED AVERAGE FOR THE YEAR			13.00	5538.46	10784.84	10046.78
===== 613-81690 Safety Switch Each =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	2.00	5000.00	6663.87	4900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	5000.00	6663.87	4900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 438

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-81690	Safety Switch		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	980.00	641.00	423.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	980.00	641.00	423.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2320.00	3378.67	1915.33
=====	613-81699	Safe Switch NEMA 3R, 30A, 2-pole, 240 V		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	1000.00	1258.33	775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	1000.00	1258.33	775.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1000.00	1258.33	775.00
=====	613-81700	Safe Switch NEMA 3R 60A 2 Pole 240V		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	1000.00	1966.67	1400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	1966.67	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1966.67	1400.00
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	179.00	35.00	26.73	27.28
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	165.00	24.00	31.31	27.00
NHPP1601-083			02/03/22	44.00	32.00	90.53	25.00
C0762-055			02/17/22	324.00	35.00	24.58	30.00
NHPP0063-063			02/24/22	852.00	18.00	24.10	25.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	60.00	20.00	22.20	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	51.00	34.00	41.45	31.00
C0761-239							
NHPP0703-472			03/10/22	38.25	24.00	27.87	30.00
ER007A-035			03/15/22	695.00	28.56	30.65	30.65
NHM765-007			03/31/22	282.00	21.00	26.86	23.94
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,690.25	25.25	28.22	27.39
NH0504-911			04/07/22	25.38	23.21	25.05	25.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00011		Sign Panel (CL I)		Sq Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	36.00	23.54	23.54	23.54
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	66.00	25.00	22.75	21.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	171.00	26.00	26.03	30.11
STA0712-019		SH 71: Frieght Improvements	05/12/22	45.00	35.00	31.05	31.05
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	15.00	25.00	40.67	30.00
CM760-047		COLFAX AND QUAIL	05/12/22	52.00	26.00	39.00	30.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	549.00	28.00	26.00	27.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	9.00	33.00	30.00	21.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	773.00	24.00	29.00	29.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	75.40	30.00	26.17	25.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	427.00	50.00	30.17	37.33
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,243.78	30.60	27.86	29.72
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	17.00	27.29	27.29	27.29
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	650.00	22.00	28.55	31.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	28.00	28.00	68.33	50.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	545.00	30.00	43.50	52.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	421.00	25.00	24.77	24.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	90.00	50.00	37.99	34.24
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,751.00	26.80	33.19	36.29
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	689.00	35.00	23.00	24.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	208.00	23.00	58.19	27.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	170.00	24.00	28.15	28.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	120.00	30.00	27.00	27.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	145.00	50.00	29.08	30.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	15.00	50.00	25.40	25.00
C5502-097		US550 MP 117.28-126.06	11/17/22	263.00	35.00	28.18	25.90
MPR200-280		PUEBLO AREA	11/17/22	923.00	21.20	22.00	22.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	23.00	27.00	29.00	33.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	286.00	24.00	30.95	47.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	255.00	25.00	27.50	30.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	17.00	80.00	36.00	42.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	155.00	23.00	27.00	27.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	54.00	35.00	39.40	35.40
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	161.00	25.00	36.74	42.47
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	101.00	35.00	34.34	24.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00011							
		Sign Panel (CL I)		Sq Foot			
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	272.00	25.00	39.76	26.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	186.00	50.00	34.82	34.15
STR0092-024		SH 9 North of Silverthorne	12/22/22	21.00	50.00	28.50	27.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	63.00	50.00	32.64	42.90
STA385A-016		SH 385 MP 97.76	12/22/22	34.00	30.00	35.70	27.78
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	438.00	21.00	28.00	26.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,599.00	28.72	30.93	28.11
WEIGHTED AVERAGE FOR THE YEAR				11,284.03	27.97	30.13	29.53
===== 614-00012							
		Sign Panel (CL II)		Sq Foot			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	45.00	36.29	39.69
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	657.00	26.00	37.60	34.00
NHPP1601-083			02/03/22	241.00	20.00	49.72	29.00
STA0252-459			02/03/22	372.00	27.00	30.70	26.00
C0762-055			02/17/22	541.00	30.00	27.43	33.00
STR0141-031			02/17/22	61.25	28.00	31.00	30.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,220.71	25.00	28.68	30.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	248.00	36.00	43.35	33.00
C0761-239							
NHPP0703-472			03/10/22	70.00	26.00	33.05	35.00
ER007A-035			03/15/22	150.00	36.72	39.35	39.35
NHM765-007			03/31/22	361.00	23.00	32.52	28.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,161.96	27.82	34.07	31.63
NH0504-911			04/07/22	259.75	26.29	28.85	28.70
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,533.00	27.00	25.92	24.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	306.00	28.00	33.28	39.27
STA0712-019		SH 71: Frieght Improvements	05/12/22	142.00	30.00	34.16	34.16
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	287.00	27.00	47.00	34.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	498.00	30.00	31.50	33.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	715.00	27.00	35.04	35.04
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	122.00	32.00	36.24	27.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1,625.00	45.00	40.61	44.21
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5,487.75	32.81	31.97	34.17
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	39.00	32.74	32.74	32.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 441

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00012 Sign Panel (CL II) Sq Foot =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	60.00	35.00	29.05	28.41
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	105.00	25.00	33.18	37.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	126.00	35.00	48.00	61.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	9.00	40.00	31.48	31.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	96.00	40.00	43.84	41.73
WEIGHTED AVERAGE FOR THE THIRD QUARTER				435.00	33.59	40.24	43.30
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2,055.00	32.00	27.00	28.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	286.00	26.00	31.93	33.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	45.00	35.00	29.00	29.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	107.00	70.00	37.95	40.50
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	3.00	27.00	30.29	29.86
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	38.00	40.00	31.82	31.00
C5502-097		US550 MP 117.28-126.06	11/17/22	264.00	40.00	32.72	28.60
MPR200-280		PUEBLO AREA	11/17/22	5,086.00	26.20	28.00	28.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	37.00	35.00	34.50	37.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	501.00	27.00	37.20	54.29
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	132.00	27.00	29.25	32.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	380.00	30.00	32.00	35.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	178.00	60.00	33.06	34.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	294.00	28.00	29.33	30.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	160.00	40.00	46.84	43.40
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	286.00	30.00	47.86	43.72
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	140.00	40.00	40.88	28.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	767.00	40.00	43.60	36.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	55.00	39.05	36.99
STR0092-024		SH 9 North of Silverthorne	12/22/22	63.00	60.00	31.90	30.20
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	84.00	30.00	40.84	49.34
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	950.00	28.00	33.33	30.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				11,876.00	30.45	32.56	31.29
WEIGHTED AVERAGE FOR THE YEAR				21,960.71	30.60	32.92	32.31
===== 614-00013 Sign Panel (CL III) Sq Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,087.00	33.00	53.54	52.00
C0762-055			02/17/22	1,066.00	35.00	38.16	36.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	563.00	38.00	43.67	34.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 442

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00013 Sign Panel (CL III) Sq Foot =====							
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2,716.00	34.82	45.79	41.99
NH0504-911			04/07/22	212.75	36.11	48.75	47.50
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	132.00	43.00	35.81	33.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	506.00	32.00	34.49	40.50
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	120.00	36.00	59.33	45.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	3,534.00	45.00	41.69	50.38
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		4,504.75	42.82	40.27	48.48
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	66.00	43.66	43.66	43.66
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	64.00	30.00	40.45	45.00
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	448.00	40.00	41.00	42.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		578.00	39.31	41.07	42.52
C0831-126	SH83 EL PASO COUNTY TO BAYOU		10/13/22	96.00	45.00	38.50	42.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	253.00	33.00	42.79	45.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	220.00	38.00	60.30	62.43
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	862.00	70.00	43.09	41.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		1,431.00	56.86	45.09	45.00
	WEIGHTED AVERAGE FOR THE YEAR			9,229.75	42.42	43.60	45.65
===== 614-00025 Inst Sign Panel (CL I) Sq Foot =====							
MT CER300-262			02/03/22	30,695.00	13.00	13.08	8.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		30,695.00	13.00	13.08	8.00
	WEIGHTED AVERAGE FOR THE YEAR			30,695.00	13.00	13.08	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 443

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00027 Inst Sign Panel (CL II) Sq Foot =====							
MT CER300-262			02/03/22	16,711.00	17.00	16.00	10.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	24.00	24.00	15.00	13.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		16,735.00	17.01	16.00	10.00
	WEIGHTED AVERAGE FOR THE YEAR			16,735.00	17.01	16.00	10.00
===== 614-00028 Inst Sign Panel (CL III) Sq Foot =====							
MT CER300-262			02/03/22	13,703.00	28.00	20.92	15.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4,534.00	9.00	15.00	9.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		18,237.00	23.28	19.85	13.51
MPR200-280 PUEBLO AREA 11/17/22 2,565.00 16.50 17.00 19.00							
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		2,565.00	16.50	17.00	19.00
	WEIGHTED AVERAGE FOR THE YEAR			20,802.00	22.44	19.58	14.19
===== 614-00035 Sign Panel (Spec) Sq Foot =====							
CM760-047		COLFAX AND QUAIL	05/12/22	28.00	26.00	75.00	47.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		28.00	26.00	75.00	47.00
FSA052A-057 SH52 BOX CULVERT EXTENSION (M 08/04/22 18.00 50.00 766.78 2229.93							
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		18.00	50.00	766.78	2229.93
IM025A-050 I25-MP103.9 - INTERSECTION DR 12/01/22 8.00 30.00 30.67 34.00							
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		8.00	30.00	30.67	34.00
	WEIGHTED AVERAGE FOR THE YEAR			54.00	34.59	241.48	772.72

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 444

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00037 Sign Panel (Spec) Each =====							
CR100-362			03/14/22	10.00	107.00	107.00	107.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	107.00	107.00	107.00
C0852-120 Rehabilitation of Culvert by 05/26/22							
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	1300.00	240.00	240.00
				3.00	1300.00	240.00	240.00
TRG0253-264 I-25 AND SH 119 PARK-N-RIDE 10/27/22							
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	9475.00	13479.63	18125.00
				4.00	9475.00	13479.63	18125.00
	WEIGHTED AVERAGE FOR THE YEAR			17.00	2521.76	9625.29	4370.00
===== 614-00041 Signpost (Spec) Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	14.00	3500.00	4215.00	4101.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	3500.00	4215.00	4101.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	3500.00	4215.00	4101.00
===== 614-00044 Timber Signpost (4x4 In) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	50.00	37.24	41.89
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	50.00	37.24	41.89
	WEIGHTED AVERAGE FOR THE YEAR			11.00	50.00	37.24	41.89
===== 614-00200 Steel Signpost (U-2) Lin Foot =====							
STA0252-459			02/03/22	108.00	27.00	41.49	35.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			108.00	27.00	41.49	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 445

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00200		Steel Signpost (U-2)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	21.00	19.26	19.26	19.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21.00	19.26	19.26	19.26
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	35.00	9.50	5.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	35.00	9.50	5.00
		WEIGHTED AVERAGE FOR THE YEAR		135.00	26.15	39.11	31.22
===== 614-00216		Steel Signpost (2x2 In T)		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	16.00	30.86	24.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		240.00	16.00	30.86	24.80
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	112.00	20.00	45.28	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		112.00	20.00	45.28	22.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	206.00	50.00	44.50	52.00
C5502-097		US550 MP 117.28-126.06	11/17/22	20.00	50.00	16.23	13.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	190.00	30.00	19.54	13.02
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		416.00	40.87	30.13	32.32
		WEIGHTED AVERAGE FOR THE YEAR		768.00	30.05	33.23	28.47
===== 614-00220		Steel Signpost (2.5x2.5 In T)		Lin Foot	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	348.00	22.00	39.50	55.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		348.00	22.00	39.50	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 446

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00220 Steel Signpost (2.5x2.5 In T) Lin Foot =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	11.00	20.00	40.43	26.28
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11.00	20.00	40.43	26.28
		WEIGHTED AVERAGE FOR THE YEAR		359.00	21.94	39.54	54.12
===== 614-00612 Steel Signpost (W 6x12) Lin Foot =====							
MTCER300-262			02/03/22	50.00	60.00	106.67	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	60.00	106.67	60.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	30.00	60.03	60.03	60.03
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	70.00	97.21	121.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		62.00	65.18	85.34	91.50
===== 614-00615 Steel Signpost (W 6x15) Lin Foot =====							
C0762-055			02/17/22	32.00	85.00	128.82	200.00
NHPP0703-472			03/10/22	90.00	55.00	136.15	150.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	58.00	150.00	143.50	157.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		180.00	90.94	136.01	161.14
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	75.00	88.00	120.33	126.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		75.00	88.00	120.33	126.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 447

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00615 Steel Signpost (W 6x15) Lin Foot =====							
MPR200-280	PUEBLO AREA		11/17/22	32.00	98.00	97.50	120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			32.00	98.00	97.50	120.00
	WEIGHTED AVERAGE FOR THE YEAR			287.00	90.96	129.30	147.37
===== 614-00818 Steel Signpost (W 8x18) Lin Foot =====							
C0762-055			02/17/22	75.00	90.00	136.65	205.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	31.00	160.00	149.50	163.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			106.00	110.47	138.85	192.72
MPR200-280	PUEBLO AREA		11/17/22	176.00	125.00	122.50	120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			176.00	125.00	123.92	120.00
	WEIGHTED AVERAGE FOR THE YEAR			282.00	119.54	131.01	146.22
===== 614-00821 Steel Signpost (W 8x21) Lin Foot =====							
C0831-126	SH83 EL PASO COUNTY TO BAYOU		10/13/22	84.00	130.00	140.00	130.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	76.00	125.00	167.00	175.00
MPR200-280	PUEBLO AREA		11/17/22	62.00	138.00	125.00	120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			222.00	130.52	156.17	142.61
	WEIGHTED AVERAGE FOR THE YEAR			222.00	130.52	156.17	142.61
===== 614-01022 Steel Signpost (W 10x22) Lin Foot =====							
C0762-055			02/17/22	73.00	140.00	143.15	210.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			73.00	140.00	143.15	210.00
MPR200-280	PUEBLO AREA		11/17/22	124.00	148.00	150.00	140.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			124.00	148.00	150.00	140.00
	WEIGHTED AVERAGE FOR THE YEAR			197.00	145.04	146.29	165.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 448

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01026 Steel Signpost (W 10x26) Lin Foot =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	96.00	150.00	170.00	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	45.00	150.00	136.17	80.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		141.00	150.00	143.29	141.28

MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	41.00	85.00	108.25	133.49
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		41.00	85.00	108.25	133.49

2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	78.00	120.00	120.23	100.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		78.00	120.00	120.23	100.00
	WEIGHTED AVERAGE FOR THE YEAR			260.00	130.75	130.50	127.67
===== 614-01226 Steel Signpost (W 12x26) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	53.00	120.00	163.05	140.00
MTCER300-262			02/03/22	50.00	80.00	150.00	140.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	46.00	160.00	147.76	90.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		149.00	118.93	153.36	124.56

STM1151-038		SH115 MP 27 TO MP 38	04/21/22	93.00	190.00	130.58	120.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	56.00	184.00	172.67	158.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	257.99	105.00	107.45	127.89
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		406.99	135.29	126.34	130.23
	WEIGHTED AVERAGE FOR THE YEAR			555.99	130.91	137.29	128.71
===== 614-01401 Steel Sign Support Casting Each =====							
MTCER300-262			02/03/22	696.00	90.00	191.67	100.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		696.00	90.00	191.67	100.00
	WEIGHTED AVERAGE FOR THE YEAR			696.00	90.00	191.67	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 449

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01502 Steel Sign Supp (2-In Rd) (Po&Sock) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	30.00	36.04	40.00
C0761-239							
NHM765-007			03/31/22	223.00	25.00	39.60	31.92
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		243.00	25.41	38.91	32.59

NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	97.00	26.75	26.75	26.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		97.00	26.75	26.75	26.75

NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	72.00	25.00	29.80	19.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		72.00	25.00	53.05	20.05
		WEIGHTED AVERAGE FOR THE YEAR		412.00	25.65	42.63	28.25
===== 614-01503 Steel Sign Supp (2-In Rd) (Po&Sock) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	250.00	418.53	435.00
C0762-055			02/17/22	83.00	275.00	386.37	500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	27.00	30.00	283.43	290.00
NHPP0703-472			03/10/22	8.00	240.00	487.36	400.00
ER007A-035			03/15/22	127.00	433.50	463.85	463.85
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		270.00	321.70	398.93	453.01

NH0504-911			04/07/22	4.00	225.00	376.30	372.60
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	22.00	270.00	323.45	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	67.00	260.00	480.31	587.82
STA0712-019		SH 71: Frieight Improvements	05/12/22	5.00	300.00	491.65	491.65
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	63.00	280.00	398.93	360.86
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		161.00	269.57	436.86	451.35

NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	500.00	512.98	455.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	500.00	512.98	455.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 450

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01503 Steel Sign Supp (2-In Rd) (Po&Sock) Each =====							
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	67.00	500.00	295.00	290.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	18.00	250.00	361.85	360.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	12.00	450.00	300.00	300.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	5.00	290.00	342.80	310.00
MPR200-280		PUEBLO AREA	11/17/22	72.00	310.00	325.00	300.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	230.00	415.81	590.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	300.00	400.00	400.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	14.00	500.00	313.50	297.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	300.00	409.53	536.80
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	500.00	513.75	500.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	52.00	260.00	379.33	400.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				277.00	351.30	354.59	355.47
WEIGHTED AVERAGE FOR THE YEAR				740.00	329.15	397.42	416.22
===== 614-01512 Steel Sign Support (2-In Rd) (Post) Lin Foot =====							
MTCER300-262			02/03/22	4,856.00	18.00	19.33	12.00
NHPP1601-083			02/03/22	12.00	20.00	248.93	35.00
NHPP0063-063			02/24/22	615.00	12.00	13.35	14.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				5,483.00	17.33	19.22	12.27
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	26.00	25.00	43.90	22.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				26.00	25.00	43.90	22.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	40.00	13.10	13.10	13.10
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	22.00	15.00	16.56	12.84
WEIGHTED AVERAGE FOR THE THIRD QUARTER				62.00	13.77	15.76	13.01
C5502-097		US550 MP 117.28-126.06	11/17/22	514.00	20.00	16.94	15.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 451

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01512	Steel Sign Support (2-In Rd) (Post)		Lin Foot	=====	=====	=====
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	60.00	30.00	22.55	27.10
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	35.00	15.00	16.85	14.24
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		609.00	20.70	17.30	16.23
		WEIGHTED AVERAGE FOR THE YEAR		6,180.00	17.66	19.17	12.71
=====	614-01522	Steel Sign Supp (2-In Rd) (Sock)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	6.00	140.00	289.57	409.27
MTCER300-262			02/03/22	347.00	90.00	258.33	200.00
NHPP1601-083			02/03/22	51.00	60.00	189.31	160.00
NHPP0063-063			02/24/22	57.00	150.00	160.00	167.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		461.00	94.75	244.67	194.22
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	170.00	187.16	225.18
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	2.00	200.00	219.76	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	177.50	194.24	218.89
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4.00	300.14	300.14	300.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	60.00	444.47	460.92
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	150.00	139.06	133.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	202.57	251.64	298.74
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	11.00	200.00	160.00	160.00
C5502-097		US550 MP 117.28-126.06	11/17/22	50.00	300.00	190.99	178.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	300.00	186.50	290.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	26.00	140.00	206.67	300.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	15.00	200.00	396.37	258.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	200.00	363.47	355.66
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		110.00	235.82	239.59	225.96
		WEIGHTED AVERAGE FOR THE YEAR		587.00	123.78	242.39	201.93

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 452

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01554 Steel Signpost (4 In Rd) (Slip) Lin Foot =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	36.00	60.00	78.98	83.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	60.00	78.98	83.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	60.00	78.98	83.00
===== 614-01572 Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip) Lin Foot =====							
NHM765-007			03/31/22	336.00	45.00	54.43	43.32
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			336.00	45.00	54.43	43.32
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	42.00	40.00	68.33	80.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			42.00	40.00	68.33	80.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22		156.00	50.00	57.13	48.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			156.00	50.00	86.22	43.05
	WEIGHTED AVERAGE FOR THE YEAR			534.00	46.07	70.21	45.66
===== 614-01573 Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip) Each =====							
NHPP0702-383 C0762-055 STA 067A-048 ER007A-035	I-70 EB AUX FRISCO TO SILVERT		01/13/22	32.00	450.00	571.54	540.00
			02/17/22	19.00	425.00	599.27	800.00
	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	122.00	400.00	476.48	500.00
			03/15/22	18.00	637.50	682.15	682.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			191.00	433.25	522.04	553.71
NH0504-911			04/07/22	14.00	400.00	483.80	507.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 453

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01573		Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	135.00	450.00	483.79	475.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	14.00	500.00	776.29	776.29
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	115.00	475.00	690.67	602.34
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		278.00	460.34	538.36	544.49
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	700.00	546.92	708.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	58.00	550.00	745.54	757.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	49.00	550.00	712.21	467.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		109.00	552.75	722.90	625.74
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	137.00	600.00	532.50	515.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	450.00	836.50	575.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	28.00	500.00	575.28	600.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	650.00	600.00	600.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	450.00	485.80	450.00
MPR200-280		PUEBLO AREA	11/17/22	257.00	503.00	532.50	515.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	70.00	430.00	548.61	561.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	430.00	626.67	600.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	500.00	565.00	500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	7.00	1000.00	677.64	770.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	45.00	425.00	546.67	590.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	450.00	578.33	510.63
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	700.00	560.28	611.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	71.00	450.00	532.33	500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		641.00	509.42	548.04	532.03
		WEIGHTED AVERAGE FOR THE YEAR		1,219.00	490.16	554.08	546.65
===== 614-01575		Steel Sign Supp (2-1/2 In Rd NP40) (Po)		Lin Foot =====			
MT CER300-262			02/03/22	232.00	40.00	39.33	20.00
NHPP1601-083			02/03/22	120.00	20.00	57.12	40.00
STR0141-031			02/17/22	74.50	25.00	34.00	30.00
NHPP0063-063			02/24/22	264.00	25.00	22.05	23.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		690.50	29.17	35.75	25.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 454

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01575 Steel Sign Supp (2-1/2 In Rd NP40) (Po) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	310.00	20.00	33.00	36.66
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	57.00	28.00	51.00	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	182.00	25.00	35.00	40.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	11.00	20.00	41.33	46.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	89.00	30.00	61.28	28.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				649.00	23.48	38.80	36.69
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	52.00	30.56	30.56	30.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	95.00	35.00	48.98	31.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	31.00	25.00	31.91	31.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				178.00	31.96	41.08	30.87
C5502-097		US550 MP 117.28-126.06	11/17/22	232.00	40.00	26.64	23.80
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	58.00	32.00	27.45	39.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	241.00	30.00	32.34	31.29
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				531.00	34.59	30.09	28.96
WEIGHTED AVERAGE FOR THE YEAR				2,048.50	29.01	35.77	30.47
===== 614-01578 Steel Sign Supp (2-1/2 In Rd NP40) (Slip) Each =====							
MTCER300-262			02/03/22	252.00	350.00	325.00	325.00
NHPP1601-083			02/03/22	24.00	250.00	373.75	250.00
STR0141-031			02/17/22	6.00	450.00	307.67	330.00
NHPP0063-063			02/24/22	25.00	300.00	359.00	375.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				307.00	340.07	329.28	323.31
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	28.00	360.00	422.79	538.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 455

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01578		Steel Sign Supp (2-1/2 In Rd NP40) (Slip)		Each =====			
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	5.00	321.00	431.67	320.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	13.00	375.00	385.00	320.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	375.00	290.67	240.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6.00	500.00	386.91	275.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		53.00	376.13	413.20	428.60
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5.00	436.56	436.56	436.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	36.00	75.00	310.26	362.73
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		41.00	119.09	313.12	371.73
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8.00	350.00	260.00	260.00
C5502-097		US550 MP 117.28-126.06	11/17/22	21.00	400.00	471.97	486.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	400.00	337.50	395.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	24.00	350.00	591.13	675.78
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		58.00	372.41	527.98	525.51
		WEIGHTED AVERAGE FOR THE YEAR		459.00	328.58	366.17	365.34
===== 614-01582		Steel Sign Supp (2-1/2 In Rd) (Po&Slip)		Lin Foot =====			
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	102.00	500.00	71.00	79.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		102.00	500.00	71.00	79.00
		WEIGHTED AVERAGE FOR THE YEAR		102.00	500.00	71.00	79.00
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	550.00	674.50	635.00
STA0252-459			02/03/22	10.00	500.00	529.07	450.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	500.00	573.20	600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	25.00	600.00	673.00	400.00
C0761-239							
NHPP0703-472			03/10/22	3.00	480.00	709.47	615.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		65.00	556.77	661.49	514.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 456

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each	=====		
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	97.00	500.00	622.34	622.34
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			97.00	500.00	622.34	622.34
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	600.00	696.38	877.50
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	11.00	600.00	778.36	566.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			13.00	600.00	765.75	613.92
MPR200-280		PUEBLO AREA	11/17/22	35.00	570.00	600.00	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	540.00	731.01	839.02
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	11.00	700.00	812.15	890.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	525.00	418.33	640.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	5.00	550.00	1083.21	843.22
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	38.00	625.00	770.77	654.54
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	81.00	500.00	870.34	630.65
STR0092-024		SH 9 North of Silverthorne	12/22/22	10.00	900.00	740.50	701.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	10.00	580.00	657.33	600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			193.00	575.34	808.04	644.25
	WEIGHTED AVERAGE FOR THE YEAR			368.00	553.07	741.32	614.42
===== 614-01585		Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot	=====		
MTCER300-262			02/03/22	2,793.00	50.00	33.33	30.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,793.00	50.00	33.33	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	116.00	30.00	60.00	45.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			116.00	30.00	60.00	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 457

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01585 Steel Sign Supp (2-1/2 In Rd 80) (Post) Lin Foot =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	84.00	40.00	58.23	38.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		84.00	40.00	58.23	38.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	84.00	70.00	53.23	64.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		84.00	70.00	53.23	64.00
		WEIGHTED AVERAGE FOR THE YEAR		3,077.00	49.52	35.56	31.71
===== 614-01588 Steel Sign Supp (2-1/2 In Rd 80) (Slip) Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	386.00	430.67	317.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	386.00	430.67	317.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	700.00	605.30	800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	700.00	605.30	800.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	532.53	512.16	542.40
===== 614-03001 Conc Footing (Ty 1) Each =====							
MTCER300-262			02/03/22	2.00	1500.00	2250.00	1250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1500.00	2250.00	1250.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	2182.80	2182.80	2182.80
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2000.00	1886.29	1815.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	2091.40	1985.12	1998.90

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 458

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-03001 Conc Footing (Ty 1) Each =====							
MPR200-280	PUEBLO AREA		11/17/22	4.00	1850.00	1800.00	2200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1850.00	1800.00	2200.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	1876.56	1990.54	1929.56
===== 614-03002 Conc Footing (Ty 2) Each =====							
C0762-055			02/17/22	2.00	2400.00	3141.44	4000.00
NHPP0703-472			03/10/22	6.00	1200.00	2779.63	2000.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	4.00	2400.00	2766.00	2923.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	1800.00	2849.26	2641.00
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	4.00	2531.00	3633.33	4400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	2531.00	3633.33	4400.00
MPR200-280	PUEBLO AREA		11/17/22	2.00	2350.00	2220.00	2700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2350.00	2220.00	2700.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	2023.56	2972.33	3038.44
===== 614-03003 Conc Footing (Ty 3) Each =====							
C0762-055			02/17/22	4.00	2500.00	3401.63	4200.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	2.00	3200.00	2894.00	3132.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	2733.33	3300.10	3844.00
MPR200-280	PUEBLO AREA		11/17/22	10.00	2550.00	3000.00	3500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.00	2550.00	2791.99	3250.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2618.75	3003.71	3448.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 459

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-03004 Conc Footing (Ty 4) Each =====							
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	4.00	2500.00	3500.00	4000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	3000.00	3436.75	3600.00
MPR200-280		PUEBLO AREA	11/17/22	4.00	2650.00	3250.00	3500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	2716.67	3416.17	3700.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	2716.67	3416.17	3700.00
===== 614-03005 Conc Footing (Ty 5) Each =====							
C0762-055			02/17/22	4.00	3500.00	3755.08	4300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	3500.00	3755.08	4300.00
MPR200-280		PUEBLO AREA	11/17/22	6.00	3200.00	3550.00	3600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	3200.00	3550.00	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	3320.00	3667.19	3880.00
===== 614-03006 Conc Footing (Ty 6) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	6.00	4500.00	10825.00	10825.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	4500.00	3105.26	2300.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	4500.00	5210.64	8693.75
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	2.00	3500.00	7563.22	6626.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3500.00	7563.22	6626.43
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	4000.00	7812.80	21200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	4000.00	7812.80	21200.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	4214.29	6546.59	11971.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 460

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-03007 Conc Footing (Ty 7) Each =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	2.00	4000.00	6524.02	5200.00
MTCER300-262			02/03/22	2.00	5000.00	4166.67	4500.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	2.00	4500.00	3537.64	3300.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6.00	4500.00	4588.82	4333.33
=====							
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	8.00	4000.00	3580.89	3300.00
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	4.00	2608.00	4666.67	5000.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	12.00	3750.00	7715.76	5931.51
WEIGHTED AVERAGE FOR THE SECOND QUARTER				24.00	3643.00	5058.08	4899.09
WEIGHTED AVERAGE FOR THE YEAR				30.00	3814.40	4919.04	4785.94
===== 614-10050 Mod Overhead Sign Str Each =====							
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	4.00	7500.00	8764.50	8179.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4.00	7500.00	8764.50	8179.00
WEIGHTED AVERAGE FOR THE YEAR				4.00	7500.00	8764.50	8179.00
===== 614-10120 Var Mesg Sign Each =====							
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	1.00	5175.00	134000.00	127000.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	3.00	75000.00	85780.50	79856.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4.00	57543.75	101853.67	91642.00
WEIGHTED AVERAGE FOR THE YEAR				4.00	57543.75	101853.67	91642.00
===== 614-10127 Var Speed Limit Sign Each =====							
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	4.00	13655.00	27333.33	27000.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	14.00	16000.00	16095.50	14500.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				18.00	15478.89	19466.85	17277.78
WEIGHTED AVERAGE FOR THE YEAR				18.00	15478.89	19466.85	17277.78

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 461

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-10140 VMS LED (Double Faced) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	22.00	70000.00	96065.00	96065.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	70000.00	96065.00	96065.00
	WEIGHTED AVERAGE FOR THE YEAR			22.00	70000.00	96065.00	96065.00
===== 614-10142 Public Info Display Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	50000.00	44043.75	45000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	50000.00	44043.75	45000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	50000.00	44043.75	45000.00
===== 614-10145 VMS LED (Single Faced) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	50000.00	107210.00	107210.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	50000.00	107210.00	107210.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	50000.00	107210.00	107210.00
===== 614-10146 VMS (LED) (Ground Mounted) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	30000.00	58775.00	58775.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	30000.00	58775.00	58775.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	30000.00	58775.00	58775.00
===== 614-10147 VMS LED (Overhead) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	40000.00	70175.00	70175.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	40000.00	70175.00	70175.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	70000.00	88074.73	88250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	70000.00	88074.73	88250.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 462

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-10147 VMS LED (Overhead) Each =====							
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	100000.00	109913.49	119153.97
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	100000.00	109913.49	119153.97
	WEIGHTED AVERAGE FOR THE YEAR			6.00	55000.00	89286.74	81350.66
===== 614-10154 12 In Heated LED (Ball) (Red) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	400.00	687.50	875.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	400.00	687.50	875.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	400.00	687.50	875.00
===== 614-10160 Sig Head B-Plates Each =====							
STU0252-457 NHPP083A-046		I-25:ALAMEDA RIVER PH 2.0 SH83 RESURFACING STROH RD TO	11/03/22 12/08/22	15.00 53.00	300.00 275.00	397.93 283.41	398.00 264.81
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			68.00	280.51	317.54	294.19
	WEIGHTED AVERAGE FOR THE YEAR			68.00	280.51	317.54	294.19
===== 614-10240 LUS LED (Double Faced) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	88.00	4200.00	11960.00	11960.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			88.00	4200.00	11960.00	11960.00
	WEIGHTED AVERAGE FOR THE YEAR			88.00	4200.00	11960.00	11960.00
===== 614-10320 System Integration and Testing LUMP SUM =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.99	23073.08	25022.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 463

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-10320	System Integration and Testing		LUMP SUM	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.99	23073.08	25022.33
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.99	23073.08	25022.33
=====	614-30110	Btrfly Str		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	30000.00	50423.75	60366.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	44100.00	58000.00	59000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	37050.00	52949.17	59683.48
	WEIGHTED AVERAGE FOR THE YEAR			2.00	37050.00	52949.17	59683.48
=====	614-30205	VMS Butterfly Support (Roadside)		Each	=====		
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	30000.00	47887.00	45000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	30000.00	47887.00	45000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	30000.00	47887.00	45000.00
=====	614-31800	Monotube Overhead Sign Cant (18 In Dia)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	54018.81	47000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	30000.00	54018.81	47000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	30000.00	54018.81	47000.00
=====	614-32000	Monotube Overhead Sign Cant (20 In Dia)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	40000.00	58102.27	51000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	40000.00	58102.27	51000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	40000.00	58102.27	51000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 464

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-32400 Monotube Overhead Sign Cant (24 In Dia) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	55000.00	86362.57	83000.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2.00	55000.00	86362.57	83000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	44000.00	87546.92	90000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	42000.00	62327.86	72230.62
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	50000.00	74791.50	66290.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	15.00	40000.00	55451.50	52185.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		18.00	40888.89	61042.55	56183.09
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	45000.00	71995.22	78045.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	7500.00	72987.24	73000.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		2.00	26250.00	72546.34	75522.93
	WEIGHTED AVERAGE FOR THE YEAR			22.00	40840.91	66796.33	60379.16
===== 614-32900 Inst Monotube Overhead Sign Cant Each =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	5.00	11000.00	9832.00	11516.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		5.00	11000.00	9832.00	11516.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	11000.00	9832.00	11516.00
===== 614-42400 Monotube Overhead Sign Brdg (24 In Dia) Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	35000.00	151012.59	151000.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		1.00	35000.00	151012.59	151000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	35000.00	151012.59	151000.00
===== 614-70000 Prog Traf Sig Face Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	5500.00	5617.38	6616.53
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		3.00	5500.00	5617.38	6616.53
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5500.00	5617.38	6616.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 465

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70010 Mod Sig Face Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	400.00	575.00	650.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	400.00	575.00	650.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	400.00	575.00	650.00
===== 614-70024 1310nm SFP Optic Module Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	120.00	500.00	350.00	350.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	500.00	185.99	160.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			124.00	500.00	315.47	343.87
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	475.00	666.28	700.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	475.00	1033.33	600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	4.00	500.00	715.00	660.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	481.25	746.18	665.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	160.00	657.50	765.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	160.00	657.50	765.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	350.00	768.73	800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	350.00	768.73	800.00
	WEIGHTED AVERAGE FOR THE YEAR			148.00	487.30	500.95	402.77
===== 614-70026 CWDM Multiplexor Demultiplexor Module Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	20000.00	4080.38	4300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	20000.00	4080.38	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	20000.00	4080.38	4300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 466

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70028 CWD M SFP Optic Module Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	4.00	800.00	953.50	880.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	800.00	953.50	880.00

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	1100.00	1220.28	1300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1100.00	1220.28	1300.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	1000.00	1190.64	1160.00
===== 614-70030 Optical Attenuator Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	4.00	500.00	146.60	125.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	500.00	146.60	125.00

NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	164.00	916.67	650.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	175.00	179.00	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	171.33	495.14	326.67

C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	125.00	282.50	365.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	125.00	282.50	365.00

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	12.00	150.00	184.28	185.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	150.00	184.28	185.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	203.53	233.60	245.67
===== 614-70032 Optical Filter Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	12.00	750.00	596.00	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	750.00	596.00	550.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 467

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70032 Optical Filter Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	1000.00	405.51	425.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	1000.00	405.51	425.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	850.00	457.46	500.00
===== 614-70150 Ped Sig Face (16) (Countdown) Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	750.00	1175.86	900.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	650.00	511.70	603.53
CM760-047		COLFAX AND QUAIL	05/12/22	6.00	480.00	672.60	707.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	8.00	700.00	635.29	635.29
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26.00	633.85	605.93	659.99
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	700.00	982.42	850.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	36.00	700.00	702.00	825.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	800.00	716.49	564.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	716.00	732.76	786.24
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	24.00	500.00	878.75	890.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	700.00	766.45	800.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	700.00	989.48	990.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	610.00	1136.40	1221.33
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	750.00	1143.37	1086.74
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	700.00	577.44	690.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			57.00	604.91	868.20	926.04
	WEIGHTED AVERAGE FOR THE YEAR			133.00	652.33	777.17	821.47
===== 614-70200 Access Ped Sig Each =====							
CR100-362			03/14/22	37.00	2327.25	2327.25	2327.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			37.00	2327.25	2327.25	2327.25

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 468

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70200	Access	Ped Sig		Each	=====		
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	32.00	1400.00	1772.81	1772.81
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32.00	1400.00	1772.81	1772.81
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	2500.00	1279.50	1400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	2500.00	1279.50	1400.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	1750.00	3077.75	2855.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	1400.00	2013.11	1730.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	1575.00	2367.99	2292.75
	WEIGHTED AVERAGE FOR THE YEAR			88.00	1859.18	2147.79	2087.75
===== 614-70225	Traf	Sig Face (12-12)		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	750.00	705.67	550.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	750.00	705.67	550.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	750.00	705.67	550.00
===== 614-70324	Traf	Sig Face (8-8-8)		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	900.00	2100.02	2100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	900.00	2100.02	2100.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	900.00	2100.02	2100.00
===== 614-70336	Traf	Sig Face (12-12-12)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	1000.00	924.93	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 469

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70336 Traf Sig Face (12-12-12) Each =====							
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1000.00	924.93	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	34.00	900.00	688.58	809.06
CM760-047		COLFAX AND QUAIL	05/12/22	12.00	750.00	1141.80	1040.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	111.00	850.00	946.94	946.94
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			157.00	853.18	837.57	924.19
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16.00	800.00	1408.82	1225.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	64.00	900.00	937.50	1175.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24.00	1100.00	920.51	719.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			104.00	930.77	979.06	1077.46
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	65.00	650.00	1044.50	990.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	830.00	1130.70	1200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	12.00	1100.00	1797.38	1800.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	11.00	1100.00	865.50	990.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	18.00	850.00	1526.54	1668.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	15.00	1200.00	1560.56	1210.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	1000.00	977.63	846.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			134.00	847.09	1215.62	1169.57
	WEIGHTED AVERAGE FOR THE YEAR			399.00	872.83	1033.00	1044.81
===== 614-70448 Traf Sig Face (12-12-12-12) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	1100.00	838.63	987.11
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	920.00	1372.00	968.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	26.00	1050.00	1396.43	1396.43
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			40.00	1031.50	1189.98	1249.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 470

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70448 Traf Sig Face (12-12-12-12) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	33.00	1100.00	1125.00	1400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		33.00	1100.00	1125.00	1400.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	1200.00	1251.50	1035.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	1200.00	2207.03	2200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	11.00	1300.00	986.00	1040.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1050.00	1811.64	1966.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	950.00	1617.59	1535.17
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	3000.00	1456.11	1328.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		31.00	1309.68	1414.52	1330.61
		WEIGHTED AVERAGE FOR THE YEAR		104.00	1136.15	1251.69	1321.37
===== 614-70560 Traf Sig Face (12-12-12-12-12) Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	1800.00	2267.65	1760.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1800.00	2267.65	1760.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1800.00	2267.65	1760.00
===== 614-72740 Blank Out Sign(LED) (Sing Fac) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	10000.00	8531.00	10500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	10000.00	8531.00	10500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	6000.00	7206.50	8100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	7206.50	8100.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	8000.00	7868.75	9300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 471

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72765 Traf Sig (24x24 Blank Out LED Sign) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	7938.66	7900.00
===== 614-72830 Communications Cabinet Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	25000.00	27800.00	27800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	16000.00	16270.09	16000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	20500.00	17551.19	21900.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	15000.00	19321.19	20400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	15000.00	19321.19	20400.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	16833.33	18932.65	20900.00
===== 614-72831 Comm Cabinet (Type 1) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	25000.00	28900.00	28900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	25000.00	28900.00	28900.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	10200.00	21747.25	20405.08
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	10200.00	21747.25	20405.08
	WEIGHTED AVERAGE FOR THE YEAR			5.00	22040.00	24348.25	27201.02
===== 614-72832 Comm Cabinet (Type 2) Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	10000.00	22143.03	22250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10000.00	22143.03	22250.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 472

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72832 Comm Cabinet (Type 2) Each =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	12400.00	15868.76	15166.37
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	12400.00	15868.76	15166.37
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	15000.00	11812.70	12400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	14513.00	25278.85	27405.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	14756.50	16301.42	19902.71
		WEIGHTED AVERAGE FOR THE YEAR		5.00	12382.60	18211.33	19894.36
===== 614-72836 Conflict Monitor Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1100.00	1629.69	1921.86
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	1000.00	3416.18	3416.18
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1066.67	1767.12	2419.97
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	1000.00	1662.50	1325.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	1000.00	1662.50	1325.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	1040.00	1742.50	1981.98
===== 614-72854 Traf Ctrl Cabinet Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	26000.00	34710.36	32755.64
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	26000.00	34710.36	32755.64
		WEIGHTED AVERAGE FOR THE YEAR		1.00	26000.00	34710.36	32755.64
===== 614-72855 Traf Sig Ctrl Cabinet Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	25000.00	22233.52	26227.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 473

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72855 Traf Sig Ctrl Cabinet Each =====							
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	21500.00	24836.40	25413.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	20000.00	35180.56	35180.56
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4.00	22875.00	23675.82	28262.31
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	35000.00	21500.00	22000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	30000.00	42011.25	38780.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3.00	33333.33	33806.75	27593.33
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	21000.00	25766.25	26950.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	40000.00	32750.00	29500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	26680.00	46716.36	50640.43
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	35000.00	50416.72	40700.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	36236.89	33330.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				7.00	28525.71	34929.80	33574.35
WEIGHTED AVERAGE FOR THE YEAR				14.00	27941.43	30970.50	30774.98
===== 614-72860 Ped Push Button Each =====							
CR100-362			03/14/22	45.00	652.70	652.70	652.70
WEIGHTED AVERAGE FOR THE FIRST QUARTER				45.00	652.70	652.70	652.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5.00	1100.00	671.26	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	700.00	436.67	514.50
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	900.00	918.80	809.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	750.00	572.96	572.96
WEIGHTED AVERAGE FOR THE SECOND QUARTER				32.00	803.13	558.39	604.48
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	600.00	700.66	605.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 474

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72860 Ped Push Button Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	10.00	800.00	487.50	475.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	800.00	873.23	344.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				24.00	750.00	750.91	463.83
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	24.00	400.00	1371.25	1355.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	1000.00	1841.10	1925.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	700.00	555.44	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	550.00	604.71	655.35
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	12.00	800.00	358.82	289.20
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				61.00	636.07	1206.48	1077.18
WEIGHTED AVERAGE FOR THE YEAR				162.00	690.56	954.49	775.03
===== 614-72862 Ped Push Button (Spec) Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	8.00	1500.00	1921.38	1600.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8.00	1500.00	1921.38	1600.00
WEIGHTED AVERAGE FOR THE YEAR				8.00	1500.00	1921.38	1600.00
===== 614-72863 Ped Push Button Post Assem Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	2600.00	2310.20	2504.70
CR100-362			03/14/22	62.00	3397.25	3397.25	3397.25
NHM765-007			03/31/22	8.00	3500.00	3582.04	3220.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				78.00	3326.02	3140.04	3287.58
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	7.00	2000.00	1920.46	1850.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	2000.00	1458.29	1705.84
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	2300.00	2969.20	2787.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	21.00	2500.00	1252.60	1252.60
WEIGHTED AVERAGE FOR THE SECOND QUARTER				42.00	2278.57	1750.13	1606.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 475

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72863 Ped Push Button Post Assem Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2000.00	3503.28	3025.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	28.00	2500.00	2475.00	3350.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	1604.92	1335.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				34.00	2411.76	2275.37	3093.82
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	17.00	1000.00	1815.25	985.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3300.00	1279.42	1350.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2000.00	2207.04	2200.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	3300.00	3951.83	3703.65
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	16.00	1500.00	1613.81	1140.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				38.00	1444.74	1773.37	1266.90
WEIGHTED AVERAGE FOR THE YEAR				192.00	2562.65	2196.58	2485.54
===== 614-72864 Fire Preempt Unit Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	3000.00	11167.72	8100.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.00	3000.00	11167.72	8100.00
WEIGHTED AVERAGE FOR THE YEAR				1.00	3000.00	11167.72	8100.00
===== 614-72875 Loop Detect Wire Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	200.00	10.00	45.55	47.00
NHPP0063-063			02/24/22	1,000.00	4.50	11.25	12.00
NHPP0703-472			03/10/22	1,200.00	6.00	16.85	17.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,400.00	5.71	19.09	17.42
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,400.00	10.00	10.65	11.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	150.00	60.00	48.08	43.16
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,550.00	14.84	12.18	14.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 476

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72875 Loop Detect Wire Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5,447.00	15.00	13.97	12.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5,447.00	15.00	13.97	12.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		100.00	8.50	43.87	47.66
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		1,870.00	12.00	17.96	15.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING 12/15/22		598.00	20.00	9.76	8.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,568.00	13.73	17.06	15.05
	WEIGHTED AVERAGE FOR THE YEAR			11,965.00	12.84	15.58	14.02
===== 614-72884 Detect (Micro Wave) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	12000.00	13217.79	17300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	12000.00	13217.79	17300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	11000.00	8484.72	8900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	11000.00	8484.72	8900.00
	WEIGHTED AVERAGE FOR THE YEAR			13.00	11153.85	9408.24	10192.31
===== 614-72885 Detect (Spec) Each =====							
MP0503-098			03/24/22	38.00	14500.00	13045.50	12222.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			38.00	14500.00	13045.50	12222.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN 06/09/22		32.00	9000.00	10182.59	10182.59
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32.00	9000.00	10182.59	10182.59

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 477

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72885 Detect (Spec) Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	6.00	7000.00	16820.50	16100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	14500.00	15956.50	17100.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	9000.00	10937.86	10030.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			19.00	8947.37	13177.55	12691.05
	WEIGHTED AVERAGE FOR THE YEAR			89.00	11337.08	12589.36	11588.86
===== 614-72886 Intersection Detect Sys (Camera) Each =====							
NHPP0063-063			02/24/22	16.00	9000.00	11280.00	12000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	9000.00	11280.00	12000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	9000.00	13430.05	12890.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	9000.00	13430.05	12890.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12621.15	12000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	12621.15	12000.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	9047.62	12222.79	12169.52
===== 614-72887 Detect (Microwave Veh) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	17198.55	12800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	8000.00	17198.55	12800.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10500.00	11093.43	11500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 478

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72887		Detect (Microwave Veh)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	10000.00	12191.89	14332.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10250.00	11692.59	12916.38
CI2111-099		SH 121 NORTH SGA SIGNALS	08/25/22	31.00	15000.00	8700.00	8900.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			31.00	15000.00	8700.00	8900.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	12.00	7000.00	14467.76	13535.51
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	7000.00	14467.76	13535.51
	WEIGHTED AVERAGE FOR THE YEAR			46.00	12554.35	10979.36	10368.67
===== 614-72894		Emergency Telephone		Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	2000.00	8442.51	8900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	2000.00	8442.51	8900.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	2000.00	8442.51	8900.00
===== 614-72895		Vehicle Detect Sys (Single Camera)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	8500.00	7130.00	7130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	8500.00	7130.00	7130.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	8500.00	7130.00	7130.00
===== 614-73000		Piezo (Elec) (CL I) (11 Ft)		Each =====			
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	6000.00	11012.11	9874.22
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	6000.00	11012.11	9874.22
	WEIGHTED AVERAGE FOR THE YEAR			2.00	6000.00	11012.11	9874.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 479

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-73005 Piezo (Elec) (CL II) Each =====							
NHPP0703-472			03/10/22	6.00	4600.00	2763.30	2800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	4600.00	2763.30	2800.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	2.00	4350.00	4956.73	5361.93
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	4350.00	4956.73	5361.93
	WEIGHTED AVERAGE FOR THE YEAR			8.00	4537.50	3311.65	3440.48
===== 614-75868 Inst Fire Preempt Unit Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	1500.00	759.75	894.16
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	1500.00	759.75	894.16
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1500.00	759.75	894.16
===== 614-80000 Flash Beacon Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	6.00	750.00	1930.00	1930.00
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	3400.00	4124.60	5500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	1412.50	3526.07	2822.50
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	4698.00	2933.33	2300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	4698.00	2933.33	2300.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	3000.00	4130.00	2870.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 480

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80000		Flash Beacon		Each =====			
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	4000.00	4571.93	5130.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	570.00	4011.50	3990.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	2761.67	4181.85	3433.33
	WEIGHTED AVERAGE FOR THE YEAR			28.00	2929.43	3677.40	2935.00
===== 614-80001		Flash Beacon (Solar Pwred)		Each =====			
STA0252-459			02/03/22	2.00	3400.00	6680.67	9500.00
NHPP0703-472			03/10/22	6.00	3400.00	5600.29	5500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	3400.00	5816.37	6500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	4000.00	10961.23	9500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	4000.00	10961.23	9500.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	8000.00	5850.00	7500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	8000.00	5850.00	7500.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	4290.91	6105.93	6954.55
===== 614-80003		Rect Rapid Flash Beacon		Each =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		12.00	7000.00	12048.28	10400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	7000.00	12048.28	10400.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	10000.00	11227.89	11800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10000.00	11227.89	11800.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	7428.57	11720.12	10600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 481

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80312 Barricade (Ty 3 F-B) Each =====							
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	1.00	2200.00	3693.33	3700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	2200.00	3693.33	3700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2200.00	3693.33	3700.00
===== 614-80321 Barricade (Ty 3 M-A) Each =====							
CM760-047	COLFAX AND QUAIL		05/12/22	4.00	400.00	1169.60	563.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	400.00	1169.60	563.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	400.00	1169.60	563.00
===== 614-80385 Rumble Strip Lin Foot =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	1,120.00	3.50	7.08	1.67
STA0252-459			02/03/22	120,000.00	0.30	0.80	1.25
STR0141-031			02/17/22	27,000.00	0.50	0.45	0.35
ER007A-035			03/15/22	74,532.00	0.16	0.16	0.16
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	201,136.00	0.50	0.10	0.10
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			423,788.00	0.39	0.47	0.46
NH0504-911			04/07/22	267,040.00	0.32	0.22	0.13
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	116,100.00	0.25	0.25	0.12
STA0712-019	SH 71: Frieght Improvements		05/12/22	17,287.00	0.50	0.58	0.58
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	11,136.00	0.50	0.69	1.10
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV		06/23/22	12.00	5.00	604.00	450.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			411,575.00	0.31	0.27	0.19
NHPP0701-253	I-70 EAST OF DEBEQUE		10/27/22	50,104.00	0.50	0.30	0.25
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	13,199.00	0.50	0.54	0.55
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU		12/01/22	65,352.00	1.00	0.30	0.15
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C		12/22/22	13,585.00	0.50	1.49	3.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 482

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80385	Rumble Strip			Lin Foot			
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22		600.00	3.00	29.45	4.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			142,840.00	0.74	0.54	0.45
	WEIGHTED AVERAGE FOR THE YEAR			978,203.00	0.41	0.40	0.35
===== 614-80387	Rumble Strip (Grind)			Lin Foot			
NHPP1601-083		02/03/22		45.33	7.75	132.35	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.33	7.75	132.35	100.00
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22		82,155.00	1.00	0.22	0.23
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22		77,616.00	0.50	0.31	0.34
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			159,771.00	0.76	0.27	0.28
	WEIGHTED AVERAGE FOR THE YEAR			159,816.33	0.76	0.30	0.31
===== 614-80390	Rumble Strip (Grinding) (Asphalt) (Sin)			Lin Foot			
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22		15,133.00	0.50	0.65	0.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15,133.00	0.50	0.65	0.60
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22		1,422.00	0.50	4.13	3.89
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22		8,350.00	0.60	1.49	0.67
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22		21,100.00	0.40	0.70	0.61
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			30,872.00	0.46	0.98	0.78
	WEIGHTED AVERAGE FOR THE YEAR			46,005.00	0.47	0.90	0.72
===== 614-80391	Rumble Strip (Grind) (Asphalt)			Lin Foot			
NHPP1601-083		02/03/22		79,044.00	0.60	0.18	0.14

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 483

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-80391	Rumble Strip (Grind) (Asphalt)		Lin Foot	=====		
C0762-055			02/17/22	48,190.00	0.25	0.24	0.20
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			127,234.00	0.47	0.21	0.16
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	98,368.00	0.15	0.17	0.17
C5502-097		US550 MP 117.28-126.06	11/17/22	49,588.00	0.50	0.26	0.35
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	98,419.00	0.30	0.17	0.14
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			246,375.00	0.28	0.20	0.19
	WEIGHTED AVERAGE FOR THE YEAR			373,609.00	0.34	0.20	0.18
=====	614-80392	Rumble Strip (Grind) (Conc)		Lin Foot	=====		
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	95,694.00	0.80	0.94	0.78
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			95,694.00	0.80	0.94	0.78
	WEIGHTED AVERAGE FOR THE YEAR			95,694.00	0.80	0.94	0.78
=====	614-81000	Sig-Light Pole Steel		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	12000.00	7162.33	7000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	12000.00	7162.33	7000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	12000.00	7162.33	7000.00
=====	614-81020	Sig-Light Pole Steel (2)		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	32000.00	50286.61	59154.67
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	32000.00	50286.61	59154.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	40000.00	64789.56	56000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	40000.00	64789.56	56000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	36000.00	53912.34	57577.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 484

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81125 Sig-Light Pole Steel (1-25 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	17000.00	26646.28	31363.69
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	17000.00	26646.28	31363.69
	WEIGHTED AVERAGE FOR THE YEAR			1.00	17000.00	26646.28	31363.69
===== 614-81130 Sig-Light Pole Steel (1-30 Ft) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	23000.00	22055.00	22110.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	23000.00	22055.00	22110.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	23000.00	22055.00	22110.00
===== 614-81135 Sig-Light Pole Steel (1-35 Ft) Each =====							
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	17000.00	41053.99	41053.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	17000.00	41053.99	41053.99
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	27000.00	22235.00	22470.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	27000.00	22235.00	22470.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	24500.00	24923.43	27116.00
===== 614-81140 Sig-Light Pole Steel (1-40 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	18000.00	29475.28	34719.09
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	13500.00	29266.19	26640.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	16500.00	29413.78	32026.38
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	23955.00	23910.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	30000.00	23955.00	23910.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 485

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81140 Sig-Light Pole Steel (1-40 Ft) Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	25000.00	28630.86	25740.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	20000.00	25518.82	22920.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	22500.00	27074.84	24330.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	20750.00	28316.41	28108.19
===== 614-81145 Sig-Light Pole Steel (1-45 Ft) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	22000.00	29369.83	30000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	22000.00	29369.83	30000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	20200.00	29865.00	27453.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20200.00	29865.00	27453.00
STAM420-001 BR2854-148 STM0091-046 NHPP0931-033		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	19450.00	35712.51	38725.04
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	25000.00	25939.66	23150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	22225.00	30826.08	30937.52
	WEIGHTED AVERAGE FOR THE YEAR			4.00	21662.50	30042.49	29832.01
===== 614-81150 Sig-Light Pole Steel (1-50 Ft) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	34000.00	25975.00	25950.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	34000.00	25975.00	25950.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	25000.00	25243.75	23900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 486

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81150	Sig-Light Pole Steel (1-50 Ft)		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	30000.00	38921.35	40500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	33000.00	25450.00	25900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	29333.33	29848.78	30100.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	30500.00	29144.46	29062.50
=====	614-81155	Sig-Light Pole Steel (1-55 Ft)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	22000.00	31288.38	33000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	3.00	20000.00	45548.95	45548.95
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	21142.86	32872.89	38378.12
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	35000.00	26410.00	25820.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	35000.00	26410.00	25820.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	40000.00	53031.99	55200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	35000.00	26850.00	26700.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	28000.00	30128.27	26620.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	35750.00	41033.75	40930.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	27166.67	34946.17	38182.24
=====	614-81160	Sig-Light Pole Steel (1-60 Ft)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	25000.00	45998.86	54192.93
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	24500.00	48616.60	43328.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	24750.00	47188.74	48760.47
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	37000.00	38415.00	38830.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	37000.00	38415.00	38830.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 487

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81160 Sig-Light Pole Steel (1-60 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	28000.00	50557.71	54810.82
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	44867.14	40620.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	31500.00	47712.42	47715.41
	WEIGHTED AVERAGE FOR THE YEAR			7.00	31928.57	45250.62	44205.96
===== 614-81165 Sig-Light Pole Steel (1-65 Ft) Each =====							
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	22500.00	48901.20	43453.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	22500.00	48901.20	43453.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	40000.00	39150.00	39300.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	26000.00	42469.26	38000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9.00	33777.78	41493.00	38722.22
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	60421.52	63000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	40000.00	35670.00	36400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	46000.00	51102.90	55406.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	30000.00	46461.43	41140.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	42000.00	49196.15	48748.87
	WEIGHTED AVERAGE FOR THE YEAR			16.00	36156.25	44806.46	42777.89
===== 614-81170 Sig-Light Pole Steel (1-70 Ft) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	42000.00	43282.50	43565.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	42000.00	43282.50	43565.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 488

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81170		Sig-Light Pole Steel (1-70 Ft)		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA 10/27/22		9.00	40000.00	39385.75	34400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	40000.00	39385.75	34400.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	40200.00	39590.84	35316.50
===== 614-81175		Sig-Light Pole Steel (1-75 Ft)		Each	=====		
STRC090-011		US 50B AND SH71/CR18 INTERSEC 11/17/22		1.00	45000.00	40065.00	41050.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	45000.00	40065.00	41050.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	40065.00	41050.00
===== 614-81255		Sig-Light Pole Steel (2-55 Ft)		Each	=====		
CI211-099		SH 121 NORTH SGA SIGNALS 08/25/22		1.00	45000.00	61225.00	62450.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	45000.00	61225.00	62450.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	61225.00	62450.00
===== 614-81570		Sig-Light Pole Steel (2-70&75 Ft)		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA 10/27/22		1.00	70000.00	66742.50	51700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	70000.00	66742.50	51700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	70000.00	66742.50	51700.00
===== 614-84000		Traf Sig Ped Pole Steel		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN 05/05/22		2.00	2600.00	2945.64	3464.06
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	2600.00	2945.64	3464.06
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		4.00	3000.00	5066.72	4400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 489

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-84000	Traf Sig Ped Pole Steel		Each =====			
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	4.00	2000.00	3400.00	3800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	2500.00	4233.36	4100.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	6.00	1400.00	3527.75	2910.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	3000.00	3719.98	3900.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	2400.00	3001.58	3336.31
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	2448.88	1900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	2160.00	3385.73	3182.77
		WEIGHTED AVERAGE FOR THE YEAR		25.00	2304.00	3468.54	3498.79
=====	614-84100	Traf Sig Ped Pole Alum		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	3000.00	1922.82	1900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	3000.00	1922.82	1900.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	3000.00	1922.82	1900.00
=====	614-85001	Impact Atten		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	30000.00	42494.82	48000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	22000.00	36252.14	39000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	24285.71	37500.68	41571.43
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	45000.00	45848.12	42650.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	5000.00	29691.68	26300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	42000.00	45694.23	53888.45
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	34250.00	39610.43	41372.11
		WEIGHTED AVERAGE FOR THE YEAR		11.00	27909.09	37936.02	41498.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 490

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-85003 Impact Atten (LM) Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	32000.00	36668.33	44000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	32000.00	36668.33	44000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	32000.00	36668.33	44000.00
===== 614-86007 Serial to IP Converter Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	1500.00	3246.88	3900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	3246.88	3900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	3246.88	3900.00
===== 614-86105 Telemetry (Field) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	3800.00	6364.72	6005.19
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3800.00	6364.72	6005.19
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.00	5196.00	2933.33	2800.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	5196.00	2933.33	2800.00
STU0252-457 STAM420-001 BR2854-148 STM0091-046		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	4000.00	8543.93	8500.00
		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	5570.00	12094.24	13106.94
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	4942.00	10910.80	11264.16
	WEIGHTED AVERAGE FOR THE YEAR			9.00	4899.78	8008.17	7858.45
===== 614-86106 Telemetry (Field) (Install Only) Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3000.00	4757.88	3080.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	3000.00	4757.88	3080.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	4757.88	3080.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 491

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-86248 Traf Ctrler (Type 2070LC) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	6800.00	6669.34	6294.01
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	6800.00	6669.34	6294.01
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	7000.00	5706.91	6716.02
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	6300.00	4902.40	4443.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	8000.00	6532.67	6532.67
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		4.00	7075.00	5529.31	6101.93
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	5000.00	5600.00	5200.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		2.00	5000.00	5600.00	5200.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	6500.00	5740.50	5175.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5300.00	6297.50	5995.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	5340.00	7388.12	8102.48
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		5.00	6028.00	6168.53	5924.50
	WEIGHTED AVERAGE FOR THE YEAR			12.00	6270.00	5900.87	5893.68
===== 614-86250 Ctrler (Ramp Metering) Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	12000.00	7498.20	7900.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	12000.00	7498.20	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	12000.00	7498.20	7900.00
===== 614-86741 Weather Monitor System Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	60000.00	62703.86	68000.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1.00	60000.00	62703.86	68000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	60000.00	62703.86	68000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 492

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-86752 Fold-Over Tower (ITS) Each =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	15900.00	29626.92	28690.23
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	15900.00	29626.92	28690.23
	WEIGHTED AVERAGE FOR THE YEAR			2.00	15900.00	29626.92	28690.23
===== 614-86800 Uninterrupted Power Supply Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	26000.00	10076.25	9508.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	26000.00	10076.25	9508.00
2670703-479 CM760-047		I-70 BRIDGE OVER HARLAN COLFAX AND QUAIL	05/05/22 05/12/22	2.00 1.00	7500.00 7100.00	6924.03 14011.80	8156.11 14059.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	7366.67	9008.67	10123.74
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	7000.00	6900.00	6800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	7000.00	6900.00	6800.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	8000.00	14598.74	15300.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	11000.00	6285.00	6470.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	7040.00	9234.24	10008.94
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	10000.00	8796.09	8160.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	8505.00	13372.82	12642.37
	WEIGHTED AVERAGE FOR THE YEAR			14.00	9295.71	11862.58	11044.15
===== 614-87006 Fiber Optic Term Panel (6 Fiber) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	12.00	800.00	830.00	830.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	800.00	830.00	830.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 493

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87006 Fiber Optic Term Panel (6 Fiber) Each =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	950.00	2250.00	1750.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	750.00	715.00	660.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	883.33	1866.25	1386.67

FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	600.00	903.75	825.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	600.00	903.75	825.00
		WEIGHTED AVERAGE FOR THE YEAR		23.00	815.22	1408.64	1047.39
===== 614-87010 Fiber Optic Cable (S Mode) (12 Fiber) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,800.00	10.00	6.43	6.50
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	225.00	20.00	9.56	8.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,025.00	10.74	6.79	6.61

STM1151-038		SH115 MP 27 TO MP 38	04/21/22	675.00	7.00	6.39	6.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,185.00	10.00	7.82	9.20
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	12,585.00	5.00	7.00	6.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	445.00	5.00	8.50	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,890.00	5.49	7.10	6.37

C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	70.00	10.00	12.50	15.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,280.00	7.40	11.90	11.36
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,350.00	7.53	11.91	11.55

TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,880.00	8.00	8.97	9.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 494

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87010		Fiber Optic Cable (S Mode) (12 Fiber)		Lin Foot			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	350.00	20.00	7.80	7.70
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,230.00	9.30	8.89	9.30
	WEIGHTED AVERAGE FOR THE YEAR			22,495.00	6.87	7.94	7.14
===== 614-87012		Fiber Optic Term Panel (12 Fiber)		Each			
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	1400.00	1851.66	1600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1400.00	1851.66	1600.00
2670703-479 CM760-047		I-70 BRIDGE OVER HARLAN COLFAX AND QUAIL	05/05/22 05/12/22	2.00 1.00	1100.00 1200.00	1731.61 1334.20	2046.23 1075.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	1133.33	1614.72	1722.49
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	1600.00	1072.50	1145.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	1600.00	1072.50	1145.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1333.33	1605.30	1509.58
===== 614-87015		Buffer Tube Fan Out Kit		Each			
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	200.00	221.75	190.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	200.00	221.75	190.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	450.00	714.29	380.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	450.00	714.29	380.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	200.00	607.50	715.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	200.00	607.50	715.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 495

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87015		Buffer Tube Fan Out Kit		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	200.00	380.00	490.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	200.00	380.00	490.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	293.75	513.10	467.50
===== 614-87024		Fiber Optic Term Panel (24 Fiber)		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	1020.00	2161.13	1720.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	1020.00	2161.13	1720.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1020.00	2161.13	1720.00
===== 614-87100		Auto Traf Rec Sta		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	15000.00	34779.66	35500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	34779.66	35500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	34779.66	35500.00
===== 614-87320		CCTV		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	63.00	4000.00	4435.00	4435.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7664.06	5900.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			64.00	4062.50	4798.84	4457.89
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	5000.00	6075.38	5700.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	5000.00	4978.05	5863.75
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	5000.00	6607.00	7500.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	5000.00	6952.21	6952.21
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	5000.00	5685.88	6234.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 496

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87320	CCTV			Each	=====		
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	5500.00	10436.94	10543.30
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5500.00	10436.94	10543.30
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	5000.00	3091.12	3300.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6500.00	5831.15	5810.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	5166.67	3289.67	3578.89
	WEIGHTED AVERAGE FOR THE YEAR			84.00	4309.52	4659.24	4647.64
===== 614-87321	CCTV (Inst)			Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	950.00	3640.00	3220.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	950.00	3640.00	3220.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	950.00	3640.00	3220.00
===== 614-87325	CCTV Pole			Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	6700.00	51362.00	56000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	6700.00	51362.00	56000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	6700.00	51362.00	56000.00
===== 614-87333	CCTV Camera (Traf Surveil)			Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	45.00	8000.00	7680.00	7680.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	8000.00	7680.00	7680.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	7500.00	6417.60	5531.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	7500.00	6417.60	5531.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 497

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87333 CCTV Camera (Traf Surveil) Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	6500.00	5700.00	5400.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	6000.00	13319.82	12161.93
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	6357.14	10144.90	7331.98
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	7500.00	6284.39	6700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	5500.00	10533.41	10600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	6833.33	6955.29	8000.00
	WEIGHTED AVERAGE FOR THE YEAR			56.00	7723.21	8100.17	7615.27
===== 614-87350 Test Fiber Optic Cable LUMP SUM =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	20000.00	19400.00	19400.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	18394.36	6200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	5000.00	3436.99	6100.00
C0761-239							
NHM765-007			03/31/22	1.00	10000.00	27895.58	25080.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	10000.00	13091.44	14195.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	23545.98	22500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	10000.00	10761.18	12683.20
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	12280.00	23666.67	16000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	7500.00	5335.00	4500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	9945.00	16497.94	13920.80
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	15279.60	15279.60	15279.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	6000.00	4000.00	5000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	10000.00	17374.29	15505.99
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	10426.53	14489.96	11928.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 498

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87350 Test Fiber Optic Cable LUMP SUM =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	12500.00	9963.90	10600.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	8000.00	13777.30	13700.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	13000.00	10272.91	10300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	11166.67	10775.48	11533.33
	WEIGHTED AVERAGE FOR THE YEAR			14.00	10325.69	13624.22	13060.63
===== 614-87364 CCTV Pole w Low Dev (50 Ft) Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	30000.00	28817.79	28900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	30000.00	28817.79	28900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	30000.00	28817.79	28900.00
===== 614-87400 Brkaway Taper ITS Pole Steel (30 Ft) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7076.32	8300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	8000.00	7076.32	8300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	8000.00	7076.32	8300.00
===== 614-87401 Fiber Optic Cable (Spec) Lin Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	22,000.00	4.80	4.80	4.80
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			22,000.00	4.80	4.80	4.80
	WEIGHTED AVERAGE FOR THE YEAR			22,000.00	4.80	4.80	4.80
===== 614-87402 Brkaway Taper ITS Pole Steel (40 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	6000.00	13930.83	16396.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 499

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87402	Brkaway Taper ITS Pole Steel (40 Ft)		Each =====			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS 06/02/22		2.00	7000.00	11235.00	8035.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	6666.67	12852.50	10822.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	6666.67	12852.50	10822.00
=====	614-87404	Brkaway Taper Pole Steel (50 Ft)		Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		2.00	15000.00	9321.45	9800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	15000.00	9321.45	9800.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	15000.00	9321.45	9800.00
=====	614-87424	Fiber Optic Cable (S Mode) (24 S)		Lin Foot =====			
NHM765-007		03/31/22		430.00	20.00	11.41	10.26
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			430.00	20.00	11.41	10.26
	WEIGHTED AVERAGE FOR THE YEAR			430.00	20.00	11.41	10.26
=====	614-87425	Fiber Optic Cable (M Mode) (24 S)		Lin Foot =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT 01/06/22		10,835.00	8.00	4.00	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,835.00	8.00	4.00	4.00
	WEIGHTED AVERAGE FOR THE YEAR			10,835.00	8.00	4.00	4.00
=====	614-87448	Fiber Optic Cable (S Mode) (48 S)		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT 01/13/22		2,200.00	5.00	7.01	7.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,200.00	5.00	7.01	7.00
	WEIGHTED AVERAGE FOR THE YEAR			2,200.00	5.00	7.01	7.00
=====	614-87495	Fiber Optic Cable (S Mode) (96 S) (Inst)		Lin Foot =====			
NHM765-007		03/31/22		8,000.00	1.00	6.35	5.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,000.00	1.00	6.35	5.70
	WEIGHTED AVERAGE FOR THE YEAR			8,000.00	1.00	6.35	5.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 500

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87496 Fiber Optic Cable (S Mode) (96 S) Lin Foot =====							
NHM765-007			03/31/22	1,500.00	50.00	10.80	9.69
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,500.00	50.00	10.80	9.69
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	31,205.00	4.50	5.41	5.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			31,205.00	4.50	5.41	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	750.00	10.00	13.18	13.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,100.00	15.00	7.81	7.90
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,850.00	12.97	9.37	9.97
	WEIGHTED AVERAGE FOR THE YEAR			34,555.00	6.93	5.74	5.47
===== 614-87498 Fiber Optic Cable (S Mode) (144 S) Lin Foot =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,300.00	3.06	3.06	3.06
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,734.00	4.60	14.82	14.77
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7,034.00	3.44	11.24	5.95
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,500.00	16.00	7.83	8.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,500.00	16.00	7.83	8.00
	WEIGHTED AVERAGE FOR THE YEAR			8,534.00	5.65	10.22	6.31
===== 614-87506 Splice FO Cable (6 S) Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	1000.00	1411.25	825.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1000.00	1411.25	825.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	1411.25	825.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 501

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87512 Splice FO Cable (12 S) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2493.28	2200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	2600.00	1472.25	1250.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	2200.00	2039.49	1883.33

C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	2000.00	950.00	1100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	2000.00	950.00	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	2120.00	1841.40	1570.00
===== 614-87524 Splice FO Cable (24 Strand) Each =====							
NHM765-007			03/31/22	16.00	4000.00	3550.34	3192.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	4000.00	3550.34	3192.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	4000.00	3550.34	3192.00
===== 614-87548 Splice FO Cable (48 Strand) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	5383.77	4300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	5383.77	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	5383.77	4300.00
===== 614-87612 Term FO Cable (12 S) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2263.15	2100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2000.00	2263.15	2100.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	2263.15	2100.00
===== 614-87624 Term FO Cable (24 Strand) Each =====							
NHM765-007			03/31/22	3.00	4000.00	9192.86	8265.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	4000.00	9192.86	8265.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	4000.00	9192.86	8265.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 502

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87648 Term FO Cable (48 Strand) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	3000.00	4459.50	3500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3000.00	4459.50	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	4459.50	3500.00
===== 614-87650 Fiber Optic Cable (S Mode) (216 S) Lin Foot =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,986.00	9.00	14.89	14.77
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,986.00	9.00	14.89	14.77
	WEIGHTED AVERAGE FOR THE YEAR			1,986.00	9.00	14.89	14.77
===== 614-87690 Ethernet Switch Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	5000.00	7840.84	7398.93
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	7840.84	7398.93
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5000.00	6850.60	6125.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	6850.60	6125.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	7000.00	9552.50	9700.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	4900.00	12136.27	11531.53
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	6300.00	11196.72	10310.51
	WEIGHTED AVERAGE FOR THE YEAR			5.00	5780.00	9439.01	8891.09
===== 614-87691 Ethernet Switch Type I Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	11.00	5500.00	4260.00	4260.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	5500.00	4260.00	4260.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 503

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87691 Ethernet Switch Type I Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	3500.00	6236.84	6500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	10000.00	6665.50	5445.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	8375.00	6470.65	5708.75
	WEIGHTED AVERAGE FOR THE YEAR			15.00	6266.67	5365.33	4646.33
===== 614-87692 Ethernet Switch Type II Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	36.00	6000.00	3475.00	3475.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7080.85	6400.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			37.00	6054.05	4130.61	3554.05
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	7500.00	6336.84	6500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4800.00	7028.08	8266.08
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	5100.00	7466.67	5400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	5800.00	6875.19	6722.03
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	5000.00	13276.47	14000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	5000.00	13276.47	14000.00
	WEIGHTED AVERAGE FOR THE YEAR			48.00	5912.50	8083.13	5038.17
===== 614-87693 Ethernet Switch Type III Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	5000.00	9184.25	7700.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	6600.00	8200.00	10000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	5400.00	9043.64	8275.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	5400.00	9043.64	8275.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 504

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87698 Ethernet Agg Switch Type II Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	3.00	15000.00	9985.00	9985.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	15000.00	9985.00	9985.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	15000.00	9985.00	9985.00
===== 614-87700 Ethernet Router Each =====							
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	3800.00	3030.40	2988.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3800.00	3030.40	2988.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3800.00	3030.40	2988.00
===== 614-87704 Ethernet Radio (Single Client) Each =====							
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2700.00	4968.00	3648.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2700.00	4968.00	3648.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2700.00	4968.00	3648.00
===== 614-87708 Cellular Modem (CDMA) Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	5000.00	5277.00	6500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	5277.00	6500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5000.00	2987.50	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	2987.50	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	4132.25	3850.00
===== 615-00030 Emb Prot Ty 3 Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2100.00	4233.41	3600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 505

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	615-00030	Emb Prot Ty 3		Each =====			
NHPP1601-083			02/03/22	2.00	2250.00	7789.16	5200.00
C0762-055			02/17/22	9.00	1750.00	2126.08	2800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	2400.00	2215.25	2200.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	2020.59	2558.50	2952.94
<hr/>							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	14.00	4000.00	1589.92	1331.35
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	4000.00	1589.92	1331.35
<hr/>							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	1675.54	2271.46	2271.46
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	3000.00	3351.00	1890.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	2006.66	2811.23	2176.10
<hr/>							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	3000.00	1889.25	1650.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	1800.00	4996.67	990.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2700.00	2823.74	1788.00
		WEIGHTED AVERAGE FOR THE YEAR		39.00	2799.40	2228.18	2162.08
<hr/>							
=====	615-00050	Emb Prot Ty 5		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	2500.00	3710.71	4600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	2800.00	3952.54	1400.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	2560.00	3779.80	3960.00
<hr/>							
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	6.00	3000.00	5608.33	2500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	3.00	4000.00	1087.67	1700.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	3333.33	4101.44	2233.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 506

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	615-00050	Emb Prot Ty 5		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1627.00	3358.97	4217.79
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	3000.00	2225.00	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2313.50	2872.98	3608.90
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2964.19	3817.49	2944.86
=====	615-00150	Emb Prot (Spec)		Each	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	6.00	3600.00	6744.60	7700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	3600.00	6744.60	7700.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	3600.00	6744.60	7700.00
=====	615-00600	Log Dam		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	818.55	818.55	818.55
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	818.55	818.55	818.55
	WEIGHTED AVERAGE FOR THE YEAR			8.00	818.55	818.55	818.55
=====	615-20804	8 In Sl Hdgate (4 Ft)		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	500.00	6162.88	8200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	500.00	6162.88	8200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	500.00	6162.88	8200.00
=====	615-20899	8 In Sl Hdgate Spec		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	6.00	500.00	1976.22	2080.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	500.00	1976.22	2080.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	500.00	1976.22	2080.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 507

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 615-21203 12 In Sl Hdgate (3 Ft) Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	500.00	6754.65	9010.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	500.00	6754.65	9010.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	500.00	6754.65	9010.00
===== 615-21503 15 In Sl Hdgate (3 Ft) Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	500.00	6926.09	9290.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	500.00	6926.09	9290.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	500.00	6926.09	9290.00
===== 615-21803 18 In Sl Hdgate (3 Ft) Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3.00	4000.00	2942.34	2600.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	4000.00	2942.34	2600.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	7253.42	9590.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	7253.42	9590.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	5500.00	3558.21	4347.50
===== 615-22404 24 In Sl Hdgate (4 Ft) Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3.00	5000.00	3824.38	3300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	5000.00	3824.38	3300.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5000.00	3824.38	3300.00
===== 615-52412 24x12 In Parshall Flume Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	12000.00	10696.61	9135.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	12000.00	10696.61	9135.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	12000.00	10696.61	9135.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 616-23180 18 In Plastic Siphon Pipe Lin Foot =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	112.00	100.00	190.00	173.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			112.00	100.00	190.00	173.00
	WEIGHTED AVERAGE FOR THE YEAR			112.00	100.00	190.00	173.00
===== 616-30018 18 In Trash Guard Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	5139.76	6100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2000.00	5139.76	6100.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	5139.76	6100.00
===== 616-30499 Trash Guard Spec Each =====							
FSA052A-057		SH52 BOX CULVERT EXTENSION (M 08/04/22		1.00	3000.00	4511.11	3577.60
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		1.00	1000.00	4395.75	6400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	2000.00	4434.20	4988.80
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	4434.20	4988.80
===== 618-00003 Prestress Steel M Kip Foot =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 07/08/22		3,872.00	77.42	77.42	77.42
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,872.00	77.42	77.42	77.42
	WEIGHTED AVERAGE FOR THE YEAR			3,872.00	77.42	77.42	77.42
===== 618-01137 Prestress Concrete I (CBT 37.5) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK 03/10/22		2,614.00	320.00	428.80	395.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,614.00	320.00	428.80	395.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 509

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 618-01137		Prestress Concrete I (CBT 37.5)		Lin Foot	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,936.00	420.00	416.87	380.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,936.00	420.00	416.87	380.00
	WEIGHTED AVERAGE FOR THE YEAR			5,550.00	372.90	423.88	387.06
===== 618-01145		Prestress Conc I (CBT45)		Lin Foot	=====		
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	408.00	350.00	873.50	1120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			408.00	350.00	873.50	1120.00
	WEIGHTED AVERAGE FOR THE YEAR			408.00	350.00	873.50	1120.00
===== 618-01154		Prestress Conc I (CBT54)		Lin Foot	=====		
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,390.00	380.00	469.94	466.06
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,390.00	380.00	469.94	466.06
	WEIGHTED AVERAGE FOR THE YEAR			1,390.00	380.00	469.94	466.06
===== 618-01163		Prestress Conc I (CBT63)		Lin Foot	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	875.00	425.00	464.30	550.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			875.00	425.00	464.30	550.00
STAM420-001 BR2854-148 STM0091-046 IM025A-050		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	995.00	600.00	548.90	500.00
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		I25-MP103.9 - INTERSECTION DR	12/01/22	1,346.00	350.00	515.00	440.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,341.00	456.26	542.53	513.00
	WEIGHTED AVERAGE FOR THE YEAR			3,216.00	447.75	527.98	518.40

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 510

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 618-01992 Prestress Conc Box (Depth Less Than 32") Sq Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17,820.00	80.00	96.36	80.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17,820.00	80.00	96.36	80.00
=====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	12,993.00	110.00	96.38	89.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12,993.00	110.00	96.38	89.00
		WEIGHTED AVERAGE FOR THE YEAR		30,813.00	92.65	96.36	83.80
===== 618-10372 Precast Concrete U Girder (U72) (Curved) Lin Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,626.00	1363.39	1363.39	1363.39
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,626.00	1363.39	1363.39	1363.39
		WEIGHTED AVERAGE FOR THE YEAR		1,626.00	1363.39	1363.39	1363.39
===== 619-00007 Connect To Existing Waterline Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		19.00	2500.00	3464.75	3000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		19.00	2500.00	3464.75	3000.00
=====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	4000.00	4642.89	2700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	4000.00	4642.89	2700.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	2575.00	3669.64	2985.00
===== 619-06060 6 In Duct Iron Pipe Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	25.00	640.00	263.20	134.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		25.00	640.00	263.20	134.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	640.00	263.20	134.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 511

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-30320 4 In Galv Pipe Lin Foot =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	33.00	300.00	386.01	210.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	9.00	350.00	391.67	400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			42.00	310.71	386.97	250.71
	WEIGHTED AVERAGE FOR THE YEAR			42.00	310.71	386.97	250.71
===== 619-30480 6 In Galv Pipe Lin Foot =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	15.00	400.00	529.81	238.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15.00	400.00	529.81	238.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	400.00	529.81	238.00
===== 619-40060 3/4 In Copper Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		560.00	100.00	111.82	97.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			560.00	100.00	111.82	97.00
	WEIGHTED AVERAGE FOR THE YEAR			560.00	100.00	111.82	97.00
===== 619-50100 1-1/4 In Plastic Pipe Lin Foot =====							
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	866.00	50.00	70.00	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			866.00	50.00	70.00	100.00
	WEIGHTED AVERAGE FOR THE YEAR			866.00	50.00	70.00	100.00
===== 619-50235 3 In Plastic Pipe (Spec) Lin Foot =====							
NH0504-911			04/07/22	40.00	30.00	76.60	33.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			40.00	30.00	76.60	33.20
	WEIGHTED AVERAGE FOR THE YEAR			40.00	30.00	76.60	33.20

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 512

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-50320 4 In Plastic Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		619.00	60.00	297.46	257.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			619.00	60.00	297.46	257.00
	WEIGHTED AVERAGE FOR THE YEAR			619.00	60.00	297.46	257.00
===== 619-50480 6 In Plastic Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		646.00	80.00	149.93	165.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			646.00	80.00	149.93	165.00
C5502-111 US 550 MP 81 AND 89 RED MOUNT 10/27/22 24.00 100.00 127.50 200.00							
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	100.00	127.50	200.00
	WEIGHTED AVERAGE FOR THE YEAR			670.00	80.72	149.13	166.25
===== 619-50640 8 In Plastic Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3,083.00	100.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,083.00	100.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE YEAR			3,083.00	100.00	294.05	255.00
===== 619-50800 10 In Plastic Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2,436.00	120.00	276.09	240.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,436.00	120.00	276.09	240.00
TRG0253-264 I-25 AND SH 119 PARK-N-RIDE 10/27/22 45.00 200.00 199.09 165.00							
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			45.00	200.00	199.09	165.00
	WEIGHTED AVERAGE FOR THE YEAR			2,481.00	121.45	270.79	238.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 513

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-51200 15 In Plastic Pipe Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		453.00	270.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			453.00	270.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE YEAR			453.00	270.00	294.05	255.00
===== 619-71516 2 In Air and Vacuum Valve Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		4.00	2000.00	6567.10	5700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	2000.00	6567.10	5700.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	2000.00	6567.10	5700.00
===== 619-75048 6 In Gate Valve Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	1100.00	2326.10	2010.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	1100.00	2326.10	2010.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		1.00	1040.00	3281.40	2850.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	1040.00	3281.40	2850.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1090.00	2750.68	2150.00
===== 619-75064 8 In Gate Valve Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	1300.00	4051.06	3500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	1300.00	4051.06	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	1300.00	4051.06	3500.00
===== 619-75080 10 In Gate Valve Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		10.00	1600.00	5796.31	5000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			10.00	1600.00	5796.31	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	1600.00	5796.31	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 514

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-75116		16 In Gate Valve		Each =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	4000.00	20906.78	18000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	4000.00	20906.78	18000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	20906.78	18000.00
===== 619-77210		Restrained Plug (Spec)		Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		1.00	4300.00	3484.26	5400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4300.00	3484.26	5400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4300.00	3484.26	5400.00
===== 619-78036		4-1/2 In Fire Hydrant		Each =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		8.00	3500.00	8176.13	6300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	3500.00	8176.13	6300.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	3500.00	8176.13	6300.00
===== 619-78048		6 In Fire Hydrant		Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		1.00	14000.00	10844.10	10000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	14000.00	10844.10	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	14000.00	10844.10	10000.00
===== 620-00001		Field Office (CL 1)		Each =====			
STR R500-171		Various locations on SH 141 a 03/17/22		1.00	22000.00	26705.59	25000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	22000.00	26705.59	25000.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU 10/13/22		1.00	24000.00	21250.00	20500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 515

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00001 Field Office (CL 1) Each =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	23400.00	61024.40	41000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	25000.00	32750.00	35500.00
CL70A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	30000.00	19512.50	17500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	36500.00	42697.61	18000.00
NHMI75-029		CANON CITY, CO	12/15/22	1.00	25000.00	31500.00	30000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				6.00	27316.67	36885.45	27083.33
WEIGHTED AVERAGE FOR THE YEAR				7.00	26557.14	35431.18	26785.71
===== 620-00002 Field Office (CL 2) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	34000.00	55339.61	66548.99
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	30000.00	26746.98	25000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	30000.00	165227.43	110000.00
NHPP1601-083			02/03/22	1.00	60000.00	44551.88	48000.00
STA0252-459			02/03/22	1.00	28000.00	69230.00	68000.00
C0762-055			02/17/22	1.00	25000.00	28626.00	50000.00
STR0141-031			02/17/22	1.00	30000.00	36666.67	16000.00
NHPP0063-063			02/24/22	1.00	35000.00	32790.00	44000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	30000.00	29874.04	31092.95
NHPP0703-472			03/10/22	1.00	28000.00	33934.57	35000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	50000.00	29154.19	24308.38
BRC040-057			03/17/22	1.00	25000.00	36893.25	40000.00
STR092A-031			03/17/22	1.00	40000.00	40000.00	40000.00
NHM765-007			03/31/22	1.00	40000.00	125944.44	64410.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				14.00	34642.86	56196.34	47311.45
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	30000.00	103706.90	88888.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	1.00	30000.00	40697.08	40697.08
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	40000.00	29576.40	35000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	29727.00	76666.67	95000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	27000.00	22771.60	10608.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	30000.00	37000.00	34000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	35000.00	39115.80	26540.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				7.00	31675.29	53557.45	47247.58
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	30000.00	163718.09	116000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00002		Field Office (CL 2)		Each =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	28000.00	41333.33	39000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	36250.00	40000.00	35000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	25000.00	13877.42	16132.26
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	10613.03	15493.60	15493.60
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	25000.00	31316.27	31348.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	60000.00	67827.81	34500.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	60000.00	110682.70	70804.77
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	40000.00	55772.98	28500.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	50000.00	41673.32	25000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	34134.19	63462.16	38843.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	45000.00	15333.33	1000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	45000.00	36215.00	50000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	30000.00	55500.00	52500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	35000.00	115778.03	500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	50000.00	25000.00	25000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	35000.00	44176.17	36528.52
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	45000.00	40495.00	55000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	35000.00	39557.43	34738.15
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	46000.00	112019.67	106382.08
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	33100.00	45000.00	55000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	50000.00	69500.00	52000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	51536.00	46072.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	35000.00	146666.67	90000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	50000.00	36850.00	17700.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	45000.00	33066.78	32907.15
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	45000.00	43090.41	41000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	40000.00	52439.95	33111.94
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	45000.00	33825.00	20650.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	30000.00	30478.84	30000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	25000.00	39812.50	31250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	36500.00	45333.33	58000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	40504.76	61042.50	42632.17
		WEIGHTED AVERAGE FOR THE YEAR		53.00	36467.98	59217.09	43652.84
===== 620-00005		Field Office (Spec)		Each =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	250000.00	311126.84	433500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 517

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00005 Field Office (Spec) Each =====							
C0761-239							
ER007A-035			03/15/22	1.00	25000.00	15000.00	15000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	137500.00	278223.86	224250.00
NH0504-911			04/07/22	1.00	25000.00	28000.00	41000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	30000.00	249721.63	173530.63
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	55000.00	80000.00	80000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	50000.00	50345.07	50345.07
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	40000.00	168467.49	86218.93
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	50000.00	110329.69	90000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	80000.00	185748.59	103000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	50000.00	51544.76	48089.51
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	50000.00	47444.34	29500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	57500.00	110899.92	67647.38
	WEIGHTED AVERAGE FOR THE YEAR			10.00	66500.00	173978.44	106396.52
===== 620-00011 Field Lab (CL 1) Each =====							
STR0505-050			01/13/22	1.00	25000.00	21666.67	30000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	25000.00	21666.67	30000.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	24300.00	49024.46	46000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	35000.00	46201.85	37403.70
NHM175-029		CANON CITY, CO	12/15/22	1.00	25000.00	27500.00	30000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	28100.00	42937.69	37801.23
	WEIGHTED AVERAGE FOR THE YEAR			4.00	27325.00	37136.50	35850.93
===== 620-00012 Field Lab (CL 2) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	32000.00	51471.36	54885.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 518

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00012 Field Lab (CL 2) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	25000.00	24650.93	22500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	123198.38	55000.00
NHPP1601-083			02/03/22	1.00	60000.00	43159.36	44000.00
STA0252-459			02/03/22	1.00	26000.00	51141.67	61225.00
C0762-055			02/17/22	1.00	20000.00	37578.37	65000.00
STR0141-031			02/17/22	1.00	30000.00	35666.67	19000.00
STR133A-051			02/17/22	1.00	25000.00	19333.33	28000.00
NHPP0063-063			02/24/22	1.00	25000.00	30445.00	41000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	25000.00	26021.60	28092.95
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	120000.00	90294.77	80000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	26000.00	26484.79	25000.00
ER007A-035			03/15/22	1.00	13000.00	5000.00	5000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	55000.00	33513.08	35026.16
BRC040-057			03/17/22	1.00	25000.00	50043.25	100000.00
STR092A-031			03/17/22	1.00	30000.00	55000.00	55000.00
NHM765-007			03/31/22	1.00	40000.00	85118.49	69008.76
WEIGHTED AVERAGE FOR THE FIRST QUARTER				17.00	35411.76	52065.81	46337.56
NH0504-911			04/07/22	1.00	20000.00	29500.00	51000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	70638.19	70638.19	70638.19
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	25000.00	75867.57	74618.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	26000.00	68869.62	46274.84
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	25000.00	33200.25	33200.25
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	25662.00	76666.67	85000.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	30000.00	41000.00	37000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	25000.00	29203.95	29203.95
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	30000.00	27816.00	24150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				9.00	30811.13	55218.38	50120.58
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	105930.00	105930.00	105930.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	25000.00	76797.40	114000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	6420.00	8800.75	8800.75
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	60000.00	38455.88	32200.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	60000.00	79352.41	44526.76
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	35000.00	46640.69	26000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				7.00	42681.43	58466.90	48608.32

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00012		Field Lab (CL 2)		Each =====			
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	45000.00	16333.33	1000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	45000.00	30290.00	40000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	28000.00	49733.33	48200.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	30000.00	77979.89	45000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	60000.00	34000.00	34000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	50703.46	56000.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	1.00	30000.00	42085.31	40255.92
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	50000.00	39425.00	55000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	30000.00	42470.00	20000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	49000.00	93303.78	73215.34
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	26400.00	43666.67	51000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	55000.00	61612.28	96800.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	60000.00	43000.00	42000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	30000.00	121666.67	60000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	50000.00	38620.00	16240.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	40000.00	26031.92	25526.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	45000.00	44769.77	41000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	26000.00	34866.50	29600.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	40000.00	50346.29	29733.17
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	45000.00	30975.00	18950.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	20401.12	5.58
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	25000.00	29205.45	30000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	20000.00	38562.50	31250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	28200.00	43666.67	54000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24.00	41150.00	49252.47	39782.85
		WEIGHTED AVERAGE FOR THE YEAR		57.00	37994.21	51839.56	44220.32
===== 620-00020		Sanitary Facility		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	2500.00	69425.00	69425.00
MTCE R500-218			01/06/22	1.00	2000.00	2250.00	1000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	2400.00	4216.39	3578.45
STR0505-050			01/13/22	1.00	3000.00	2666.67	5000.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	3000.00	2636.54	3125.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	1500.00	3000.00	1000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	3000.00	11655.66	4300.00
NHPP1601-083			02/03/22	2.00	4000.00	7956.30	8300.00
STA0252-459			02/03/22	1.00	2500.00	12696.67	14000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each =====			
C0762-055			02/17/22	2.00	2500.00	3812.29	1200.00
STR0141-031			02/17/22	1.00	3000.00	8666.67	15000.00
STR133A-051			02/17/22	1.00	2000.00	2933.33	5000.00
NHPP0063-063			02/24/22	1.00	2700.00	30485.00	50000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	2500.00	5110.45	6000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	5000.00	11698.04	7000.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2400.00	2639.04	2400.00
ER007A-035			03/15/22	1.00	2465.00	2933.00	2933.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	2500.00	7119.71	8839.41
BRC040-057			03/17/22	2.00	3000.00	2732.00	2400.00
STR R500-171		Various locations on SH 141 a	03/17/22	2.00	3500.00	2610.26	3000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	2000.00	1500.00	1566.00
STR092A-031			03/17/22	1.00	2500.00	8000.00	8000.00
NHM765-007			03/31/22	1.00	7500.00	13026.98	5739.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	5000.00	3340.00	4500.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				34.00	3007.79	6501.63	7979.71
NH0504-911			04/07/22	2.00	5000.00	3750.00	3500.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	4815.00	4815.00	4815.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	2700.00	3663.56	2100.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	2500.00	1071.03	842.06
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3200.00	10892.29	4049.05
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	2250.00	1000.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	2.00	3000.00	2210.41	2210.41
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	3000.00	8889.00	9000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	3356.00	5666.67	8000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5600.00	9065.00	875.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	2000.00	8450.00	5400.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	2500.00	1731.95	1568.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	5000.00	230.00	230.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	7000.00	7500.00	7500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	2000.00	3559.00	3500.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	2000.00	873.33	650.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	3000.00	2539.47	2539.47
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	2.00	3000.00	2029.00	2300.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2.00	1350.00	3474.50	5000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				36.00	3181.31	4180.49	3137.71
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	2000.00	1500.00	1500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4815.00	4815.00	4815.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	2500.00	1666.67	1500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	3000.00	34210.85	51000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	2400.00	2833.33	3800.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	6000.00	4225.00	3950.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	4000.00	1242.43	1152.30
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	738.30	505.04	505.04
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	1600.00	1890.00	1890.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	1500.00	3564.80	2094.40
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	1.00	4170.00	3325.00	1850.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5000.00	3925.00	200.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3000.00	5297.22	2875.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	3000.00	11047.14	2385.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	3500.00	3734.78	1800.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	4000.00	2188.55	2000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				21.00	2974.36	5259.59	4485.10
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	2000.00	1509.56	1500.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	3000.00	4166.67	500.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	2300.00	5000.00	7500.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	5000.00	7505.00	2500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	3350.00	6260.13	8780.40
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	3500.00	7191.60	11000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	1000.00	5375.00	3000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	2000.00	3750.00	5000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	3300.00	1896.25	3125.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2500.00	7672.41	5000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	20000.00	34000.00	34000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	3200.00	2646.05	1500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	4000.00	12492.13	6500.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	3500.00	3795.18	2385.54
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	5000.00	6390.00	1500.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	8000.00	3899.05	3215.25
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	3500.00	6634.33	5400.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	2000.00	1725.00	1950.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1200.99	8801.76	12067.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2.00	3000.00	7166.67	7000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	8000.00	7000.00	9000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	4000.00	11446.60	19000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	3065.00	3630.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00020		Sanitary Facility		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	3500.00	5166.67	2500.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	5000.00	7220.00	11040.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	3000.00	10369.00	3052.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	2.00	3500.00	1999.21	2003.69
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2.00	3000.00	4733.33	1300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	3000.00	5436.57	2673.13
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	4000.00	5572.88	6000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	3000.00	2051.20	500.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	2500.00	748.85	1000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	5147.24	6150.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	3000.00	7391.53	2229.98
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	5000.00	8245.00	8490.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	5000.00	2726.60	558.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	4000.00	8866.98	5000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	3000.00	3581.25	3125.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	3200.00	11009.08	9000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			55.00	3937.31	6205.07	5675.73
	WEIGHTED AVERAGE FOR THE YEAR			146.00	3395.93	5674.51	5420.45
===== 621-00411		Str Temp Acc Rd (Loc 1)		LUMP SUM	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	150000.00	115424.99	142300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	150000.00	115424.99	142300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	150000.00	115424.99	142300.00
===== 621-00412		Str Temp Acc Rd (Loc 2)		LUMP SUM	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	50000.00	69104.07	55400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	50000.00	69104.07	55400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	50000.00	69104.07	55400.00
===== 621-00450		Detour Pvmt		Sq Yard	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,560.00	50.00	167.19	177.00
C0762-055			02/17/22	6,006.00	100.00	95.95	100.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8,810.00	62.00	63.85	58.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 523

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 621-00450	Detour Pvmt			Sq Yard	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		16,376.00	74.79	79.26	84.74
NH0504-911			04/07/22	1,440.00	57.30	78.00	36.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	1,841.00	47.86	47.86	47.86
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	7,800.00	50.00	63.43	53.48
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	702.00	70.00	155.01	250.00
STA0712-019	SH 71: Frieght Improvements		05/12/22	529.00	80.00	72.53	72.53
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		12,312.00	52.96	71.76	62.62
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	33,467.00	90.07	90.07	90.07
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	1,600.00	200.00	144.23	108.00
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	100.00	100.00	225.00	250.00
2670403-065	US40 FLOYD HILL ROUNDABOUTS		09/15/22	5,240.00	80.00	85.97	109.00
2670703-497	I-70_GENESEE WILDLIFE XING		09/15/22	11,032.00	57.00	70.12	62.48
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		51,439.00	85.39	79.25	86.95
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	9,943.00	75.00	98.50	78.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	1,800.00	65.00	103.51	116.38
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	11,760.00	80.00	84.59	80.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	7,070.00	60.00	78.33	72.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		30,573.00	72.87	91.25	79.64
	WEIGHTED AVERAGE FOR THE YEAR			110,700.00	76.76	82.91	81.90
===== 621-00451	Detour Pavement			Ton	=====		
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	372.00	200.00	348.68	339.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		372.00	200.00	348.68	339.00
	WEIGHTED AVERAGE FOR THE YEAR			372.00	200.00	348.68	339.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 524

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 621-00650 Ped Stair Str LUMP SUM =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	30000.00	11071.88	6500.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	30000.00	11071.88	6500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	30000.00	11071.88	6500.00
===== 622-00000 Sewage Pumping Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	70574.30	55287.70
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	70574.30	55287.70
===== 622-00010 Bicycle Rack Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	1700.00	1018.35	750.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		11.00	1700.00	1018.35	750.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	1700.00	1018.35	750.00
===== 622-00100 Shade Shelter Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	37450.00	48772.72	75000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		2.00	37450.00	48772.72	75000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	37450.00	48772.72	75000.00
===== 622-00155 Planter Box (Spec) Each =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	26.00	2731.73	2127.31	2127.31
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		26.00	2731.73	2127.31	2127.31
		WEIGHTED AVERAGE FOR THE YEAR		26.00	2731.73	2127.31	2127.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 525

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 622-00200 Table Each =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	2736.32	2736.32	2736.32
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	2736.32	2736.32	2736.32
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2736.32	2736.32	2736.32
===== 622-00250 Bench Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000.00	3204.80	3300.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	3204.80	3300.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	2000.00	2813.41	2500.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		3.00	2000.00	2813.41	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2000.00	2880.89	2700.00
===== 622-00251 Inst Bench Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	4556.67	3600.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	4556.67	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	4556.67	3600.00
===== 622-00270 Bollard Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	29.00	545.00	1022.23	900.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	11.00	2000.00	2125.37	3200.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		40.00	945.13	1159.60	1532.50
		WEIGHTED AVERAGE FOR THE YEAR		40.00	945.13	1159.60	1532.50
===== 622-00350 Trash Receptacle Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	1800.00	2571.04	2500.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		7.00	1800.00	2571.04	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1800.00	2571.04	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 526

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 622-20080 Flagpole Each =====							
NHM765-007			03/31/22	50.00	250.00	336.09	171.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	250.00	336.09	171.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	250.00	336.09	171.00
===== 623-00603 3 In Plastic Pipe (Irrig/Sleeve) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1,270.00	31.73	33.84	33.84
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,270.00	31.73	33.84	33.84
	WEIGHTED AVERAGE FOR THE YEAR			1,270.00	31.73	33.84	33.84
===== 623-00604 4 In Plastic Pipe (Irrig/Sleeve) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	305.00	40.48	43.19	43.19
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			305.00	40.48	43.19	43.19
	WEIGHTED AVERAGE FOR THE YEAR			305.00	40.48	43.19	43.19
===== 623-07006 3/4 In Water Meter Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	1000.00	5702.55	1900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	1000.00	5702.55	1900.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1000.00	5702.55	1900.00
===== 623-09900 Sprinkler System LUMP SUM =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	526344.30	133187.30	133187.30
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	526344.30	133187.30	133187.30
===== 2670703-479 I-70 BRIDGE OVER HARLAN 05/05/22 =====							
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	9500.00	16589.40	21811.60
	WEIGHTED AVERAGE FOR THE YEAR			2.00	267922.15	33246.25	77499.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 527

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 623-09905 Irrig Assembly Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	5000.00	7297.54	6300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5000.00	7297.54	6300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	7297.54	6300.00
===== 624-20016 15 In Drainage Pipe (CL 0) (CIP) Lin Foot =====							
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG 08/31/22 US 6/US 34 TIMBER BRIDGE REPL		96.00	153.92	70.51	70.51
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			96.00	153.92	70.51	70.51
	WEIGHTED AVERAGE FOR THE YEAR			96.00	153.92	70.51	70.51
===== 624-20025 24 In Drainage Pipe (CL 0) (CIP) Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40 01/13/22		140.00	150.00	118.49	68.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			140.00	150.00	118.49	68.75
	WEIGHTED AVERAGE FOR THE YEAR			140.00	150.00	118.49	68.75
===== 624-20300 Detour Drainage Pipe (CL 0) Lin Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 07/08/22 VAIL PASS AUX BE F-12-AT PHAS		248.00	279.92	279.92	279.92
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			248.00	279.92	279.92	279.92
STU0252-457 BR012A-048		I-25:ALAMEDA RIVER PH 2.0 11/03/22 CO 12 STRUCTURE P-17-F AT MP 12/22/22		100.00 315.00	200.00 300.00	302.20 318.29	295.00 375.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			415.00	275.90	313.10	355.72
	WEIGHTED AVERAGE FOR THE YEAR			663.00	277.41	306.11	327.37
===== 624-20301 Detour Drainage Pipe (CL 0) LUMP SUM =====							
NHPP 0761-238		I-76 DAHLIA TO YORK 03/10/22		1.00	20000.00	43688.71	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 528

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-20301 C0761-239		Detour Drainage Pipe (CL 0)		LUMP SUM	=====		
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	43688.71	7500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	31334.01	48000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	100000.00	31334.01	48000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	60000.00	40319.24	27750.00
===== 624-23019		18 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	549.00	100.00	131.25	112.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			549.00	100.00	131.25	112.00
	WEIGHTED AVERAGE FOR THE YEAR			549.00	100.00	131.25	112.00
===== 624-23025		24 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	237.00	150.00	173.30	180.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			237.00	150.00	173.30	180.00
	WEIGHTED AVERAGE FOR THE YEAR			237.00	150.00	173.30	180.00
===== 624-23031		30 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	79.00	200.00	215.70	155.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			79.00	200.00	215.70	155.00
	WEIGHTED AVERAGE FOR THE YEAR			79.00	200.00	215.70	155.00
===== 624-23055		54 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	134.00	300.00	401.08	320.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			134.00	300.00	401.08	320.00
	WEIGHTED AVERAGE FOR THE YEAR			134.00	300.00	401.08	320.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 529

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-25031 30 In Drainage Pipe (CL 5) (CIP) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	112.00	180.00	253.33	180.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			112.00	180.00	253.33	180.00
	WEIGHTED AVERAGE FOR THE YEAR			112.00	180.00	253.33	180.00
===== 624-27015 15 In Drainage Pipe (CL 7) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	137.00	75.00	76.37	60.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			137.00	75.00	76.37	60.00
	WEIGHTED AVERAGE FOR THE YEAR			137.00	75.00	76.37	60.00
===== 624-27024 24 In Drainage Pipe (CL 7) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	143.00	95.00	311.83	105.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			143.00	95.00	311.83	105.00
	WEIGHTED AVERAGE FOR THE YEAR			143.00	95.00	311.83	105.00
===== 624-28007 6 In Drainage Pipe (CL 8) (CIP) Lin Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	85.00	385.81	385.81	385.81
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			85.00	385.81	385.81	385.81
	WEIGHTED AVERAGE FOR THE YEAR			85.00	385.81	385.81	385.81
===== 624-28019 18 In Drainage Pipe (CL 8) (CIP) Lin Foot =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,050.00	233.29	233.29	233.29
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,050.00	233.29	233.29	233.29
	WEIGHTED AVERAGE FOR THE YEAR			2,050.00	233.29	233.29	233.29

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 530

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
===== 624-28025	24 In Drainage Pipe (CL 8) (CIP)			Lin Foot	=====		
NHPP0702-414 FBR0702-423	VAIL PASS AUX PHASE 1 CAP 3	07/08/22		207.00	343.86	343.86	343.86
	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			207.00	343.86	343.86	343.86
	WEIGHTED AVERAGE FOR THE YEAR			207.00	343.86	343.86	343.86
=====							
===== 624-28031	30 In Drainage Pipe (CL 8) (CIP)			Lin Foot	=====		
NHPP0702-414 FBR0702-423	VAIL PASS AUX PHASE 1 CAP 3	07/08/22		342.00	317.91	317.91	317.91
	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			342.00	317.91	317.91	317.91
	WEIGHTED AVERAGE FOR THE YEAR			342.00	317.91	317.91	317.91
=====							
===== 624-29015	15 In Drainage Pipe (CL 9)			Lin Foot	=====		
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22		276.00	160.00	76.65	59.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			276.00	160.00	76.65	59.00
	WEIGHTED AVERAGE FOR THE YEAR			276.00	160.00	76.65	59.00
=====							
===== 624-29018	18 In Drainage Pipe (CL 9)			Lin Foot	=====		
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22		163.00	160.00	176.38	79.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			163.00	160.00	176.38	79.00
	WEIGHTED AVERAGE FOR THE YEAR			163.00	160.00	176.38	79.00
=====							
===== 624-29019	18 In Drainage Pipe (CL 9) (CIP)			Lin Foot	=====		
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22		372.00	125.00	132.77	85.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			372.00	125.00	132.77	85.00
	WEIGHTED AVERAGE FOR THE YEAR			372.00	125.00	132.77	85.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 531

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-29024 24 In Drainage Pipe (CL 9) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	155.00	220.00	196.64	105.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			155.00	220.00	196.64	105.00
	WEIGHTED AVERAGE FOR THE YEAR			155.00	220.00	196.64	105.00
===== 624-29025 24 In Drainage Pipe (CL 9) (CIP) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	468.00	200.00	152.96	90.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			468.00	200.00	152.96	90.00
	WEIGHTED AVERAGE FOR THE YEAR			468.00	200.00	152.96	90.00
===== 624-29031 30 In Drainage Pipe (CL 9) (CIP) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	289.00	320.00	188.24	117.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			289.00	320.00	188.24	117.00
	WEIGHTED AVERAGE FOR THE YEAR			289.00	320.00	188.24	117.00
===== 624-30013 12 In Drainage Pipe (CL 10) (CIP) Lin Foot =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	180.00	157.33	133.75
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			100.00	180.00	157.33	133.75
	WEIGHTED AVERAGE FOR THE YEAR			100.00	180.00	157.33	133.75
===== 624-30018 18 In Drainage Pipe (CL 10) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	288.00	110.00	160.00	140.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			288.00	110.00	160.00	140.00
	WEIGHTED AVERAGE FOR THE YEAR			288.00	110.00	160.00	140.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 532

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-30019 18 In Drainage Pipe (CL 10) (CIP) Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	566.00	235.16	235.16	235.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		566.00	235.16	235.16	235.16
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	111.00	200.00	173.47	144.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		111.00	200.00	173.47	144.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	208.00	125.00	176.67	160.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		208.00	125.00	176.67	160.00
		WEIGHTED AVERAGE FOR THE YEAR		885.00	204.86	193.36	206.06
===== 624-30025 24 In Drainage Pipe (CL 10) (CIP) Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	102.00	350.26	350.26	350.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		102.00	350.26	350.26	350.26
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	125.00	160.00	218.33	220.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	160.00	218.33	220.00
		WEIGHTED AVERAGE FOR THE YEAR		227.00	245.49	246.54	278.53
===== 624-30031 30 In Drainage Pipe (CL 10) CIP) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	151.00	180.00	286.67	260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		151.00	180.00	286.67	260.00
		WEIGHTED AVERAGE FOR THE YEAR		151.00	180.00	286.67	260.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-30037	36 In Drainage Pipe (CL 10) (CIP)			Lin Foot	=====		
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	203.00	330.84	330.84	330.84	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		203.00	330.84	330.84	330.84	
	WEIGHTED AVERAGE FOR THE YEAR		203.00	330.84	330.84	330.84	
===== 624-30043	42 In Drainage Pipe (CL 10) (CIP)			Lin Foot	=====		
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	63.00	406.01	406.01	406.01	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		63.00	406.01	406.01	406.01	
	WEIGHTED AVERAGE FOR THE YEAR		63.00	406.01	406.01	406.01	
===== 624-30055	54 In Drainage Pipe (CL 10) (CIP)			Lin Foot	=====		
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	429.00	415.00	510.00	440.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		429.00	415.00	510.00	440.00	
	WEIGHTED AVERAGE FOR THE YEAR		429.00	415.00	510.00	440.00	
===== 624-49018	18 In Equiv Drain Pipe E (CL 9)			Lin Foot	=====		
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	03/10/22	589.00	90.00	149.36	64.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		589.00	90.00	149.36	64.00	
	WEIGHTED AVERAGE FOR THE YEAR		589.00	90.00	149.36	64.00	
===== 624-49031	30 In Equiv Drain Pipe E (CL 9) (CIP)			Lin Foot	=====		
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	314.00	300.00	208.65	103.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		314.00	300.00	208.65	103.00	
	WEIGHTED AVERAGE FOR THE YEAR		314.00	300.00	208.65	103.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 534

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-50019 18 In Equiv Drain Pipe E (CL 10) (CIP) Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	48.00	292.77	292.77	292.77
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48.00	292.77	292.77	292.77
		WEIGHTED AVERAGE FOR THE YEAR		48.00	292.77	292.77	292.77
===== 625-00000 Const Surveying LUMP SUM =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	20000.00	32500.00	32500.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	80000.00	153941.80	145680.79
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	25000.00	25733.33	16666.67
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	150000.00	424347.35	280000.00
NHPP1601-083			02/03/22	1.00	150000.00	211269.43	130000.00
C0762-055			02/17/22	1.00	15000.00	66558.26	50000.00
STR0141-031			02/17/22	1.00	20000.00	27000.00	27000.00
NHPP0063-063			02/24/22	1.00	200000.00	99205.00	125000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	20000.00	14334.48	14000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	192000.00	313622.73	188000.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	61723.27	89636.36	89636.36
CR100-362			03/14/22	1.00	7393.27	7393.27	7393.27
ER007A-035			03/15/22	1.00	41540.00	44448.00	44448.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	15000.00	22601.73	23203.45
BRC040-057			03/17/22	1.00	10000.00	41625.00	50000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	19000.00	24197.00	16594.00
NHM765-007			03/31/22	1.00	250000.00	109731.12	113715.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	75097.44	133829.75	79637.50
NH0504-911			04/07/22	1.00	20000.00	126500.00	153000.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	70000.00	27384.54	4000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	469491.15	469491.15	469491.15
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	310000.00	497446.46	250975.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	350000.00	237150.92	86765.32
STA0712-019		SH 71: Frieght Improvements	05/12/22	1.00	35000.00	187083.96	187083.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	42000.00	103333.33	135000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	14000.00	10118.00	6350.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	10000.00	42500.00	30000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	30000.00	28000.00	28000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	10000.00	31356.50	35000.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	4000.00	8033.33	4500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	625-00000	Const Surveying		LUMP SUM	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	65000.00	90175.05	90175.05
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	80000.00	62863.75	23000.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	25000.00	43062.36	43674.71
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	102299.41	141735.43	103134.35
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	728948.15	728948.15	728948.15
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	8000.00	15364.67	10634.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	10000.00	13500.00	13000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	200000.00	331659.65	450000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	8000.00	46000.00	45000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	90000.00	40500.00	26000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	25000.00	14093.14	16390.53
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	25421.36	32100.00	32100.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	45000.00	44750.00	66250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	100000.00	155334.98	108000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	100000.00	162199.45	134436.18
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	15000.00	112125.00	62000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	42434.00	34868.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		13.00	100413.63	107440.25	125694.78
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	20000.00	52100.00	88300.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	35000.00	48065.89	35500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	10000.00	29925.00	22000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	10000.00	16575.28	13611.11
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	80000.00	264411.25	125000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	120000.00	120000.00	120000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	25000.00	45585.19	26000.00
STU0252-457		I-25-ALAMEDA RIVER PH 2.0	11/03/22	1.00	300000.00	353013.65	280000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	35000.00	49825.07	29475.21
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	50000.00	32265.00	45000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	35000.00	23720.00	45000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	200000.00	211133.81	180000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	50000.00	29000.00	28000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	200000.00	307934.15	254774.13
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	66825.00	64666.67	40000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	100000.00	217980.90	110000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	625-00000	Const Surveying		LUMP SUM	=====		
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	20250.00	20000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	149000.00	195000.00	230000.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	95000.00	49755.22	30690.83
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	60000.00	86338.39	152000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	20000.00	58510.17	76900.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	120000.00	103260.84	94578.09
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	42342.84	26114.18
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50000.00	65908.40	50000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	40000.00	54222.22	31888.89
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	40000.00	53333.33	35000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				26.00	76570.19	110750.80	85992.23
WEIGHTED AVERAGE FOR THE YEAR				71.00	86218.94	120941.50	95518.41
=====							
=====	625-00001	Const Surveying (Hour)		Hour	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	180.00	250.69	245.81
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	200.00	222.86	264.00
STA0252-459			02/03/22	150.00	183.75	256.10	220.00
NHPP0063-063			02/24/22	10.00	200.00	177.50	185.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				480.00	184.92	245.13	239.51
=====							
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	220.00	200.00	200.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				10.00	220.00	200.00	200.00
=====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	280.00	200.00	210.59	210.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	250.00	204.75	215.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				290.00	201.72	210.39	210.17
=====							
C5502-097		US550 MP 117.28-126.06	11/17/22	240.00	200.00	256.22	240.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	250.00	249.50	224.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	220.00	250.00	297.29	257.80
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	50.00	175.00	258.90	299.79

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 537

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 625-00001							
		Const Surveying (Hour)		Hour			
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	200.00	217.72	180.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	20.00	125.00	241.18	200.88
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		590.00	215.68	270.45	245.77
		WEIGHTED AVERAGE FOR THE YEAR		1,370.00	201.98	251.93	235.71
===== 626-00000							
		Mobilization		LUMP SUM			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	700000.00	780000.00	780000.00
MTCE R500-219			01/06/22	1.00	60000.00	96666.67	75000.00
MTCE R500-218			01/06/22	1.00	75000.00	76184.50	100000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	380207.00	428203.10	321624.56
STR0505-050			01/13/22	1.00	175000.00	232037.08	275000.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	229601.00	246791.10	165124.86
MTCE R400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	1.00	50000.00	73750.00	45000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000000.00	2673888.12	2067000.00
MTCE R300-262			02/03/22	1.00	200000.00	353333.33	180000.00
NHPP1601-083			02/03/22	1.00	1700000.00	1859589.50	2000000.00
STA0252-459			02/03/22	1.00	400000.00	530225.33	201000.00
C0762-055			02/17/22	1.00	694114.50	1088724.56	700000.00
STR0141-031			02/17/22	1.00	637754.29	743046.79	660640.38
STR133A-051			02/17/22	1.00	120000.00	169333.33	225000.00
NHPP0063-063			02/24/22	1.00	700000.00	1037000.00	914000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	321199.25	381542.22	450000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	1000000.00	1092058.79	1150000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	521125.20	543595.54	671250.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	654967.00	641994.83	643989.66
BRC040-057			03/17/22	1.00	451919.00	358979.88	255000.00
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	360000.00	457851.67	200555.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	73077.00	130237.00	153524.00
STR092A-031			03/17/22	1.00	800000.00	800000.00	800000.00
MP0503-098			03/24/22	1.00	101620.00	66180.00	61000.00
NHM765-007			03/31/22	1.00	1866244.00	1271408.30	1574060.76
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	175000.00	170600.00	131000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	572104.75	706952.48	590732.19
NH0504-911			04/07/22	1.00	1841988.88	1562500.00	1155000.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	200000.00	277825.42	202976.25
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	1507599.90	3292354.76	3608092.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	63350.00	193500.00	185000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-00000 Mobilization LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	1855630.20	1674815.66	1625525.96
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	250000.00	472500.00	345000.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	780000.00	937665.73	937665.73
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	650000.00	212500.00	300000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	805912.50	770000.00	680000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2650.00	91669.60	62348.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	975000.00	1356315.01	897798.60
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1.00	199937.00	239364.00	135092.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	85000.00	58000.00	58000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	660000.00	750000.00	750000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	219795.00	334927.95	460000.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	20000.00	29191.67	9000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	600000.00	585384.22	585384.22
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	300000.00	228195.00	175350.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	1.00	120000.00	83333.33	75000.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	1.00	32001.55	40000.00	35000.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	161253.55	318953.50	400000.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	334355.00	294493.25	371973.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	1.00	239858.11	75000.00	75000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				23.00	517579.64	724444.35	570835.03
MT CER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	1.00	35000.00	42333.33	42000.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	99988.00	95000.00	95000.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	1.00	35000.00	23125.00	20000.00
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	1.00	40000.00	39333.33	33000.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	50000.00	93889.31	75000.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	59585.87	83333.33	105000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2000000.00	1403962.76	1807000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	425530.80	143000.00	141000.00
MT CER400-396		REGION 4	08/25/22	1.00	20000.00	18333.33	25000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	700000.00	459562.50	244125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	100000.00	109784.37	93467.73
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	460790.60	507868.90	507868.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	1.00	165420.00	241564.95	241564.95
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	198379.00	212775.89	262146.67
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	1.00	50000.00	102500.00	95000.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	20000.00	521179.75	20800.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	800000.00	808041.60	750000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	1170660.40	1180743.63	474032.90
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	365000.00	657242.97	380000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	300000.00	548798.65	297597.30
WEIGHTED AVERAGE FOR THE THIRD QUARTER				20.00	359816.44	422244.70	285480.17

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 539

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-00000		Mobilization		LUMP SUM	=====		
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	200000.00	173967.00	85000.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	200000.00	244833.33	250000.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	1.00	35406.00	105000.00	60000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	650000.00	538500.00	412000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	770784.50	714363.00	475000.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	400000.00	509111.82	511000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	309066.29	305150.00	145000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	50000.00	96300.00	67600.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	68530.50	84681.96	75527.82
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	719011.55	1341771.51	980000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	1483430.38	1542000.90	1542000.90
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	400000.00	267401.45	123688.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	2500000.00	2261717.98	2092000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	412941.90	226659.04	223977.13
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	680000.00	860000.00	840000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	600683.30	313007.60	345000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	1900000.00	1716991.13	1895000.89
MPR200-280		PUEBLO AREA	11/17/22	1.00	108129.70	140000.00	85000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	320620.75	407000.00	264000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1670011.38	2327674.33	2315469.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	1200000.00	1351666.67	934000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	1500000.00	1707500.00	905000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	1072997.30	1538231.21	1631000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	1200000.00	476500.00	284000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	597119.00	1143333.33	1000000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	780000.00	771000.07	600000.14
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	998932.00	1180012.98	1230025.96
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	300000.00	293795.76	204249.23
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1.00	400000.00	422340.00	495000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	980366.75	434065.19	308130.38
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	450000.00	422634.11	400000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	296150.20	275500.00	301000.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	35000.00	76384.45	28000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	565857.00	371773.50	306000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	800000.00	968174.52	552753.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	800000.00	1010000.25	875000.49
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	350000.00	285872.84	213648.18
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	655191.00	1030000.00	460000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	300000.00	578534.71	464138.85
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	1074879.80	1403566.72	1761000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				40.00	695877.73	773422.84	657926.10
WEIGHTED AVERAGE FOR THE YEAR				109.00	565246.98	688319.00	558224.79

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 540

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-00100 Mobilization (w/o Autopay) LUMP SUM =====							
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5		03/11/22	1.00	319481.37	432828.97	432828.97
CR100-362			03/14/22	1.00	1152902.83	1152902.83	1152902.83
ER007A-035			03/15/22	1.00	171239.00	149920.78	149920.78
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	490776.14	542120.39	542120.39

NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	1.00	6642018.74	6642018.74	6642018.74
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	6642018.74	6642018.74	6642018.74

NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	1.00	12721547.66	12721547.67	12721547.67
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	12721547.66	12721547.67	12721547.67
	WEIGHTED AVERAGE FOR THE YEAR			5.00	3554445.16	3588674.66	3588674.66
===== 626-01111 Public Info Manage (Tier I) Day =====							
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5		03/11/22	205.00	125.00	133.75	133.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			205.00	125.00	133.75	133.75

2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	588.00	300.00	158.98	130.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			588.00	300.00	158.98	130.00
	WEIGHTED AVERAGE FOR THE YEAR			793.00	254.76	157.33	130.97
===== 626-01112 Public Info Manage (Tier II) Day =====							
NHM765-007			03/31/22	600.00	100.00	87.55	79.80
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			600.00	100.00	87.55	79.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 541

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01112 Public Info Manage (Tier II) Day =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	180.00	474.37	474.37	474.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		180.00	474.37	474.37	474.37
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	330.00	256.80	256.80	256.80
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		330.00	256.80	256.80	256.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	510.00	300.00	103.70	110.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		510.00	300.00	103.70	110.00
		WEIGHTED AVERAGE FOR THE YEAR		1,620.00	236.50	126.66	169.20
===== 626-01113 Public Info Manage (Tier III) Day =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	100.00	100.00	2635.00	2635.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	100.00	200.00	102.36	122.18
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	426.00	75.00	78.77	75.00
STA0252-459			02/03/22	200.00	80.00	84.00	75.00
STR0141-031			02/17/22	94.00	200.00	64.50	72.00
NHPP0063-063			02/24/22	175.00	217.00	57.50	55.00
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	800.00	120.00	70.58	125.00
NHPP0703-472			03/10/22	90.00	100.00	148.94	100.00
BRC040-057			03/17/22	125.00	100.00	84.00	63.00
STR092A-031			03/17/22	145.00	70.00	68.00	68.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,255.00	116.35	99.24	206.56
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	696.00	90.00	83.17	92.50
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	185.00	180.00	81.50	88.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01113 Public Info Manage (Tier III) Day =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	313.00	78.00	73.33	80.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	150.00	100.00	67.61	64.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	140.00	110.00	90.00	90.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	180.00	120.00	102.92	102.92
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	222.00	95.00	76.23	85.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,886.00	102.57	80.58	87.64
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	189.00	70.00	87.22	87.22
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	100.00	694.50	340.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	290.00	80.00	82.08	80.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	445.00	87.00	77.53	91.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	144.00	110.00	100.67	110.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,088.00	85.46	91.14	94.63
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	130.00	90.00	60.75	60.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	171.00	70.00	80.50	98.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	44.00	200.00	141.00	120.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	80.00	107.15	76.44
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	179.00	90.00	66.80	65.00
C5502-097		US550 MP 117.28-126.06	11/17/22	275.00	70.00	63.40	59.40
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	165.00	90.00	94.00	105.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	600.00	70.00	82.37	82.69
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	215.00	80.00	55.00	55.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	152.00	90.00	53.45	53.90
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	420.00	75.00	46.40	41.80
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	55.00	150.00	110.26	104.35
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	99.00	90.00	145.76	128.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	200.00	120.00	86.32	82.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	284.00	75.00	44.19	41.84
STR0092-024		SH 9 North of Silverthorne	12/22/22	180.00	200.00	67.55	70.10
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				3,269.00	89.79	74.46	70.47
WEIGHTED AVERAGE FOR THE YEAR				8,498.00	99.12	86.31	112.50
===== 626-01114 Public Info Manage (Tier IV) Day =====							
MTCE R500-219			01/06/22	95.00	90.00	78.50	85.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01114 Public Info Manage (Tier IV) Day =====							
MTCE R500-218			01/06/22	50.00	50.00	102.50	75.00
STR0505-050			01/13/22	75.00	100.00	91.00	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	184.00	70.00	70.51	66.67
NHPP1601-083			02/03/22	277.00	150.00	73.48	66.00
C0762-055			02/17/22	160.00	70.00	58.53	57.00
STR133A-051			02/17/22	49.00	100.00	81.67	65.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	115.00	80.00	68.75	55.00
CR100-362			03/14/22	300.00	74.90	74.90	74.90
STR R500-171		Various locations on SH 141 a	03/17/22	140.00	46.00	88.59	150.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	86.00	100.00	84.50	96.00
MP0503-098			03/24/22	35.00	80.00	94.50	80.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,566.00	88.50	74.34	78.56
NH0504-911			04/07/22	350.00	100.00	63.80	77.60
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	120.00	75.00	73.29	60.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	10.00	300.00	199.08	163.15
STA0712-019		SH 71: Frieght Improvements	05/12/22	180.00	75.00	55.49	55.49
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	86.00	85.00	81.95	75.00
CM760-047		COLFAX AND QUAIL	05/12/22	70.00	60.00	94.20	63.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	103.00	100.00	59.50	60.00
C0852-120		Rehabilitation of Culvert by	05/26/22	37.00	175.00	80.00	80.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	50.00	80.00	83.50	77.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	24.00	100.00	122.67	140.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	161.00	125.00	88.33	105.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	47.00	100.00	130.00	115.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,238.00	96.94	79.93	77.14
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	15.00	180.00	115.00	115.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	100.00	76.67	90.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	160.00	100.00	53.17	60.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	150.00	80.00	82.50	80.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				365.00	95.07	66.88	73.77
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	25.00	200.00	112.41	119.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	60.00	120.00	66.60	64.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	77.00	90.00	85.00	75.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 544

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01114 Public Info Manage (Tier IV) Day =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	210.00	75.00	60.37	76.10
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	201.00	75.00	70.76	68.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	91.00	65.00	92.50	100.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	160.00	75.00	57.00	57.00
MPR200-280		PUEBLO AREA	11/17/22	177.00	67.00	97.50	120.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	115.00	63.00	71.00	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	169.00	250.00	49.50	57.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	138.00	60.00	73.97	25.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	114.00	75.00	117.09	83.17
NHM175-029		CANON CITY, CO	12/15/22	75.00	100.00	57.50	90.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	99.00	75.00	91.69	61.38
STA385A-016		SH 385 MP 97.76	12/22/22	224.00	50.00	76.53	69.10
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	175.00	68.00	55.33	55.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,110.00	87.24	73.62	70.51
	WEIGHTED AVERAGE FOR THE YEAR			5,279.00	90.43	74.64	74.63
===== 627-00001 Pvmt Mkg Paint Gallon =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	68.00	70.00	106.57	127.78
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			68.00	70.00	106.57	127.78
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	933.33	1300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	200.00	933.33	1300.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	200.00	462.39	430.00
STA385A-016		SH 385 MP 97.76	12/22/22	186.00	130.00	109.22	138.89
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	3,835.00	51.00	57.00	54.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,041.00	55.37	61.48	59.77
	WEIGHTED AVERAGE FOR THE YEAR			4,111.00	55.69	63.80	61.50
===== 627-00002 Thermoplastic Pvmt Mkg Sq Foot =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	10.00	75.00	56.53	61.11
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.00	75.00	56.53	61.11
	WEIGHTED AVERAGE FOR THE YEAR			10.00	75.00	56.53	61.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 545

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00003 Thermoplastic Pvmnt Mkg (Inlaid) Sq Foot =====							
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	32.00	25.00	49.67	54.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			32.00	25.00	37.49	37.84
	WEIGHTED AVERAGE FOR THE YEAR			32.00	25.00	37.49	37.84
===== 627-00005 Epoxy Pvmnt Mkg Gallon =====							
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV	06/23/22		27.00	60.00	1700.00	1700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			27.00	60.00	1700.00	1700.00
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22		28.00	98.00	299.62	238.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			28.00	98.00	299.62	238.85
	WEIGHTED AVERAGE FOR THE YEAR			55.00	79.35	1087.33	956.14
===== 627-00006 Mod Epoxy Pvmnt Mkg (On-Call) Gallon =====							
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR	06/09/22		188.00	140.00	174.55	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			188.00	140.00	174.55	200.00
	WEIGHTED AVERAGE FOR THE YEAR			188.00	140.00	174.55	200.00
===== 627-00008 Mod Epoxy Pvmnt Mkg Gallon =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22		182.00	68.00	246.57	217.26
STR0505-050		01/13/22		513.00	110.00	156.42	200.00
NH0504-910	US50B L-24-B MIN REP AT MP 40	01/13/22		10.00	500.00	761.72	472.22
MTCER400-391	VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22		6,541.00	68.00	93.44	85.75
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		1,318.00	135.00	98.55	81.00
STA0252-459		02/03/22		124.00	100.00	447.93	225.00
C0762-055		02/17/22		946.00	120.00	101.40	121.00
STR0141-031		02/17/22		968.00	70.00	115.67	110.00
STR133A-051		02/17/22		1,534.00	80.00	124.67	124.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 546

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00008	Mod Epoxy Pvmk Mkg		Gallon =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	324.00	70.00	122.53	150.00
C0761-239							
NHPP0703-472			03/10/22	705.00	74.00	109.92	110.00
ER007A-035			03/15/22	1,434.00	99.45	106.45	106.45
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,343.00	100.00	118.01	116.02
BRC040-057			03/17/22	41.00	75.00	490.75	425.00
STR092A-031			03/17/22	838.00	140.00	175.00	175.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				16,821.00	88.29	110.99	110.12
NH0504-911			04/07/22	976.00	71.83	202.25	154.50
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	9.00	500.00	633.55	575.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	95.00	219.35	219.35	219.35
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	4.00	750.00	1555.65	526.29
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	55.00	85.00	493.96	645.23
STA0712-019		SH 71: Frieight Improvements	05/12/22	335.00	150.00	119.03	119.03
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	916.00	95.00	125.25	110.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	60.00	92.00	268.33	315.00
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	280.00	1164.40	625.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1,205.00	75.00	147.00	149.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	6.00	350.00	666.67	500.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	199.00	95.00	136.47	136.47
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	22,133.00	80.00	89.08	89.75
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	56,785.00	90.50	90.50	90.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				82,781.00	87.80	94.89	93.15
MT CER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	12,271.00	93.00	91.25	82.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	852.00	130.00	130.00	130.00
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	240.00	450.00	416.67	450.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	339.00	256.80	256.80	256.80
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	10.00	500.00	644.83	1280.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	61.00	100.00	537.60	225.00
MT CER400-396		REGION 4	08/25/22	12,024.00	80.00	82.83	75.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	62.00	500.00	312.50	200.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	165.85	165.85	165.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	10.00	150.00	243.59	190.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	392.00	230.00	200.73	198.78
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	227.00	180.00	213.63	168.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				26,536.00	97.66	98.76	89.64

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00008		Mod Epoxy Pvmt Mkg		Gallon	=====		
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	14.00	500.00	233.51	230.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	405.00	250.00	154.50	160.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	110.00	200.00	302.75	237.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	300.00	466.75	440.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	178.00	100.00	477.05	160.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	747.00	130.00	120.00	120.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	200.00	296.53	118.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	43.00	100.00	245.97	238.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,615.00	150.00	125.50	130.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	554.00	150.00	159.40	140.00
C5502-097		US550 MP 117.28-126.06	11/17/22	735.00	160.00	179.88	167.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	86.00	210.00	356.00	420.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	179.00	90.00	212.82	216.44
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,067.00	110.00	149.33	160.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2,184.00	110.00	152.50	150.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	452.00	300.00	185.50	140.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	366.00	200.00	303.50	275.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,417.00	120.00	125.50	124.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	95.00	250.00	228.47	202.56
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2,628.00	150.00	128.83	105.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	225.00	195.00	193.56	206.11
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	128.00	200.00	237.24	181.50
NHM175-029		CANON CITY, CO	12/15/22	620.00	110.00	132.50	150.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	9.00	500.00	624.09	500.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	368.00	65.00	136.96	125.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	213.00	200.00	240.90	260.61
STR0092-024		SH 9 North of Silverthorne	12/22/22	2,186.00	90.00	127.50	119.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	798.00	130.00	174.28	164.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17,492.00	137.67	161.61	142.72
		WEIGHTED AVERAGE FOR THE YEAR		143,630.00	95.75	110.57	101.31
===== 627-00009		Mod Epoxy (Inlaid)		Gallon	=====		
NHM765-007			03/31/22	86.00	352.00	375.94	342.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	352.00	375.94	342.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,461.00	120.00	174.63	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,461.00	120.00	174.63	165.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 548

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00009 Mod Epoxy (Inlaid) Gallon =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	51.00	250.00	349.83	328.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		51.00	250.00	349.83	328.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	45.00	400.00	368.70	250.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	71.00	300.00	295.00	160.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	9.00	500.00	1236.62	1150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	350.40	368.53	263.68
		WEIGHTED AVERAGE FOR THE YEAR		1,723.00	152.14	195.09	185.82
===== 627-00011 Pvmt Mkg Paint (Waterborne) Gallon =====							
NHM765-007			03/31/22	490.00	75.00	174.47	74.67
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		490.00	75.00	174.47	74.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2,900.00	45.00	56.32	58.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,900.00	45.00	56.32	58.50
		WEIGHTED AVERAGE FOR THE YEAR		3,390.00	49.34	67.19	60.84
===== 627-00013 Pvmt Mkg Paint (High Build) Gallon =====							
MTCE R500-219			01/06/22	62,700.00	33.00	34.93	33.70
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	884.00	32.00	67.95	65.18
STR0505-050			01/13/22	1,195.00	100.00	72.22	65.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	344.00	100.00	55.13	43.00
NHPP1601-083			02/03/22	3,015.00	60.00	42.53	42.67
STA0252-459			02/03/22	71.00	104.00	198.57	125.00
C0762-055			02/17/22	1,818.00	60.00	60.17	90.00
STR0141-031			02/17/22	1,643.00	40.00	83.33	79.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 549

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00013	Pvmt Mkg Paint (High Build)		Gallon =====			
STR133A-051			02/17/22	772.00	35.00	62.67	54.00
NHPP0063-063			02/24/22	979.00	50.00	138.00	162.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	3,978.00	40.00	46.02	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,510.00	125.00	78.94	80.00
C0761-239							
NHPP0703-472			03/10/22	3,028.00	31.00	44.93	34.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	2,500.00	60.00	57.63	55.25
STR R500-171		Various locations on SH 141 a	03/17/22	19.00	137.00	121.82	110.00
STR092A-031			03/17/22	782.00	80.00	75.00	75.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				86,238.00	40.26	43.61	41.42
NH0504-911			04/07/22	3,904.00	34.46	66.60	83.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	133.00	142.76	142.76	142.76
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	138.00	40.00	132.19	129.05
STA0712-019		SH 71: Frieight Improvements	05/12/22	762.00	150.00	46.58	46.58
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	2,000.00	40.00	64.05	72.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	40.00	36.00	128.00	159.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3,058.00	65.00	87.50	90.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,737.00	60.00	77.13	77.13
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	476.00	80.00	83.35	75.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				12,248.00	56.81	76.33	81.02
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	223.00	144.45	144.45	144.45
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	250.00	466.67	780.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	933.33	1300.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	186.00	80.00	517.99	900.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	87.00	165.85	165.85	165.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	60.00	83.31	74.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				603.00	114.71	231.71	378.01
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	2,078.00	80.00	50.53	41.60
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	557.00	150.00	88.55	110.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,711.00	80.00	82.00	74.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	384.00	76.00	134.13	60.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00013							
		Pvmt Mkg Paint (High Build)		Gallon			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	146.00	120.00	137.56	95.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,074.00	75.00	75.00	75.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	791.00	85.00	74.38	72.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	50.00	42.00	151.48	119.43
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,172.00	100.00	76.50	87.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2,000.00	80.00	73.20	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4,964.00	90.00	40.01	37.30
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	120.00	217.00	230.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	477.00	35.00	94.84	105.13
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2,386.00	75.00	73.33	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,900.00	55.00	106.50	80.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	453.00	80.00	125.86	79.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	309.00	150.00	61.00	55.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	96.00	60.00	147.00	91.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2,158.00	100.00	68.50	48.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	37.00	150.00	330.25	104.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	596.00	75.00	90.51	67.52
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	7,154.00	70.00	39.53	32.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	161.00	48.00	104.72	102.43
NHM175-029		CANON CITY, CO	12/15/22	1,033.00	100.00	87.50	90.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,092.00	80.00	82.09	79.45
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	470.00	100.00	153.52	225.78
STR0092-024		SH 9 North of Silverthorne	12/22/22	2,799.00	90.00	50.50	41.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	488.00	90.00	95.07	96.85
STA385A-016		SH 385 MP 97.76	12/22/22	68.00	80.00	120.33	183.33
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2,425.00	51.00	48.33	54.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				40,129.00	80.24	67.56	58.38
WEIGHTED AVERAGE FOR THE YEAR				139,218.00	53.56	53.16	51.37
===== 627-00014							
		Pvmt Mkg Paint (Low Temp)		Gallon			
ER007A-035			03/15/22	2,000.00	63.75	68.25	68.25
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,000.00	63.75	68.25	68.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	610.00	60.00	92.31	93.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				610.00	60.00	92.31	93.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	70.00	242.16	248.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				30.00	70.00	242.16	248.00
WEIGHTED AVERAGE FOR THE YEAR				2,640.00	62.95	84.68	76.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 551

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00029 24 In Pvmt Mkg Tape (Rem) Lin Foot =====							
STA0711-021		SH71: REGION LINE NORTH	12/01/22	120.00	28.00	29.00	30.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			120.00	28.00	29.00	30.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	28.00	29.00	30.00
===== 627-00030 Raised Pvmt Marker (Temp) Each =====							
C0762-055			02/17/22	300.00	10.00	8.44	17.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			300.00	10.00	8.44	17.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	3,375.00	2.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,375.00	2.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE YEAR			3,675.00	2.65	5.90	5.98
===== 627-00031 Raised Pvmt Marker Each =====							
NHPP0063-063			02/24/22	112.00	200.00	176.73	345.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			112.00	200.00	176.73	345.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	53.00	250.00	48.49	25.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			53.00	250.00	48.49	25.00
	WEIGHTED AVERAGE FOR THE YEAR			165.00	216.06	135.53	242.21
===== 627-00032 Raised Flex Pvmt Marker (Temp) Each =====							
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	4,000.00	2.00	1.57	0.95
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,000.00	2.00	1.57	0.95
	WEIGHTED AVERAGE FOR THE YEAR			4,000.00	2.00	1.57	0.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 552

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00070 Preform Thermoplastic Pvmnt Mkg Sq Foot =====							
CM760-047		COLFAX AND QUAIL	05/12/22	33.00	17.00	115.25	444.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33.00	17.00	115.25	444.00
	WEIGHTED AVERAGE FOR THE YEAR			33.00	17.00	115.25	444.00
===== 627-01001 Preform Plastic Pvmnt Mkg (Ty I) Sq Foot =====							
STR0505-050			01/13/22	14,340.00	14.00	18.37	15.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14,340.00	14.00	18.37	15.00
	WEIGHTED AVERAGE FOR THE YEAR			14,340.00	14.00	18.37	15.00
===== 627-01010 Preform Plastic Pvmnt Mkg (TY I) (Inlaid) Sq Foot =====							
MTCE R500-218			01/06/22	9,178.00	16.50	16.25	14.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,417.00	17.00	14.32	12.00
STA0252-459			02/03/22	5,150.00	17.42	26.98	12.00
C0762-055			02/17/22	3,765.00	18.00	12.96	15.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	6,008.00	12.00	15.63	19.00
C0761-239							
NHPP0703-472			03/10/22	10,694.00	12.00	15.43	15.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			40,212.00	14.96	16.24	14.64
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19,116.00	15.00	14.85	16.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	18,221.00	15.00	19.58	19.58
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	21,034.00	15.00	14.03	13.25
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	174,271.00	12.25	12.25	12.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			232,642.00	12.94	13.66	13.28
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	48,840.00	14.00	13.83	13.00
ER0253-297		WCR 34 BRIDGE OVER I-25 (MM 24	09/14/22	350.00	15.00	59.35	36.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			49,190.00	14.01	14.15	13.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 553

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-01010 Preform Plastic Pvmnt Mkg (TY I) (Inlaid) Sq Foot =====							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4,329.00	20.00	18.85	19.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	409.00	20.00	28.38	27.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,100.00	20.00	20.64	19.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6,003.00	11.00	23.37	23.73
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	10,314.00	18.00	19.84	17.95
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				25,155.00	17.03	21.52	20.33
WEIGHTED AVERAGE FOR THE YEAR				347,199.00	13.62	15.45	14.16
===== 627-01011 Preform Plastic Pvmnt Mkg (Contr) (Inlaid) Sq Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	3,004.00	12.00	16.64	18.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,004.00	12.00	16.64	18.50
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	67.00	60.00	43.03	21.05
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	55,784.00	12.00	12.25	12.25
WEIGHTED AVERAGE FOR THE SECOND QUARTER				55,851.00	12.06	12.32	12.26
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4.00	65.00	35.72	42.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	65.00	35.72	42.00
WEIGHTED AVERAGE FOR THE YEAR				58,859.00	12.06	13.63	12.58
===== 627-02001 Preform Plastic Pvmnt Mkg (Ty II) Sq Foot =====							
BRC040-057			03/17/22	779.00	20.00	34.00	30.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				779.00	20.00	34.00	30.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1,873.00	25.00	36.32	35.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,873.00	25.00	36.32	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 554

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-02001 Preform Plastic Pvm Mt Mkg (Ty II) Sq Foot =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	147.00	24.00	31.02	60.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		147.00	24.00	31.02	60.00
		WEIGHTED AVERAGE FOR THE YEAR		2,799.00	23.56	35.39	34.92
===== 627-02010 Preform Plastic Pvm Mt Mkg (Ty II) (Inlaid) Sq Foot =====							
MTCE R500-218			01/06/22	39,155.00	17.50	16.88	15.50
STA0252-459			02/03/22	203.00	20.00	23.12	15.00
C0762-055			02/17/22	9,421.00	19.00	14.05	16.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	352.00	22.00	17.29	25.00
C0761-239							
NHM765-007			03/31/22	1,065.00	14.00	26.87	27.36
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50,196.00	17.75	16.31	15.91
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	14,750.00	12.50	12.50	12.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,750.00	12.50	12.50	12.50
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	397.00	20.00	40.50	36.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		397.00	20.00	40.50	36.00
		WEIGHTED AVERAGE FOR THE YEAR		65,343.00	16.58	16.04	15.26
===== 627-30110 Pvm Mt Mkg Paint (XS) Sq Foot =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	240.00	15.00	22.50	24.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		240.00	15.00	22.50	24.00
		WEIGHTED AVERAGE FOR THE YEAR		240.00	15.00	22.50	24.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 555

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30205 Thermoplastic Pvmnt Mkg (WS) Sq Foot =====							
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	514.00	20.00	33.02	37.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	1,521.00	20.00	22.83	22.55	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,035.00	20.00	26.94	26.20	
	WEIGHTED AVERAGE FOR THE YEAR		2,035.00	20.00	26.94	26.20	
===== 627-30210 Thermoplastic Pvmnt Mkg (XS) Sq Foot =====							
FSA052A-057	SH52 BOX CULVERT EXTENSION (M	08/04/22	40.00	25.00	29.67	32.50	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	25.00	29.67	32.50	
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,006.00	13.00	21.24	23.00	
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	24.00	15.00	26.31	14.93	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	5,788.00	15.00	14.68	13.80	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,818.00	14.70	16.39	15.16	
	WEIGHTED AVERAGE FOR THE YEAR		6,858.00	14.76	16.45	15.26	
===== 627-30310 Plastic Pvmnt Mkg (60 Mil) (XS) Sq Foot =====							
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	479.00	15.00	28.95	29.90	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		479.00	15.00	28.95	29.90	
	WEIGHTED AVERAGE FOR THE YEAR		479.00	15.00	28.95	29.90	
===== 627-30324 Preform Plastic Pvmnt Mkg (WS) (TY I) Sq Foot =====							
ER007A-035		03/15/22	145.00	18.87	20.20	20.20	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		145.00	18.87	20.20	20.20	
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV	06/23/22	488.00	22.00	47.38	47.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		488.00	22.00	47.38	47.00	
	WEIGHTED AVERAGE FOR THE YEAR		633.00	21.28	45.50	40.86	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 556

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30329 Preform Plastic Pvmnt Mkg (XS) (TY I) Sq Foot =====							
ER007A-035			03/15/22	140.00	12.75	13.65	13.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		140.00	12.75	13.65	13.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	549.00	15.00	26.50	26.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		549.00	15.00	26.50	26.00
		WEIGHTED AVERAGE FOR THE YEAR		689.00	14.54	25.73	23.49
===== 627-30405 Preform Thermoplastic Pvmnt Mkg (WS) Sq Foot =====							
MTCE R500-218			01/06/22	4,337.00	18.00	22.13	20.50
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	344.00	16.00	25.09	19.55
STR0505-050			01/13/22	1,387.00	30.00	22.32	25.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	26,783.00	12.50	17.11	15.05
NHPP1601-083			02/03/22	490.00	18.00	36.56	32.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	393.10	25.00	26.85	30.00
NHPP0703-472			03/10/22	396.00	16.00	21.69	23.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	451.00	30.00	23.55	22.10
BRC040-057			03/17/22	28.00	17.00	28.50	25.00
NHM765-007			03/31/22	512.00	28.00	21.85	21.09
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35,121.10	14.61	18.12	16.84
NH0504-911			04/07/22	1,718.56	13.15	22.10	23.20
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,193.00	30.00	28.80	32.26
STA0712-019		SH 71: Frieight Improvements	05/12/22	522.00	27.00	15.53	15.53
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	885.00	22.00	17.75	17.00
CM760-047		COLFAX AND QUAIL	05/12/22	1,123.00	20.00	17.15	15.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,759.00	19.00	21.36	21.36
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	268.00	32.00	23.54	26.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	12,628.03	15.00	17.40	15.25
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	44,250.00	12.00	12.00	12.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		64,346.59	13.63	16.17	13.78
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	567.00	22.00	58.42	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 557

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30405	Preform Thermoplastic Pvmt Mkg (WS)	Sq Foot					
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	1,450.00	25.00	29.75	33.75	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,017.00	24.16	34.44	39.72	
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22	100.00	30.00	32.27	32.80	
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA	10/27/22	698.95	15.00	18.73	17.90	
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	220.00	30.00	23.00	23.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	525.00	30.00	40.13	39.00	
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	1,055.00	20.00	24.22	22.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	566.00	15.00	29.55	30.10	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,246.00	17.00	20.49	22.26	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	145.00	30.00	31.23	25.00	
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22	76.00	40.00	32.13	29.26	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	283.00	30.00	32.04	34.37	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	676.00	23.00	24.24	27.48	
NHM175-029	CANON CITY, CO	12/15/22	2,399.10	30.00	25.00	25.00	
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	31.00	35.00	77.39	35.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,021.05	23.82	25.16	25.50	
	WEIGHTED AVERAGE FOR THE YEAR		109,505.74	14.88	18.64	16.10	
===== 627-30407	Preform Thermoplastic Pvmt Mkg (WS) (Sp)	Sq Foot					
MTCE R500-218		01/06/22	1,534.00	27.00	23.38	24.50	
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	138.00	30.00	25.15	22.00	
NHPP0063-063		02/24/22	1,740.00	20.00	19.88	20.75	
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	138.00	30.00	26.85	30.00	
STR092A-031		03/17/22	2,673.00	22.00	19.00	19.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,223.00	23.03	21.32	21.16	
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	1,649.00	24.00	19.43	16.50	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,649.00	24.00	19.43	16.50	
MTCER300-272	REGION 3 ROUNDABOUT STRIPING	07/07/22	2,300.00	24.00	26.17	22.50	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 558

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30407	Preform Thermoplastic Pvmt Mkg (WS) (Sp)		Sq Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3,434.00	25.00	25.40	22.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,734.00	24.60	25.78	22.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	97.00	30.00	36.90	40.00
C5502-097		US550 MP 117.28-126.06	11/17/22	872.00	30.00	37.16	34.60
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	656.00	22.00	28.00	26.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	691.00	30.00	28.15	28.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	484.00	20.00	33.89	35.21
STR0092-024		SH 9 North of Silverthorne	12/22/22	129.00	30.00	21.00	20.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,237.00	20.00	27.86	18.69
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,166.00	24.61	30.30	27.25
		WEIGHTED AVERAGE FOR THE YEAR		17,772.00	24.00	25.28	22.49
=====	627-30408	Pre Thermo Pvmt Mkg (Shield)		Sq Foot	=====		
NHPP0703-472			03/10/22	744.00	24.00	23.68	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		744.00	24.00	23.68	25.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	4,790.00	22.50	22.50	22.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,790.00	22.50	22.50	22.50
		WEIGHTED AVERAGE FOR THE YEAR		5,534.00	22.70	22.95	22.84
=====	627-30410	Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
MTCE R500-218			01/06/22	11,111.00	13.00	13.38	12.50
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	17,017.00	14.00	15.46	13.35
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	34,174.00	10.50	13.01	11.05
NHPP1601-083			02/03/22	36.00	20.00	94.42	22.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	184.00	30.00	18.24	20.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	68.00	44.00	24.45	18.00
C0761-239							
NHPP0703-472			03/10/22	232.00	12.00	16.48	19.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 559

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30410	Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====	=====	=====
CR100-362			03/14/22	3,662.00	16.05	16.05	16.05
NHM765-007			03/31/22	1,470.00	20.00	20.87	16.53
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		67,954.00	12.39	14.02	12.32
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	6,005.00	15.00	14.60	12.25
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,352.00	30.00	16.68	19.25
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	797.00	20.00	15.25	17.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	55.00	20.00	51.00	25.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	10,734.00	13.00	14.24	14.24
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	68.00	30.00	20.05	19.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	118,301.00	9.75	9.75	9.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		137,312.00	10.51	11.09	10.36
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	250.00	25.00	22.80	20.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7,762.00	24.00	20.00	18.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,930.00	15.00	19.51	20.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9,942.00	22.28	19.84	18.49
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	192.00	25.00	21.13	20.40
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,154.00	22.00	16.00	16.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,494.00	30.00	13.63	13.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	478.00	15.00	16.99	16.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	140.00	12.72	17.64	22.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	264.00	16.00	36.67	40.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	116.00	12.00	24.49	22.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	120.00	25.00	26.09	27.17
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	5,540.00	18.00	18.01	14.73
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	7,234.00	11.00	16.56	18.11
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	48.00	25.00	52.59	21.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	120.00	20.00	16.69	13.31
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		18,900.00	17.75	17.17	16.42
		WEIGHTED AVERAGE FOR THE YEAR		234,108.00	12.14	13.75	11.76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30411		Preform Thermoplastic Pvmnt Mkg (XS) (Sp)		Sq Foot	=====		
MTCE R500-218			01/06/22	207.00	28.00	17.75	16.00
STR0505-050			01/13/22	1,820.00	20.00	16.32	17.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	350.00	20.00	17.06	13.00
STR0141-031			02/17/22	850.00	40.00	17.67	16.00
NHPP0063-063			02/24/22	5,352.00	15.00	14.35	15.00
STR092A-031			03/17/22	415.00	17.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,994.00	18.96	15.59	15.54
NH0504-911			04/07/22	1,344.00	12.91	15.60	17.20
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	16,124.00	12.00	13.37	11.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17,468.00	12.07	13.48	12.03
MTCE300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	4,000.00	22.00	21.83	18.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,953.00	18.00	25.40	22.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,953.00	20.30	23.01	19.70
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	5,233.33	12.00	16.66	13.90
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,050.00	12.00	17.07	19.79
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	912.00	20.00	26.33	23.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	730.00	18.00	21.22	18.75
NHM175-029		CANON CITY, CO	12/15/22	4,765.84	20.00	15.00	15.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	28.00	17.00	31.75	28.18
STR0092-024		SH 9 North of Silverthorne	12/22/22	130.00	25.00	16.55	15.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13,849.17	15.73	17.32	16.05
		WEIGHTED AVERAGE FOR THE YEAR		47,264.17	15.66	16.35	15.00
===== 628-00001		Brdg Girder + Deck Unit		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	72652.26	72652.26	72652.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	72652.26	72652.26	72652.26
		WEIGHTED AVERAGE FOR THE YEAR		2.00	72652.26	72652.26	72652.26

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 561

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 629-01001 Survey Monument (Ty 1) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	19.00	1020.00	459.76	215.09
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		19.00	1020.00	459.76	215.09
===== 629-01002 Survey Monument (Ty 2) Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	86.00	200.00	156.53	136.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		86.00	200.00	156.53	136.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	794.46	1000.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	8.00	1000.00	1840.89	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		10.00	1000.00	1555.50	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			115.00	405.04	355.88	258.98
===== 629-01003 Survey Monument (Ty 3) Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	5350.00	5350.00	5350.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		6.00	5350.00	5350.00	5350.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	5350.00	5350.00	5350.00
===== 629-01004 Survey Monument (Ty 4) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1500.00	1361.05	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		2.00	1500.00	1361.05	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1500.00	1361.05	1500.00
===== 629-01004 Survey Monument (Ty 4) Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	10.00	400.00	1010.00	440.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		10.00	400.00	1010.00	440.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	400.00	1010.00	440.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 562

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 629-01005 Survey Monument (Ty 5) Each =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		6.00	400.00	173.20	150.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	400.00	173.20	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	535.00	1988.81	500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	1108.74	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	690.00	1849.85	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	545.00	1447.46	575.00
===== 629-01006 Survey Monument (Ty 6) Each =====							
NHM765-007			03/31/22	68.00	500.00	239.18	399.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			68.00	500.00	239.18	399.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	800.00	323.72	280.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	800.00	323.72	280.00
	WEIGHTED AVERAGE FOR THE YEAR			73.00	520.55	243.13	390.85
===== 629-01031 Survey Monument (Ty 3A) Each =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	1000.00	1358.27	1358.27
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	9.00	1000.00	1425.00	2000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	1000.00	1418.33	1883.32
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3.00	1200.00	850.00	850.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	970.00	1683.33	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1142.50	1266.67	1137.50
	WEIGHTED AVERAGE FOR THE YEAR			15.00	1038.00	1383.33	1684.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 563

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 629-01050 Monument Box Each =====							
NHPP0063-063			02/24/22	6.00	1200.00	1436.50	2000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	1200.00	1436.50	2000.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1200.00	1436.50	2000.00
===== 629-01065 Survey Monument (Ty 5S) Each =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	21.00	900.00	443.33	184.36
CR100-362			03/14/22	10.00	891.31	891.31	891.31
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			31.00	897.20	490.99	412.41
C1211-099 SH 121 NORTH SGA SIGNALS 08/25/22							
				5.00	500.00	825.00	550.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	500.00	825.00	550.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	842.03	523.10	431.52
===== 629-01110 Locate Monuments Hour =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	8.00	300.00	250.69	245.81
NHPP0063-063			02/24/22	70.00	300.00	177.00	185.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			78.00	300.00	190.71	191.24
	WEIGHTED AVERAGE FOR THE YEAR			78.00	300.00	190.71	191.24
===== 629-01210 Adjust Monument Box Each =====							
NHPP0063-063			02/24/22	25.00	800.00	1058.50	1325.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	800.00	1058.50	1325.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	800.00	1058.50	1325.00
===== 630-00000 Flagging Hour =====							
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT		01/06/22	1,200.00	35.00	40.00	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00000	Flagging		Hour =====			
MTCE R500-218			01/06/22	1,440.00	30.00	26.40	12.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	800.00	30.00	46.49	55.26
STR0505-050			01/13/22	2,000.00	28.00	24.33	15.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	600.00	40.00	33.86	33.33
MTCE400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	600.00	20.00	27.25	12.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,500.00	32.00	38.58	38.00
MTCE300-262			02/03/22	500.00	31.00	21.67	1.00
NHPP1601-083			02/03/22	7,680.00	30.00	31.96	28.00
STA0252-459			02/03/22	150.00	30.00	40.65	35.90
C0762-055			02/17/22	3,500.00	28.00	39.31	48.00
STR0141-031			02/17/22	3,000.00	35.00	35.53	39.60
STR133A-051			02/17/22	2,500.00	30.00	21.67	20.00
NHPP0063-063			02/24/22	5,000.00	30.00	25.70	25.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4,000.00	25.00	31.72	29.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,000.00	30.00	44.05	39.00
C0761-239							
NHPP0703-472			03/10/22	600.00	30.00	39.49	38.00
CR100-362			03/14/22	500.00	40.66	40.66	40.66
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4,500.00	30.00	32.08	33.15
BRC040-057			03/17/22	500.00	30.00	44.75	32.00
STR R500-171		Various locations on SH 141 a	03/17/22	3,300.00	42.25	37.80	35.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	55.00	47.50	53.00
STR092A-031			03/17/22	7,000.00	30.00	31.00	31.00
NHM765-007			03/31/22	11,000.00	30.00	48.27	39.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	500.00	38.00	46.00	44.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				66,420.00	30.73	36.92	32.83
NH0504-911			04/07/22	3,000.00	25.00	34.40	35.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	500.00	30.00	40.42	40.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8,200.00	42.80	42.80	42.80
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6,300.00	31.00	42.05	32.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	800.00	35.00	41.06	33.11
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,000.00	32.00	32.95	35.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	4,392.00	35.00	36.50	36.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	6,600.00	30.00	45.54	45.54
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	4,100.00	36.00	47.45	52.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,300.00	30.00	50.33	56.00
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	31.00	42.40	68.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3,750.00	35.00	59.00	42.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1,500.00	32.00	27.02	27.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2,000.00	41.00	45.00	45.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	480.00	35.00	42.75	36.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	800.00	35.00	43.07	45.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,500.00	30.00	45.50	45.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00000							
		Flagging		Hour			
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,000.00	35.00	48.15	46.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	140.00	25.00	42.33	12.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	500.00	30.00	46.33	44.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2,000.00	35.00	45.00	43.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				52,892.00	34.15	41.46	40.82
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	550.00	30.00	16.00	16.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	200.00	30.00	53.25	150.00
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	300.00	30.00	65.00	25.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,196.00	46.14	46.14	46.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	50.00	62.22	64.35
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	800.00	33.00	35.33	40.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11,520.00	38.00	40.18	41.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2,000.00	30.00	39.17	35.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	200.00	40.00	34.50	32.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1,100.00	45.00	40.92	39.08
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2,500.00	42.80	42.80	42.80
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	900.00	32.00	55.12	55.12
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	800.00	25.00	55.06	47.17
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	320.00	35.00	41.27	46.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6,800.00	25.00	44.45	58.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2,000.00	30.00	39.92	37.49
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,000.00	45.00	35.86	33.92
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,700.00	45.00	17.21	2.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				41,006.00	36.88	40.18	42.31
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	900.00	45.00	39.67	54.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	350.00	65.00	34.00	38.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	900.00	45.00	42.95	50.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	3,200.00	32.00	37.58	39.75
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,580.00	35.00	44.68	47.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	100.00	30.00	44.00	42.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	800.00	35.00	41.10	39.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	720.00	35.00	47.75	50.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9,600.00	30.00	31.44	25.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4,500.00	40.00	46.00	46.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,198.00	30.00	44.00	48.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,500.00	40.00	47.37	44.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
===== 630-00000	Flagging			Hour =====			
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,200.00	33.00	41.80	39.41	
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	3,300.00	45.00	41.10	40.00	
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	2,250.00	40.00	51.50	52.80	
C5502-097	US550 MP 117.28-126.06	11/17/22	11,000.00	45.00	40.71	41.10	
MPR200-280	PUEBLO AREA	11/17/22	10.00	24.20	22.50	20.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	300.00	30.00	38.25	39.50	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3,120.00	32.00	44.49	48.15	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71: REGION LINE NORTH	12/01/22	3,330.00	30.00	41.33	37.00	
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22	8,000.00	45.00	38.00	36.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,000.00	40.00	45.18	46.00	
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	3,600.00	45.00	41.50	38.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	28.00	38.33	35.00	
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,930.00	45.00	48.60	47.50	
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22	500.00	35.00	45.36	39.71	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	500.00	50.00	48.58	49.11	
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1,750.00	45.00	46.33	42.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	1,000.00	31.00	46.98	47.95	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	2,000.00	45.00	44.91	40.00	
NHM175-029	CANON CITY, CO	12/15/22	2,000.00	30.00	32.50	50.00	
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	80.00	65.00	54.32	54.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	2,300.00	35.00	44.62	40.50	
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22	5,830.00	40.00	45.98	42.79	
STR0092-024	SH 9 North of Silverthorne	12/22/22	4,000.00	45.00	43.65	45.30	
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22	3,500.00	45.00	49.12	40.04	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,500.00	35.00	39.27	38.00	
STA385A-016	SH 385 MP 97.76	12/22/22	500.00	30.00	43.61	44.44	
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22	3,400.00	30.00	37.67	36.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				101,348.00	38.99	40.84	40.61
WEIGHTED AVERAGE FOR THE YEAR				261,666.00	35.58	39.95	38.99
===== 630-00001	Pilot Car Operation			Hour =====			
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	200.00	80.00	75.00	75.00	
NHPP1601-083		02/03/22	1,350.00	50.00	67.33	70.00	
STR133A-051		02/17/22	200.00	60.00	50.00	40.00	
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,000.00	50.00	61.87	40.00	
STR092A-031		03/17/22	240.00	65.00	57.00	57.00	
C0703-499	EJMT GROUT BED REPAIR AND PAN	03/31/22	550.00	70.00	191.00	207.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,540.00	56.38	81.14	80.52
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	600.00	52.00	112.34	120.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				600.00	52.00	112.34	120.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 567

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00001 Pilot Car Operation Hour =====							
MTCE 072A-045	SH 72B MP 37.00 TO MP 45.3 NE	07/07/22		165.00	75.00	40.00	40.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			165.00	75.00	40.00	40.00
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS	10/13/22		300.00	120.00	78.00	119.00
STA3852-015	US 385 HOLYOKE NORTH	10/27/22		800.00	90.00	120.00	120.00
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22		300.00	80.00	77.10	75.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22		1,100.00	90.00	100.00	90.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22		480.00	70.00	95.45	80.90
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22		300.00	100.00	91.50	50.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,280.00	89.82	93.52	96.23
	WEIGHTED AVERAGE FOR THE YEAR			7,585.00	70.90	90.85	89.79
===== 630-00003 Uniformed Traf Ctrl Hour =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22		750.00	120.00	163.30	155.03
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22		120.00	150.00	167.81	160.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22		1,000.00	100.00	56.48	6.00
BRC040-057		03/17/22		100.00	110.00	129.75	120.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC	03/17/22		20.00	120.00	139.00	146.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,990.00	111.26	116.12	78.59
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	04/18/22		200.00	171.20	171.20	171.20
STM1151-038	SH115 MP 27 TO MP 38	04/21/22		800.00	110.00	121.30	115.00
CM760-047	COLFAX AND QUAIL	05/12/22		25.00	125.00	168.20	163.00
STAR100-358	3 STRUCTURES IN REGION 1 METR	05/26/22		300.00	150.00	142.32	148.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS	05/26/22		500.00	160.00	145.00	145.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS	06/02/22		48.00	110.00	116.00	138.00
MPR200-278	R2 - VARIOUS LOCATIONS	06/09/22		150.00	200.00	166.67	125.00
MPR200-279	FY 23 STENCIL MARKING PROJECT	06/09/22		140.00	100.00	146.67	115.00
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV	06/23/22		280.00	130.00	144.50	138.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,443.00	137.55	134.51	133.99

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 568

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
===== 630-00003	Uniformed Traf Ctrl			Hour	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	200.00	164.79	164.79	164.79
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	60.00	150.00	148.00	146.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	560.00	150.00	185.50	185.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	120.00	138.17	132.50
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	100.00	120.00	180.88	198.78
WEIGHTED AVERAGE FOR THE THIRD QUARTER				970.00	148.41	174.53	177.42
<hr/>							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	144.00	120.00	109.50	110.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	100.00	183.87	154.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	120.00	120.00	171.33	208.99
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	150.00	171.50	150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	160.00	120.00	145.39	228.07
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	150.00	147.28	160.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	400.00	175.00	201.24	245.53
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,674.00	133.44	168.79	183.76
WEIGHTED AVERAGE FOR THE YEAR				7,077.00	130.67	141.10	136.14
<hr/>							
===== 630-00004	Traf Ctrl Vehicle			Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	6000.00	17413.04	9301.64
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1.00	6000.00	17413.04	9301.64
<hr/>							
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	5000.00	8501.25	8120.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	5000.00	8501.25	8120.00
<hr/>							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2500.00	23223.33	13000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 569

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
===== 630-00004				Each	=====		
2670703-487		Traf Ctrl Vehicle					
		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	10000.00	12844.00	13800.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	9500.00	27850.51	24552.66
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5.00	6900.00	18959.10	15630.53
WEIGHTED AVERAGE FOR THE YEAR				7.00	6500.00	17244.26	13653.47
=====							
===== 630-00006				Hour	=====		
BRC040-057			03/17/22	100.00	30.00	100.00	105.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	20.00	30.00	44.00	35.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	200.00	125.00	236.50	250.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				320.00	89.38	162.33	191.25
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	600.00	70.00	123.20	170.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	48.00	40.00	88.50	83.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,000.00	50.00	149.68	149.68
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,648.00	56.99	128.13	155.14
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	60.00	35.00	99.50	49.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	35.00	60.50	79.50
WEIGHTED AVERAGE FOR THE THIRD QUARTER				110.00	35.00	77.83	62.86
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	220.00	38.90	29.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	100.00	128.64	25.65
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,050.00	128.57	103.43	26.45
WEIGHTED AVERAGE FOR THE YEAR				3,128.00	83.56	118.89	112.39
=====							
===== 630-00007				Day	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	30.00	250.00	395.00	395.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
MTCE R500-218			01/06/22	11.00	400.00	180.60	150.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	30.00	300.00	255.40	186.03
STR0505-050			01/13/22	22.00	350.00	277.67	250.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	135.00	300.00	402.35	277.78
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	189.00	400.00	598.47	845.00
NHPP1601-083			02/03/22	81.00	250.00	273.98	240.00
STA0252-459			02/03/22	74.00	300.00	359.38	373.00
C0762-055			02/17/22	55.00	250.00	322.94	750.00
STR0141-031			02/17/22	34.00	500.00	391.67	450.00
STR133A-051			02/17/22	10.00	425.00	278.33	375.00
NHPP0063-063			02/24/22	46.00	250.00	332.00	400.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	36.00	200.00	254.12	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	206.00	400.00	299.78	170.00
C0761-239							
NHPP0703-472			03/10/22	28.00	300.00	317.80	275.00
CR100-362			03/14/22	60.00	187.25	187.25	187.25
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	70.00	300.00	227.87	165.74
BRC040-057			03/17/22	50.00	300.00	223.50	200.00
STR R500-171		Various locations on SH 141 a	03/17/22	42.00	1012.00	907.56	700.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	16.00	100.00	249.50	313.00
STR092A-031			03/17/22	42.00	300.00	218.00	218.00
MP0503-098			03/24/22	10.00	200.00	313.00	308.00
NHM765-007			03/31/22	150.00	250.00	924.10	627.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	80.00	400.00	435.50	500.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,507.00	336.49	421.25	407.82
NH0504-911			04/07/22	150.00	250.00	99.70	119.40
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	55.00	275.00	380.91	500.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	28.00	481.50	481.50	481.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	230.00	250.00	162.83	150.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	8.00	350.00	224.37	123.74
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	256.00	265.00	327.09	375.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	53.00	300.00	430.00	400.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	50.00	350.00	465.77	465.77
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	300.00	208.00	230.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	90.00	265.00	586.67	650.00
CM760-047		COLFAX AND QUAIL	05/12/22	14.00	240.00	194.40	88.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	38.00	200.00	650.00	350.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	34.00	350.00	193.66	265.00
C0852-120		Rehabilitation of Culvert by	05/26/22	21.00	300.00	300.00	300.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	60.00	440.00	400.00	400.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	5.00	200.00	453.50	650.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	6.00	300.00	153.83	162.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	54.00	230.00	179.62	179.62

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 571

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	33.00	500.00	294.45	200.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	20.00	250.00	315.96	318.92
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	53.00	250.00	314.00	300.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,288.00	284.18	287.67	308.16
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	2.00	350.00	120.00	120.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	180.00	549.30	549.30	549.30
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	250.00	317.67	325.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	16.00	300.00	186.67	260.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	125.00	500.00	407.98	245.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	250.00	213.33	300.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	30.00	400.00	165.50	81.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	350.00	450.52	432.11
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	55.00	139.10	267.50	267.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	46.00	275.00	556.50	556.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	65.00	250.00	523.33	848.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	15.00	400.00	410.00	275.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	8.00	400.00	249.69	180.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	90.00	300.00	373.67	600.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	300.00	300.00	257.34	255.57
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	77.00	280.00	291.83	212.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	32.00	450.00	589.09	800.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,101.00	357.48	314.11	390.32
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	10.00	250.00	261.40	420.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	400.00	488.67	486.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	18.00	200.00	275.00	400.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	35.00	400.00	397.00	410.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	65.00	330.00	235.63	235.90
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	208.00	300.00	577.25	650.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	71.00	200.00	221.50	170.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	10.00	700.00	442.00	410.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	15.00	325.00	322.45	227.78
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	110.00	250.00	771.88	1200.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	60.00	300.00	415.00	415.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	50.00	250.00	373.28	295.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	257.00	400.00	462.45	408.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	24.00	230.00	382.25	256.76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
===== 630-00007	Traf Ctrl Inspection			Day =====			
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	45.00	400.00	465.50	535.00	
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	28.00	350.00	237.30	247.50	
C5502-097	US550 MP 117.28-126.06	11/17/22	80.00	350.00	418.04	378.00	
MPR200-280	PUEBLO AREA	11/17/22	4.00	75.00	75.00	100.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	70.00	250.00	395.00	390.00	
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	390.00	250.38	488.61	570.17	
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71: REGION LINE NORTH	12/01/22	48.00	240.00	571.67	330.00	
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	12/01/22	50.00	500.00	660.00	320.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	248.00	400.00	397.24	430.00	
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	51.00	400.00	445.00	350.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	118.00	260.00	118.33	160.00	
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	350.00	502.00	534.00	
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22	116.00	800.00	525.46	545.92	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	300.00	577.68	982.11	
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22	27.00	400.00	304.50	250.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	40.00	250.00	229.71	233.42	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	39.00	400.00	468.03	275.00	
NHML75-029	CANON CITY, CO	12/15/22	22.00	350.00	537.50	1000.00	
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	12/15/22	16.00	250.00	237.64	231.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	55.00	250.00	287.46	256.00	
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22	56.00	300.00	475.21	533.50	
STR0092-024	SH 9 North of Silverthorne	12/22/22	52.00	400.00	467.50	485.00	
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22	30.00	350.00	272.10	400.36	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	180.00	350.00	428.34	350.00	
STA385A-016	SH 385 MP 97.76	12/22/22	60.00	300.00	446.61	444.44	
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22	46.00	250.00	363.33	400.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,874.00	338.78	433.12	427.82	
WEIGHTED AVERAGE FOR THE YEAR			6,770.00	330.92	388.64	397.28	
=====							
===== 630-00012	Traf Ctrl Mgmt			Day =====			
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	241.00	900.00	2285.00	2285.00	
MTCE R500-218		01/06/22	36.00	900.00	1209.00	450.00	
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22	170.00	900.00	1475.64	1121.23	
STR0505-050		01/13/22	40.00	1100.00	983.33	1000.00	
NH0504-910	US50B L-24-B MIN REP AT MP 40	01/13/22	45.00	1100.00	984.49	888.89	
MTCER400-391	VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	65.00	250.00	656.25	250.00	
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	237.00	1300.00	1642.26	1580.00	
MTCER300-262		02/03/22	150.00	1200.00	1500.00	1000.00	
NHPP1601-083		02/03/22	180.00	900.00	1280.98	1500.00	
STA0252-459		02/03/22	185.00	900.00	1879.00	1415.00	
C0762-055		02/17/22	135.00	1500.00	1894.27	2400.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012 Traf Ctrl Mgmt Day =====							
STR0141-031			02/17/22	68.00	1200.00	1416.67	1500.00
STR133A-051			02/17/22	25.00	1200.00	1343.33	1000.00
NHPP0063-063			02/24/22	115.00	1000.00	1277.50	1395.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	75.00	850.00	1214.33	1000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	516.00	1200.00	1569.89	1600.00
C0761-239							
NHPP0703-472			03/10/22	80.00	900.00	1563.64	1750.00
CR100-362			03/14/22	240.00	1096.75	1096.75	1096.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	100.00	1000.00	997.22	994.43
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	1012.00	1374.23	2100.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	60.00	1600.00	1361.00	1462.00
STR092A-031			03/17/22	89.00	1000.00	1305.00	1305.00
MP0503-098			03/24/22	25.00	1200.00	1350.00	1045.00
NHM765-007			03/31/22	450.00	1500.00	1990.37	1710.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	70.00	1200.00	2289.50	2315.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,487.00	1130.20	1569.17	1512.82
NH0504-911			04/07/22	180.00	1000.00	1245.00	1490.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	110.00	1100.00	1604.36	2000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	168.00	2354.00	2354.00	2354.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	310.00	1000.00	1379.81	1250.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	20.00	1300.00	1533.68	1567.35
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	437.00	950.00	1173.61	1025.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	122.00	900.00	2250.00	2300.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	180.00	1500.00	2018.35	2018.35
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	72.00	1000.00	1294.75	1800.00
CM760-047		COLFAX AND QUAIL	05/12/22	35.00	900.00	1364.80	1161.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	75.00	800.00	2550.00	1100.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	86.00	1500.00	943.37	1113.00
C0852-120		Rehabilitation of Culvert by	05/26/22	32.00	1500.00	1650.00	1650.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	120.00	1500.00	1600.00	1600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	115.00	800.00	1558.00	1540.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	20.00	950.00	851.33	818.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	105.00	1000.00	1227.38	1227.38
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	60.00	2000.00	1352.40	892.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	1000.00	516.67	225.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	37.00	200.00	600.00	150.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	50.00	1000.00	1337.45	1236.90
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	118.00	1000.00	1266.75	1210.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,467.00	1165.11	1362.77	1449.94
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	8.00	1000.00	575.00	575.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00012	Traf Ctrl Mgmt		Day =====			
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	20.00	800.00	350.00	100.00
MTCE0702-426		REGION 3 ROUNDABOUT STRIPING	07/07/22	30.00	500.00	383.33	250.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	232.00	2746.52	2746.52	2746.52
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	44.00	1200.00	1119.82	1170.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	1000.00	1266.67	1300.00
NHPP063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	375.00	1800.00	1543.39	1250.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	100.00	900.00	1033.33	1000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	120.00	1900.00	1320.00	1190.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	45.00	1500.00	1391.37	1218.55
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	150.00	1073.57	1073.57	1073.57
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	113.00	1200.00	2093.50	2093.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	450.00	1594.63	960.89
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	30.00	1500.00	1497.50	815.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	2000.00	1717.67	1500.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	190.00	1000.00	1795.83	2055.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	140.00	1000.00	1676.55	1703.82
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	200.00	1200.00	1548.00	1575.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	1600.00	1508.90	1000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2,042.00	1450.60	1551.72	1517.28
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	25.00	1600.00	1635.90	1260.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	1500.00	1290.00	1620.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	45.00	1300.00	1425.00	1500.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	81.00	1200.00	1380.00	1430.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	140.00	1100.00	1487.00	1676.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	61.00	1100.00	1910.00	1540.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	122.00	2000.00	1202.50	1095.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	1200.00	999.50	925.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	30.00	1200.00	1142.50	1150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	300.00	1200.00	1379.04	1200.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	140.00	2300.00	1875.00	1875.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	109.00	1200.00	1356.25	1300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	1850.00	1413.33	1220.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	60.00	1200.00	1563.78	1791.34
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	110.00	1500.00	1615.00	1750.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	75.00	1200.00	1553.00	1650.00
C5502-097		US550 MP 117.28-126.06	11/17/22	180.00	1200.00	1362.17	1350.00
MPR200-280		PUEBLO AREA	11/17/22	116.00	1240.00	850.00	1000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	115.00	1300.00	1502.50	1410.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	1100.00	1366.40	1900.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012 Traf Ctrl Mgmt Day =====							
STA0711-021		SH71: REGION LINE NORTH	12/01/22	102.00	1200.00	1808.33	1400.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	105.00	1200.00	1850.00	1400.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	340.00	1200.00	1447.70	1270.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	128.00	1500.00	1550.00	1300.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	265.00	925.00	1008.33	1200.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	105.00	1300.00	1550.00	1400.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	290.00	1200.00	1154.00	1045.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	1500.00	1618.70	908.45
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	50.00	1500.00	1104.50	750.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	60.00	1000.00	1630.54	1461.07
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	85.00	1400.00	1668.10	1200.00
NHM175-029		CANON CITY, CO	12/15/22	40.00	1100.00	827.50	1200.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	17.00	1300.00	1546.50	1250.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	115.00	1300.00	1614.04	1540.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	120.00	1500.00	1759.35	2062.86
STR0092-024		SH 9 North of Silverthorne	12/22/22	104.00	1300.00	1505.00	1560.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	85.00	1200.00	1497.61	1487.06
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	30.00	1000.00	1156.68	1300.00
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	1000.00	1365.28	1111.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	115.00	990.00	2100.00	1400.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,710.00	1332.51	1463.94	1381.50
WEIGHTED AVERAGE FOR THE YEAR				12,706.00	1263.46	1487.67	1451.00
===== 630-00015 Uniformed Traf Ctrl Coordination Hour =====							
STA0252-459			02/03/22	10.00	40.00	42.45	25.65
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	150.00	35.00	18.17	11.00
C0761-239							
NHPP0703-472			03/10/22	80.00	60.00	70.29	70.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				240.00	43.54	29.40	31.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	30.00	50.00	28.64	30.41
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	100.00	30.00	20.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	100.00	66.67	25.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				69.00	78.26	38.06	26.27
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	20.00	40.00	30.50	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 576

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00015 Uniformed Traf Ctrl Coordination Hour =====							
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22		20.00	50.00	64.58	27.50
STRC090-011		US 50B AND SH71/CR18 INTERSEC 11/17/22		20.00	30.00	41.00	10.00
2670703-487		I-70 BRIDGES OVER WARD ROAD- 12/01/22		100.00	15.00	36.70	29.00
NHPP083A-046		SH83 RESURFACING STROH RD TO 12/08/22		90.00	40.00	118.97	120.94
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		25.00	30.00	110.86	95.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			275.00	30.00	61.39	62.22
	WEIGHTED AVERAGE FOR THE YEAR			584.00	41.27	41.54	45.25
===== 630-00017 Traffic Control Management (Special) Day =====							
BRC040-057			03/17/22	125.00	800.00	1866.00	1500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			125.00	800.00	1866.00	1500.00
STM1151-038		SH115 MP 27 TO MP 38 04/21/22		24.00	2000.00	5492.97	4200.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS 05/12/22		160.00	1013.00	2033.33	2300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			184.00	1141.74	2725.26	2547.83
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		25.00	1100.00	2253.90	1900.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	1100.00	2253.90	1900.58
	WEIGHTED AVERAGE FOR THE YEAR			334.00	1010.72	2327.96	2107.23
===== 630-00030 Courtesy Patrol Day =====							
NHPP 0761-238		I-76 DAHLIA TO YORK 03/10/22		722.00	870.00	1417.35	1490.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			722.00	870.00	1417.35	1490.00
	WEIGHTED AVERAGE FOR THE YEAR			722.00	870.00	1417.35	1490.00
===== 630-00031 Courtesy Patrol Hour =====							
STM1151-038		SH115 MP 27 TO MP 38 04/21/22		144.00	100.00	221.56	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			144.00	100.00	221.56	200.00
	WEIGHTED AVERAGE FOR THE YEAR			144.00	100.00	221.56	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 577

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00040 Develop Traf Incident Mgmt Plan LUMP SUM =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1.00	4000.00	5460.96	3300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	4000.00	5460.96	3300.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1.00	3500.00	6381.63	5000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3500.00	6381.63	5000.00
TRG0253-264 IM025A-050	I-25 AND SH 119 PARK-N-RIDE	10/27/22		1.00	3300.00	6140.63	5700.00
	I25-MP103.9 - INTERSECTION DR	12/01/22		1.00	3000.00	11766.67	4300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	3150.00	7675.00	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	3450.00	6667.54	4575.00
===== 630-00041 Implement Traf Incident Mgmt Plan Month =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	24.00	800.00	648.87	450.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	800.00	648.87	450.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	18.00	1500.00	3211.43	500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	1500.00	3211.43	500.00
TRG0253-264 IM025A-050	I-25 AND SH 119 PARK-N-RIDE	10/27/22		12.00	450.00	968.13	600.00
	I25-MP103.9 - INTERSECTION DR	12/01/22		12.00	500.00	1066.67	1100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	475.00	995.00	850.00
	WEIGHTED AVERAGE FOR THE YEAR			66.00	872.73	1316.31	609.09

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 578

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80001		Flash Beacon (Port)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	150.00	1084.20	330.00
C0762-055			02/17/22	12.00	1000.00	1018.50	800.00
STR0141-031			02/17/22	6.00	2000.00	1583.33	1650.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	8.00	850.00	885.79	1200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	61.00	1000.00	1051.86	1050.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	13.00	1000.00	1152.47	1104.93
BRC040-057			03/17/22	10.00	1000.00	1085.75	1000.00
NHM765-007			03/31/22	16.00	1600.00	1659.91	2166.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	12.00	900.00	2629.50	2750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		148.00	1031.76	1151.88	1273.45
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	1712.00	1712.00	1712.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	20.00	850.00	919.23	850.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	6.00	1500.00	1582.62	2120.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	8.00	1200.00	536.00	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		38.00	1117.05	937.73	1078.11
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	1647.91	1647.91	1647.91
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	6.00	1200.00	604.00	108.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	12.00	6.00	6.00	6.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	6.00	2200.00	795.00	795.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	20.00	1100.00	1911.13	95.40
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	6.00	1500.00	910.93	200.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	3.00	970.00	989.47	1135.88
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		69.00	1170.27	1296.46	556.12
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	8.00	30.00	1215.00	1200.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	1000.00	1248.33	1245.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	24.00	1300.00	1723.86	3000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	6.00	1800.00	289.17	316.67
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	850.00	2417.88	2800.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80001 Flash Beacon (Port) Each =====							
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	2.00	1200.00	2100.00	2100.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	12.00	1500.00	1863.65	1900.00	
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	6.00	1000.00	1471.22	1313.65	
STR064A-010	SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	2500.00	1215.00	1000.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	8.00	900.00	1175.00	1250.00	
STA0711-021	SH71: REGION LINE NORTH	12/01/22	8.00	920.00	1376.67	1500.00	
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10.00	2000.00	1127.50	500.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	900.00	1200.00	1100.00	
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	2000.00	1535.00	1620.00	
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22	10.00	1000.00	1385.00	1254.00	
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22	6.00	25.00	1386.67	1100.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	16.00	650.00	1515.09	1530.18	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	17.00	1500.00	1270.86	1100.00	
STR0092-024	SH 9 North of Silverthorne	12/22/22	4.00	600.00	1245.00	1290.00	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	9.00	1000.00	1256.68	1500.00	
STA385A-016	SH 385 MP 97.76	12/22/22	2.00	650.00	1674.17	1666.67	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				172.00	1099.71	1444.82	1519.34
WEIGHTED AVERAGE FOR THE YEAR				427.00	1089.10	1244.15	1246.85
===== 630-80002 Flash Beacon (Solar) Each =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40	01/13/22	8.00	1500.00	1142.04	1333.33	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				8.00	1500.00	1142.04	1333.33
NH0504-911		04/07/22	44.00	1000.00	927.50	955.00	
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20	05/06/22	10.00	1000.00	1050.00	1000.00	
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	1000.00	2200.00	1400.00	
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR	06/09/22	4.00	1500.00	1387.93	700.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				60.00	1033.33	1054.38	960.33
STR0711-022	SH 71 OVER THE ARKANSAS	08/04/22	4.00	900.00	1433.33	2100.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4.00	900.00	1433.33	2100.00
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1000.00	666.95	660.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 580

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80002	Flash Beacon (Solar)		Each =====			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	1500.00	2749.60	3220.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	5.00	1400.00	1827.14	2134.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	8.00	900.00	1400.00	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	1208.00	1858.73	2202.80
	WEIGHTED AVERAGE FOR THE YEAR			97.00	1111.34	1363.00	1358.32
=====	630-80305	Flagging Station Light		Each =====			
MT CER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	4.00	400.00	562.50	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	400.00	562.50	250.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	4.00	500.00	766.67	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	500.00	766.67	150.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	450.00	650.00	200.00
=====	630-80310	Automated Flagging Assistance Device		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	10000.00	9618.56	12000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10000.00	9618.56	12000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	9618.56	12000.00
=====	630-80331	Barricade (3 F-A) (Temp)		Each =====			
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	1000.00	413.93	447.36
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	1000.00	413.93	447.36
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	413.93	447.36
=====	630-80335	Barricade (3 M-A) (Temp)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	250.00	66.00	66.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	630-80335	Barricade (3 M-A) (Temp)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	6.00	180.00	97.35	93.02
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	4.00	300.00	214.39	111.11
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	300.00	323.83	66.00
NHPP1601-083			02/03/22	2.00	300.00	1617.51	300.00
STA0252-459			02/03/22	8.00	200.00	85.02	61.50
C0762-055			02/17/22	6.00	225.00	228.68	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	55.00	150.00	113.81	110.00
C0761-239							
NHPP0703-472			03/10/22	4.00	160.00	134.10	40.00
CR100-362			03/14/22	10.00	133.75	133.75	133.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4.00	200.00	263.12	276.23
BRC040-057			03/17/22	10.00	175.00	436.25	350.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4.00	220.00	84.00	104.00
STR092A-031			03/17/22	14.00	200.00	380.50	380.50
NHM765-007			03/31/22	30.00	400.00	345.00	456.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				165.00	221.74	186.95	221.81
<hr/>							
NH0504-911			04/07/22	4.00	142.00	239.50	239.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	6.00	481.50	481.50	481.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	150.00	381.80	350.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	4.00	300.00	290.60	191.20
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	4.00	180.00	98.95	102.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	4.00	200.00	175.79	238.00
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	200.00	375.00	375.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	250.00	89.81	89.81
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	14.00	150.00	125.25	150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				44.00	222.20	209.92	236.35
<hr/>							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	494.37	494.37	494.37
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	271.67	65.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	10.00	140.00	200.19	245.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	6.00	225.00	140.50	81.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	36.00	62.08	62.08	62.08
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	4.00	250.00	190.80	190.80
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	4.00	95.00	130.67	53.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	19.00	150.00	504.58	667.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	350.00	412.08	500.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				91.00	156.81	290.88	262.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 582

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80335	Barricade (3 M-A) (Temp)			Each =====			
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4.00	300.00	235.70	395.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	220.00	1029.13	1500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	4.00	160.00	321.55	165.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	75.00	300.00	431.60	410.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	7.00	150.00	392.66	417.98
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	8.00	200.00	104.10	104.50
STR090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	400.00	287.50	190.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	15.00	400.00	409.50	430.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	24.00	175.00	256.67	320.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	250.00	133.54	141.08
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	4.00	250.00	279.19	184.14
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	8.00	500.00	286.84	250.00
NHM175-029		CANON CITY, CO	12/15/22	8.00	200.00	225.00	300.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	8.00	300.00	156.52	80.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	300.00	114.48	128.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2.00	160.00	350.00	300.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				186.00	279.41	403.27	384.18
WEIGHTED AVERAGE FOR THE YEAR				486.00	231.70	282.69	294.03
===== 630-80336	Barricade (3 M-B) (Temp)			Each =====			
MTCE R500-218			01/06/22	3.00	200.00	127.50	75.00
STR0141-031			02/17/22	2.00	350.00	496.67	700.00
NHPP0063-063			02/24/22	14.00	230.00	514.00	500.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	250.00	2894.87	50.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				25.00	240.80	1211.12	357.00
NH0504-911			04/07/22	10.00	300.00	299.00	298.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	360.00	434.34	400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	220.00	287.95	273.71
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	4.00	250.00	900.85	1394.70
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	8.00	260.00	125.25	150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				31.00	278.06	313.82	410.56
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	10.00	240.00	372.12	51.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 583

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80336	Barricade (3 M-B) (Temp)			Each =====			
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22		4.00	150.00	376.67	397.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			14.00	214.29	373.83	149.86
NHPP0705-088	I-70 AGATE STRUCTURE REHAB	10/27/22		24.00	400.00	468.20	385.00
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22		2.00	300.00	529.23	477.69
C5502-097	US550 MP 117.28-126.06	11/17/22		2.00	180.00	775.73	864.00
STA0711-021	SH71: REGION LINE NORTH	12/01/22		4.00	250.00	438.33	300.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22		15.00	180.00	429.50	430.00
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	12/01/22		5.00	350.00	380.67	193.33
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22		6.00	300.00	505.91	711.33
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22		4.00	300.00	402.67	400.00
STA385A-016	SH 385 MP 97.76	12/22/22		8.00	250.00	444.11	444.44
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			70.00	300.14	480.40	431.94
	WEIGHTED AVERAGE FOR THE YEAR			140.00	276.07	513.36	386.90
===== 630-80337	Barricade (3 M-C) (Temp)			Each =====			
C0703-499	EJMT GROUT BED REPAIR AND PAN	03/31/22		2.00	250.00	391.50	280.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	250.00	391.50	280.00
NH0504-911		04/07/22		4.00	300.00	409.00	418.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	300.00	409.00	418.00
2670703-497	I-70_GENESEE WILDLIFE XING	09/15/22		1.00	300.00	623.72	511.15
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	300.00	623.72	511.15
	WEIGHTED AVERAGE FOR THE YEAR			7.00	285.71	484.42	391.88
===== 630-80338	Barricade (3 M-D) (Temp)			Each =====			
STR0505-050		01/13/22		8.00	300.00	567.67	600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 584

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80338	Barricade (3 M-D) (Temp)		Each =====			
C0762-055			02/17/22	4.00	400.00	796.62	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	333.33	659.25	566.67
NH0504-911			04/07/22	2.00	600.00	409.00	418.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	250.00	517.53	517.53
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	300.00	490.40	503.31
		WEIGHTED AVERAGE FOR THE YEAR		26.00	315.38	611.00	532.55
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	50.00	35.42	46.00
NHPP0063-063			02/24/22	100.00	45.00	30.55	40.00
CR100-362			03/14/22	500.00	37.45	37.45	37.45
STR092A-031			03/17/22	350.00	40.00	27.00	27.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		990.00	39.62	33.10	34.36
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	55.00	73.98	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	55.00	73.98	60.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	17.00	34.54	38.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	400.00	35.00	75.50	98.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	50.00	84.98	39.94
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		800.00	30.13	62.71	68.24
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	195.00	50.00	73.57	80.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	35.80	55.34	62.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 585

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot	=====	=====	=====
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	50.00	124.83	46.26
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	100.00	45.00	45.69	46.37
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		445.00	45.69	71.68	65.11
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		2,335.00	38.18	58.13	52.93
<hr/>							
=====	630-80341	Const Traf Sign (A)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	26.00	50.00	44.00	44.00
MTCE R500-218			01/06/22	72.00	35.00	30.20	10.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	46.00	60.27	55.81
STR0505-050			01/13/22	68.00	40.00	72.00	90.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	34.00	80.00	60.67	55.56
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	56.00	20.00	20.00	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	56.00	80.00	67.10	43.00
MTCER300-262			02/03/22	18.00	40.00	43.33	10.00
NHPP1601-083			02/03/22	40.00	35.00	113.66	35.00
STA0252-459			02/03/22	36.00	69.59	69.45	41.00
C0762-055			02/17/22	66.00	60.00	203.84	56.00
STR0141-031			02/17/22	100.00	60.00	68.33	85.00
STR133A-051			02/17/22	35.00	50.00	58.33	67.00
NHPP0063-063			02/24/22	174.00	45.00	88.25	92.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	64.00	55.00	40.82	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	281.00	50.00	90.94	110.00
C0761-239							
NHPP0703-472			03/10/22	70.00	50.00	53.00	50.00
CR100-362			03/14/22	20.00	58.85	58.85	58.85
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	89.00	40.00	52.63	55.25
BRC040-057			03/17/22	56.00	51.00	51.25	35.00
STR R500-171		Various locations on SH 141 a	03/17/22	117.00	52.00	34.41	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	27.00	52.00	75.00	63.00
STR092A-031			03/17/22	79.00	50.00	54.50	54.50
MP0503-098			03/24/22	20.00	40.00	59.00	61.00
NHM765-007			03/31/22	148.00	125.00	129.69	171.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	14.00	80.00	64.00	70.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,786.00	56.25	79.39	70.92
<hr/>							
NH0504-911			04/07/22	53.00	50.00	52.85	53.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	44.00	60.00	52.03	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	52.00	74.90	74.90	74.90
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	170.00	100.00	70.31	65.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80341	Const Traf Sign (A)		Each =====			
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	18.00	65.00	182.64	265.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	35.00	58.00	92.72	54.74
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	26.00	30.00	147.50	145.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	60.00	70.00	62.10	62.10
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	92.00	64.00	83.75	38.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	57.00	52.00	51.00
CM760-047		COLFAX AND QUAIL	05/12/22	32.00	54.00	50.20	60.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	12.00	65.00	300.00	50.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	18.00	75.00	37.36	51.00
C0852-120		Rehabilitation of Culvert by	05/26/22	12.00	75.00	65.00	65.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	8.00	44.00	40.00	40.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	16.00	50.00	79.00	61.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	28.00	50.00	28.67	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	180.00	50.00	53.89	53.89
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6.00	65.00	80.65	132.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	24.00	15.00	13.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	15.00	16.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	14.00	50.00	81.02	68.03
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	110.00	75.00	61.25	70.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,038.00	64.40	67.95	59.59
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	20.00	50.00	20.00	20.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	8.00	10.00	21.25	50.00
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	8.00	50.00	50.00	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	28.00	109.86	109.86	109.86
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	78.00	75.00	70.46	71.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	14.00	62.00	63.33	55.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	84.00	50.00	63.40	75.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	9.00	50.00	83.33	105.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	18.00	50.00	60.00	54.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	28.00	35.00	59.08	69.14
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	785.00	84.24	84.24	84.24
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	18.00	60.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	52.00	55.00	86.83	79.50
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	36.00	75.00	91.50	62.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	16.00	60.00	80.79	33.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	223.00	60.00	137.93	278.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	16.00	54.00	139.13	85.19
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	45.00	60.59	58.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	34.00	60.00	29.51	5.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,525.00	72.17	90.48	106.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80341	Const Traf Sign (A)			Each =====			
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	22.00	180.00	67.06	110.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	58.00	70.00	35.93	37.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	22.00	60.00	70.00	100.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	50.00	50.00	75.95	75.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	20.00	80.00	61.10	68.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	32.00	65.00	93.12	106.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	22.00	60.00	64.75	65.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	22.00	60.00	70.00	68.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	8.00	150.00	151.42	146.67
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	35.00	55.00	372.99	625.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	26.00	75.00	115.00	115.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	40.00	54.00	135.35	212.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	126.00	65.00	98.21	99.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	102.00	50.00	80.90	65.69
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	50.00	87.25	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	60.00	70.48	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	176.00	65.00	99.16	113.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	68.00	60.00	73.00	85.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	76.00	57.10	104.52	103.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	40.00	52.00	77.33	50.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	66.00	60.00	80.00	50.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	152.00	60.00	96.28	100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	88.00	60.00	75.00	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	106.00	45.00	79.00	65.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	12.00	50.00	77.35	64.70
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	8.00	55.00	77.75	104.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	44.00	65.00	92.87	92.07
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	42.00	50.00	84.33	75.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	52.00	65.00	62.05	63.09
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	29.00	45.00	71.84	60.00
NHM175-029		CANON CITY, CO	12/15/22	68.00	40.00	100.00	125.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	14.00	120.00	54.90	80.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	184.00	55.00	68.59	56.40
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	79.00	50.00	91.52	113.81
STR0092-024		SH 9 North of Silverthorne	12/22/22	40.00	50.00	93.55	97.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	24.00	50.00	89.49	93.33
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	31.00	50.00	70.34	90.00
STA385A-016		SH 385 MP 97.76	12/22/22	8.00	35.00	69.61	44.44
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	50.00	54.00	101.67	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,102.00	59.01	95.70	92.53
WEIGHTED AVERAGE FOR THE YEAR				6,451.00	62.23	85.51	84.70

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342		Const Traf Sign (B)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	84.00	70.00	55.00	55.00
MTCE R500-218			01/06/22	18.00	40.00	33.40	20.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	66.00	66.00	70.26	68.21
STR0505-050			01/13/22	54.00	50.00	81.33	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	100.00	77.55	66.67
MTCE400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	40.00	20.00	21.25	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	61.00	80.00	84.83	54.00
MTCE300-262			02/03/22	78.00	40.00	76.67	50.00
NHPP1601-083			02/03/22	93.00	50.00	78.67	40.00
STA0252-459			02/03/22	102.00	90.17	108.19	51.25
C0762-055			02/17/22	154.00	85.00	379.10	69.00
STR0141-031			02/17/22	16.00	70.00	71.67	85.00
STR133A-051			02/17/22	100.00	60.00	67.33	78.00
NHPP0063-063			02/24/22	28.00	75.00	93.85	98.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	32.00	65.00	45.22	46.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	145.00	70.00	96.31	110.00
C0761-239							
NHPP0703-472			03/10/22	58.00	70.00	67.00	70.00
CR100-362			03/14/22	33.00	69.55	69.55	69.55
BRC040-057			03/17/22	84.00	75.00	58.00	40.00
STR R500-171		Various locations on SH 141 a	03/17/22	48.00	61.00	39.26	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	27.00	71.00	138.00	77.00
STR092A-031			03/17/22	161.00	80.00	65.25	65.25
MP0503-098			03/24/22	30.00	60.00	71.00	72.00
NHM765-007			03/31/22	35.00	150.00	160.00	210.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	21.00	90.00	104.00	113.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,573.00	70.35	115.03	67.36
NH0504-911			04/07/22	108.00	75.00	94.85	59.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	4.00	70.00	55.77	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	67.00	85.60	85.60	85.60
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	40.00	70.00	107.09	100.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	52.00	75.00	194.49	83.98
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	55.00	70.00	129.03	105.83
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	80.00	40.00	170.00	165.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	114.00	80.00	72.45	72.45
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	24.00	84.00	178.00	55.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	34.00	74.00	63.00	64.00
CM760-047		COLFAX AND QUAIL	05/12/22	32.00	92.00	54.40	63.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	56.00	90.00	302.50	55.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	47.00	100.00	80.25	95.00
C0852-120		Rehabilitation of Culvert by	05/26/22	4.00	100.00	75.00	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342		Const Traf Sign (B)		Each =====			
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	64.00	60.00	100.00	100.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	38.00	60.00	212.50	72.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	20.00	65.00	64.33	68.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	102.00	70.00	65.86	65.86
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	28.00	70.00	200.45	305.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	28.00	15.00	13.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	48.00	15.00	18.33	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	34.00	70.00	216.08	88.16
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	42.00	100.00	61.25	70.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,121.00	70.33	114.23	83.23
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	53.00	70.00	25.00	25.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	48.00	10.00	21.25	50.00
MTCE0300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	18.00	50.00	50.00	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	43.00	137.33	137.33	137.33
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	85.00	74.77	71.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	80.00	84.67	79.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	30.00	60.00	75.90	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11.00	70.00	91.67	105.00
CI211-099		SH 121 NORTH SGA SIGNALS	08/25/22	16.00	60.00	65.50	54.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	8.00	50.00	68.41	74.90
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	49.00	195.30	195.30	195.30
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	47.00	100.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	60.00	95.67	106.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	48.00	90.00	128.00	135.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	37.00	70.00	204.51	77.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	135.00	70.00	153.29	278.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	14.00	78.00	164.50	119.27
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	55.00	80.75	79.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	76.00	65.00	34.92	5.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		723.00	79.93	106.72	120.87
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	42.00	100.00	108.75	134.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	8.00	100.00	42.60	37.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	52.00	65.00	85.00	120.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	152.00	60.00	96.20	95.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	120.00	70.00	83.10	99.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	175.00	78.00	106.48	130.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342		Const Traf Sign (B)		Each =====			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	70.00	74.75	72.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	8.00	70.00	91.50	87.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	27.00	95.00	214.36	224.45
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	28.00	87.00	381.72	630.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	78.00	95.00	125.00	125.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	78.00	1246.49	4590.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	47.00	75.00	117.78	120.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	14.00	80.00	82.19	89.57
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	98.00	60.00	98.85	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	122.00	80.00	105.08	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	27.00	80.00	120.44	119.00
MPR200-280		PUEBLO AREA	11/17/22	25.00	62.00	70.00	65.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	46.00	70.00	91.50	95.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	25.00	83.10	134.13	120.61
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	99.00	77.00	87.67	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	111.00	70.00	87.50	55.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	76.00	100.00	121.32	130.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	117.00	80.00	82.50	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	58.00	80.00	92.67	58.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	70.00	60.00	114.50	129.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	26.00	65.00	103.32	130.63
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	64.00	75.00	119.79	107.42
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	105.00	50.00	96.33	85.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	106.00	85.00	43.77	44.54
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	61.00	60.00	81.32	70.00
NHM175-029		CANON CITY, CO	12/15/22	54.00	50.00	175.00	250.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	46.00	90.00	86.90	120.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	103.00	70.00	100.40	66.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	21.00	75.00	114.06	128.04
STR0092-024		SH 9 North of Silverthorne	12/22/22	126.00	60.00	98.50	102.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	41.00	90.00	139.60	108.89
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	65.00	75.34	100.00
STA385A-016		SH 385 MP 97.76	12/22/22	62.00	40.00	93.70	77.78
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	10.00	78.00	116.67	55.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,495.00	72.42	109.88	104.91
		WEIGHTED AVERAGE FOR THE YEAR		5,912.00	72.39	111.67	93.32
===== 630-80343		Const Traf Sign (C)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	8.00	90.00	65.00	65.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	86.00	78.56	80.61
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	80.00	90.91	60.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 591

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
<hr/>							
=====	630-80343	Const Traf Sign (C)		Each	=====	=====	=====
MTCER300-262			02/03/22	8.00	50.00	86.67	60.00
STA0252-459			02/03/22	20.00	88.00	81.17	56.50
STR0141-031			02/17/22	24.00	80.00	77.33	92.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	72.00	90.00	103.19	110.00
C0761-239							
NHPP0703-472			03/10/22	14.00	90.00	78.45	80.00
BRC040-057			03/17/22	20.00	90.00	82.75	65.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	14.00	100.00	159.00	90.00
MP0503-098			03/24/22	8.00	80.00	373.00	664.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	24.00	100.00	144.50	157.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				222.00	88.41	103.23	116.14
<hr/>							
NH0504-911			04/07/22	20.00	90.00	67.85	65.70
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	60.00	32.10	32.10	32.10
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	16.00	80.00	225.70	96.40
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	95.00	182.80	127.73
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	84.00	70.00	70.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	12.00	200.00	105.00	132.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	16.00	75.00	120.00	120.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14.00	80.00	233.85	310.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	8.00	15.00	21.67	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	15.00	18.33	5.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	10.00	200.00	61.25	70.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				192.00	69.05	101.12	75.82
<hr/>							
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	8.00	10.00	21.25	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	32.00	164.79	164.79	164.79
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	8.00	100.00	102.33	92.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	90.00	100.90	150.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	90.00	125.00	105.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	12.00	135.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	4.00	65.00	119.50	132.50
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	9.00	90.00	174.71	79.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	10.00	110.00	194.05	141.99
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	65.00	113.79	106.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				97.00	113.44	135.74	123.71
<hr/>							
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	22.00	120.00	123.09	145.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80343 Const Traf Sign (C) Each =====							
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	12.00	90.00	95.00	130.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	32.00	110.00	135.83	136.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	16.00	80.00	87.50	82.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	100.00	261.47	248.89
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	105.00	381.25	635.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	90.00	127.60	127.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	16.00	70.00	92.50	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	18.00	90.00	115.84	66.00
MPR200-280		PUEBLO AREA	11/17/22	25.00	62.00	72.50	65.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	100.00	118.00	120.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	100.00	96.00	65.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	37.00	150.00	129.84	140.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	90.00	90.00	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	110.00	118.33	100.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	12.00	70.00	146.50	173.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	5.00	75.00	133.54	141.08
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8.00	120.00	146.75	184.15
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	16.00	60.00	117.00	95.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	100.00	56.77	57.54
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	75.00	90.79	80.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				323.00	97.43	125.53	115.39
WEIGHTED AVERAGE FOR THE YEAR				834.00	90.36	114.84	107.56
===== 630-80344 Const Traf Sign (Spec) Sq Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	30.00	38.72	49.61
C0762-055			02/17/22	518.00	31.00	50.97	115.00
STR0141-031			02/17/22	96.00	35.00	28.67	31.00
STR133A-051			02/17/22	292.00	25.00	26.00	28.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	520.00	30.00	46.34	28.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	98.00	19.00	21.72	30.00
STR092A-031			03/17/22	160.00	50.00	32.50	32.50
NHM765-007			03/31/22	160.00	25.00	44.51	21.66
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,894.00	30.45	43.39	52.46
NH0504-911			04/07/22	128.00	20.00	22.35	22.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	28.00	32.22	36.49
STA0712-019		SH 71: Frieight Improvements	05/12/22	380.00	28.00	87.98	87.98
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	140.00	35.00	67.00	24.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80344							
		Const Traf Sign (Spec)		Sq Foot			
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	96.00	35.00	30.00	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	35.00	47.90	47.90
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.00	20.00	52.75	32.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				939.00	28.23	53.98	53.11
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	238.00	26.00	41.87	45.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	600.00	23.00	29.36	38.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	27.00	50.00	54.02	57.62
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	40.00	26.27	15.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	80.00	30.00	35.81	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				965.00	25.43	34.60	40.92
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	262.00	50.00	47.17	53.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	480.00	40.00	28.85	26.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	192.00	29.72	57.94	66.00
C5502-097		US550 MP 117.28-126.06	11/17/22	120.00	80.00	38.46	32.40
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	50.00	30.00	40.50	32.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	580.00	25.00	28.67	25.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	672.00	30.00	36.02	40.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	209.00	25.00	34.67	30.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	21.00	55.00	35.92	30.00
STA385A-016		SH 385 MP 97.76	12/22/22	64.00	20.00	44.58	33.33
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	64.00	26.00	23.00	26.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,714.00	34.30	36.96	35.54
WEIGHTED AVERAGE FOR THE YEAR				6,512.00	30.99	40.39	43.44
===== 630-80348							
		Const Info Sign		Each			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	6.00	300.00	233.15	66.30
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	2.00	11350.00	517.50	696.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				8.00	3062.50	304.24	223.73
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	200.00	519.50	539.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	200.00	519.50	539.00
WEIGHTED AVERAGE FOR THE YEAR				12.00	2108.33	375.99	328.82

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80350 Vert Panel Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	30.00	25.00	28.00	28.00
MTCE R500-218			01/06/22	40.00	30.00	25.00	20.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	36.00	35.00	37.21
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	80.00	26.58	40.00
MTCER300-262			02/03/22	26.00	10.00	38.33	15.00
NHPP1601-083			02/03/22	100.00	35.00	66.50	50.00
STA0252-459			02/03/22	100.00	40.00	34.78	25.65
C0762-055			02/17/22	40.00	32.00	55.72	90.00
STR R500-171		Various locations on SH 141 a	03/17/22	75.00	23.00	34.31	60.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	30.00	25.00	35.00
MP0503-098			03/24/22	40.00	30.00	49.00	28.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				555.00	31.59	40.84	40.69
NH0504-911			04/07/22	40.00	30.00	35.40	35.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	30.00	50.00	57.44	60.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	29.00	48.69	45.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	50.00	35.00	52.76	54.74
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	33.00	41.20	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	40.00	80.00	50.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	25.00	30.00	60.65	21.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				400.00	32.48	50.30	44.71
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	50.00	10.00	13.75	25.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	100.00	35.00	24.07	26.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	150.00	38.00	56.67	75.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	200.00	32.00	46.29	5.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	11.00	35.00	69.26	72.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	35.00	63.53	58.30
WEIGHTED AVERAGE FOR THE THIRD QUARTER				611.00	32.71	47.38	37.19
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	180.00	50.00	20.25	20.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	100.00	32.00	91.37	120.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	60.00	46.85	55.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	10.00	40.00	50.90	65.69

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80350 Vert Panel Each =====							
MPR200-280		PUEBLO AREA	11/17/22	30.00	30.00	45.00	65.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	18.00	30.00	37.00	60.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	150.00	50.00	29.50	25.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	100.00	35.00	51.67	50.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	40.00	47.98	24.55
NHMI175-029		CANON CITY, CO	12/15/22	32.00	35.00	40.00	50.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	40.00	40.00	8.98	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	30.00	27.06	22.22
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				790.00	42.61	52.57	43.90
WEIGHTED AVERAGE FOR THE YEAR				2,356.00	35.73	48.46	41.54
===== 630-80351 Vert Panel (Plastic) Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	30.00	59.50	61.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				100.00	30.00	59.50	61.00
WEIGHTED AVERAGE FOR THE YEAR				100.00	30.00	59.50	61.00
===== 630-80354 Vert Panel (Light) (SB) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	250.00	40.00	55.22	55.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				250.00	40.00	55.22	55.00
WEIGHTED AVERAGE FOR THE YEAR				250.00	40.00	55.22	55.00
===== 630-80355 Port Mesg Panel Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	6000.00	5885.00	5885.00
MTCE R500-218			01/06/22	4.00	4000.00	812.50	250.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	5400.00	7211.86	6945.24
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	10000.00	8472.64	11111.11
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	6000.00	5125.00	500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	5000.00	11659.99	6200.00
NHPP1601-083			02/03/22	3.00	4000.00	13521.96	18000.00
STA0252-459			02/03/22	2.00	5500.00	6361.67	5400.00
C0762-055			02/17/22	4.00	5000.00	7817.35	8500.00
STR0141-031			02/17/22	4.00	8000.00	12500.00	13000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80355							
		Port Mesg Panel		Each			
STR133A-051			02/17/22	3.00	5000.00	3866.67	4500.00
NHPP0063-063			02/24/22	2.00	5500.00	7180.00	7500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	6500.00	6359.01	9000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	5500.00	11493.56	11000.00
C0761-239							
NHPP0703-472			03/10/22	8.00	5500.00	3846.96	2490.00
CR100-362			03/14/22	6.00	5885.00	5885.00	5885.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	3.00	4000.00	9649.04	6298.08
BRC040-057			03/17/22	6.00	6250.00	4362.25	3500.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	5863.00	6492.30	8500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	2.00	8000.00	5064.00	7796.00
STR092A-031			03/17/22	4.00	7000.00	655.00	655.00
NHM765-007			03/31/22	3.00	15000.00	13873.09	18240.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	6000.00	19800.00	20000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				91.00	6069.10	8421.68	7393.83
NH0504-911			04/07/22	12.00	4000.00	5975.00	5950.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	7500.00	9755.14	10000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	6500.00	9192.28	8500.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	7500.00	4589.20	5623.39
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	6000.00	18959.94	19000.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	7.00	6000.00	5434.02	5434.02
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	2.00	6500.00	4852.50	6000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	6045.00	13500.00	10500.00
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	5300.00	3055.00	2500.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	6600.00	7250.00	9000.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	7500.00	5976.49	7950.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	7500.00	9900.00	9900.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	4.00	11000.00	15000.00	15000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	2500.00	13381.50	8800.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	4.00	5200.00	795.67	850.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	5500.00	6705.70	6705.70
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4.00	6500.00	7025.00	3850.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	4.00	6500.00	7209.76	5669.52
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	6.00	6000.00	6930.25	7000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				80.00	6011.00	9404.30	7992.32
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	2.00	3500.00	185.00	185.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	6000.00	9296.67	10075.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	5000.00	9089.45	13000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80355	Port Mesq Panel		Each	=====	=====	=====
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	6000.00	3366.67	3800.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	4.00	8500.00	5250.00	3240.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	3.00	4000.00	5158.47	5761.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	2251.06	2251.06	2251.06
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	8000.00	8480.00	8480.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	5.00	6500.00	12066.67	15900.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	7000.00	5500.00	1900.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2.00	9000.00	5315.57	1200.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	9.00	10000.00	10037.13	10500.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	2.00	10000.00	11785.04	14198.59
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	10000.00	9245.83	7950.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5500.00	11011.61	15000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				53.00	6868.04	8531.56	8139.21
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	6000.00	3632.11	9000.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	3.00	10000.00	2746.67	3240.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	7000.00	5625.00	8000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	9000.00	7080.00	7500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	10000.00	11230.00	8690.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2.00	7000.00	10994.41	22300.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	4000.00	6875.00	6400.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	3600.00	4350.00	4500.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	6.00	7000.00	1717.72	1938.89
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	6500.00	6299.38	500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3.00	10000.00	13000.00	13000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	6000.00	13256.25	5900.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	21.00	10000.00	15359.90	19100.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	7100.00	7903.32	6209.97
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	3.00	10000.00	9750.00	10000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	5000.00	6485.00	7150.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	5500.00	14945.74	16210.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	4.00	4000.00	7675.00	8750.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	5618.50	3196.29	10.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	5600.00	13166.67	12000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	6000.00	12750.00	12000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	20000.00	18276.00	20700.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	9000.00	6380.00	1500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	7500.00	12333.33	10000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	9000.00	10795.00	8090.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	10000.00	21230.75	23512.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	4.00	6500.00	4668.80	184.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80355	Port Mesg Panel			Each =====			
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2.00	6000.00	8566.67	8500.00	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	4.00	5250.00	3127.18	3154.36	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	5.00	10000.00	6242.46	5775.00	
NHM175-029	CANON CITY, CO	12/15/22	6.00	4000.00	5500.00	7500.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	5500.00	6284.16	5740.00	
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	7000.00	12301.44	15293.68	
STR0092-024	SH 9 North of Silverthorne	12/22/22	4.00	8000.00	11170.00	11590.00	
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22	2.00	7000.00	6524.09	7588.94	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	3.00	6000.00	7803.44	7500.00	
STA385A-016	SH 385 MP 97.76	12/22/22	2.00	5500.00	11850.00	11200.00	
STR096A-050	SH 96 MP 168.99 TO 193.77	12/22/22	4.00	6000.00	9833.33	14000.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		155.00	8062.89	9464.39	9878.35	
	WEIGHTED AVERAGE FOR THE YEAR		379.00	6983.96	9080.97	8672.31	
===== 630-80356	Flash Arrow Panel (A Ty)			Each =====			
CM760-047	COLFAX AND QUAIL	05/12/22	2.00	1050.00	931.60	313.00	
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2	06/16/22	2.00	1500.00	2767.95	1785.90	
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV	06/23/22	2.00	1500.00	1267.50	1500.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	1350.00	1387.63	1199.63	
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22	4.00	3000.00	2082.00	864.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	3000.00	2082.00	864.00	
	WEIGHTED AVERAGE FOR THE YEAR		10.00	2010.00	1572.79	1065.38	
===== 630-80357	Flash Arrow Panel (B Ty)			Each =====			
MTCE R500-218		01/06/22	1.00	700.00	1187.50	1000.00	
NHPP0063-063		02/24/22	4.00	1300.00	1335.00	1400.00	
CR100-362		03/14/22	8.00	1605.00	1605.00	1605.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	1441.54	1438.61	1495.38	
STM1151-038	SH115 MP 27 TO MP 38	04/21/22	6.00	1200.00	1636.28	1500.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 599

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80357	Flash Arrow Panel (B Ty)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	1700.00	3110.51	1338.12
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	1500.00	2095.53	2095.53
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	1428.57	2277.98	1623.90
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	2000.00	1603.93	1728.46
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2000.00	1603.93	1728.46
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	3.00	1300.00	1580.00	1510.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	1600.00	2766.00	2880.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	2000.00	1492.66	1535.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2000.00	3029.97	2489.66
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	1691.67	2209.20	2056.64
		WEIGHTED AVERAGE FOR THE YEAR		40.00	1526.00	2116.37	1714.57
=====	630-80358	Flash Arrow Panel (C Ty)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	1250.00	1760.00	1760.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	3.00	1600.00	2246.44	2170.39
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	300.00	756.25	750.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	3500.00	2559.24	1800.00
MTCER300-262			02/03/22	2.00	500.00	2100.00	1800.00
STA0252-459			02/03/22	4.00	1800.00	1410.67	1354.00
C0762-055			02/17/22	2.00	1650.00	3668.00	8500.00
STR0141-031			02/17/22	2.00	3500.00	2033.33	1600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	11.00	1600.00	3672.42	4200.00
C0761-239							
NHPP0703-472			03/10/22	4.00	1500.00	640.05	350.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	5.00	2000.00	1690.58	1381.16
BRC040-057			03/17/22	2.00	1500.00	2073.50	1200.00
MP0503-098			03/24/22	3.00	1000.00	1157.50	495.00
NHM765-007			03/31/22	4.00	3500.00	5266.86	3990.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	2500.00	3470.00	3760.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	1840.00	2808.30	2524.36
NH0504-911			04/07/22	12.00	2000.00	1197.50	1195.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80358	Flash Arrow Panel (C Ty)		Each =====			
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	2000.00	3467.52	5000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	2942.50	2942.50	2942.50
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	2000.00	1370.69	1771.37
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	1500.00	1825.00	1800.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	4.00	1800.00	4657.73	4657.73
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	1500.00	1499.28	2120.00
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	3000.00	2300.00	2300.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	4.00	2200.00	2000.00	2000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	1500.00	3070.50	1650.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	4.00	100.00	283.33	100.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	4.00	100.00	333.33	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	1627.87	1508.18	1804.78
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	2.00	500.00	375.00	150.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	4614.15	4614.15	4614.15
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	1500.00	4653.67	6200.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	2200.00	2968.00	2968.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	2000.00	4033.00	4770.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	3000.00	1650.00	275.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	3.00	1800.00	1329.29	250.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	2346.50	1908.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	4000.00	3148.30	5000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		23.00	2262.10	2443.60	2988.53
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	2000.00	1048.36	2300.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	3000.00	2175.00	2500.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	2500.00	2449.96	4200.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	1000.00	1812.75	1790.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	1700.00	1804.47	1400.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	5000.00	2441.57	2700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	2000.00	2116.50	3600.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1500.00	1155.00	1210.00
MPR200-280		PUEBLO AREA	11/17/22	2.00	1560.00	1750.00	2500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	4800.00	2995.02	3160.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	2400.00	2070.00	500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1500.00	2200.00	1600.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	3000.00	4507.50	5225.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	3.00	2200.00	1123.90	55.24
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	1600.00	1006.01	1022.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 601

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	630-80358	Flash Arrow Panel (C Ty)		Each	=====		
NHM175-029		CANON CITY, CO	12/15/22	2.00	100.00	1875.00	2250.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	1500.00	728.07	380.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	4000.00	3895.00	4040.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	1700.00	1918.68	2399.42
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2.00	1700.00	2166.67	2400.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			55.00	2336.73	2033.83	2215.71
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			169.00	2007.64	2300.52	2310.27
=====							
=====	630-80359	Port Mesq Panel		Day	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	392.00	90.95	90.95	90.95
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	244.00	70.00	177.50	175.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			636.00	82.91	138.95	123.20
=====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	824.00	98.87	98.87	98.87
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	168.00	53.50	53.50	53.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			992.00	91.19	91.19	91.19
=====							
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	52.00	150.00	116.97	110.00
				-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			52.00	150.00	116.97	110.00
				=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR			1,680.00	89.87	113.89	103.89
=====							
=====	630-80360	Drum Channel Dev		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	150.00	32.00	38.67	43.41
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	300.00	32.00	22.54	22.00
MTCER300-262			02/03/22	26.00	25.00	56.67	25.00
NHPP1601-083			02/03/22	150.00	25.00	62.92	30.00
STA0252-459			02/03/22	300.00	35.00	30.90	20.50
C0762-055			02/17/22	250.00	40.00	54.40	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360 Drum Channel Dev Each =====							
STR0141-031			02/17/22	250.00	40.00	37.33	37.00
STR133A-051			02/17/22	50.00	25.00	38.00	30.00
NHPP0063-063			02/24/22	400.00	30.00	27.70	29.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	100.00	30.00	46.93	40.00
NHPP0703-472			03/10/22	200.00	34.00	36.05	30.00
CR100-362			03/14/22	75.00	26.75	26.75	26.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	100.00	30.00	50.13	55.25
BRC040-057			03/17/22	75.00	32.00	66.25	55.00
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	25.00	35.51	60.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	40.00	33.00	42.00
STR092A-031			03/17/22	100.00	30.00	54.00	54.00
NHM765-007			03/31/22	225.00	55.00	56.30	74.10
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	270.00	40.00	115.50	125.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,161.00	34.86	43.64	44.84
NH0504-911			04/07/22	300.00	38.02	40.90	41.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	60.00	35.00	55.57	60.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	50.00	26.75	26.75	26.75
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	150.00	60.00	75.51	54.01
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	200.00	40.00	59.43	66.91
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	300.00	30.00	24.50	24.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	330.00	30.00	56.93	56.93
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	40.00	43.00	33.05	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	150.00	35.00	40.00	40.00
CM760-047		COLFAX AND QUAIL	05/12/22	50.00	31.00	41.20	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	45.00	80.00	50.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	50.00	50.00	56.05	69.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	60.00	62.00	62.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	30.00	25.00	25.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	40.00	71.50	72.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	40.00	35.00	8.67	10.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	50.00	30.00	41.91	41.91
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.00	60.00	73.05	36.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	250.00	40.00	13.33	10.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	100.00	40.00	26.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	400.00	35.00	75.35	56.70
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	35.00	23.50	30.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,995.00	37.83	47.13	42.18
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	38.45	38.45	38.45

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360		Drum Channel Dev		Each =====			
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	43.00	70.00	95.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	200.00	30.00	38.40	25.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	14.00	34.00	65.00	65.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	100.00	70.00	32.50	25.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	25.00	25.00	54.83	63.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	155.00	23.37	23.37	23.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	50.00	70.00	31.80	31.80
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	250.00	45.00	44.00	53.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	30.00	60.00	53.00	15.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	40.00	45.29	6.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	57.00	70.00	71.93	83.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	100.00	36.00	60.38	68.15
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	200.00	30.00	67.53	58.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	80.00	55.00	38.51	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,561.00	41.26	53.50	44.88
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	150.00	60.00	35.55	66.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	30.00	70.00	23.60	10.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	50.00	42.00	37.50	65.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	90.00	50.00	30.40	30.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	300.00	25.00	66.10	68.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	500.00	38.00	50.87	65.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	55.00	64.50	62.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	30.00	5.00	24.00	24.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	100.00	50.00	92.68	120.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	150.00	75.00	36.00	36.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	82.00	36.00	54.78	40.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	60.00	40.00	60.03	61.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	40.00	53.70	81.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	25.00	36.30	19.24	16.50
C5502-097		US550 MP 117.28-126.06	11/17/22	650.00	50.00	39.95	43.20
MPR200-280		PUEBLO AREA	11/17/22	15.00	47.00	47.50	65.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	84.00	43.00	51.07	79.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	260.00	35.00	33.67	50.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	100.00	50.00	37.50	50.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	70.00	61.06	63.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	300.00	40.00	75.50	75.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	250.00	30.00	60.00	53.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	50.00	50.00	38.20	32.40
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	100.00	75.00	65.47	67.93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360 Drum Channel Dev Each =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	200.00	35.00	62.02	30.69
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	40.00	22.00	33.00	25.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	600.00	30.00	43.58	44.16
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	50.00	27.27	15.25
NHMI75-029		CANON CITY, CO	12/15/22	50.00	60.00	22.50	25.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	40.00	70.00	10.97	12.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	30.00	38.22	35.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	275.00	40.00	43.37	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	400.00	35.00	36.40	37.80
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	125.00	40.00	38.83	71.85
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	75.00	65.00	56.84	63.00
STA385A-016		SH 385 MP 97.76	12/22/22	200.00	20.00	63.89	55.56
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	150.00	36.00	60.33	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				6,031.00	41.45	50.64	52.12
WEIGHTED AVERAGE FOR THE YEAR				13,748.00	39.12	48.74	47.53
===== 630-80363 Drum Channel Dev (Light) (F) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	50.00	50.00	22.00	22.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	35.00	26.44	23.00
NHPP1601-083			02/03/22	25.00	40.00	154.66	32.00
C0762-055			02/17/22	6.00	40.00	102.17	45.00
STR0141-031			02/17/22	20.00	50.00	42.00	41.00
NHPP0063-063			02/24/22	50.00	40.00	33.35	35.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	40.00	80.37	85.00
C0761-239							
NHPP0703-472			03/10/22	16.00	38.00	45.74	40.00
CR100-362			03/14/22	16.00	26.75	26.75	26.75
STR092A-031			03/17/22	50.00	40.00	70.00	70.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	6.00	65.00	146.00	160.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				339.00	41.49	68.47	51.71
===== 630-80363 Drum Channel Dev (Light) (F) Each =====							
NH0504-911			04/07/22	150.00	45.00	46.90	47.80
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10.00	32.10	32.10	32.10
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	10.00	50.00	84.71	59.41
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	50.00	50.00	24.50	24.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	35.00	77.63	77.63
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	20.00	35.00	25.00	25.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	200.00	45.00	84.68	62.36
WEIGHTED AVERAGE FOR THE SECOND QUARTER				452.00	44.67	62.46	51.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 605

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80363 Drum Channel Dev (Light) (F) Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10.00	43.94	43.94	43.94
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	50.00	35.00	50.90	50.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	38.00	71.67	65.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	30.00	80.00	65.00	35.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	25.00	40.00	56.70	40.33
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	55.00	41.21	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				127.00	48.94	55.11	44.31
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	50.00	70.00	55.93	133.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	30.00	75.00	26.93	10.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	25.00	40.00	55.00	100.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	25.00	55.00	35.45	35.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	56.35	81.00
C5502-097		US550 MP 117.28-126.06	11/17/22	25.00	50.00	58.70	48.60
MPR200-280		PUEBLO AREA	11/17/22	1.00	47.00	57.50	85.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	50.00	89.00	95.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	40.00	38.67	55.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	25.00	60.00	40.00	55.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	26.00	50.00	92.50	75.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	40.00	65.00	60.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	80.00	54.85	64.70
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	50.00	100.00	107.42	88.83
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	4.00	30.00	46.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	50.00	27.96	18.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	25.00	50.00	56.78	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	40.00	41.55	43.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	4.00	40.00	52.62	102.62
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				670.00	54.26	60.82	66.62
WEIGHTED AVERAGE FOR THE YEAR				1,588.00	48.38	62.87	57.75
===== 630-80364 Drum Channel Dev (Light) (SB) Each =====							
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	50.00	90.00	69.85	55.56
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	35.00	27.08	24.00
NHPP1601-083			02/03/22	200.00	40.00	66.57	40.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 606

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80364	Drum Channel Dev (Light) (SB)		Each =====			
STR0141-031			02/17/22	40.00	60.00	42.00	41.00
NHPP0063-063			02/24/22	50.00	40.00	33.35	35.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	350.00	40.00	80.37	85.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	100.00	45.00	60.91	71.82
STR R500-171		Various locations on SH 141 a	03/17/22	30.00	50.00	51.03	60.00
STR092A-031			03/17/22	25.00	60.00	70.00	70.00
NHM765-007			03/31/22	10.00	65.00	118.26	96.90
WEIGHTED AVERAGE FOR THE FIRST QUARTER				895.00	45.20	72.27	63.22
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10.00	32.10	32.10	32.10
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	50.00	50.00	24.50	24.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	40.00	25.00	25.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	150.00	40.00	15.00	10.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	50.00	40.00	44.17	7.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				270.00	41.56	22.77	13.50
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10.00	43.94	43.94	43.94
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	50.00	40.00	50.90	50.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	25.00	50.00	56.70	40.33
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	50.00	45.00	56.26	8.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	60.00	41.21	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				145.00	45.10	53.97	33.43
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	30.00	75.00	26.93	10.80
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	50.00	50.00	35.45	35.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	25.00	55.00	75.00	73.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	56.35	81.00
C5502-097		US550 MP 117.28-126.06	11/17/22	25.00	50.00	58.70	48.60
MPR200-280		PUEBLO AREA	11/17/22	4.00	47.00	57.50	85.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	39.00	38.67	55.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	10.00	70.00	40.00	55.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	66.00	80.00	92.50	75.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	75.00	40.00	69.67	60.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	90.00	54.85	64.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 607

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====							
=====	630-80364	Drum Channel Dev (Light) (SB)		Each	=====		
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	4.00	30.00	46.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	50.00	28.46	20.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	25.00	52.00	56.78	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	45.00	41.55	43.10
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	25.00	75.00	85.67	70.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	150.00	40.00	68.67	55.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			749.00	51.71	62.05	55.95
	WEIGHTED AVERAGE FOR THE YEAR			2,059.00	47.08	63.74	52.14
=====							
=====	630-80367	Port Traf Speed Monitor		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	5000.00	4909.54	4700.00
C0762-055			02/17/22	4.00	1800.00	3375.33	8500.00
STR0141-031			02/17/22	2.00	5000.00	6100.00	7800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	6000.00	5188.67	4200.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	3920.00	4639.99	6740.00
=====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	2175.00	2500.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	7000.00	8000.00	8000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	5333.33	3340.00	4333.33
=====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	3500.00	4128.67	5150.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	3500.00	4128.67	5150.00
=====							
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	3000.00	1578.87	2845.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	1000.00	7080.00	7500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	5000.00	8700.00	8700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	7000.00	3700.00	540.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	3600.00	4883.33	3000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	8000.00	3500.00	500.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	5000.00	5495.00	2700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	4911.11	4326.93	3253.89
	WEIGHTED AVERAGE FOR THE YEAR			33.00	4563.64	4420.86	4523.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 608

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80370 Barrier (Temp) Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,600.00	60.00	41.75	37.50
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	19,000.00	50.00	44.32	38.00
NHPP1601-083			02/03/22	1,125.00	100.00	121.16	120.00
C0762-055			02/17/22	1,197.00	50.00	54.79	60.00
STR0141-031			02/17/22	1,400.00	45.00	40.67	42.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30,800.00	43.00	52.94	25.00
C0761-239							
NHPP0703-472			03/10/22	600.00	35.00	42.78	45.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,275.00	40.00	47.39	39.78
STR R500-171		Various locations on SH 141 a	03/17/22	750.00	190.00	64.98	82.00
NHM765-007			03/31/22	2,200.00	85.00	46.92	42.12
WEIGHTED AVERAGE FOR THE FIRST QUARTER				59,947.00	50.17	50.56	34.19
NH0504-911			04/07/22	600.00	40.00	60.35	40.70
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	12,045.00	55.44	55.44	55.44
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,500.00	36.00	55.91	50.22
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,000.00	50.00	58.22	45.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				18,145.00	52.12	57.14	52.22
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	23,461.00	56.46	56.46	56.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	300.00	60.00	48.13	30.80
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	850.00	80.00	66.62	64.86
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	500.00	50.00	29.31	9.50
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	400.00	70.00	66.54	68.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	8,000.00	44.00	70.07	29.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,000.00	40.00	58.96	45.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				37,511.00	52.67	63.71	48.94
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	664.00	50.00	56.50	70.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,800.00	38.00	128.17	98.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	810.00	50.00	65.13	62.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,272.00	44.00	47.51	53.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,640.00	80.00	86.00	113.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80370 Barrier (Temp) Lin Foot =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	900.00	52.00	51.12	53.34
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,500.00	50.00	37.56	35.20
C5502-097		US550 MP 117.28-126.06	11/17/22	2,790.00	75.00	144.65	220.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2,000.00	41.00	38.50	40.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,270.00	45.00	83.01	76.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	200.00	43.00	62.33	66.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	500.00	50.00	143.00	223.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,500.00	40.00	56.00	70.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,000.00	40.00	118.04	67.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	500.00	60.00	46.81	40.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,750.00	50.00	27.34	30.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	6,900.00	45.00	65.22	45.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,550.00	50.00	87.71	80.00
STA385A-016		SH 385 MP 97.76	12/22/22	800.00	45.00	85.69	68.75
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				32,346.00	49.39	75.60	77.84
WEIGHTED AVERAGE FOR THE YEAR				147,949.00	50.87	57.83	49.73
===== 630-80371 Reset Concrete Barrier (Temp) Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,500.00	3.18	3.18	3.18
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,500.00	3.18	3.18	3.18
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	22,680.00	4.29	4.29	4.29
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
WEIGHTED AVERAGE FOR THE THIRD QUARTER				22,680.00	4.29	4.29	4.29
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	470.00	20.00	14.88	10.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				470.00	20.00	14.88	10.00
WEIGHTED AVERAGE FOR THE YEAR				24,650.00	4.52	4.99	4.33
===== 630-80372 Conc Barrier (Temp) (Furnish & Install) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5,630.00	40.00	69.20	50.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 610

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80372 Conc Barrier (Temp) (Furnish & Install) Lin Foot =====							
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	3,600.00	30.00	29.50	34.00
STR092A-031			03/17/22	2,500.00	50.00	65.00	65.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,730.00	39.06	63.79	48.29
STA0712-019		SH 71: Frieight Improvements	05/12/22	550.00	50.00	70.54	70.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		550.00	50.00	70.54	70.54
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,000.00	50.00	109.11	67.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	600.00	35.10	51.36	51.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,600.00	44.41	95.78	61.14
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4,395.00	65.00	67.25	40.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,180.00	80.00	108.17	139.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,938.00	78.09	62.39	34.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,513.00	73.29	63.02	46.50
		WEIGHTED AVERAGE FOR THE YEAR		25,393.00	55.15	63.93	48.44
===== 630-80377 Port Water Filled Barrier (Temp) Lin Foot =====							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	400.00	50.00	51.41	65.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		400.00	50.00	51.41	65.00
		WEIGHTED AVERAGE FOR THE YEAR		400.00	50.00	51.41	65.00
===== 630-80378 Glare Screen (Temp) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	22,580.00	32.00	20.69	18.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 611

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80378	Glare Screen (Temp)		Lin Foot	=====		
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,580.00	32.00	20.69	18.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7,370.00	26.75	26.75	26.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,370.00	26.75	26.75	26.75
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,200.00	50.00	31.18	22.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,200.00	50.00	27.18	20.53
		WEIGHTED AVERAGE FOR THE YEAR		31,150.00	31.45	21.51	20.20
=====	630-80380	Traffic Cone		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	275.00	10.00	5.00	5.00
MTCE R500-218			01/06/22	300.00	5.00	5.00	5.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	9.00	14.80	21.70
STR0505-050			01/13/22	225.00	10.00	18.33	25.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	50.00	20.00	15.04	1.11
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	300.00	6.00	7.50	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,000.00	10.00	9.44	10.00
MTCER300-262			02/03/22	250.00	10.00	10.33	1.00
NHPP1601-083			02/03/22	300.00	10.00	27.06	22.00
STA0252-459			02/03/22	300.00	9.00	7.12	4.10
C0762-055			02/17/22	200.00	7.00	17.24	23.00
STR0141-031			02/17/22	300.00	15.00	12.00	16.00
STR133A-051			02/17/22	500.00	10.00	11.67	15.00
NHPP0063-063			02/24/22	300.00	10.00	16.40	17.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	350.00	10.00	10.29	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	300.00	9.00	10.29	11.00
C0761-239							
NHPP0703-472			03/10/22	350.00	9.00	11.55	10.00
CR100-362			03/14/22	200.00	9.63	9.63	9.63
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	220.00	5.00	9.13	13.26
BRC040-057			03/17/22	75.00	10.00	19.50	12.00
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	9.00	7.18	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	600.00	12.00	9.00	11.00
STR092A-031			03/17/22	680.00	10.00	10.50	10.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80380	Traffic Cone		Each =====			
MP0503-098			03/24/22	250.00	8.00	19.00	19.00
NHM765-007			03/31/22	200.00	20.00	21.77	28.50
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	50.00	10.00	17.50	19.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				7,715.00	9.89	11.55	11.76
NH0504-911			04/07/22	400.00	11.95	12.00	12.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	10.00	16.73	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	288.00	16.05	16.05	16.05
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	50.00	15.00	17.86	9.72
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	10.00	16.08	18.25
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	200.00	11.00	19.00	18.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	300.00	8.00	25.88	25.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	200.00	10.00	11.65	12.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	100.00	11.00	14.33	13.00
CM760-047		COLFAX AND QUAIL	05/12/22	50.00	10.00	11.00	3.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	500.00	15.00	3.63	6.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	200.00	20.00	10.99	16.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	13.00	20.00	20.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	500.00	15.00	15.00	15.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	20.00	22.50	20.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	100.00	10.00	2.77	3.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	300.00	10.00	20.96	20.96
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	350.00	10.00	6.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	150.00	10.00	6.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	200.00	15.00	21.10	10.20
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,238.00	12.74	12.36	13.16
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	500.00	10.00	2.50	2.50
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	660.00	10.00	4.50	3.00
MTCE300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	80.00	10.00	18.33	10.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	16.48	16.48	16.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	11.00	12.50	2.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	15.00	13.57	1.25
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	250.00	9.00	11.67	10.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	100.00	15.00	9.00	8.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	10.00	17.73	11.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	120.00	6.91	6.90	6.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	300.00	16.00	23.50	10.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80380 Traffic Cone Each =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	500.00	10.00	14.45	3.10
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	60.00	10.00	21.19	28.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	200.00	10.00	20.70	20.45
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	15.00	18.99	15.90
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	100.00	30.00	6.41	2.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3,570.00	11.80	12.70	6.64
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	200.00	15.00	2.37	1.10
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	100.00	10.00	14.00	18.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	200.00	10.00	10.15	10.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,000.00	12.00	12.22	18.65
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	11.00	24.00	24.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	60.00	10.00	1.60	2.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	350.00	25.00	15.00	15.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	110.00	10.00	17.03	20.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	15.00	22.10	16.60
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	120.00	10.00	21.40	27.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	260.00	8.00	11.56	11.00
C5502-097		US550 MP 117.28-126.06	11/17/22	300.00	12.00	22.14	27.00
MPR200-280		PUEBLO AREA	11/17/22	300.00	15.00	12.50	15.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	210.00	10.00	12.94	34.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	600.00	9.30	8.08	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	400.00	10.00	7.00	4.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	500.00	20.00	16.78	17.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	100.00	10.00	34.00	35.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	156.00	10.00	18.33	15.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	200.00	10.00	13.23	6.45
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	50.00	20.00	10.04	18.81
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	12.00	25.06	24.55
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	325.00	10.00	12.10	15.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	600.00	10.00	18.47	18.93
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	200.00	15.00	15.97	10.00
NHM175-029		CANON CITY, CO	12/15/22	225.00	10.00	15.00	20.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	300.00	10.00	23.10	35.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	270.00	12.00	16.92	21.33
STR0092-024		SH 9 North of Silverthorne	12/22/22	400.00	10.00	15.60	16.20
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	150.00	12.00	17.93	27.45
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	150.00	16.00	13.01	25.00
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	10.00	18.03	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	350.00	10.00	13.33	4.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				8,586.00	12.19	14.49	16.05
=====							
WEIGHTED AVERAGE FOR THE YEAR				24,109.00	11.49	12.99	12.87

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 614

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80384 Tubular Marker Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	60.00	25.98	39.00
NHM765-007			03/31/22	100.00	50.00	89.10	96.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120.00	51.67	73.32	87.25
NH0504-911			04/07/22	400.00	25.66	35.90	35.80
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	500.00	20.00	70.31	65.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		900.00	22.52	61.97	52.02
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	28.00	48.33	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		100.00	28.00	48.33	50.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	25.00	49.82	50.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	30.00	30.00	50.57	59.72
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		230.00	25.65	49.92	51.27
		WEIGHTED AVERAGE FOR THE YEAR		1,350.00	26.05	60.29	54.88
===== 630-80385 Lane Divider (Temp) Each =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	54.00	80.00	101.74	205.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		54.00	80.00	101.74	205.00
		WEIGHTED AVERAGE FOR THE YEAR		54.00	80.00	101.74	205.00
===== 630-80390 Channel Dev (Spec) Each =====							
C0762-055			02/17/22	942.00	50.00	33.70	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		942.00	50.00	33.70	28.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 615

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80390 Channel Dev (Spec) Each =====							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	100.00	30.00	65.52	50.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			100.00	30.00	65.52	50.00
	WEIGHTED AVERAGE FOR THE YEAR			1,042.00	48.08	35.31	30.11
===== 630-80392 Stackable Tubular Marker Each =====							
C0762-055			02/17/22	300.00	22.00	26.97	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			300.00	22.00	26.97	28.00
	WEIGHTED AVERAGE FOR THE YEAR			300.00	22.00	26.97	28.00
===== 630-80393 Stackable Vertical Panels Each =====							
MT CER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	50.00	6.00	16.25	5.00
NHPP0703-472			03/10/22	100.00	38.00	27.60	20.00
CR100-362			03/14/22	50.00	26.75	26.75	26.75
BRC040-057			03/17/22	100.00	35.00	56.25	55.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			300.00	29.79	36.31	30.29
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	25.00	21.40	21.40	21.40
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	120.00	50.00	46.96	48.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	40.00	50.00	50.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	45.00	35.92	35.92
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			295.00	44.19	43.99	41.99
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	60.00	15.00	8.00	8.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	27.47	27.47	27.47
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	25.00	38.00	34.00	40.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 616

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80393	Stackable Vertical Panels		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	50.00	20.00	28.50	17.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	120.00	13.61	13.61	13.61
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	120.00	50.00	21.20	21.20
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		475.00	27.85	22.27	19.48
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	136.00	36.93	17.84	16.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	30.00	52.14	52.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	25.00	27.21	15.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	50.00	45.91	66.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		386.00	33.74	32.73	31.80
		WEIGHTED AVERAGE FOR THE YEAR		1,456.00	33.12	33.69	29.54
=====	630-80401	Delin (Ty I) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	150.00	45.00	49.60	22.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		150.00	45.00	49.60	22.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	45.00	49.60	22.00
=====	630-80402	Delin (Ty II) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	75.00	20.00	56.02	33.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		75.00	20.00	56.02	33.00
		WEIGHTED AVERAGE FOR THE YEAR		75.00	20.00	56.02	33.00
=====	630-80403	Delin (Ty III) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	20.00	15.00	74.25	55.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	15.00	74.25	55.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	15.00	74.25	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 617

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80415 Adv Warn Flash or Seq Panel (C Type) Day =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	40.00	130.00	69.00	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	130.00	69.00	90.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	130.00	69.00	90.00
===== 630-80417 Seq Flashing Warning Light Each =====							
STA0252-459			02/03/22	75.00	36.00	170.68	180.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	100.00	35.00	20.50	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	35.43	100.01	97.14
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	50.00	62.25	27.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	50.00	62.25	27.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	30.00	150.00	98.62	100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	150.00	98.62	100.00
		WEIGHTED AVERAGE FOR THE YEAR		305.00	51.48	88.86	74.59
===== 630-80430 Rumble Strip (Port) Each =====							
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	1000.00	2587.63	2587.63
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	1000.00	2587.63	2587.63
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	36.00	2600.00	1625.24	2134.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		36.00	2600.00	1625.24	2134.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	2200.00	1685.39	2247.41

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 618

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80440 Port Rumble Strips (Temp) Each =====							
NHPP1601-083			02/03/22	12.00	2050.00	1305.26	1200.00
STR133A-051			02/17/22	12.00	800.00	1353.33	1560.00
NHPP0063-063			02/24/22	36.00	1500.00	1327.50	1385.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	1575.00	2305.15	4500.00
STR092A-031			03/17/22	12.00	1500.00	900.00	900.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				78.00	1482.69	1406.91	1548.46
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	24.00	1000.00	1208.95	1900.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	6.00	2000.00	2310.37	3000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				30.00	1200.00	1429.23	2120.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12.00	2000.00	2225.00	2600.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	18.00	1500.00	1173.36	1100.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				30.00	1700.00	1460.01	1608.57
WEIGHTED AVERAGE FOR THE YEAR				138.00	1468.48	1431.46	1679.60
===== 630-80511 Mobile Pvmr Marking Zone LUMP SUM =====							
MTCE R500-219			01/06/22	1.00	70000.00	86666.67	60000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	7500.00	8598.83	11000.00
NHPP1601-083			02/03/22	1.00	5000.00	15655.53	12000.00
STR0141-031			02/17/22	1.00	10000.00	12166.67	8500.00
STR133A-051			02/17/22	1.00	10000.00	10000.00	10000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	3500.00	8319.42	6000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	20000.00	11024.63	11049.26
STR092A-031			03/17/22	1.00	10000.00	15000.00	15000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				8.00	17000.00	21036.94	16693.66
NH0504-911			04/07/22	1.00	10000.00	15645.00	11290.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	20491.59	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 619

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80511 Mobile Pvmnt Marking Zone LUMP SUM =====							
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	10000.00	4581.44	5262.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	15000.00	8208.25	8000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4.00	11250.00	14484.30	7388.22
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	3500.00	3000.00	3000.00
MTCER400-396		REGION 4	08/25/22	1.00	15000.00	15833.33	15000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	8000.00	7312.99	5679.44
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3.00	8833.33	9244.63	7893.15
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	5000.00	6129.14	6050.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	2500.00	3644.03	3932.10
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	15000.00	7640.00	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	13494.02	9276.07
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	15000.00	13500.00	12000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	15000.00	8195.00	5390.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1.00	15000.00	9827.77	7500.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	10000.00	6366.67	5000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				8.00	10937.50	8831.60	7631.82
WEIGHTED AVERAGE FOR THE YEAR				23.00	12826.09	13361.88	10523.99
===== 630-80520 Mobile Pvmnt Mkg Zone Day =====							
C0762-055			02/17/22	2.00	1300.00	2592.70	2000.00
NHM765-007			03/31/22	8.00	1000.00	1627.64	228.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				10.00	1060.00	1868.90	582.40
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	97.00	650.00	150.00	100.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				97.00	650.00	150.00	100.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	12.00	1200.00	1415.00	495.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 620

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80520 Mobile Pymt Mkg Zone Day =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	3000.00	2750.00	2750.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1500.00	1641.10	1650.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	2000.00	566.67	600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	1600.00	1308.71	901.67
	WEIGHTED AVERAGE FOR THE YEAR			131.00	855.34	508.56	283.69
===== 630-80560 Mobile Profilograph Oper Zone LUMP SUM =====							
NH0504-911			04/07/22	1.00	3000.00	7200.00	9400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	7200.00	9400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	7200.00	9400.00
===== 630-85006 Impact Atten (Sand Fill) (Temp) Each =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2.00	1850.00	4329.50	490.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	4800.00	6897.70	5679.44
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	3325.00	5963.81	3084.72
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	7000.00	7733.33	4900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	7000.00	7733.33	4900.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	5530.00	6760.10	4173.89
===== 630-85010 Impact Atten (Temp) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	4.00	10000.00	7363.06	8444.44
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	16.00	2500.00	9595.60	14400.00
NHPP1601-083			02/03/22	2.00	6000.00	8675.47	5000.00
C0762-055			02/17/22	4.00	6500.00	8372.76	8500.00
STR0141-031			02/17/22	4.00	10000.00	7166.67	8000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	19.00	9000.00	8599.85	5000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	4000.00	5714.07	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 621

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85010							
		Impact Atten (Temp)		Each			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4.00	6000.00	3709.85	4419.70
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	5600.00	7507.36	7500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	5.00	6000.00	6408.00	3356.00
NHM765-007			03/31/22	4.00	11800.00	11260.95	9690.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				69.00	6779.71	8482.72	8114.44
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3.00	9362.50	9362.50	9362.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	8500.00	7865.83	6800.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	7000.00	14097.37	17353.06
STA0712-019		SH 71: Frieight Improvements	05/12/22	6.00	8000.00	7762.88	7762.88
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2.00	8000.00	8000.00	8000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				19.00	8188.82	10019.69	9301.26
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10.00	13047.68	13047.68	13047.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	8000.00	3757.50	4125.55
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	3500.00	2471.47	3700.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	10000.00	5523.08	8930.36
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	7276.00	8990.13	8990.13
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	10000.00	7820.22	7110.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	5000.00	6433.12	5250.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				30.00	9104.43	6968.35	8713.35
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	8000.00	4255.00	4200.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	8.00	7500.00	6402.47	14200.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2.00	8000.00	2940.28	1761.11
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	7500.00	9324.08	11800.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	5500.00	8055.55	4700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	16.00	10000.00	9175.97	14000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	8400.00	3791.34	5374.01
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	7500.00	7903.00	8250.00
C5502-097		US550 MP 117.28-126.06	11/17/22	10.00	8000.00	7681.11	9720.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	6500.00	9775.00	12400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	7500.00	6695.79	12493.16
BR2854-148		INTERSECTION OF US 285 & SH 9					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85010 Impact Atten (Temp) Each =====							
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	5500.00	5383.33	3000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	18000.00	11339.02	12100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	9000.00	7250.00	2000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	7000.00	7766.67	5000.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	10000.00	7981.09	7700.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	8500.00	6112.11	14350.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	6000.00	9053.44	10000.00
STA385A-016		SH 385 MP 97.76	12/22/22	4.00	8500.00	9347.22	8888.89
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			92.00	8856.52	8227.95	10220.35
	WEIGHTED AVERAGE FOR THE YEAR			210.00	8149.14	8348.73	9261.91
===== 630-85011 Imp Atten (Temp) Day =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	25.00	400.00	138.00	65.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	400.00	138.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	400.00	138.00	65.00
===== 630-85020 Mobile Attenuator Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	70000.00	55700.00	55700.00
MTCE R500-218			01/06/22	1.00	5000.00	3875.00	2500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	70000.00	92555.92	56000.00
STR0141-031			02/17/22	1.00	20000.00	24333.33	21000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	30000.00	38590.22	32000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	2.00	30000.00	40098.53	44197.05
BRC040-057			03/17/22	3.00	25000.00	25216.50	25000.00
MP0503-098			03/24/22	2.00	30000.00	10225.00	7150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	37333.33	43096.34	32572.94
NH0504-911			04/07/22	4.00	5000.00	29950.00	29900.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	20000.00	34785.68	30000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.00	10000.00	30666.67	27000.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	2.00	10000.00	18866.67	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	9000.00	28198.35	23080.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 623

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85020 Mobile Attenuator Each =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	35000.00	100804.45	31813.36
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	5000.00	39725.00	25000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	25000.00	42128.33	37100.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6.00	21666.67	57693.94	31304.45
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	20000.00	93193.52	83000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	50000.00	84519.80	66000.00
MPR200-280		PUEBLO AREA	11/17/22	2.00	39000.00	38000.00	31000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	30000.00	39125.00	43050.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	30000.00	52772.29	48696.58
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2.00	25700.00	32000.00	35000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				11.00	30854.55	52023.14	46501.65
WEIGHTED AVERAGE FOR THE YEAR				42.00	26652.38	45212.76	34627.64
===== 630-85040 Impact Atten (T-M-A) (Temp) Each =====							
STR0505-050			01/13/22	2.00	8000.00	15500.00	10000.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	7500.00	29375.00	1000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4.00	7750.00	23428.57	5500.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	20000.00	14960.20	13115.39
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	125000.00	120000.00	120000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3.00	55000.00	35968.16	48743.59
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	2.00	3000.00	785.00	40.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	3000.00	785.00	40.00
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	15000.00	25570.97	19370.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85040		Impact Atten (T-M-A) (Temp)		Each =====			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	40000.00	36337.50	30050.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	15000.00	87610.00	86300.00
NHM175-029		CANON CITY, CO	12/15/22	2.00	8000.00	32500.00	45000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	19500.00	50045.59	45180.00
	WEIGHTED AVERAGE FOR THE YEAR			17.00	21058.82	35359.45	31161.81
===== 630-85041		Mobile Attenuator		Day =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	25.00	550.00	1015.88	1364.02
MTCER300-262			02/03/22	150.00	180.00	1033.33	550.00
STA0252-459			02/03/22	185.00	900.00	745.83	820.50
C0762-055			02/17/22	30.00	500.00	1741.69	2000.00
NHPP0063-063			02/24/22	50.00	500.00	462.50	450.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	800.00	575.68	510.00
C0761-239							
NHPP0703-472			03/10/22	80.00	320.00	1045.80	1000.00
CR100-362			03/14/22	240.00	535.00	535.00	535.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	620.00	798.50	696.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	40.00	800.00	1380.50	1065.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,050.00	594.52	766.77	703.52
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	60.00	856.00	856.00	856.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	450.00	936.21	1094.82
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	250.00	550.00	1037.50	1025.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	5.00	600.00	1800.00	3000.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	91.00	650.00	755.91	1007.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	115.00	750.00	1242.00	1650.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	105.00	800.00	598.72	598.72
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	600.00	243.33	100.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	80.00	550.00	774.67	736.33
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	16.00	800.00	918.25	900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			738.00	660.58	923.80	1006.46
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	933.82	933.82	933.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	70.00	640.00	547.50	245.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 625

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85041 Mobile Attenuator Day =====							
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	113.00	1000.00	802.97	802.97
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	60.00	350.00	1273.04	900.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	1100.00	721.71	525.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				428.00	854.40	903.00	700.68
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	5.00	2000.00	922.33	917.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	30.00	900.00	797.00	825.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	35000.00	1433.33	1550.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	20.00	700.00	1077.69	1433.07
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	30.00	550.00	798.93	998.72
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	300.00	1000.00	825.00	700.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	20.00	550.00	883.33	1500.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	25.00	1000.00	1170.84	1129.42
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	60.00	550.00	1316.83	1333.66
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	750.00	1140.68	820.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				594.00	1096.80	981.75	882.85
WEIGHTED AVERAGE FOR THE YEAR				2,810.00	757.63	856.25	820.56
===== 630-86801 Traffic Signal (Temp) LUMP SUM =====							
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	82000.00	11960.31	8420.61
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	82000.00	11960.31	8420.61
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	20000.00	95532.77	95000.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.00	20000.00	95532.77	95000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	167447.43	198000.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50000.00	38626.95	36000.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2.00	75000.00	115919.24	117000.00
WEIGHTED AVERAGE FOR THE YEAR				4.00	63000.00	88286.93	84355.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 626

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-86810 Traffic Signal (Temp) Each =====							
NHPP1601-083			02/03/22	1.00	30000.00	39780.84	50000.00
STR R500-171		Various locations on SH 141 a	03/17/22	3.00	30000.00	18115.23	500.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	75000.00	48625.00	45000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	45000.00	29139.92	23583.33
===== 630-86810 Traffic Signal (Temp) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	50711.64	52756.84
STA0712-019		SH 71: Frieight Improvements	05/12/22	3.00	12000.00	30016.48	30016.48
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	25250.00	43813.25	35701.57
===== 630-86810 Traffic Signal (Temp) Each =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	20000.00	151946.11	135820.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	20000.00	151946.11	135820.00
===== 630-86810 Traffic Signal (Temp) Each =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	3.00	8000.00	4852.64	3955.56
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	20000.00	6430.00	6000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	15000.00	151739.44	43757.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	29800.00	11833.33	12000.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	100000.00	124166.50	159903.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	30000.00	55388.89	50555.56
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	27350.00	34284.16	27173.58
	WEIGHTED AVERAGE FOR THE YEAR			23.00	31269.57	44792.54	32443.88
===== 630-88001 Work Zone Intrusion Alarm System Day =====							
NHPP0063-063			02/24/22	115.00	100.00	123.50	120.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			115.00	100.00	123.50	120.00
===== 630-88001 Work Zone Intrusion Alarm System Day =====							
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	45.00	130.00	164.58	5.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			45.00	130.00	164.58	5.00
	WEIGHTED AVERAGE FOR THE YEAR			160.00	108.44	135.05	87.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 632-00000 Night Work Lighting LUMP SUM =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	60000.00	57207.24	57724.44	
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	100000.00	75394.20	60000.00	
STA0252-459		02/03/22	1.00	68036.37	118195.00	230225.00	
NHPP0063-063		02/24/22	1.00	50000.00	150430.00	150000.00	
NHPP 0761-238	I-76 DAHLIA TO YORK	03/10/22	1.00	144000.00	99956.98	80000.00	
C0761-239							
NHPP0703-472		03/10/22	1.00	30000.00	49728.14	55000.00	
BRC040-057		03/17/22	1.00	30000.00	81125.00	79000.00	
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	12500.00	29364.50	9009.00	
C0703-499	EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	75000.00	47350.00	22000.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	63281.82	80521.83	82550.94	
2670703-479	I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	62372.60	42681.59	
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	20000.00	33500.00	7000.00	
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	45000.00	16670.93	16670.93	
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	15000.00	9440.41	15635.82	
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	10000.00	24185.00	5000.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	22000.00	38235.16	17397.67	
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	100000.00	37421.45	50000.00	
C1211-099	SH 121 NORTH SGA SIGNALS	08/25/22	1.00	7150.00	19250.00	20000.00	
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	12339.24	8834.99	8834.99	
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	32957.12	21835.48	21917.50	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	43356.44	28100.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	50000.00	84930.71	87400.00	
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	83000.00	151000.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	20000.00	39133.33	38900.00	
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	40000.00	51814.16	23815.53	
NHPP083A-046	SH83 RESURFACING STROH RD TO	12/08/22	1.00	50000.00	25349.68	20699.36	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	75000.00	64249.43	21000.00	
NHM175-029	CANON CITY, CO	12/15/22	1.00	20000.00	21000.00	7000.00	
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	39452.08	3585.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	48888.89	54098.08	40649.99	
WEIGHTED AVERAGE FOR THE YEAR				26.00	46346.85	59403.63	47289.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 628

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 641-10000 Shotcrete Sq Yard =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	428.00	126.00	473.33	470.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			428.00	126.00	473.33	470.00
	WEIGHTED AVERAGE FOR THE YEAR			428.00	126.00	473.33	470.00
===== 641-10010 Initial Shotcrete Facing Sq Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	23,934.00	17.58	17.58	17.58
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			23,934.00	17.58	17.58	17.58
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	49,623.00	21.30	21.30	21.30
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	9,885.00	20.00	33.48	22.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			59,508.00	21.08	25.85	21.42
	WEIGHTED AVERAGE FOR THE YEAR			83,442.00	20.08	23.94	20.32
===== 641-10070 Shotcrete Sculpting Sq Yard =====							
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,130.00	250.00	157.81	237.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,130.00	250.00	157.81	237.00
	WEIGHTED AVERAGE FOR THE YEAR			1,130.00	250.00	157.81	237.00
===== 641-11000 Shotcrete (CL A) Cubic Yard =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	754.00	1027.20	1027.20	1027.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			754.00	1027.20	1027.20	1027.20
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,454.00	979.11	979.11	979.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 629

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	641-11000	Shotcrete (CL A)		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		1,454.00	979.11	979.11	979.11
		WEIGHTED AVERAGE FOR THE YEAR		2,208.00	995.53	995.53	995.53
=====	641-11003	Shotcrete (CL D)		Cubic Yard	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	520.00	900.00	646.21	520.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		520.00	900.00	646.21	520.00
		WEIGHTED AVERAGE FOR THE YEAR		520.00	900.00	646.21	520.00
=====	641-11006	Shotcrete (Smooth) (Suppl)		Cubic Yard	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	81.00	1001.81	1001.81	1001.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		81.00	1001.81	1001.81	1001.81
		WEIGHTED AVERAGE FOR THE YEAR		81.00	1001.81	1001.81	1001.81
=====	642-00010	Exploder (Ty 1) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	60000.00	27250.00	21000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		2.00	60000.00	27250.00	21000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	60000.00	27250.00	21000.00
=====	642-00020	Exploder (Ty 2) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	3.00	20000.00	20500.00	17000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		3.00	20000.00	20500.00	17000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	20000.00	20500.00	17000.00
=====	642-00030	Cntrl Shelter (Ty 1) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	30000.00	22500.00	14000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	30000.00	22500.00	14000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	30000.00	22500.00	14000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 630

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70002 F/A ANTICIPATED CMO Force Acct =====							
NHPP0343-048		US 34 (MP 169.3-171.4)	.	1.00	644309.40	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	.	1.00	2419959.60	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1532134.50	.	.
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1532134.50	.	.
===== 700-70010 F/A Minor Contract Revisions Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	.	1.00	400000.00	.	.
MTCE R500-219			.	1.00	40000.00	.	.
MTCE R500-218			.	1.00	75000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	.	1.00	225000.00	.	.
STR0505-050			.	1.00	100000.00	.	.
NH0504-910		US50B L-24-B MIN REP AT MP 40	.	1.00	200000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	.	1.00	60000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	.	1.00	950000.00	.	.
MTCER300-262			.	1.00	40000.00	.	.
NHPP1601-083			.	1.00	400000.00	.	.
STA0252-459			.	1.00	200000.00	.	.
C0762-055			.	1.00	200000.00	.	.
STR0141-031			.	1.00	260000.00	.	.
STR133A-051			.	1.00	60000.00	.	.
NHPP0063-063			.	1.00	186000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	.	1.00	180000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK	.	2.00	550000.00	.	.
C0761-239			.			.	.
NHPP0703-472			.	1.00	650000.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	.	1.00	5000.00	.	.
CR100-362			.	1.00	30000.00	.	.
ER007A-035			.	1.00	250000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF	.	1.00	250000.00	.	.
BRC040-057			.	1.00	300000.00	.	.
STR R500-171		Various locations on SH 141 a	.	1.00	80000.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	.	1.00	75000.00	.	.
STR092A-031			.	1.00	125000.00	.	.
MP0503-098			.	1.00	40000.00	.	.
NHM765-007			.	1.00	500000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN	.	1.00	100000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	236033.33	.	.
NH0504-911			.	1.00	200000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 631

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70010	F/A Minor Contract Revisions		Force Acct	=====		
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	200000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	600000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	1300000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE .		1.00	25000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	700000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	500000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	500000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	75000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	200000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	56900.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	800000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	100000.00	.	.
C0852-120		Rehabilitation of Culvert by .		1.00	90000.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS .		1.00	65000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	80000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	25000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	330000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	110000.00	.	.
MPR200-278		R2 - VARIOUS LOCATIONS .		1.00	100000.00	.	.
MPR200-279		FY 23 STENCIL MARKING PROJECT .		1.00	55000.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2 .		1.00	75000.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	200000.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	25000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				24.00	267162.50	.	.
MT CER300-273		I-70 MM 75-116, OTHER REGION .		1.00	25000.00	.	.
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE .		1.00	25000.00	.	.
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP .		1.00	20000.00	.	.
MT CER300-272		REGION 3 ROUNDABOUT STRIPING .		1.00	30000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	475000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	30000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS .		1.00	15000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	400000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	200000.00	.	.
MT CER400-396		REGION 4 .		1.00	50000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	290000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	75000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	18100.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	100000.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	150000.00	.	.
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9 .		1.00	50000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	50000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70010	F/A Minor Contract Revisions		Force Acct	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS .		1.00	300000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE XING .		1.00	350000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	210000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	250000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		23.00	156791.30	.	.
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP .		1.00	20000.00	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS .		1.00	70000.00	.	.
C0831-126		SH83 EL PASO COUNTY TO BAYOU .		1.00	15000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	150000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	200000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	300000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	90000.00	.	.
C5502-111		US 550 MP 81 AND 89 RED MOUNT .		1.00	40000.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	45000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	1200000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	200000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	200000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	1500000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	40000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	183000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	150000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	500000.00	.	.
MPR200-280		PUEBLO AREA .		1.00	50000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	120000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	450000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH .		1.00	1000000.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	356000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	815000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	255000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	400000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	188000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	175000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	200000.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	60000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	175000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	90000.00	.	.
NHM175-029		CANON CITY, CO .		1.00	200000.00	.	.
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO .		1.00	5000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	360000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	200000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	300000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 633

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70010 F/A Minor Contract Revisions Force Acct =====							
STA0361-129	US 36: HYGIENE RD AND NELSON .			1.00	275000.00	.	.
BR012A-048	CO 12 STRUCTURE P-17-F AT MP .			1.00	200000.00	.	.
STA385A-016	SH 385 MP 97.76 .			1.00	130000.00	.	.
STR096A-050	SH 96 MP 168.99 TO 193.77 .			1.00	300000.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				40.00	280175.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				117.00	241932.48	.	.
===== 700-70012 F/A Asph Pvmnt Incentive Force Acct =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA .			1.00	53100.00	.	.
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT .			1.00	15000.00	.	.
C0762-055				1.00	150000.00	.	.
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I .			1.00	71000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4.00	72275.00	.	.
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2 .			1.00	2100.00	.	.
STM1151-038	SH115 MP 27 TO MP 38 .			1.00	245000.00	.	.
2670703-479	I-70 BRIDGE OVER HARLAN .			1.00	22000.00	.	.
STA0712-019	SH 71: Frieight Improvements .			1.00	100000.00	.	.
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC .			1.00	175000.00	.	.
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS .			1.00	15000.00	.	.
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN .			1.00	126000.00	.	.
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR .			1.00	46498.05	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8.00	91449.76	.	.
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3 .			2.00	4350.00	.	.
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS .			1.00	1000.00	.	.
FSA052A-057	SH52 BOX CULVERT EXTENSION (M .			2.00	6000.00	.	.
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG .			1.00	9000.00	.	.
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL .			1.00	5300.00	.	.
2670403-065	US40 FLOYD HILL ROUNDABOUTS .			1.00		.	.
SHE2873-193	US 287 & CO 52 INTERSECTION I .			1.00		.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				7.00	5142.86	.	.
STA3852-015	US 385 HOLYOKE NORTH .			1.00	170000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 634

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70012 F/A Asph Pvmnt Incentive Force Acct =====							
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	200000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	5000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	19000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	7000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	67108.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	61000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	126000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	137665.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				9.00	88085.89	.	.
WEIGHTED AVERAGE FOR THE YEAR				28.00	66052.54	.	.
===== 700-70013 F/A Conc Pvmnt Incentive Force Acct =====							
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	100000.00	.	.
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	100000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	293000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	293000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	44000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.00	44000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	17000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	1000.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2.00	9000.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				6.00	92500.00	.	.
===== 700-70014 F/A Incentive Force Acct =====							
MTCE R500-219				1.00	15000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 635

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70014 F/A Incentive Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	40000.00	.	.
BRC040-057				1.00	10000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	21666.67	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	40000.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	50000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.00	45000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	50000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.00	50000.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				6.00	34166.67	.	.
===== 700-70016 F/A Fuel Cost Adjustment Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	31000.00	.	.
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	1000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	50000.00	.	.
NHPP1601-083				1.00	50000.00	.	.
STA0252-459				1.00	5000.00	.	.
C0762-055				1.00	140000.00	.	.
STR0141-031				1.00	40000.00	.	.
STR133A-051				1.00	0.01	.	.
NHPP0063-063				1.00	46500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	25000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	100000.00	.	.
C0761-239							
NHPP0703-472				1.00	250.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	1.00	.	.
ER007A-035				1.00	39000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	45000.00	.	.
BRC040-057				1.00	5000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	700.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC .		1.00	100.00	.	.
STR092A-031				1.00	30000.00	.	.
NHM765-007				1.00	20000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				22.00	33161.41	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 636

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70016 F/A Fuel Cost Adjustment Force Acct =====							
NH0504-911				1.00	80787.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	150000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	10000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE .		1.00	2500.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	15000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	5000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	40000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	100000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	1000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	107000.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS .		1.00	2000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	1000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	500.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	30000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	38683.63	.	.
MPR200-278		R2 - VARIOUS LOCATIONS .		1.00	500.00	.	.
MPR200-279		FY 23 STENCIL MARKING PROJECT .		1.00	500.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	500.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				19.00	31051.09	.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	70000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	10000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	9500.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9 .		1.00	500.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	33000.00	.	.
2670703-497		I-70 GENESEE WILDLIFE KING .		1.00	20000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	19000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	30000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10.00	20250.00	.	.
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP .		1.00	0.01	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS .		1.00	1500.00	.	.
C0831-126		SH83 EL PASO COUNTY TO BAYOU .		1.00	4800.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70016	F/A Fuel Cost Adjustment	Force Acct	=====				
NHPP0701-253	I-70 EAST OF DEBEQUE .	1.00	0.01
STA207A-004	Resurfacing SH207A MANZANOLA .	1.00	10000.00
NHPP0705-088	I-70 AGATE STRUCTURE REHAB .	1.00	0.01
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA .	1.00	1000.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE .	1.00	40000.00
STA3852-015	US 385 HOLYOKE NORTH .	1.00	75000.00
NHPP0343-048	US 34 (MP 169.3-171.4) .	1.00	1000.00
STU0252-457	I-25:ALAMEDA RIVER PH 2.0 .	1.00	25000.00
SHE0242-087	US 24 SAFETY IMPRVMTS, E OF .	1.00	2000.00
STR064A-010	SH 64 AND SH 13 AT MEEKER .	1.00	45750.00
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (.	1.00	150000.00
C5502-097	US550 MP 117.28-126.06 .	1.00	15000.00
STRC090-011	US 50B AND SH71/CR18 INTERSEC .	1.00	10000.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS .	1.00	56000.00
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71: REGION LINE NORTH .	1.00	190428.57
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3 .	1.00	25000.00
2670703-487	I-70 BRIDGES OVER WARD ROAD- .	1.00	20000.00
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA .	1.00	65000.00
IM025A-050	I25-MP103.9 - INTERSECTION DR .	1.00	50000.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU .	1.00	47000.00
STR109A-019	M-22-AY BRIDGE REHAB ON SH109 .	1.00	1000.00
NHPP0021-041	SH2 RESURFACING MLK TO 52ND .	1.00	10000.00
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT .	1.00	15000.00
NHPP083A-046	SH83 RESURFACING STROH RD TO .	1.00	20000.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM .	1.00	21500.00
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO .	1.00	1000.00
NHPP0931-033	SH93:US6 TO 58TH RESURFACING .	1.00	30000.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C .	1.00	15000.00
STR0092-024	SH 9 North of Silverthorne .	1.00	41500.00
STA0361-129	US 36: HYGIENE RD AND NELSON .	1.00	28000.00
BR012A-048	CO 12 STRUCTURE P-17-F AT MP .	1.00	3600.00
STA385A-016	SH 385 MP 97.76 .	1.00	25000.00
STR096A-050	SH 96 MP 168.99 TO 193.77 .	1.00	55500.00
		-----	-----	-----	-----	-----	-----
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER	36.00	30599.41
		=====	=====	=====	=====	=====	=====
	WEIGHTED AVERAGE FOR THE YEAR	87.00	30156.32
===== 700-70018	F/A Road Smooth Incentive	Force Acct	=====				
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA .	1.00	90910.00
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT .	1.00	100000.00
NHPP1601-083	.	1.00	150000.00
C0762-055	.	1.00	125000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70018	F/A Road Smooth Incentive		Force Acct	=====		
STR0141-031			.	1.00	50000.00	.	.
NHPP0063-063			.	1.00	53500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	.	1.00	159000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK	.	2.00	50000.00	.	.
C0761-239							
NHPP0703-472			.	1.00	225745.00	.	.
ER007A-035			.	1.00	233200.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF	.	1.00	200000.00	.	.
STR092A-031			.	1.00	100000.00	.	.
NHM765-007			.	1.00	105000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	120882.50	.	.
NH0504-911			.	1.00	412000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	557000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN	.	1.00	11500.00	.	.
STA0712-019		SH 71: Frieight Improvements	.	1.00	28000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	.	1.00	100000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	.	1.00	250700.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	.	1.00	224000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	.	1.00	154000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	217150.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	.	1.00	10000.00	.	.
2670403-065		US40_FLOYD HILL ROUNDABOUTS	.	1.00	8000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE XING	.	1.00	43000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I	.	1.00	59500.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	30125.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE	.	1.00	42500.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA	.	1.00	165000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	.	1.00	50000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH	.	1.00	150000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	.	1.00	10500.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	.	1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER	.	1.00	29357.50	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.	1.00	100000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70018	F/A Road Smooth Incentive	Force Acct	=====				
C5502-097	US550 MP 117.28-126.06	1.00	80000.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	1.00	26000.00
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71: REGION LINE NORTH	1.00	204576.77
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3	1.00	175000.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-	1.00	14000.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU	1.00	176000.00
NHPP0021-041	SH2 RESURFACING MLK TO 52ND	1.00	96100.00
NHPP083A-046	SH83 RESURFACING STROH RD TO	1.00	100000.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	1.00	10000.00
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO	1.00	1000.00
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	1.00	175000.00
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	1.00	22083.50
STA0361-129	US 36: HYGIENE RD AND NELSON	1.00	67000.00
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	1.00	1000.00
STA385A-016	SH 385 MP 97.76	1.00	6000.00
STR096A-050	SH 96 MP 168.99 TO 193.77	1.00	268000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER	24.00	82129.91
	WEIGHTED AVERAGE FOR THE YEAR	50.00	110423.46
===== 700-70019	F/A Asphalt Cement Cost Adjustment	Force Acct	=====				
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA	1.00	50950.00
NH0504-910	US50B L-24-B MIN REP AT MP 40	1.00	1000.00
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	1.00	20000.00
NHPP1601-083		1.00	25000.00
C0762-055		1.00	225000.00
STR0141-031		1.00	20000.00
STR133A-051		1.00	0.01
NHPP0063-063		1.00	12500.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I	1.00	1000.00
NHPP 0761-238	I-76 DAHLIA TO YORK	2.00	10000.00
C0761-239							
NHPP0703-472		1.00	194820.00
ER007A-035		1.00	189500.00
STR160A-034	US160A LA VETA PASS EAST SURF	1.00	1000.00
BRC040-057		1.00	5000.00
STR092A-031		1.00	20000.00
NHM765-007		1.00	4000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER	17.00	46457.06
NH0504-911		1.00	24040.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 640

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70019	F/A Asphalt Cement Cost Adjustment		Force Acct	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	2025.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	82107.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	145000.00	.	.
STA0712-019		SH 71: Frieght Improvements .		1.00	15000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	175000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	5000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	375000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	200.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	124000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	98441.01	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	95073.91	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	2550.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	17000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	20000.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	16500.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING .		1.00	43000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	31000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	17066.67	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	0.01	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	50000.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	5000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	135000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	200000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	1000.00	.	.
STU0252-457		I-25-ALAMEDA RIVER PH 2.0 .		1.00	65000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	17575.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	225000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	1000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	577811.23	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	25000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	52000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 641

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70019 F/A Asphalt Cement Cost Adjustment Force Acct =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	20000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	22138.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	1000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	53861.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	49000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	60000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	0.01	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	9250.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	11500.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	170000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	3500.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	10000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	137500.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				28.00	68361.97	.	.
WEIGHTED AVERAGE FOR THE YEAR				65.00	60051.05	.	.
===== 700-70023 F/A On-The-Job Trainee Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	5000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	1920.00	.	.
STR0505-050		. .		1.00	1000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	5120.00	.	.
NHPP1601-083		. .		1.00	10000.00	.	.
STA0252-459		. .		1.00	10000.00	.	.
C0762-055		. .		1.00	19200.00	.	.
STR0141-031		. .		1.00	10000.00	.	.
NHPP0063-063		. .		1.00	6400.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	5000.00	.	.
C0761-239		. .					
NHPP0703-472		. .		1.00	10000.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	12800.00	.	.
ER007A-035		. .		1.00	12800.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	3200.00	.	.
STR092A-031		. .		1.00	3200.00	.	.
NHM765-007		. .		1.00	20000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN .		1.00	6400.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				18.00	8168.89	.	.
NH0504-911		. .		1.00	25000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	25600.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70023	F/A On-The-Job Trainee		Force Acct	=====		
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	42000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	19200.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	16000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	6400.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	15000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	3000.00	.	.
C0852-120		Rehabilitation of Culvert by .		1.00	500.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	2000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	8000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	6400.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	6400.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13.00	13500.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	12800.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	3200.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	10000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	19200.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	16000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	12333.33	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	5000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	12800.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	6400.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	1000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	19200.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	1000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	40000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF .		1.00	2000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	12800.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	1000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	22000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	18000.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	20000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	6400.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	16000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	0.01	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	11000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70023 F/A On-The-Job Trainee Force Acct =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	3400.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	3200.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	3200.00	.	.
NHM175-029		CANON CITY, CO .		1.00	2000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	16000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	20000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	6400.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	6000.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				27.00	9807.41	.	.
WEIGHTED AVERAGE FOR THE YEAR				64.00	10333.44	.	.
===== 700-70025 F/A Quality Incentive Pymt Force Acct =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	1000.00	.	.
NHPP1601-083				1.00	250000.00	.	.
STA0252-459				1.00	100000.00	.	.
STR0141-031				1.00	15000.00	.	.
NHPP0063-063				1.00	8000.00	.	.
NHPP0703-472				1.00	263720.00	.	.
ER007A-035				1.00	215000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	200000.00	.	.
STR092A-031				1.00	15000.00	.	.
NHM765-007				1.00	200000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				10.00	126772.00	.	.
NH0504-911				1.00	335000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	295000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.00	315000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	50000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE XING .		1.00	27000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	38500.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	7750.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70025	F/A Quality Incentive Pymt	Force Acct	=====				
STA207A-004	Resurfacing SH207A MANZANOLA .	1.00	75000.00	.	.		
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE .	1.00	50000.00	.	.		
STU0252-457	I-25:ALAMEDA RIVER PH 2.0 .	1.00	50000.00	.	.		
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF .	1.00	2000.00	.	.		
STR064A-010	SH 64 AND SH 13 AT MEEKER .	1.00	22241.00	.	.		
C5502-097	US550 MP 117.28-126.06 .	1.00	10000.00	.	.		
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS .	1.00	60000.00	.	.		
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
STA0711-021	SH71: REGION LINE NORTH .	1.00	472399.88	.	.		
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3 .	1.00	150000.00	.	.		
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU .	1.00	21834.00	.	.		
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM .	1.00	6000.00	.	.		
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO .	1.00	1000.00	.	.		
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C .	1.00	6000.00	.	.		
STR0092-024	SH 9 North of Silverthorne .	1.00	14000.00	.	.		
STA0361-129	US 36: HYGIENE RD AND NELSON .	1.00	60000.00	.	.		
BR012A-048	CO 12 STRUCTURE P-17-F AT MP .	1.00	3000.00	.	.		
STA385A-016	SH 385 MP 97.76 .	1.00	17000.00	.	.		
STR096A-050	SH 96 MP 168.99 TO 193.77 .	1.00	269000.00	.	.		
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER	19.00	68274.99	.	.		
	WEIGHTED AVERAGE FOR THE YEAR	33.00	99149.84	.	.		
===== 700-70031	F/A Interim Surface Repair	Force Acct	=====				
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA .	1.00	10350.00	.	.		
NHPP 0761-238	I-76 DAHLIA TO YORK .	2.00	7500.00	.	.		
C0761-239							
NHPP0703-472		1.00	43480.00	.	.		
NHM765-007		1.00	10000.00	.	.		
	WEIGHTED AVERAGE FOR THE FIRST QUARTER	5.00	15766.00	.	.		
STM1151-038	SH115 MP 27 TO MP 38 .	1.00	20000.00	.	.		
2670703-479	I-70 BRIDGE OVER HARLAN .	1.00	1100.00	.	.		
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN .	1.00	36000.00	.	.		
	WEIGHTED AVERAGE FOR THE SECOND QUARTER	3.00	19033.33	.	.		
2670403-065	US40_FLOYD HILL ROUNDABOUTS .	1.00	1000.00	.	.		

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 645

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70031	F/A	Interim Surface Repair		Force Acct	=====		
2670703-497	I-70	GENESEE WILDLIFE XING .		1.00	4000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	2500.00	.	.
2670703-487	I-70	BRIDGES OVER WARD ROAD- .		1.00	2000.00	.	.
NHPP0021-041	SH2	RESURFACING MLK TO 52ND .		1.00	10941.00	.	.
NHPP0931-033	SH93	US6 TO 58TH RESURFACING .		1.00	40000.00	.	.
NHPP0502-090	SH 50 MP	134.6-136 GUNNISON C .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	15735.25	.	.
	WEIGHTED AVERAGE FOR THE YEAR			14.00	14562.21	.	.
===== 700-70034	F/A			Force Acct	=====		
NHPP 0761-238	I-76	DAHLIA TO YORK .		1.00	12000.00	.	.
C0761-239				1.00	10000.00	.	.
STR092A-031				2.00	11000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	11000.00	.	.
NH0504-911				1.00	50000.00	.	.
NHPP0702-413	VAIL PASS AUX	PHASE 1 CAP 2 .		1.00	40000.00	.	.
ER0702-420	PR I-70 GWC	MATERIAL FLOWS 20 .		3.00	183333.33	.	.
NHC540-017	R2	CHAINUP STA @ KENOSHA/HOOS .		1.00	43000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	113833.33	.	.
NHPP0702-414	VAIL PASS AUX	PHASE 1 CAP 3 .		2.00	20000.00	.	.
FBR0702-423	VAIL PASS AUX	BE F-12-AT PHAS .		1.00	60000.00	.	.
FBR0761-236	I-76	OVER CLR CRK SCOUR MIT .		3.00	33333.33	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	33333.33	.	.
STU0252-457	I-25	ALAMEDA RIVER PH 2.0 .		2.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 646

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70034 F/A Force Acct =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	120000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	46666.67	.	.
	WEIGHTED AVERAGE FOR THE YEAR			14.00	67500.00	.	.
===== 700-70035 F/A Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	75000.00	.	.
NHPP1601-083				1.00	643283.53	.	.
NHPP0063-063				1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	242761.18	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	1000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	500.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		2.00	35000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	20000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	120000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	35166.67	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		2.00	20000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	5000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	30000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	40000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	18571.43	.	.
	WEIGHTED AVERAGE FOR THE YEAR			17.00	62957.85	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 647

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70036 F/A Force Acct =====						
STAM420-001 BR2854-148 STM0091-046	US 285 AT HWY 9C IMPROVEMENTS . INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	.	.
===== 700-70040 F/A Railroad Force Acct =====						
C0762-055			1.00	38400.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	38400.00	.	.
STAR100-374	5 STRUCTURES IN REGION 1 .		1.00	15000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	15000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		2.00	26700.00	.	.
===== 700-70042 F/A RR Flagging Force Acct =====						
BRC040-057			1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	.	.
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC .		1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	25000.00	.	.
BR0343-046 FBR0343-047 STAR100-374	US 34 TIMBER BRIDGE REPL. PKG . US 6/US 34 TIMBER BRIDGE REPL 5 STRUCTURES IN REGION 1 .		1.00 1.00	22500.00 125000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	73750.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 648

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70042	F/A RR Flagging			Force Acct	=====		
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	12000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	8000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	25000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	50000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	25000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	28333.33	.	.
	WEIGHTED AVERAGE FOR THE YEAR			10.00	39250.00	.	.
===== 700-70060	F/A Adjust			Force Acct	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	30000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	15000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	22500.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			3.00	16666.67	.	.
===== 700-70070	F/A Obtain			Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	50000.00	.	.
===== 700-70072	F/A Obtain Power from Xcel			Force Acct	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	100000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	100000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	100000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 649

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70074 F/A Obtain Power from Force Acct =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
===== 700-70081 F/A Provide Force Acct =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	150000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	150000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	150000.00	.	.
===== 700-70082 F/A Furn & Inst Elec Serv Force Acct =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	20000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	7500.00	.	.
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	5000.00	.	.
NHM765-007				1.00	20000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	12000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	60000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	7000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	60000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	33000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 650

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70082 F/A Furn & Inst Elec Serv Force Acct =====							
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	40000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	25000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	5000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4.00	20000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	12000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	40000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	8000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	20000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	15000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	60000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	10000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	10000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	5000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	2000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	5000.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				11.00	17000.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				24.00	19125.00	.	.
===== 700-70090 F/A Reset Force Acct =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		1.00	5000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.00	5000.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				1.00	5000.00	.	.
===== 700-70100 F/A Relocate Force Acct =====							
NH0504-911		I-70 BRIDGE OVER HARLAN .		1.00	10000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	10000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.00	10000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	152000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 651

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70100	F/A Relocate		Force Acct	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	78500.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			4.00	44250.00	.	.
=====	700-70110	F/A Install		Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	.	.
=====	700-70111	Project First Program		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	1000.00	.	.
MTCE R500-219		.		1.00	1000.00	.	.
MTCE R500-218		.		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	2500.00	.	.
STR0505-050		.		1.00	2000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO .		1.00	500.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	15000.00	.	.
NHPP1601-083		.		1.00	4000.00	.	.
STA0252-459		.		1.00	8000.00	.	.
C0762-055		.		1.00	2000.00	.	.
STR0141-031		.		1.00	2000.00	.	.
STR133A-051		.		1.00	1500.00	.	.
NHPP0063-063		.		1.00	2000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	10000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		1.00	5000.00	.	.
C0761-239		.					
NHPP0703-472		.		1.00	500.00	.	.
ER007A-035		.		1.00	10000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	1000.00	.	.
BRC040-057		.		1.00	5000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	500.00	.	.
STR092A-031		.		1.00	2500.00	.	.
NHM765-007		.		1.00	10000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN .		1.00	2000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23.00	3869.57	.	.
NH0504-911		.		1.00	5000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70111	Project First Program		Force Acct	=====		
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	5000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	3000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	30000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	4000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	7000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	3000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	5000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	2000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	1000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	5000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	500.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS .		1.00	4000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	1000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	2000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	2000.00	.	.
MPR200-278		R2 - VARIOUS LOCATIONS .		1.00	500.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2 .		1.00	100.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	1500.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	500.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	4105.00	.	.
MT CER300-273		I-70 MM 75-116, OTHER REGION .		1.00	2000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	1500.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	3000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	5000.00	.	.
MT CER400-396		REGION 4 .		1.00	500.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	1000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	2500.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	500.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	10000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	5000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	2000.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING .		1.00	2000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	5000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		18.00	2666.67	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS .		1.00	1000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70111		Project First Program		Force Acct	=====		
C0831-126		SH83 EL PASO COUNTY TO BAYOU .		1.00	5000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	7000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	5000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	3000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	1500.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	500.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	10000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	2000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	500.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	20000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF .		1.00	2000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	5000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
MPR200-280		PUEBLO AREA .		1.00	1000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	3000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	20000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .					
STA0711-021		SH71: REGION LINE NORTH .		1.00	2500.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	5000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	5000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	7000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	5000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	7000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	5000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	2500.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	1500.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	15000.00	.	.
NHM175-029		CANON CITY, CO .		1.00	2000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	2000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	10000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	2000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	3000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	5000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		36.00	5222.22	.	.
		WEIGHTED AVERAGE FOR THE YEAR		97.00	4196.91	.	.
===== 700-70129		F/A Deck Rehab		Force Acct	=====		
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 654

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70130 F/A Repair Force Acct =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	.	.
===== 700-70155 F/A Pvmt Surf Course Maint Force Acct =====							
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	.	.
===== 700-70160 F/A Detour Force Acct =====							
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG . US 6/US 34 TIMBER BRIDGE REPL		2.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	.	.
===== 700-70195 F/A Util and Maint of Field Facil Force Acct =====							
STR0505-050				1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	.	.
STAM420-001 BR2854-148 STM0091-046 NHM175-029		US 285 AT HWY 9C IMPROVEMENTS . INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP CANON CITY, CO .		1.00 1.00	20000.00 5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	12500.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			3.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 655

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70200 F/A Power Lines Force Acct =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
===== 700-70210 F/A Lights Force Acct =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	.	.
===== 700-70220 F/A Phone Serv Force Acct =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
===== 700-70230 F/A Communication Lines Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	130000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	130000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	10000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	7500.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		4.00	48750.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 656

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70255 F/A Water Force Acct =====						
STU0252-457	I-25:ALAMEDA RIVER PH 2.0 .		1.00	30000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	30000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		1.00	30000.00	.	.
===== 700-70310 F/A Landscaping Force Acct =====						
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA .		1.00	3000.00	.	.
STR092A-031	.		1.00	3500.00	.	.
NHM765-007	.		1.00	20000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	8833.33	.	.
CM760-047	COLFAX AND QUAIL .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	.	.
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	10000.00	.	.
STA3852-015	US 385 HOLYOKE NORTH .		1.00	5000.00	.	.
STU0252-457	I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS .		1.00	26500.00	.	.
BR2854-148	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP					
BR012A-048	CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	21625.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		9.00	14222.22	.	.
===== 700-70320 F/A Sprinklers Force Acct =====						
CC030-081	ADA RAMP AND CURBS - FT. LUPT .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 657

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70320 F/A Sprinklers Force Acct =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	10000.00	.	.
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS . INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		3.00	8333.33	.	.
===== 700-70350 F/A Removal of Obstruction Force Acct =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	.	.
===== 700-70380 F/A Erosion Ctrl Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	20000.00	.	.
MTCE R500-219		.		1.00	1000.00	.	.
MTCE R500-218		.		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	6000.00	.	.
STR0505-050		.		1.00	5000.00	.	.
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	5000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO .		1.00	500.00	.	.
MTCER300-262		.		1.00	5000.00	.	.
NHPP1601-083		.		1.00	5000.00	.	.
STA0252-459		.		1.00	15000.00	.	.
C0762-055		.		1.00	5000.00	.	.
STR133A-051		.		1.00	2000.00	.	.
NHPP0063-063		.		1.00	7500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 658

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK .		1.00	20000.00	.	.
C0761-239							
NHPP0703-472				1.00	2500.00	.	.
ER007A-035				1.00	10000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	10000.00	.	.
BRC040-057				1.00	10000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	5000.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC .		1.00	2500.00	.	.
STR092A-031				1.00	5000.00	.	.
NHM765-007				1.00	20000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN .		1.00	2000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				24.00	7291.67	.	.
NH0504-911				1.00	5000.00	.	.
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	10000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	10000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE .		1.00	2500.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	5000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	8000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	3000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	5000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	33600.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	3000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	10000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	2500.00	.	.
C0852-120		Rehabilitation of Culvert by .		1.00	2000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	5000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	3750.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	5000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	3600.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2 .		1.00	2000.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	1200.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	5000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				20.00	6257.50	.	.
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE .		1.00	2000.00	.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	5000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
MTCE400-396		REGION 4	.	1.00	500.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS	.	1.00	20000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	.	1.00	5000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	.	2.00	10000.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL	.			.	.
STAR100-374		5 STRUCTURES IN REGION 1	.	1.00	1200.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS	.	1.00	10000.00	.	.
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	.	1.00	1000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS	.	1.00	5000.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING	.	1.00	5000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I	.	1.00	5000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	.	1.00	10000.00	.	.
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		17.00	5982.35	.	.
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	.	1.00	2000.00	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	.	1.00	12000.00	.	.
C0831-126		SH83 EL PASO COUNTY TO BAYOU	.	1.00	5000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE	.	1.00	1500.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA	.	1.00	5000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	.	1.00	5000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	.	1.00	2500.00	.	.
C5502-111		US 550 MP 81 AND 89 RED MOUNT	.	1.00	1000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	.	1.00	25000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH	.	1.00	2000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4)	.	1.00	5000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	.	1.00	75000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	.	1.00	5000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER	.	1.00	5000.00	.	.
C5502-097		US550 MP 117.28-126.06	.	1.00	20000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC	.	1.00	5000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	.	1.00	90000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9	.			.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP	.			.	.
STA0711-021		SH71: REGION LINE NORTH	.	1.00	25000.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	.	1.00	5000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD-	.	1.00	5000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	.	1.00	5000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR	.	1.00	5000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	.	1.00	5000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	.	1.00	10000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	.	1.00	5000.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	.	1.00	2000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO	.	1.00	5000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	.	1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 660

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70380	F/A Erosion Ctrl			Force Acct	=====		
NHM175-029	CANON CITY, CO	.		1.00	5000.00	.	.
NHPP0931-033	SH93:US6 TO 58TH RESURFACING	.		1.00	5000.00	.	.
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C	.		1.00	5000.00	.	.
STA0361-129	US 36: HYGIENE RD AND NELSON	.		1.00	5000.00	.	.
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	.		1.00	5000.00	.	.
STA385A-016	SH 385 MP 97.76	.		1.00	10000.00	.	.
STR096A-050	SH 96 MP 168.99 TO 193.77	.		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			35.00	11085.71	.	.
	WEIGHTED AVERAGE FOR THE YEAR			96.00	8227.60	.	.
===== 700-70495	F/A Asbestos Abatement Work			Force Acct	=====		
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	.		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	.	.
===== 700-70496	F/A Lead Abatement Work			Force Acct	=====		
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	.		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	.	.
===== 700-70530	F/A Drainage Improvement			Force Acct	=====		
NHPP083A-046	SH83 RESURFACING STROH RD TO	.		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	.	.
===== 700-70587	F/A Hazardous Waste Disposal			Force Acct	=====		
NHPP0063-063		.		1.00	10000.00	.	.
NHPP 0761-238	I-76 DAHLIA TO YORK	.		1.00	7000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 661

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70587 F/A Hazardous Waste Disposal Force Acct =====							
C0761-239				1.00	10000.00	.	.
NHM765-007				1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	9000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	7500.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	150000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	80000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			7.00	28857.14	.	.
===== 700-70589 F/A Environ Health & Safety Mgmt Force Acct =====							
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	7500.00	.	.
C0761-239				1.00	5000.00	.	.
ER007A-035				1.00	4000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	4000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	6000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	15000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	10000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	50000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	8000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 662

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70589	F/A Environ Health & Safety Mgmt		Force Acct	=====		
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	22666.67	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	155000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	10000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	10000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	2000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	37400.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			15.00	20600.00	.	.
=====	700-70595	F/A DRB On-Demand Committee		Force Acct	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	4000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	4000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	20000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	20000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			2.00	12000.00	.	.
=====	700-70596	Standing DRB		Force Acct	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	25000.00	.	.
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	25000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			3.00	25000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 663

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-71000 CMGC Overrun Pool Force Acct =====						
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5 .		1.00	270000.00	.	.
CR100-362			1.00	80000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	175000.00	.	.
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG .		2.00	72900.00	.	.
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	72900.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		4.00	123950.00	.	.
===== 700-71002 CDOT Risk Pool Force Acct =====						
CR100-362			1.00	90000.00	.	.
ER007A-035			1.00	250000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	170000.00	.	.
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2 .		1.00	542581.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	542581.00	.	.
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3 .		2.00	700000.00	.	.
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	700000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR		5.00	456516.20	.	.
===== 700-73351 F/A Force Acct =====						
STA0252-459			1.00	255000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 664

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-73351	F/A		Force Acct	=====		
NHPP0063-063			.	1.00	10000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	.	1.00	50000.00	.	.
NHPP0703-472			.	1.00	81600.00	.	.
BRC040-057			.	1.00	160000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	111320.00	.	.
NH0504-911			.	1.00	30000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	100000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN	.	1.00	50000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	.	1.00	10000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	.	1.00	100000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	.	1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	56666.67	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	.	1.00	10000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	.	1.00	30000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I	.	1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	30000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE	.	1.00	10000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	.	1.00	15000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER	.	1.00	15000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.	1.00	50000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	.	1.00	50000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9	.				
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP	.				
2670703-487		I-70 BRIDGES OVER WARD ROAD-	.	1.00	50000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	.	1.00	10000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO	.	1.00	120000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	.	1.00	10000.00	.	.
NHM175-029		CANON CITY, CO	.	1.00	40000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.00	37000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			24.00	56525.00	.	.
=====	700-90026	F/A Landscaping		Force Acct	=====		
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-90026		F/A Landscaping		Force Acct	=====		
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	7500.00	.	.